
Kivy Documentation

Release 2.2.0.dev0

The Kivy Developers

March 06, 2022

CONTENTS

I Getting Started	3
1 Introduction	5
2 Installing Kivy	7
3 A first App	15
4 Properties	17
5 Kv Design Language	19
6 Events	21
7 Non-widget stuff	23
8 Layouts	25
9 Drawing	27
10 Packaging	29
11 Diving in	31
II Kivy Project	33
12 Philosophy	35
13 Contributing	37
14 FAQ	53
15 Contact Us	59
III Programming Guide	61
16 Kivy Basics	63
17 Controlling the environment	69
18 Configure Kivy	73
19 Architectural Overview	75

20 Events and Properties	79
21 Input management	89
22 Widgets	97
23 Graphics	117
24 Kv language	119
25 Integrating with other Frameworks	131
26 Packaging your application	135
27 Package licensing	153
IV Tutorials	157
28 Pong Game Tutorial	159
29 A Simple Paint App	173
30 Crash Course	183
V API Reference	185
31 Kivy framework	187
32 Core Abstraction	297
33 Kivy module for binary dependencies.	335
34 Effects	337
35 Event Manager	343
36 Garden	347
37 Graphics	351
38 Input management	429
39 Kivy Language	455
40 External libraries	477
41 Modules	481
42 Network support	493
43 Storage	497
44 Tools	503
45 Widgets	505

VI Appendix	759
46 License	761
Python Module Index	763
Index	765

Welcome to Kivy's documentation. Kivy is an open source software library for the rapid development of applications equipped with novel user interfaces, such as multi-touch apps.

We recommend that you get started with [Getting Started](#). Then head over to the [Programming Guide](#). We also have [Create an application](#) if you are impatient.

You are probably wondering why you should be interested in using Kivy. There is a document outlining our [Philosophy](#) that we encourage you to read, and a detailed [Architectural Overview](#).

If you want to contribute to Kivy, make sure to read [Contributing](#). If your concern isn't addressed in the documentation, feel free to [Contact Us](#).

Part I

GETTING STARTED

INTRODUCTION

Start Developing Kivy Apps Right Away!

Creating Kivy apps is fun and rewarding. This guide should be the perfect starting point to get you on the right track for app development. You will require a basic knowledge of Python to follow this introduction.



If you need more background on the Python language, you might be interested in these tutorials:

- [The Official Python Tutorial](#)
- [Learn Python in 10 minutes](#)
- [Learn Python the hard way](#)

With Kivy, you can create apps that run on:

- Desktop computers: macOS, Linux, Windows.
- iOS devices: iPad, iPhone.
- Android devices: tablets, phones.
- Any other touch-enabled professional/homebrew devices supporting TUIO (Tangible User Interface Objects).

Kivy empowers you with the freedom to write your code once and have it run as-is on different platforms.

Follow this guide to get the tools you need, understand the major concepts and learn best practices. As this is an introduction, pointers to more information will be provided at the end of each section.

As you proceed through the guide, you will, using Kivy:

- **Learn:** The basics of programming with the Kivy language.

- **Explore:** The Kivy framework.
- **Create:** A simple cross-platform app.
- **Package:** For your choice of platform.

Finally, you will learn how to **Deploy** on the device of your choice.

Each section of the guide introduces a new topic, trying to give you enough information to get started and links to related articles for more in-depth explanations. When you are done with this guide, you'll be able to develop Kivy apps and you will know where to look for information for the more challenging stuff your innovative applications will require.

Enough introductions, let's get down to business.

INSTALLING KIVY

Installation for Kivy version **2.2.0.dev0**. Read the changelog here. For other Kivy versions, select the documentation from the dropdown on the top left.

Kivy 2.2.0.dev0 officially supports Python versions **3.7 - 3.10**.

	Platform	Installation	Packaging
	Windows	<i>pip</i>	<i>PyInstaller</i>
	macOS	<i>pip</i> , Kivy.app	<i>Kivy.app</i> , <i>PyInstaller</i>
	Linux	<i>pip</i> , PPA	—
	RPi	<i>pip</i>	—
	Android	<i>python-for-android</i>	<i>python-for-android</i>
	iOS	<i>kivy-ios</i>	<i>kivy-ios</i>
	Anaconda	<i>conda</i>	—

2.1 Using pip

The easiest way to install Kivy is with **pip**, which installs Kivy using either a *pre-compiled wheel*, if available, otherwise from source (see below).

Kivy provides *pre-compiled wheels* for the supported Python versions on Windows, macOS, Linux, and RPi. Alternatively, installing *from source* is required for newer Python versions not listed above or if the wheels do not work or fail to run properly.

2.1.1 Setup terminal and pip

Before Kivy can be installed, Python and pip needs to be *pre-installed*. Then, start a *new terminal* that has *Python available*. In the terminal, update pip and other installation dependencies so you have the latest version as follows (for linux users you may have to substitute `python3` instead of `python` and also add a `--user` flag in the subsequent commands outside the virtual environment):

```
python -m pip install --upgrade pip setuptools virtualenv
```

2.1.2 Create virtual environment

Create a new **virtual environment** for your Kivy project. A virtual environment will prevent possible installation conflicts with other Python versions and packages. It's optional **but strongly recommended**:

1. Create the virtual environment named `kivy_venv` in your current directory:

```
python -m virtualenv kivy_venv
```

2. Activate the virtual environment. You will have to do this step from the current directory **every time** you start a new terminal. This sets up the environment so the new `kivy_venv` Python is used.

For **Windows default CMD**, in the command line do:

```
kivy_venv\Scripts\activate
```

If you are in a bash terminal on **Windows**, instead do:

```
source kivy_venv/Scripts/activate
```

If you are in **linux** or **macOS**, instead do:

```
source kivy_venv/bin/activate
```

Your terminal should now preface the path with something like `(kivy_venv)`, indicating that the `kivy_venv` environment is active. If it doesn't say that, the virtual environment is not active and the following won't work.

2.1.3 Install Kivy

Finally, install Kivy using one of the following options:

Pre-compiled wheels

The simplest is to install the current stable version of `kivy` and optionally `kivy_examples` from the `kivy-team` provided PyPi wheels. Simply do:

```
python -m pip install "kivy[base]" kivy_examples
```

This also installs the minimum dependencies of Kivy. To additionally install Kivy with **audio/video** support, install either `kivy[base,media]` or `kivy[full]`. See Kivy's dependencies for the list of selectors.

For the Raspberry Pi, you must additionally install the dependencies listed in source dependencies before installing Kivy above.

From source

If a wheel is not available or is not working, Kivy can be installed from source with some additional steps. Installing from source means that Kivy will be installed from source code and compiled directly on your system.

First install the additional system dependencies listed for each platform: Windows, macOS, Linux, RPi.

With the dependencies installed, you can now install Kivy into the virtual environment.

To install the stable version of Kivy, from the terminal do:

```
python -m pip install "kivy[base]" kivy_examples --no-binary kivy
```

To install the latest cutting-edge Kivy from **master**, instead do:

```
python -m pip install "kivy[base] @ https://github.com/kivy/kivy/archive/→master.zip"
```

If you want to install Kivy from a different branch, from your forked repository, or from a specific commit (e.g. to test a fix from a user's PR) replace the corresponding components of the url.

For example to install from the **stable** branch, the url becomes <https://github.com/kivy/kivy/archive/stable.zip>. Or to try a specific commit hash, use e.g. <https://github.com/kivy/kivy/archive/3d3e45dda146fef3f4758aea548da199e10eb382.zip>

Pre-release, pre-compiled wheels

To install a pre-compiled wheel of the last **pre-release** version of Kivy, instead of the current stable version, add the **--pre** flag to pip:

```
python -m pip install --pre "kivy[base]" kivy_examples
```

This will only install a development version of Kivy if one was released to [PyPi](#). Instead, one can also install the latest **cutting-edge** Nightly wheels from the Kivy server with:

```
python -m pip install kivy --pre --no-deps --index-url https://kivy.org/→downloads/simple/  
python -m pip install "kivy[base]" --pre --extra-index-url https://kivy.org/→downloads/simple/
```

It is done in two steps, because otherwise **pip** may ignore the wheels on the server and install an older pre-release version from PyPi.

For the Raspberry Pi, remember to additionally install the dependencies listed in source dependencies before installing Kivy above.

Development install

If you want to edit Kivy before installing it, or if you want to try fixing some Kivy issue and submit a pull request with the fix, you will need to first download the Kivy source code. The following steps assumes git is pre-installed and available in the terminal.

The typical process is to clone Kivy locally with:

```
git clone git://github.com/kivy/kivy.git
```

This creates a kivy named folder in your current path. Next, install the additional system dependencies listed for each OS: Windows, macOS, Linux, RPi.

Then change to the kivy directory and install Kivy as an [editable install](#):

```
cd kivy  
python -m pip install -e ".[dev,full]"
```

Now, you can use git to change branches, edit the code and submit a PR. Remember to compile Kivy each time you change cython files as follows:

```
python setup.py build_ext --inplace
```

Or if using bash or on Linux, simply do:

```
make
```

to recompile.

To run the test suite, simply run:

```
pytest kivy/tests
```

or in bash or Linux:

```
make test
```

2.1.4 Checking the demo

Kivy should now be installed. You should be able to `import kivy` in Python or, if you installed the Kivy examples, run the demo.

on Windows:

```
python kivy_venv\share\kivy-examples\demo\showcase\main.py
```

or in bash, Linux and macOS:

```
python kivy_venv/share/kivy-examples/demo/showcase/main.py
```

The exact path to the Kivy examples directory is also stored in `kivy.kivy_examples_dir`.

The 3d monkey demo under `kivy-examples/3Drendering/main.py` is also fun to see.

2.2 Installation using Conda

If you use [Anaconda](#), you can install Kivy with its package manager [Conda](#) using:

```
conda install kivy -c conda-forge
```

Do not use `pip` to install kivy if you're using Anaconda, unless you're installing from source.

2.3 Installing Kivy's dependencies

Kivy supports one or more backends for its core providers. E.g. it supports glew, angle, and sdl2 for the graphics backend on Windows. For each category (window, graphics, video, audio, etc.), at least one backend must be installed to be able to use the category.

To facilitate easy installation, we provide `extras_require` groups that will install selected backends to ensure a working Kivy installation. So one can install Kivy more simply with e.g. `pip install "kivy[base,media,tuio]"`. The full list of selectors and the packages they install is listed in `setup.py`. The exact packages in each selector may change in the future, but the overall goal of each selector will remain as described below.

We offer the following selectors:

base: The minimum typical dependencies required for Kivy to run, not including video/audio.

media: Only the video/audio dependencies required for Kivy to be able to play media.

full: All the typical dependencies required for Kivy to run, including video/audio and most optional dependencies.

dev: All the additional dependencies required to run Kivy in development mode (i.e. it doesn't include the base/media/full dependencies). E.g. any headers required for compilation, and all dependencies required to run the tests and creating the docs.

tuio: The dependencies required to make TUIO work (primarily oscpy).

The following selectors install backends packaged as wheels by kivy under the `Kivy_deps` namespace. They are typically released and versioned to match specific Kivy versions, so we provide selectors to facilitate installation (i.e. instead of having to do `pip install kivy kivy_deps.sdl2==x.y.z`, you can now do `pip install "kivy[sdl2]"` to automatically install the correct sdl2 for the Kivy version).

gstreamer: The gstreamer video/audio backend, if it's available (currently only on Windows)

angle: A alternate OpenGL backend, if it's available (currently only on Windows)

sdl2: The window/image/audio backend, if it's available (currently only on Windows, on macOS and Linux it is already included in the main Kivy wheel).

glew: A alternate OpenGL backend, if it's available (currently only on Windows)

Following are the `kivy_deps` dependency wheels:

- **gstreamer** (optional)

`kivy_deps.gstremer` is an optional dependency which is only needed for audio/video support. We only provide it on Windows, for other platforms it must be installed independently. Alternatively, use `ffpyplayer` instead.

- **glew** and/or **angle**

`kivy_deps.glew` and `kivy_deps.angle` are for `OpenGL`. You can install both, that is no problem. It is only available on Windows. On other platforms it is not required externally.

One can select which of these to use for OpenGL using the `KIVY_GL_BACKEND` environment variable: By setting it to `glew` (the default), `angle_sdl2`, or `sdl2`. Here, `angle_sdl2` is a substitute for `glew` but requires `kivy_deps.sdl2` be installed as well.

- **sdl2**

`kivy_deps.sdl2` is for window/images/audio and optionally OpenGL. It is only available on Windows and is included in the main Kivy wheel for other platforms.

2.4 Python glossary

Here we explain how to install Python packages, how to use the command line and what wheels are.

2.4.1 Installing Python

Kivy is written in [Python](#) and as such, to use Kivy, you need an existing installation of [Python](#). Multiple versions of Python can be installed side by side, but Kivy needs to be installed as package under each Python version that you want to use Kivy in.

To install Python, see the instructions for each platform: Windows, macOS, Linux, RPi.

Once Python is installed, open the [console](#) and make sure Python is available by typing `python --version`.

2.4.2 How to use the command line

To execute any of the `pip` or `wheel` commands given here, you need a *command line* (here also called *console*, *terminal*, [shell](#) or [bash](#), where the last two refer to Linux style command lines) and Python must be on the [PATH](#).

The default command line on Windows is the [command prompt](#), short `cmd`. The quickest way to open it is to press `Win+R` on your keyboard. In the window that opens, type `cmd` and then press enter.

Alternative Linux style command lines on Windows that we recommend are [Git for Windows](#) or [Msys](#).

Note, the default Windows command line can still be used, even if a bash terminal is installed.

To temporarily add your Python installation to the PATH, simply open your command line and then use the `cd` command to change the current directory to where python is installed, e.g. `cd C:\Python37`.

If you have installed Python using the default options, then the path to Python will already be permanently on your PATH variable. There is an option in the installer which lets you do that, and it is enabled by default.

If however Python is not on your PATH, follow the these instructions to add it:

- Instructions for [the windows command line](#)
- Instructions for [bash command lines](#)

2.4.3 What is pip and what are wheels

In Python, packages such as Kivy can be installed with the python package manager, named [pip](#) (“python install package”).

When installing from source, some packages, such as Kivy, require additional steps, like compilation.

Contrary, wheels (files with a `.whl` extension) are pre-built distributions of a package that has already been compiled. These wheels do not require additional steps when installing them.

When a wheel is available on [pypi.org](#) (“Python Package Index”) it can be installed with `pip`. For example when you execute `python -m pip install kivy` in a command line, this will automatically find the appropriate wheel on PyPI.

When downloading and installing a wheel directly, use the command `python -m pip install <wheel_file_name>`, for example:

```
python -m pip install C:\Kivy-1.9.1.dev-cp27-none-win_amd64.whl
```

2.4.4 What are nightly wheels

Every day we create a snapshot wheel of the current development version of Kivy ('nightly wheel'). You can find the development version in the master branch of the [Kivy Github repository](#).

As opposed to the last *stable* release (which we discussed in the previous section), nightly wheels contain all the latest changes to Kivy, including experimental fixes. For installation instructions, see [Pre-release, pre-compiled wheels](#).

Warning: Using the latest development version can be risky and you might encounter issues during development. If you encounter any bugs, please report them.

A FIRST APP

Immerse yourself in the world of Kivy with your first App.



The [Pong Game Tutorial](#) introduces the fundamental design patterns and the application development process. As you follow the tutorial, you will create a simple app. You will also learn how to run the app on your OS. The simple steps in the tutorial introduce elegant, useful concepts that you will use over and over again in app development.

The [Pong Game Tutorial](#) is the most important article in the road map. It lays the foundation for the concepts that you will learn more about later. Each of the other articles expands on one of those concepts.

PROPERTIES

Kivy introduces a new way of declaring properties within a class. Before:

```
class MyClass(object):
    def __init__(self):
        super(MyClass, self).__init__()
        self.numeric_var = 1
```

After, using Kivy's properties:

```
class MyClass(EventDispatcher):
    numeric_var = NumericProperty(1)
```

These properties implement the [Observer pattern](#). They help you to:

- Easily manipulate widgets defined in the [Kv language](#)
- Automatically observe any changes and dispatch functions/code accordingly
- Check and validate values
- Optimize memory management


To use them, **you have to declare them at class level**. That is, directly in the class, not in any method of the class. A property is a class attribute that will automatically create instance attributes. Each property by default provides an `on_<propertynname>` event that is called whenever the property's state/value changes.

Kivy provides the following properties: [NumericProperty](#), [StringProperty](#), [ListProperty](#), [ObjectProperty](#), [BooleanProperty](#), [BoundedNumericProperty](#), [OptionProperty](#), [ReferenceListProperty](#), [AliasProperty](#), [DictProperty](#), [VariableListProperty](#), [ConfigParserProperty](#), [ColorProperty](#)

For an in-depth explanation, take a look at [Properties](#).

KV DESIGN LANGUAGE

Kivy provides a design language specifically geared towards easy and scalable GUI Design. The language makes it simple to separate the interface design from the application logic, adhering to the **separation of concerns principle**. For example:



In the above code :

```
<LoginScreen>: # every class in your app can be represented by a rule like
    # this in the kv file
    GridLayout: # this is how you add your widget/layout to the parent
        # (note the indentation).
        rows: 2 # this how you set each property of your widget/layout
```

That's it, that's how simple it is to design your GUI in the Kv language. For a more in-depth understanding, please refer to the [Kv language](#) documentation.

EVENTS

Kivy is mostly **event-based**, meaning the flow of the program is determined by events.

Clock events



The ***Clock object*** allows you to schedule a function call in the future as a one-time event with `schedule_once()`, or as a repetitive event with `schedule_interval()`.

You can also create Triggered events with `create_trigger()`. Triggers have the advantage of being called only once per frame, even if you have scheduled multiple triggers for the same callback.

Input events



All the mouse click, touch and scroll wheel events are part of the ***MotionEvent***, extended by ***Input Postprocessing*** and dispatched through the `on_motion` event in the ***Window*** class. This event then generates the `on_touch_down()`, `on_touch_move()` and `on_touch_up()` events in the ***Widget***.

For an in-depth explanation, have a look at [Input management](#).

Class events



Our base class ***EventDispatcher***, used by ***Widget***, uses the power of our ***Properties*** for dispatching changes. This means when a widget changes its position or size, the corresponding event is automatically fired.

In addition, you have the ability to create your own events using `register_event_type()`, as the `on_press` and `on_release` events in the ***Button*** widget demonstrate.

Another thing to note is that if you override an event, you become responsible for implementing all its behaviour previously handled by the base class. The easiest way to do this is to call `super()`:

```
def on_touch_down(self, touch):
    if super().on_touch_down(touch):
        return True
    if not self.collide_point(touch.x, touch.y):
        return False
```

(continues on next page)

(continued from previous page)

```
print('you touched me!')  
return True
```

Get more familiar with events by reading the [Events and Properties](#) documentation.

NON-WIDGET STUFF

<p>Animation is used to change a widget's properties (size/pos/center etc.) to a target value within a target time. Various transition functions are provided. You can use them to animate widgets and build very smooth UI behaviours.</p>	
<p>Atlas is a class for managing texture maps, i.e. packing multiple textures into one image. This allows you to reduce the number of images loaded and thus speed up the application start.</p>	
<p>Clock provides you with a convenient way to schedule jobs at set time intervals and is preferred over <code>sleep()</code>, which would block the kivy event loop. These intervals can be set relative to the OpenGL drawing instructions, before or after. The Clock also provides you with a way to create triggered events that are grouped together and called only once before the next frame.</p>	<ul style="list-style-type: none">• <code>schedule_once()</code>• <code>schedule_interval()</code>• <code>unschedule()</code>• <code>create_trigger()</code>
<p>UrlRequest is useful for asynchronous requests that do not block the event loop. You can use it to manage the progress of URL requests via callbacks.</p>	

LAYOUTS

Layouts are containers used to arrange widgets in a particular manner.

AnchorLayout: Widgets can be anchored to the ‘top’, ‘bottom’, ‘left’, ‘right’ or ‘center’.

BoxLayout: Widgets are arranged sequentially, in either a ‘vertical’ or a ‘horizontal’ orientation.

FloatLayout: Widgets are essentially unrestricted.

RelativeLayout: Child widgets are positioned relative to the layout.

GridLayout: Widgets are arranged in a grid defined by the *rows* and *cols* properties.

PageLayout: Used to create simple multi-page layouts, in a way that allows easy flipping from one page to another using borders.

ScatterLayout: Widgets are positioned similarly to a RelativeLayout, but they can be translated, rotated and scaled.

StackLayout: Widgets are stacked in a *lr-tb* (left to right then top to bottom) or *tb-lr* order.

When you add a widget to a layout, the following properties are used to determine the widget’s size and position, depending on the type of layout:

size_hint: defines the size of a widget as a fraction of the parents size. Values are restricted to the range 0.0 - 1.0 i.e. 0.01 = 1/100th of the parent size (1%) and 1. = same size (100%).

pos_hint: is used to place the widget relative to the parent.

The **size_hint** and **pos_hint** are used to calculate a widget’s size and position only if the value(s) are not set to **None**. If you set these values to **None**, the layout will not position/size the widget and you can specify the values (x, y, width, height) directly in screen coordinates.

DRAWING

Each widget has a canvas, i.e. a place to draw on. The canvas is a group of drawing instructions that should be executed whenever there is a change to the widget's graphical representation.

You can add two types of instructions to the canvas: *context* instructions and *vertex* instructions. You can add instructions either from Python code or from the kv file (the preferred way). If you add them via the kv file, the advantage is that they are automatically updated when any property they depend on changes. In Python, you need to do this yourself.

```
from kivy.app import App
from kivy.uix.widget import Widget
from kivy.graphics import *

class MyWidget(Widget):
    def __init__(self, **kwargs):
        super(MyWidget, self).__init__(**kwargs)
        self.bind(pos=self.update_canvas)
        self.bind(size=self.update_canvas)
        self.update_canvas()

    def update_canvas(self, *args):
        # need to reset everything
        self.canvas.clear()
        with self.canvas:
            # context instruction
            Color(0.5, 0.5, 0.5, 0.5)
            # vertex instruction
            Ellipse(pos = self.pos, size = self.size)

class MyApp(App):
    def build(self):
        return MyWidget()

if __name__ == '__main__':
    MyApp().run()
```

```
from kivy.app import App
from kivy.uix.widget import Widget
class MyWidget(Widget):
    pass
class MyApp(App):
    def build(self):
        return MyWidget()
if __name__ == '__main__':
    MyApp().run()
```

my.kv

```
#kivy 1.0
<MyWidget>
    canvas:
        Color:
            rgba: .5, .5, .5, .5
        Ellipse:
            size: self.size
            pos: self.pos
```

In both cases, the canvas of *MyWidget* is re-drawn whenever the `position` or the `size` of the widget changes.

You can use the `canvas.before` or `canvas.after` groups to separate your instructions based on when you want them to be executed.

For an in-depth look at how Kivy's graphics are handled, look [here](#).

PACKAGING

- *Create a package for Windows*
 - Requirements
 - PyInstaller default hook
- *Creating packages for macOS*
 - Using Buildozer
 - Using PyInstaller and Homebrew
- *Create a package for Android*
 - Packaging with python-for-android
 - Packaging your application for the Kivy Launcher
- *Create a package for iOS*
 - Compile the distribution
 - Create an Xcode project
 - Customize the Xcode project
 - Known issues
 - FAQ

DIVING IN

To get straight into kivy, take a look at [Welcome to Kivy](#).

Kivy comes with a set of examples ([Gallery of Examples](#)) in the `kivy_installation/examples` directory. You should try modifying/improving/adapting them to your needs.

Browse our [wiki](#) for info on related projects, tutorials and snippets.

Understand the basics about [Graphics](#).

Take a look at the built-in [Widgets](#).

Follow the [Programming Guide](#) to get even more familiar with kivy.

See how to use different [Modules](#) in the modules section, such as the [Inspector](#) for live inspection.

Learn how to handle custom [Input management](#).

Familiarize yourself with the [Kivy Framework](#).

Kivy is open source, so you can [contribute](#). Take a look at the [Contributing](#) section for guidelines.

Part II

KIVY PROJECT

This part of the documentation explains the basic ideas behind Kivy's design and why you'd want to use it.

PHILOSOPHY

In case you are wondering what Kivy is all about and what sets it apart from other solutions, this document is for you.

12.1 Why bother?

Why would you want to use Kivy? After all, there are many great toolkits (or frameworks, or platforms) available out there – for free. You have Qt and Flash, to name just two good choices for application development. Many of these numerous solutions already support Multi-Touch, so what is it that makes Kivy special and worth using?

12.1.1 Fresh

Kivy is made for today and tomorrow. Novel input methods such as Multi-Touch have become increasingly important. We created Kivy from scratch, specifically for this kind of interaction. That means we were able to rethink many things in terms of human computer interaction, whereas older (not to mean ‘outdated’, rather ‘well-established’) toolkits carry their legacy, which is often a burden. We’re not trying to force this new approach to using a computer into the corset of existing models (say single-pointer mouse interaction). We want to let it flourish and let you explore the possibilities. *This* is what really sets Kivy apart.

12.1.2 Fast

Kivy is fast. This applies to both *application development* and *application execution* speeds. We have optimized Kivy in many ways. We implement time-critical functionality on the *C level* to leverage the power of existing compilers. More importantly, we also use *intelligent algorithms* to minimize costly operations. We also use the *GPU* wherever it makes sense in our context. The computational power of today’s graphics cards surpasses that of today’s CPUs by far for some tasks and algorithms, especially drawing. That’s why we try to let the GPU do as much of the work as possible, thus increasing performance considerably.

12.1.3 Flexible

Kivy is flexible. This means it can be run on *a variety of different devices*, including iOS and Android powered smartphones and tablets. We support *all major operating systems* (Windows, Linux, macOS). Being flexible also means that Kivy's fast-paced development allows it to *adapt to new technologies quickly*. More than once have we added support for new external devices and software protocols, sometimes even before they were released. Lastly, Kivy is also flexible in that it is possible to use it in combination with a great number of different third-party solutions. For example, on Windows we support WM_TOUCH, which means that any device that has Windows 7 Pen & Touch drivers will *just work* with Kivy. On macOS you can use Apple's Multi-Touch capable devices, such as trackpads and mice. On Linux, you can use HID kernel input events. In addition to that, we support TUIO (Tangible User Interface Objects) and a number of other input sources.

12.1.4 Focused

Kivy is focused. You can write a simple application with a few lines of code. Kivy programs are created using the *Python* programming language, which is incredibly versatile and powerful, yet easy to use. In addition, we created our own description language, the *Kivy Language*, for creating sophisticated user interfaces. This language allows you to set up, connect and arrange your application elements quickly. We feel that allowing you to focus on the essence of your application is more important than forcing you to fiddle with compiler settings. We took that burden off your shoulders.

12.1.5 Funded

Kivy is actively developed by professionals in their field. Kivy is a community-influenced, professionally developed and commercially backed solution. Some of our core developers develop Kivy for a living. Kivy is here to stay. It's not a small, vanishing student project.

12.1.6 Free

Kivy is free to use. You don't have to pay for it. You don't even have to pay for it if you're making money out of selling an application that uses Kivy.

CONTRIBUTING

There are many ways in which you can contribute to Kivy. Code patches are just one thing amongst others that you can submit to help the project. We also welcome feedback, bug reports, feature requests, documentation improvements, advertisement & advocating, testing, graphics contributions and many other ideas. Just talk to us if you want to help, and we will help you help us.

13.1 Discussions

Discussions around Kivy development happens on Github's issues and pull requests for specific things. For things that don't fit in either, discussions happen on the [#dev Discord channel](#), and on the [kivy-dev google group](#). Please come ask for guidance if you are unsure about how to contribute, or you want confirmation about your ideas fitting in the project before working on them. If you want to ask for — or contribute — support, you can join the [#support Discord channel](#), and the [kivy-users google group](#).

13.2 Code of Conduct

In the interest of fostering an open and welcoming community, we as contributors and maintainers need to ensure participation in our project and our sister projects is a harassment-free and positive experience for everyone.

As such, it is vital that all interaction is conducted in a manner conveying respect, open-mindedness and gratitude. For a more comprehensive discussion of these guidelines, please refer to the [Contributor Covenant](#). This document provides an accurate description of what is expected of you, both as a core developer or a first time contributor.

13.3 Feedback

This is by far the easiest way to contribute something. If you're using Kivy for your own project, don't hesitate sharing. It doesn't have to be a high-class enterprise app, obviously. It's just incredibly motivating to know that people use the things you develop and what it enables them to do. If you have something that you would like to tell us, please don't hesitate. Screenshots and videos are also very welcome! We're also interested in the problems you had when getting started. Please feel encouraged to report any obstacles you encountered such as missing documentation, misleading directions or similar. We are perfectionists, so even if it's just a typo, let us know.

13.4 Reporting an Issue

If you found anything wrong, a crash, segfault, missing documentation, invalid spelling or just weird examples, please take 2 minutes to report the issue.

1. Move your logging level to debug by editing `<user_directory>/kivy/config.ini`:

```
[kivy]
log_level = debug
```

2. Execute your code again, and copy/paste the complete output to <http://gist.github.com/>, including the log from Kivy and the python backtrace.
3. Open <https://github.com/kivy/kivy/issues/>
4. Set the title of your issue
5. Explain exactly what to do to reproduce the issue and paste the link of the output posted on <http://gist.github.com/>
6. Validate the issue and you're done!

If you are feeling up to it, you can also try to resolve the bug, and contribute by sending us the patch :) Read the next section to find out how to do this.

13.5 Code Contributions

Code contributions (patches, new features) are the most obvious way to help with the project's development. Since this is so common we ask you to follow our workflow to most efficiently work with us. Adhering to our workflow ensures that your contribution won't be forgotten or lost. Also, your name will always be associated with the change you made, which basically means eternal fame in our code history (you can opt-out if you don't want that).

13.5.1 Coding style

- If you haven't done it yet, read the [PEP8](#) about coding style in python.
- Activate the pep8 and other basic checks on git commits like this:

```
make hook
```

This will pass the code added to the git staging zone (about to be committed) through a checker program when you do a commit, and ensure that you didn't introduce style errors. If you did, the commit will be rejected: please correct the errors and try again.

The checker used is [pre-commit](#). If you need to skip a particular check see [documentation](#), TLDR being that putting `SKIP=hookname` in front of `git commit` will skip that hook, the name of the offending hook is shown when it fails.

13.5.2 Performance

- take care of performance issues: read [Python performance tips](#)
- cpu intensive parts of Kivy are written in cython: if you are doing a lot of computation, consider using it too.

13.5.3 Git & GitHub

We use git as our version control system for our code base. If you have never used git or a similar DVCS (or even any VCS) before, we strongly suggest you take a look at the great documentation that is available for git online. The [Git Community Book](#) or the [Git Videos](#) are both great ways to learn git. Trust us when we say that git is a great tool. It may seem daunting at first, but after a while you'll (hopefully) love it as much as we do. Teaching you git, however, is well beyond the scope of this document.

Also, we use [GitHub](#) to host our code. In the following we will assume that you have a (free) GitHub account. While this part is optional, it allows for a tight integration between your patches and our upstream code base. If you don't want to use GitHub, we assume you know what you are doing anyway.

13.5.4 Code Workflow

So here is the initial setup to begin with our workflow (you only need to do this once to install Kivy). Basically you follow the installation instructions from [Development install](#), but you don't clone our repository, you fork it. Here are the steps:

1. Log in to GitHub
2. Create a fork of the [Kivy repository](#) by clicking the *fork* button.
3. Clone your fork of our repository to your computer. Your fork will have the git remote name 'origin' and you will be on branch 'master':

```
git clone https://github.com/username/kivy.git
```

4. Compile and set up PYTHONPATH or install (see [Development install](#)).
5. Install our pre-commit hook that ensures your code doesn't violate our styleguide by executing *make hook* from the root directory of your clone. This will run our styleguide check whenever you do a commit, and if there are violations in the parts that you changed, your commit will be aborted. Fix & retry.
6. Add the kivy repo as a remote source:

```
git remote add kivy https://github.com/kivy/kivy.git
```

Now, whenever you want to create a patch, you follow the following steps:

1. See if there is a ticket in our bug tracker for the fix or feature and announce that you'll be working on it if it doesn't yet have an assignee.
2. Create a new, appropriately named branch in your local repository for that specific feature or bugfix. (Keeping a new branch per feature makes sure we can easily pull in your changes without pulling any other stuff that is not supposed to be pulled.):

```
git checkout -b new_feature
```

3. Modify the code to do what you want (e.g. fix it).

4. Test the code. Try to do this even for small fixes. You never know whether you have introduced some weird bug without testing.
5. Do one or more minimal, atomic commits per fix or per feature. Minimal/Atomic means *keep the commit clean*. Don't commit other stuff that doesn't logically belong to this fix or feature. This is **not** about creating one commit per line changed. Use `git add -p` if necessary.
6. Give each commit an appropriate commit message, so that others who are not familiar with the matter get a good idea of what you changed.
7. Once you are satisfied with your changes, pull our upstream repository and merge it with your local repository. We can pull your stuff, but since you know exactly what's changed, you should do the merge:

```
git pull kivy master
```

8. Push your local branch into your remote repository on GitHub:

```
git push origin new_feature
```

9. Send a *Pull Request* with a description of what you changed via the button in the GitHub interface of your repository. (This is why we forked initially. Your repository is linked against ours.)

Warning: If you change parts of the code base that require compilation, you will have to recompile in order for your changes to take effect. The `make` command will do that for you (see the `Makefile` if you want to know what it does). If you need to clean your current directory from compiled files, execute `make clean`. If you want to get rid of **all** files that are not under version control, run `make distclean` (**Caution:** If your changes are not under version control, this command will delete them!)

Now we will receive your pull request. We will check whether your changes are clean and make sense (if you talked to us before doing all of this we will have told you whether it makes sense or not). If so, we will pull them and you will get instant karma. Congratulations, you're a hero!

13.6 Documentation Contributions

Documentation contributions generally follow the same workflow as code contributions, but are just a bit more lax.

1. Following the instructions above,
 1. Fork the repository.
 2. Clone your fork to your computer.
 3. Setup kivy repo as a remote source.
2. Install python-sphinx. (See `docs/README` for assistance.)
3. Use [ReStructuredText Markup](#) to make changes to the HTML documentation in `docs/sources`.

To submit a documentation update, use the following steps:

1. Create a new, appropriately named branch in your local repository:

```
git checkout -b my_docs_update
```

2. Modify the documentation with your correction or improvement.
3. Re-generate the HTML pages, and review your update:

```
make html
```

4. Give each commit an appropriate commit message, so that others who are not familiar with the matter get a good idea of what you changed.
5. Keep each commit focused on a single related theme. Don't commit other stuff that doesn't logically belong to this update.
6. Push to your remote repository on GitHub:

```
git push
```

7. Send a *Pull Request* with a description of what you changed via the button in the GitHub interface of your repository.

We don't ask you to go through all the hassle just to correct a single typo, but for more complex contributions, please follow the suggested workflow.

13.6.1 Docstrings

Every module/class/method/function needs a docstring, so use the following keywords when relevant:

- ... `versionadded::` to mark the version in which the feature was added.
- ... `versionchanged::` to mark the version in which the behaviour of the feature was changed.
- ... `note::` to add additional info about how to use the feature or related feature.
- ... `warning::` to indicate a potential issue the user might run into using the feature.

Examples:

```
def my_new_feature(self, arg):
    """
    New feature is awesome

    .. versionadded:: 1.1.4

    .. note:: This new feature will likely blow your mind

    .. warning:: Please take a seat before trying this feature
    """
```

Will result in:

```
def my_new_feature(self, arg): New feature is awesome
```

New in version 1.1.4.

Note: This new feature will likely blow your mind

Warning: Please take a seat before trying this feature

When referring to other parts of the api use:

- `:mod:`~kivy.module`` to refer to a module
- `:class:`~kivy.module.Class`` to refer to a class
- `:meth:`~kivy.module.Class.method`` to refer to a method
- `:doc:`api-kivy.module`` to refer to the documentation of a module (same for a class and a method)

Obviously replacing *module Class* and *method* with their real name, and using using ‘.’ to separate modules referring to imbricated modules, e.g:

```
:mod:`~kivy.uix.floatlayout`  
:class:`~kivy.uix.floatlayout.FloatLayout`  
:meth:`~kivy.core.window.WindowBase.toggle_fullscreen`  
:doc:`/api-kivy.core.window`
```

Will result in:

floatlayout FloatLayout toggleFullscreen() Window

`:doc:` and `:mod:` are essentially the same, except for an anchor in the url which makes `:doc:` preferred for the cleaner url.

To build your documentation, run:

```
make html
```

If you updated your kivy install, and have some trouble compiling docs, run:

```
make clean force html
```

The docs will be generated in `docs/build/html`. For more information on docstring formatting, please refer to the official [Sphinx Documentation](#).

13.7 Unit tests contributions

For the testing team, we have the document [Unit tests](#) that explains how Kivy unit tests work and how you can create your own. Use the same approach as the [Code Workflow](#) to submit new tests.

13.7.1 Unit tests

Tests are located in the `kivy/tests` folder. If you find a bug in Kivy, a good thing to do can be to write a minimal case showing the issue and to ask core devs if the behaviour shown is intended or a real bug. If you write your code as a `unittest`, it will prevent the bug from coming back unnoticed in the future, and will make Kivy a better, stronger project. Writing a unittest may be a really good way to get familiar with Kivy while doing something useful.

Unit tests are separated into two cases:

- Non graphical unit tests: these are standard unit tests that can run in a console
- Graphical unit tests: these need a GL context, and if requested, work via image comparison

To be able to run unit tests, you need to install pytest (<https://pytest.org/>), and coverage (<http://nedbatchelder.com/code/coverage/>). You can use pip for that:

```
sudo pip install pytest coverage
```

Then, in the kivy directory:

```
make test
```

How it works

All the tests are located in *kivy/tests*, and the filename starts with *test_<name>.py*. Pytest will automatically gather all the files and classes inside this folder, and use them to generate test cases.

To write a test, create a file that respects the previous naming, then start with this template:

```
import unittest

class XXXTestCase(unittest.TestCase):

    def setUp(self):
        # import class and prepare everything here.
        pass

    def test_YYY(self):
        # place your test case here
        a = 1
        self.assertEqual(a, 1)
```

Replace XXX with an appropriate name that covers your tests cases, then replace 'YYY' with the name of your test. If you have any doubts, check how the other tests have been written.

Then, to execute them, just run:

```
make test
```

If you want to execute that file only, you can run:

```
pytest kivy/tests/test_your testcase.py
```

or include this simple *unittest.main()* call at the end of the file and run the test with *python test_your testcase.py*:

```
if __name__ == '__main__':
    unittest.main()
```

Graphical unit tests

While simple unit tests are fine and useful to keep things granular, in certain cases we need to test Kivy after the GL Window is created to interact with the graphics, widgets and to test more advanced stuff such as widget, modules, various cases of input and interaction with everything that becomes available only after the Window is created and Kivy properly initialized.

These tests are executed the same way like the ordinary unit tests i.e. either with *pytest* or via *unittest.main()*.

Here are two similar examples with different approaches of running the app. In the first one you are setting up the required stuff manually and the *tearDown()* of the *GraphicUnitTest* may only attempt to clean it after you:

```

from kivy.tests.common import GraphicUnitTest

class MyTestCase(GraphicUnitTest):

    def test_runtouchapp(self):
        # non-integrated approach
        from kivy.app import runTouchApp
        from kivy.uix.button import Button

        button = Button()
        runTouchApp(button)

        # get your Window instance safely
        from kivy.base import EventLoop
        EventLoop.ensure_window()
        window = EventLoop.window

        # your asserts
        self.assertEqual(window.children[0], button)
        self.assertEqual(
            window.children[0].height,
            window.height
        )

```

In the second test case both `setUp()` and `tearDown()` work together with `GraphicUnitTest.render()`. This is the basic setup it does automatically:

- Window is sized to 320 x 240 px
- Only the default Config is used during the test, it's restricted with the `KIVY_USE_DEFAULTCONFIG` environment variable
- Any input (mouse/touch/...) is *removed* and if you need to test it, either mock it or manually add it
- Window's canvas is cleared before displaying any widget tree

Warning: Do NOT use absolute numbers in your tests to preserve the functionality across all resolutions. Instead, use e.g. relative position or size and multiply it by the `Window.size` in your test.

```

from kivy.tests.common import GraphicUnitTest, UnitTestTouch

class MyTestCase(GraphicUnitTest):

    def test_render(self):
        from kivy.uix.button import Button

        # with GraphicUnitTest.render() you basically do this:
        # runTouchApp(Button()) + some setup before
        button = Button()
        self.render(button)

        # get your Window instance safely
        from kivy.base import EventLoop

```

(continues on next page)

```

EventLoop.ensure_window()
window = EventLoop.window

touch = UnitTestTouch(
    *[s / 2.0 for s in window.size]
)

# bind something to test the touch with
button.bind(
    on_release=lambda instance: setattr(
        instance, 'test_released', True
    )
)

# then let's touch the Window's center
touch.touch_down()
touch.touch_up()
self.assertTrue(button.test_released)

if __name__ == '__main__':
    import unittest
    unittest.main()

```

Note: Make sure you check the source of *kivy.tests.common* before writing comprehensive test cases.

GL unit tests

GL unit test are more difficult. You must know that even if OpenGL is a standard, the output/rendering is not. It depends on your GPU and the driver used. For these tests, the goal is to save the output of the rendering at frame X, and compare it to a reference image.

Currently, images are generated at 320x240 pixels, in *png* format.

Note: Currently, image comparison is done per-pixel. This means the reference image that you generate will only be correct for your GPU/driver. If somebody can implement image comparison with “delta” support, patches are welcome :)

To execute GL unit tests, you need to create a directory:

```

mkdir kivy/tests/results
KIVY_UNITTEST_SCREENSHOTS=1 make test

```

The results directory will contain all the reference images and the generated images. After the first execution, if the results directory is empty, no comparison will be done. It will use the generated images as reference. After the second execution, all the images will be compared to the reference images.

A html file is available to show the comparison before/after the test, and a snippet of the associated unit test. It will be generated at:

`kivy/tests/build/index.html`

Note: The build directory is cleaned after each call to *make test*. If you don't want that, just use `pytest` command.

Writing GL Unit tests

The idea is to create a root widget, as you would do in `build()`, or in `kivy.base.runTouchApp()`. You'll give that root widget to a rendering function which will capture the output in X frames.

Here is an example:

```
from kivy.tests.common import GraphicUnitTest

class VertexInstructionTestCase(GraphicUnitTest):

    def test_ellipse(self):
        from kivy.uix.widget import Widget
        from kivy.graphics import Ellipse, Color
        r = self.render

        # create a root widget
        wid = Widget()

        # put some graphics instruction on it
        with wid.canvas:
            Color(1, 1, 1)
            self.e = Ellipse(pos=(100, 100), size=(200, 100))

        # render, and capture it directly
        r(wid)

        # as alternative, you can capture in 2 frames:
        r(wid, 2)

        # or in 10 frames
        r(wid, 10)
```

Each call to `self.render` (or `r` in our example) will generate an image named as follows:

```
<classname>_<funcname>-<r-call-count>.png
```

r-call-count represents the number of times that `self.render` is called inside the test function.

The reference images are named:

```
ref_<classname>_<funcname>-<r-call-count>.png
```

You can easily replace the reference image with a new one if you wish.

Coverage reports

Coverage is based on the execution of previous tests. Statistics on code coverage are automatically calculated during execution. You can generate an html report of the coverage with the command:

```
make cover
```

Then, open `kivy/htmlcov/index.html` with your favorite web browser.

13.8 GSOC

13.8.1 Google Summer of Code - 2017

Introduction

Kivy is a cross-platform, business friendly, GPU accelerated open source Python library for rapid development of applications that make use of innovative user interfaces, such as multi-touch apps.

The Kivy Organization oversees several major projects:

- The [Kivy](#) GUI Library
- The [Python-For-Android](#) compilation tool.
- The [Kivy-iOS](#) compilation tool.
- The [PyJNIus](#) library for interfacing with Java from Python.
- The [PyOBJus](#) library for interfacing with Objective-C from Python.
- The [Plyer](#) platform-independent Python wrapper for platform dependent APIs.
- [Buildozer](#) - A generic Python packager for Android, iOS, and desktop.
- [KivEnt](#) - A 2d Game Engine that provides optimized methods of handling large amounts of dynamic visual data.
- [Kivy Designer](#) - A graphical GUI designer for Kivy built in Kivy.

Altogether, these projects allow the user to create applications for every major operating system that make use of any native APIs present. Our goal is to enable development of Python applications that run everywhere off the same codebase and make use of platform dependent APIs and features that users of specific operating systems have come to expect.

Depending on which project you choose you may need to know Cython, OpenGL ES2, Java, Objective-C, or C in addition to Python. We make heavy use of Cython and OpenGL for computational and graphics performance where it matters, and the other languages are typically involved in accessing OS or provider level APIs.

We are hoping to participate in Google Summer of Code 2017. This page showcases some ideas for GSoC projects and corresponding guidelines for students contributing to the Kivy Framework.

Requirements

It is assumed that the incoming student meets some basic requirements as highlighted here:

- Intermediate level familiarity with Python.
- Comfortable with git and github (Kivy and its sister projects are all managed on github) If you have never used github before you may be interested in this [tutorial](#).
- Comfortable with event driven programming.
- Has suitable tools/environment for Kivy or the sister project you are going to work on. For example to be able to work on PyOBJus you would need access to an iOS device, OS X with Xcode and a developer license, to work on PyJNIus you would need an Android device, and to work on Plyer you would need access to hardware for both platforms.

Additional desired skills may be listed with specific projects.

Familiarize yourself with the [contribution guide](#) We can help you get up to speed, however students demonstrating ability in advance will be given preference.

How to get started

For Kivy, the easiest way is to follow the installation instructions for the development version for your specific platform:

<http://kivy.org/docs/installation/installation.html#development-version>

For the rest it's usually sufficient to install the relevant project from git and add it to your PYTHONPATH.

e.g. for PyJNIus:

```
git clone http://github.com/kivy/pyjnius  
export PYTHONPATH=/path/to/pyjnius:$PYTHONPATH
```

Project Ideas

Here are some prospective ideas sourced from the Kivy development team, if none of these projects interest you come talk to us in #kivy-dev about a project idea of your own.

Beginner Projects

These projects should be suitable for anyone with a college level familiarity with Python and require little knowledge of platform specifics.

Intermediate Projects

These projects may involve cursory level knowledge of several OS level details, some OpenGL interaction, or other topics that may be a bit out of the wheelhouse of the average Pythonista.

Plyer:

Description: Plyer is a platform-independent Python API to use features commonly found on the desktop and mobile platforms supported by Kivy. The idea is to provide a stable API to the user for accessing features of their desktop or mobile device.

The student would replace some `.java` code currently in the p4a project to a more appropriate place in Plyer. In addition, the student would work on improving access to platform specific features through Plyer, including accessibility, Bluetooth Low Energy, accessing and editing contacts, sharing, NFC, in-app browser, Wi-Fi (enable, disable, access to Wi-Fi services (Wi-Fi direct, network accessibility, current IP info on network etc.), Camera capture (video), camera display, Google Play integration, launch phone call interface, sms interface, geolocation, interaction with notifications, internationalization (I18N), and all the missing platform implementations from existing features.

Under the hood you'll use PyJNIus on Android, PyOBJus on OS X and iOS, ctypes on Windows, and native APIs on Linux. This probably would also include improving PyOBJus and PyJNIus to handle interfaces that they can't right now.

References:

- <https://github.com/kivy/plyer>
- <https://github.com/kivy/pyjnius>
- <https://github.com/kivy/pyobjus>
- <https://github.com/kivy/python-for-android>
- <https://github.com/kivy/kivy-ios>

Expected outcome: A successful outcome would include moving the Java/PyOBJus code from p4a/kivy-ios to plyer and implementing some or all of the new facades to be decided with the student.

- **Mentors:** Akshay Arora
- **Requirements:** Access to Linux, Windows, OS X, iOS device, Android device.
- **Task level:** Intermediate
- **Desired Skills:** Familiarity with PyJNIus, PyOBJus.

Font Reshaping and Font Fallback Support

Description: Currently Kivy does not support reshaping for alphabets such as Arabic, Persian, Thai, or Devanagari. The solution is to integrate a text shaping and layout engine (Pango and Harfbuzz). You would need to ensure that Pango and Harfbuzz can be compiled on every platform, and integrate it as a core text provider.

The second part of the same project would involve font fallback support. If a particular character/glyph is missing, currently we show a [] box. The solution for this would involve either using an OS API if available or maintaining a hashtable for the default fonts on each OS which can be used for glyph fallback.

References:

- <http://www.pango.org>
- <https://www.freedesktop.org/wiki/Software/HarfBuzz/>
- <https://github.com/kivy/kivy/tree/master/kivy/core/text>

Expected outcome: Font fallback and text reshaping support in Kivy, compilation recipes for Python-For-Android and packaging on desktop platforms.

- **Mentors:** Akshay Arora, Jacob Kovac, Matthew Einhorn
- **Requirements:** Access to a desktop OS and ideally at least one mobile platform
- **Task level:** Intermediate
- **Desired Skills:** Familiarity with text rendering, Pango, HarfBuzz and Kivy's provider abstraction.

Advanced Projects

These projects may involve very in-depth knowledge of Kivy's existing internals, the hairy details of cross-platform compilation, or other fairly advanced topics. If you are comfortable with the internals of Python, working with C code, and using Cython to build your own C extensions these projects may appeal to you.

Kivent: Chipmunk 7 Integration

Description: KivEnt is a modular entity-component based game engine built on top of Kivy. KivEnt provides a highly performant approach to building games in Python that avoids some of the worst overhead of Python using specialized Cython constructs.

At the moment, KivEnt internally makes use of the cymunk library (<https://github.com/tito/cymunk>) for physics simulation and collision detection. Cymunk is based on Chipmunk2d 6.x, recently Chipmunk 7 has released and brought many previously premium features into the core library. In addition to the API changes present in the newest Chipmunk, the KivEnt - Cymunk bridging does not make most efficient use of the KivEnt API for handling C level objects and data. The student will be responsible for creating a new wrapper over Chipmunk2d 7 that better matches KivEnt's approach to handling game data.

References:

- <http://chipmunk-physics.net/>
- <https://github.com/kivy/kivent>

Expected Outcome: A successful outcome involves a new kivent_tiled module being released for the KivEnt game engine.

- **Mentors:** Jacob Kovac
- **Requirements:** Access to at least one Kivy platform.
- **Task level:** Advanced
- **Desired Skills:** Familiarity with Cython, Python, and game dev related math concepts.

KV Compiler: A compiler for the KV language

Description: The KV language is a fundamental component of Kivy. The KV language allows one to describe a GUI; from the creation of a Widget tree to the actions that should be taken in response value changes and events. In effect it is a concise way to create rule bindings using the Kivy properties and events. Internally, python code that reflects these rules are created and bound to the properties and events. Currently, these bindings are not at all optimized because upon each widget creation all of these rules are re-evaluated and bound. This process can be significantly optimized by pre-compiling the kv code, especially the bindings. A compiler would also allow us to update and fix some of the long-standing kv language issues.

Work on a kv-compiler has already progressed quite far, in fact a PR in the pre-alpha stage, is currently open. However, it is out of sync with the current codebase due to some unrelated kv changes in the meantime. Also, that PR would require a significant re-write to make things more modular, self-contained, and extensible. So there is much work still to be done on it.

Theming has also been a prepatual issue in Kivy, a KV compiler may help implement bindings that facilitate theming.

References:

- <https://kivy.org/docs/guide/lang.html>

- <https://github.com/kivy/kivy/pull/3456>
- <https://github.com/kivy/kivy/wiki/KEP001:-Instantiate-things-other-than-widgets-from-kv>
- <https://github.com/kivy/kivy/issues/691>
- <https://github.com/kivy/kivy/issues/2727>

Expected Outcome: A successful outcome would be a compiler which compiles kv code into python code. The compiler should be modular and extensible so that we can continue to improve the kv language. The compiler should have the common debug/optimization options. The compiled code should also be human readable so issues could be traced back to the original kv code. The compiler should also be a drop in replacement for the current KV runtime compiler, and would require extensive testing.

- **Mentors:** Matthew Einhorn
- **Requirements:** Access to at least one Kivy platform.
- **Task level:** Advanced
- **Desired Skills:** Familiarity with Cython, Python, and Kivy. Familiarity with typical computer science concepts and data structures is also desired.

How to Contact devs

All communication must happen via public channels, private emails and Discord private messages are discouraged.

Ask your questions on the Kivy Users forum <https://groups.google.com/group/kivy-users> or send a mail at kivy-users@googlegroups.com

Make sure to join the kivy-dev user group too: <https://groups.google.com/forum/#!forum/kivy-dev>.

You can also try to contact us on Discord, to get the Discord handles of the devs mentioned above visit <https://kivy.org/#aboutus>.

Make sure to read the [Discord rules](#) before connecting. [Connect to Discord](#).

Most of our developers are located in Europe, India, and North America so keep in mind typical waking hours for these areas.

How to be a good student

If you want to participate as a student and want to maximize your chances of being accepted, start talking to us today and try fixing some smaller problems to get used to our workflow. If we know you can work well with us, you will have much better chances of being selected.

Here's a checklist:

- Make sure to read through the website and at least skim the documentation.
- Look at the source code.
- Read our contribution guidelines.
- Make a contribution! Kivy would like to see how you engage with the development process. Take a look at the issue tracker for a Kivy project that interests you and submit a Pull Request. It can be a simple bug or a documentation change. We are looking to get a feel for how you work, not evaluating your capabilities. Don't worry about trying to pick something to impress us.
- Pick an idea that you think is interesting from the ideas list or come up with your own idea.

- Do some research **yourself**. GSoC is about give and take, not just one sided interaction. It is about you trying to achieve agreed upon goals with our support. The main driving force in this should be, obviously, yourself. Many students pop up and ask what they should do. You should base that decision on your interests and your skills. Show us you're serious about it and take the initiative.
- Write a draft **proposal** about what you want to do. Include what you understand the current state of the project to be, what you would like to improve, how, etc.
- Discuss that proposal with us in a timely manner. Get feedback.
- Be patient! Especially on Discord. We will try to get to you if we're available. If not, send an email and just wait. Most questions are already answered in the docs or somewhere else and can be found with some research. Your questions should reflect that you've actually thought through what you're asking and done some rudimentary research.
- Most of all don't forget to have fun and interact with the community. The community is as big a part of Open Source as the code itself.

What to expect if you are chosen

- All students should join the #support and the #dev Discord channels daily, this is how the development team communicates both internally and with the users.
- You and your mentors will agree on two week milestones for the duration of the summer.
- Development will occur in your fork of the master branch of Kivy, we expect you to submit at least one PR a week from your branch into a branch reserved for you in the primary repo. This will be your forum for reporting progress as well as documenting any struggles you may have encountered.
- Missing 2 weekly PR or 2 milestones will result in your failure unless there have been extenuating circumstances. If something comes up, please inform your mentors as soon as possible. If a milestone seems out of reach we will work with you to reevaluate the goals.
- Your changes will be merged into master once the project has been completed and we have thoroughly tested on every platform that is relevant.

FAQ

There are a number of questions that repeatedly need to be answered. The following document tries to answer some of them.

14.1 Technical FAQ

14.1.1 Unable to get a Window, abort.

If Kivy cannot instantiate a Window core provider (mostly SDL2), you'll see this. The underlying issue depends on many things:

- Check your installation. Twice.
- Check that your graphics driver support OpenGL 2.1 at the minimum. Otherwise, Kivy can't run.
- If you use windows and ANGLE (`KIVY_GL_BACKEND=angle_sdl2`), check that you have DirectX 9 support.
- If your platform doesn't supports OpenGL, SDL2 cannot initialize OpenGL.
- Don't mix the architecture of the dependencies (e.g. Python 64-bit and 32-bit extensions/SDL2)
- Don't mix python installation: e.g. if you have Python and Anaconda installed, the Python actually run may be different than you think. Similarly, if you have multiple Python versions available on the PATH, they may clash.
- Check your PATH to ensure that other programs in it don't provide the same dlls as Kivy/Python, or bad stuff can happen.
 - This commonly happens if some other program that uses similar dependencies as Kivy adds itself to the PATH so that Kivy's dependencies clash with theirs.
 - Please read [this](#) and [this](#) for more details on PATH.
 - The best tool to troubleshoot this is with [Dependency Walker](#) explained [here](#) and [here](#).
 - But ensure that you're launching it from the identical environment that you start Python.
- Ensure you have all dependencies installed (like `kivy_deps.sdl2`).
- Maybe your drivers have some missing OpenGL symbols? Try to switch to another graphics backend with `KIVY_GL_BACKEND`.
- Maybe your [Pycharm configuration is incorrect](#).

14.1.2 Fatal Python error: (pygame parachute) Segmentation Fault

Most of time, this issue is due to the usage of old graphics drivers. Install the latest graphics driver available for your graphics card, and it should be ok.

If not, this means you have probably triggered some OpenGL code without an available OpenGL context. If you are loading images, atlases, using graphics instructions, you must spawn a Window first:

```
# method 1 (preferred)
from kivy.base import EventLoop
EventLoop.ensure_window()

# method 2
from kivy.core.window import Window
```

If not, please report a detailed issue on github by following the instructions in the [Reporting an Issue](#) section of the [Contributing](#) documentation. This is very important for us because that kind of error can be very hard to debug. Give us all the information you can give about your environment and execution.

14.1.3 undefined symbol: glGenerateMipmap

Your graphics card or its drivers might be too old. Update your graphics drivers to the latest available version and retry.

14.1.4 ImportError: No module named event

If you use Kivy from our development version, you must compile it before using it. In the kivy directory, do:

```
make force
```

14.2 Android FAQ

14.2.1 Crash on touch interaction on Android 2.3.x

There have been reports of crashes on Adreno 200/205 based devices. Apps otherwise run fine but crash when interacted with/through the screen.

These reports also mentioned the issue being resolved when moving to an ICS or higher ROM.

14.2.2 Is it possible to have a kiosk app on android 3.0 ?

Thomas Hansen have wrote a detailed answer on the kivy-users mailing list:

https://groups.google.com/d/msg/kivy-users/QKoCekAR1c0/yV-85Y_iAwoJ

Basically, you need to root the device, remove the SystemUI package, add some lines to the xml configuration, and you're done.

14.2.3 What's the difference between python-for-android from Kivy and SL4A?

Despite having the same name, Kivy's python-for-android is not related to the python-for-android project from SL4A, Py4A, or android-python27. They are distinctly different projects with different goals. You may be able to use Py4A with Kivy, but no code or effort has been made to do so. The Kivy team feels that our python-for-android is the best solution for us going forward, and attempts to integrate with and support Py4A is not a good use of our time.

14.3 Project FAQ

14.3.1 Why do you use Python? Isn't it slow?

Let us try to give a thorough answer; please bear with us.

Python is a very agile language that allows you to do many things in a (by comparison) short time. For many development scenarios, we strongly prefer writing our application quickly in a high-level language such as Python, testing it, then optionally optimizing it.

But what about speed? If you compare execution speeds of implementations for a certain set of algorithms (esp. number crunching) you will find that Python is a lot slower than say, C++. Now you may be even more convinced that it's not a good idea in our case to use Python. Drawing sophisticated graphics (and we are not talking about your grandmother's OpenGL here) is computationally quite expensive and given that we often want to do that for rich user experiences, that would be a fair argument. **But**, in virtually every case your application ends up spending most of the time (by far) executing the same part of the code. In Kivy, for example, these parts are event dispatching and graphics drawing. Now Python allows you to do something to make these parts much faster.

By using Cython, you can compile your code down to the C level, and from there your usual C compiler optimizes things. This is a pretty pain free process and if you add some hints to your code, the result becomes even faster. We are talking about a speed up in performance by a factor of anything between 1x and up to more than 1000x (greatly depends on your code). In Kivy, we did this for you and implemented the portions of our code, where efficiency really is critical, on the C level.

For graphics drawing, we also leverage today's GPUs which are, for some tasks such as graphics rasterization, much more efficient than a CPU. Kivy does as much as is reasonable on the GPU to maximize performance. If you use our Canvas API to do the drawing, there is even a compiler that we invented which optimizes your drawing code automatically. If you keep your drawing mostly on the GPU, much of your program's execution speed is not determined by the programming language used, but by the graphics hardware you throw at it.

We believe that these (and other) optimizations that Kivy does for you already make most applications fast enough by far. Often you will even want to limit the speed of the application in order not to waste resources. But even if this is not sufficient, you still have the option of using Cython for your own code to *greatly* speed it up.

Trust us when we say that we have given this very careful thought. We have performed many different benchmarks and come up with some clever optimizations to make your application run smoothly.

14.3.2 Does Kivy support Python 3.x?

Yes! Kivy **2.2.0.dev0** officially supports Python versions **3.7 - 3.10**.

As of version **2.0.0** Kivy dropped support for Python 2. You can still use older versions with Python 2 support.

Python 3 is also supported by python-for-android and kivy-ios.

14.3.3 How is Kivy related to PyMT?

Our developers are professionals and are pretty savvy in their area of expertise. However, before Kivy came around there was (and still is) a project named PyMT that was led by our core developers. We learned a great deal from that project during the time that we developed it. In the more than two years of research and development we found many interesting ways to improve the design of our framework. We have performed numerous benchmarks and as it turns out, to achieve the great speed and flexibility that Kivy has, we had to rewrite quite a big portion of the codebase, making this a backwards-incompatible but future-proof decision. Most notable are the performance increases, which are just incredible. Kivy starts and operates just so much faster, due to these heavy optimizations. We also had the opportunity to work with businesses and associations using PyMT. We were able to test our product on a large diversity of setups and made PyMT work on all of them. Writing a system such as Kivy or PyMT is one thing. Making it work under all these different conditions is another. We have a good background here, and brought our knowledge to Kivy.

Furthermore, since some of our core developers decided to drop their full-time jobs and turn to this project completely, it was decided that a more professional foundation had to be laid. Kivy is that foundation. It is supposed to be a stable and professional product. Technically, Kivy is not really a successor to PyMT because there is no easy migration path between them. However, the goal is the same: Producing high-quality applications for novel user interfaces. This is why we encourage everyone to base new projects on Kivy instead of PyMT. Active development of PyMT has stalled. Maintenance patches are still accepted.

14.3.4 Do you accept patches?

Yes, we love patches. In order to ensure a smooth integration of your precious changes however, please make sure to read our contribution guidelines. Obviously we don't accept every patch. Your patch has to be consistent with our styleguide and, more importantly, make sense. It does make sense to talk to us before you come up with bigger changes, especially new features.

14.3.5 Does the Kivy project participate in Google's Summer of Code ?

Potential students ask whether we participate in GSoC. The clear answer is: Indeed. :-)

If you want to participate as a student and want to maximize your chances of being accepted, start talking to us today and try fixing some smaller (or larger, if you can ;-) problems to get used to our workflow. If we know you can work well with us, that'd be a big plus.

Here's a checklist:

- Make sure to read through the website and at least skim the documentation.
- Look at the source code.
- Read our contribution guidelines.
- Pick an idea that you think is interesting from the ideas list (see link above) or come up with your own idea.

- Do some research **yourself**. GSoC is not about us teaching you something and you getting paid for that. It is about you trying to achieve agreed upon goals by yourself with our support. The main driving force in this should be, obviously, yourself. Many students come up and ask what they should do. Well, we don't know because we know neither your interests nor your skills. Show us you're serious about it and take initiative.
- Write a draft proposal about what you want to do. Include what you understand the current state is (very roughly), what you would like to improve and how, etc.
- Discuss that proposal with us in a timely manner. Get feedback.
- Be patient! Especially on Discord. We will try to get to you if we're available. If not, send an email and just wait. Most questions are already answered in the docs or somewhere else and can be found with some research. If your questions don't reflect that you've actually thought through what you're asking, it might not be well received.

Good luck! :-)

CONTACT US

You can contact us in several different ways:

15.1 Issue Tracker

If you have found an issue with the code or have a feature request, please see our [issue tracker](#). If there is no issue yet that matches your inquiry, feel free to create a new one. Please make sure you receive the mails that github sends if we comment on the issue in case we need more information. For bugs, please provide all the information necessary, like the operating system you're using, the [full error message](#) or any other logs, a description of what you did to trigger the bug and what the actual bug was, as well as anything else that might be of interest. Obviously, we can only help if you tell us precisely what the actual problem is.

15.2 Mail

For users of our framework, there is a mailing list for support inquiries on the [kivy-users Google Group](#). Use this list if you have issues with your Kivy-based app. We also have a mailing list for matters that deal with development of the actual Kivy framework code on the [kivy-dev Google Group](#).

15.3 Discord

Kivy on Discord at <https://chat.kivy.org>

Discord is great for real-time communication, but please make sure to [wait](#) after you asked your question. If you just join, ask and quit we have [no way](#) of knowing who you were and where we're supposed to send our answer. Also, keep in mind we're mostly based in Europe, so take into account any timezone issues. If you're unlucky more than once, try the mailing list.

If you don't have the Discord app, you can also use [Discord's web client](#), but please, don't leave too soon. Just make sure to ask on the [support](#) channels.

Please read our [Community Guidelines](#) before asking for help on the mailing list or Discord channel.

Part III

PROGRAMMING GUIDE

KIVY BASICS

16.1 Installation of the Kivy environment

Kivy depends on many libraries, such as SDL2, gstreamer, PIL, Cairo, and more. They are not all required, but depending on the platform you're working on, they can be a pain to install. To ease your development process, we provide pre-packaged binaries for Windows, macOS and Linux.

Have a look at one of these pages for detailed installation instructions:

- [installation_windows](#)
- [installation_osx](#)
- [installation_linux](#)
- [installation_rpi](#)

Alternatively, instructions for the development version can be found here:

- [*Development install*](#)

16.2 Create an application

Creating a kivy application is as simple as:

- sub-classing the [App](#) class
- implementing its [build\(\)](#) method so it returns a [Widget](#) instance (the root of your widget tree)
- instantiating this class, and calling its [run\(\)](#) method.

Here is an example of a minimal application:

```
import kivy
kivy.require('2.1.0') # replace with your current kivy version !

from kivy.app import App
from kivy.uix.label import Label


class MyApp(App):

    def build(self):
        return Label(text='Hello world')
```

(continues on next page)


(continued from previous page)

```
if __name__ == '__main__':
    MyApp().run()
```

You can save this to a text file, *main.py* for example, and run it.

16.3 Kivy App Life Cycle

First off, let's get familiar with the Kivy app life cycle.



As you can see above, for all intents and purposes, our entry point into our App is the `run()` method, and in our case that is “`MyApp().run()`”. We will get back to this, but let’s start from the line:

```
from kivy.app import App
```

It’s required that the base Class of your App inherits from the `App` class. It’s present in the `kivy_installation_dir/kivy/app.py`.

Note: Go ahead and open up that file if you want to delve deeper into what the Kivy App class does. We encourage you to open the code and read through it. Kivy is based on Python and uses Sphinx for documentation, so the documentation for each class is in the actual file.

Similarly on line 5:

```
from kivy.uix.label import Label
```

One important thing to note here is the way packages/classes are laid out. The *uix* module is the section that holds the user interface elements like layouts and widgets.

Moving on to line 8:

```
class MyApp(App):
```

This is where we are *defining* the Base Class of our Kivy App. You should only ever need to change the name of your app *MyApp* in this line.

Further on to line 10:

```
def build(self):
```

As highlighted by the image above, show casing the *Kivy App Life Cycle*, this is the function where you should initialize and return your *Root Widget*. This is what we do on line 11:

```
return Label(text='Hello world')
```

Here we initialize a Label with text 'Hello World' and return its instance. This Label will be the Root Widget of this App.

Note: Python uses indentation to denote code blocks, therefore take note that in the code provided above, at line 11 the class and function definition ends.

Now on to the portion that will make our app run at line 14 and 15:

```
if __name__ == '__main__':
    MyApp().run()
```

Here the class *MyApp* is initialized and its *run()* method called. This initializes and starts our Kivy application.

16.4 Running the application

To run the application, follow the instructions for your operating system:

For Windows, Linux, macOS, or the RPi. From the *terminal* where you installed Kivy simply run:

```
python main.py
```

For Android or iOS, your application needs some complementary files to be able to run. See *Create a package for Android* or See *Create a package for iOS* for further reference.

A window should open, showing a single Label (with the Text 'Hello World') that covers the entire window's area. That's all there is to it.



16.5 Customize the application

Lets extend this application a bit, say a simple UserName/Password page.

```
from kivy.app import App
from kivy.uix.gridlayout import GridLayout
from kivy.uix.label import Label
from kivy.uix.textinput import TextInput

class LoginScreen(GridLayout):

    def __init__(self, **kwargs):
        super(LoginScreen, self).__init__(**kwargs)
        self.cols = 2
        self.add_widget(Label(text='User Name'))
        self.username = TextInput(multiline=False)
        self.add_widget(self.username)
        self.add_widget(Label(text='password'))
        self.password = TextInput(password=True, multiline=False)
        self.add_widget(self.password)

class MyApp(App):

    def build(self):
        return LoginScreen()

if __name__ == '__main__':
    MyApp().run()
```

At line 2 we import a Gridlayout:

```
from kivy.uix.gridlayout import GridLayout
```

This class is used as a Base for our Root Widget (LoginScreen) defined at line 7:

```
class LoginScreen(GridLayout):
```

At line 9 in the class LoginScreen, we override the method `__init__()` so as to add widgets and to define their behavior:

```
def __init__(self, **kwargs):
    super(LoginScreen, self).__init__(**kwargs)
```

One should not forget to call `super` in order to implement the functionality of the original class being overloaded. Also note that it is good practice not to omit the `**kwargs` while calling `super`, as they are sometimes used internally.

Moving on to Line 11 and beyond:

```
self.cols = 2
self.add_widget(Label(text='User Name'))
self.username = TextInput(multiline=False)
self.add_widget(self.username)
self.add_widget(Label(text='password'))
self.password = TextInput(password=True, multiline=False)
self.add_widget(self.password)
```

We ask the `GridLayout` to manage its children in two columns and add a `Label` and a `TextInput` for the username and password.

Running the above code will give you a window that should look like this:



Try re-sizing the window and you will see that the widgets on screen adjust themselves according to the size of the window without you having to do anything. This is because widgets use size hinting by default.

The code above doesn't handle the input from the user, does no validation or anything else. We will delve deeper into this and `Widget` size and positioning in the coming sections.

CONTROLLING THE ENVIRONMENT

Many environment variables are available to control the initialization and behavior of Kivy.

For example, in order to restrict text rendering to the PIL implementation:

```
$ KIVY_TEXT=pil python main.py
```

Environment variables should be set before importing kivy:

```
import os
os.environ['KIVY_TEXT'] = 'pil'
import kivy
```

17.1 Path control

New in version 1.0.7.

You can control the default directories where config files, modules and kivy data are located.

KIVY_DATA_DIR Location of the Kivy data, defaults to *<kivy path>/data*

KIVY_MODULES_DIR Location of the Kivy modules, defaults to *<kivy path>/modules*

KIVY_HOME Location of the Kivy home. This directory is used for local configuration, and must be in a writable location.

Defaults to:

- Desktop: *<user home>/.kivy*
- Android: *<android app path>/.kivy*
- iOS: *<user home>/Documents/.kivy*

New in version 1.9.0.

KIVY SDL2_PATH If set, the SDL2 libraries and headers from this path are used when compiling kivy instead of the ones installed system-wide. To use the same libraries while running a kivy app, this path must be added at the start of the PATH environment variable.

New in version 1.9.0.

Warning: This path is required for the compilation of Kivy. It is not required for program execution.

17.2 Configuration

KIVY_USE_DEFAULTCONFIG If this name is found in environ, Kivy will not read the user config file.

KIVY_NO_CONFIG If set, no configuration file will be read or written to. This also applies to the user configuration directory.

KIVY_NO_FILELOG If set, logs will not print to a file

KIVY_NO_CONSOLELOG If set, logs will not print to the console

KIVY_NO_ARGS If set to one of ('true', '1', 'yes'), the argument passed in command line will not be parsed and used by Kivy. Ie, you can safely make a script or an app with your own arguments without requiring the – delimiter:

```
import os
os.environ["KIVY_NO_ARGS"] = "1"
import kivy
```

New in version 1.9.0.

KCFG_section_key If a such format environment name is detected, it will be mapped to the Config object. They are loaded only once when *kivy* is imported. The behavior can be disabled using **KIVY_NO_ENV_CONFIG**.

```
import os
os.environ["KCFG_KIVY_LOG_LEVEL"] = "warning"
import kivy
# during import it will map it to:
# Config.set("kivy", "log_level", "warning")
```

New in version 1.11.0.

KIVY_NO_ENV_CONFIG If set, no environment key will be mapped to configuration object. If unset, any *KCFG_section_key=value* will be mapped to Config.

New in version 1.11.0.

17.3 Restrict core to specific implementation

kivy.core try to select the best implementation available for your platform. For testing or custom installation, you might want to restrict the selector to a specific implementation.

KIVY_WINDOW Implementation to use for creating the Window

Values: sdl2, pygame, x11, egl_rpi

KIVY_TEXT Implementation to use for rendering text

Values: sdl2, pil, pygame, sdlttf

KIVY_VIDEO Implementation to use for rendering video

Values: gstplayer, ffpyleplayer, ffmpeg, null

KIVY_AUDIO Implementation to use for playing audio

Values: sdl2, gstplayer, ffpyleplayer, pygame, avplayer

KIVY_IMAGE Implementation to use for reading image

Values: sdl2, pil, pygame, imageio, tex, dds

Changed in version 2.0.0.

Removed GPL *gif* implementation

KIVY_CAMERA Implementation to use for reading camera

Values: avfoundation, android, opencv

KIVY SPELLING Implementation to use for spelling

Values: enchant, osxappkit

KIVY_CLIPBOARD Implementation to use for clipboard management

Values: sdl2, pygame, dummy, android

17.4 Metrics

KIVY_DPI If set, the value will be used for `Metrics.dpi`.

New in version 1.4.0.

KIVY_METRICS_DENSITY If set, the value will be used for `Metrics.density`.

New in version 1.5.0.

KIVY_METRICS_FONTSIZE

If set, the value will be used for `Metrics.fontsize`.

New in version 1.5.0.

17.5 Graphics

KIVY_GL_BACKEND The OpenGL backend to use. See [cgl](#).

KIVY_GL_DEBUG Whether to log OpenGL calls. See [cgl](#).

KIVY_GRAPHICS Whether to use OpenGL ES2. See [cgl](#).

KIVY_GLES_LIMITS Whether the GLES2 restrictions are enforced (the default, or if set to 1). If set to false, Kivy will not be truly GLES2 compatible.

Following is a list of the potential incompatibilities that result when set to true.

Mesh in- dices	If true, the number of indices in a mesh is limited to 65535
Tex- ture blit	When blitting to a texture, the data (color and buffer) format must be the same format as the one used at the texture creation. On desktop, the conversion of different color is correctly handled by the driver, while on Android, most of devices fail to do it. Ref: https://github.com/kivy/kivy/issues/1600

New in version 1.8.1.

KIVY_BCM_DISPMANX_ID Change the default Raspberry Pi display to use. The list of available value is accessible in `vc_dispmanx_types.h`. Default value is 0:

- 0: `DISPMANX_ID_MAIN_LCD`

- 1: DISPMANX_ID_AUX_LCD
- 2: DISPMANX_ID_HDMI
- 3: DISPMANX_ID_SDTV
- 4: DISPMANX_ID_FORCE_LCD
- 5: DISPMANX_ID_FORCE_TV
- 6: DISPMANX_ID_FORCE_OTHER

KIVY_BCM_DISPMANX_LAYER Change the default Raspberry Pi dispmanx layer. Default value is 0.

New in version 1.10.1.

17.6 Event Loop

KIVY_EVENTLOOP Which async library should be used when the app is run in an asynchronous manner. See [kivy.app](#) for example usage.

'asyncio': When the app is run in an asynchronous manner and the standard library `asyncio` package should be used. The default if not set.

'trio': When the app is run in an asynchronous manner and the `trio` package should be used.

New in version 2.0.0.

CONFIGURE KIVY

The configuration file for kivy is named *config.ini*, and adheres to the **standard INI** format.

18.1 Locating the configuration file

The location of the configuration file is controlled by the environment variable *KIVY_HOME*:

```
<KIVY_HOME>/config.ini
```

On desktop, this defaults to:

```
<HOME_DIRECTORY>/.kivy/config.ini
```

Therefore, if your user is named “tito”, the file will be here:

- Windows: C:\Users\tito\.kivy\config.ini
- macOS: /Users/tito/.kivy/config.ini
- Linux: /home/tito/.kivy/config.ini

On Android, this defaults to:

```
<ANDROID_APP_PATH>/.kivy/config.ini
```

If your app is named “org.kivy.launcher”, the file will be here:

```
/data/data/org.kivy.launcher/files/.kivy/config.ini
```

On iOS, this defaults to:

```
<HOME_DIRECTORY>/Documents/.kivy/config.ini
```

18.2 Local configuration

Sometimes it’s desired to change configuration only for certain applications or during testing of a separate part of Kivy for example input providers. To create a separate configuration file you can simply use these commands:

```
from kivy.config import Config  
Config.read(<file>)
```

(continues on next page)

(continued from previous page)

```
# set config  
Config.write()
```

When a local configuration of single `.ini` file isn't enough, e.g. when you want to have separate environment for `garden`, kivy logs and other things, you'll need to change the `KIVY_HOME` environment variable in your application to get desired result:

```
import os  
os.environ['KIVY_HOME'] = <folder>
```

or before each run of the application change it manually in the console:

1. Windows:

```
set KIVY_HOME=<folder>
```

2. Linux & OSX:

```
export KIVY_HOME=<folder>
```

After the change of `KIVY_HOME`, the folder will behave exactly the same as the default `.kivy/` folder mentioned above.


18.3 Understanding config tokens

All the configuration tokens are explained in the `kivy.config` module.

ARCHITECTURAL OVERVIEW

We would like to take a moment to explain how we designed Kivy from a software engineering point of view. This is key to understanding how everything works together. If you just look at the code, chances are you will get a rough idea already, but since this approach certainly is daunting for most users, this section explains the basic ideas of the implementation in more detail. You can skip this section and refer to it later, but we suggest at least skimming it for a rough overview.

Kivy consists of several building blocks that we will explain shortly. Here is a graphical summary of the architecture:



19.1 Core Providers and Input Providers

One idea that is key to understanding Kivy's internals is that of modularity and abstraction. We try to abstract basic tasks such as opening a window, displaying images and text, playing audio, getting images from a camera, spelling correction and so on. We call these *core* tasks. This makes the API both easy to use and easy to extend. Most importantly, it allows us to use – what we call – specific providers for the respective scenarios in which your app is being run. For example, on macOS, Linux and Windows, there are different native APIs for the different core tasks. A piece of code that uses one of these specific APIs to talk to the operating system on one side and to Kivy on the other (acting as an intermediate communication layer) is what we call a *core provider*. The advantage of using specialized core providers for each platform is that we can fully leverage the functionality exposed by the operating system and act as efficiently as possible. It also gives users a choice. Furthermore, by using libraries that are shipped with any one platform, we effectively reduce the size of the Kivy distribution and make packaging easier. This also makes it easier to port Kivy to other platforms. The Android port benefited greatly from this.

We follow the same concept with input handling. An *input provider* is a piece of code that adds support for a specific input device, such as Apple's trackpads, TUIO or a mouse emulator. If you need to add support for a new input device, you can simply provide a new class that reads your input data from your device and transforms them into Kivy basic events.

19.2 Graphics

Kivy's graphics API is our abstraction of OpenGL. On the lowest level, Kivy issues hardware-accelerated drawing commands using OpenGL. Writing OpenGL code however can be a bit confusing, especially to newcomers. That's why we provide the graphics API that lets you draw things using simple metaphors that do not exist as such in OpenGL (e.g. Canvas, Rectangle, etc.).

All of our widgets themselves use this graphics API, which is implemented on the C level for performance reasons.

Another advantage of the graphics API is its ability to automatically optimize the drawing commands that your code issues. This is especially helpful if you're not an expert at tuning OpenGL. This makes your drawing code more efficient in many cases.

You can, of course, still use raw OpenGL commands if you prefer. The version we target is OpenGL 2.0 ES (GLES2) on all devices, so if you want to stay cross-platform compatible, we advise you to only use the GLES2 functions.

19.3 Core

The code in the core package provides commonly used features, such as:

Clock You can use the clock to schedule timer events. Both one-shot timers and periodic timers are supported.

Cache If you need to cache something that you use often, you can use our class for that instead of writing your own.

Gesture Detection We ship a simple gesture recognizer that you can use to detect various kinds of strokes, such as circles or rectangles. You can train it to detect your own strokes.

Kivy Language The kivy language is used to easily and efficiently describe user interfaces.

Properties These are not the normal properties that you may know from python. They are our own property classes that link your widget code with the user interface description.

19.4 UIX (Widgets & Layouts)

The UIX module contains commonly used widgets and layouts that you can reuse to quickly create a user interface.

Widgets Widgets are user interface elements that you add to your program to provide some kind of functionality. They may or may not be visible. Examples would be a file browser, buttons, sliders, lists and so on. Widgets receive MotionEvents.

Layouts You use layouts to arrange widgets. It is of course possible to calculate your widgets' positions yourself, but often it is more convenient to use one of our ready made layouts. Examples would be Grid Layouts or Box Layouts. You can also nest layouts.

19.5 Modules

If you've ever used a modern web browser and customized it with some add-ons then you already know the basic idea behind our module classes. Modules can be used to inject functionality into Kivy programs, even if the original author did not include it.

An example would be a module that always shows the FPS of the current application and some graph depicting the FPS over time.

You can also write your own modules.

19.6 Input Events (Touches)

Kivy abstracts different input types and sources such as touches, mice, TUIO or similar. What all of these input types have in common is that you can associate a 2D onscreen-position with any individual input event. (There are other input devices such as accelerometers where you cannot easily find a 2D position for e.g. a tilt of your device. This kind of input is handled separately. In the following we describe the former types.)

All of these input types are represented by instances of the Touch() class. (Note that this does not only refer to finger touches, but all the other input types as well. We just called it *Touch* for the sake of simplicity. Think of it of something that *touches* the user interface or your screen.) A touch instance, or object, can be in one of three states. When a touch enters one of these states, your program is informed that the event occurred. The three states a touch can be in are:

Down A touch is down only once, at the very moment where it first appears.

Move A touch can be in this state for a potentially unlimited time. A touch does not have to be in this state during its lifetime. A 'Move' happens whenever the 2D position of a touch changes.

Up A touch goes up at most once, or never. In practice you will almost always receive an up event because nobody is going to hold a finger on the screen for all eternity, but it is not guaranteed. If you know the input sources your users will be using, you will know whether or not you can rely on this state being entered.

19.7 Widgets and Event Dispatching

The term *widget* is often used in GUI programming contexts to describe some part of the program that the user interacts with. In Kivy, a widget is an object that receives input events. It does not necessarily have to have a visible representation on the screen. All widgets are arranged in a *widget tree* (which is a tree data structure as known from computer science classes): One widget can have any number of child widgets or none. There is exactly one *root widget* at the top of the tree that has no parent widget, and all other widgets are directly or indirectly children of this widget (which is why it's called the root).

When new input data is available, Kivy sends out one event per touch. The root widget of the widget tree first receives the event. Depending on the state of the touch, the `on_touch_down`, `on_touch_move` or `on_touch_up` event is dispatched (with the touch as the argument) to the root widget, which results in the root widget's corresponding `on_touch_down`, `on_touch_move` or `on_touch_up` event handler being called.

Each widget (this includes the root widget) in the tree can choose to either digest or pass the event on. If an event handler returns True, it means that the event has been digested and handled properly. No further processing will happen with that event. Otherwise, the event handler passes the widget on to its own children by calling its superclass's implementation of the respective event handler. This goes all the way up to the base Widget class, which – in its touch event handlers – does nothing but pass the touches to its children:

```
# This is analogous for move/up:  
def on_touch_down(self, touch):  
    for child in self.children[:]:  
        if child.dispatch('on_touch_down', touch):  
            return True
```


This really is much easier than it first seems. An example of how this can be used to create nice applications quickly will be given in the following section.

Often times you will want to restrict the *area* on the screen that a widget watches for touches. You can use a widget's `collide_point()` method to achieve this. You simply pass it the touch's position and it returns True if the touch is within the 'watched area' or False otherwise. By default, this checks the rectangular region on the screen that's described by the widget's pos (for position; x & y) and size (width & height), but you can override this behaviour in your own class.

EVENTS AND PROPERTIES

Events are an important part of Kivy programming. That may not be surprising to those with GUI development experience, but it's an important concept for newcomers. Once you understand how events work and how to bind to them, you will see them everywhere in Kivy. They make it easy to build whatever behavior you want into Kivy.

The following illustration shows how events are handled in the Kivy framework.



20.1 Introduction to the Event Dispatcher

One of the most important base classes of the framework is the `EventDispatcher` class. This class allows you to register event types, and to dispatch them to interested parties (usually other event dispatchers). The `Widget`, `Animation` and `Clock` classes are examples of event dispatchers.

`EventDispatcher` objects depend on the main loop to generate and handle events.

20.2 Main loop

As outlined in the illustration above, Kivy has a *main loop*. This loop is running during all of the application's lifetime and only quits when exiting the application.

Inside the loop, at every iteration, events are generated from user input, hardware sensors or a couple of other sources, and frames are rendered to the display.

Your application will specify callbacks (more on this later), which are called by the main loop. If a callback takes too long or doesn't quit at all, the main loop is broken and your app doesn't work properly anymore.

In Kivy applications, you have to avoid long/infinite loops or sleeping. For example the following code does both:

```
while True:  
    animate_something()  
    time.sleep(.10)
```

When you run this, the program will never exit your loop, preventing Kivy from doing all of the other things that need doing. As a result, all you'll see is a black window which you won't be able to interact with. Instead, you need to "schedule" your `animate_something()` function to be called repeatedly.

20.2.1 Scheduling a repetitive event

You can call a function or a method every X times per second using `schedule_interval()`. Here is an example of calling a function named `my_callback` 30 times per second:

```
def my_callback(dt):  
    print('My callback is called', dt)  
event = Clock.schedule_interval(my_callback, 1 / 30.)
```

You have multiple ways of unscheduling a previously scheduled event. One, is to use `cancel()` or `unschedule()`:

```
event.cancel()
```

or:

```
Clock.unschedule(event)
```

Alternatively, you can return False in your callback, and your event will be automatically unscheduled:

```
count = 0  
def my_callback(dt):  
    global count  
    count += 1
```

(continues on next page)

```

if count == 10:
    print('Last call of my callback, bye bye !')
    return False
print('My callback is called')
Clock.schedule_interval(my_callback, 1 / 30.)

```

20.2.2 Scheduling a one-time event

Using `schedule_once()`, you can call a function “later”, like in the next frame, or in X seconds:

```

def my_callback(dt):
    print('My callback is called !')
Clock.schedule_once(my_callback, 1)

```

This will call `my_callback` in one second. The second argument is the amount of time to wait before calling the function, in seconds. However, you can achieve some other results with special values for the second argument:

- If X is greater than 0, the callback will be called in X seconds
- If X is 0, the callback will be called after the next frame
- If X is -1, the callback will be called before the next frame

The -1 is mostly used when you are already in a scheduled event, and if you want to schedule a call BEFORE the next frame is happening.

A second method for repeating a function call is to first schedule a callback once with `schedule_once()`, and a second call to this function inside the callback itself:

```

def my_callback(dt):
    print('My callback is called !')
    Clock.schedule_once(my_callback, 1)
Clock.schedule_once(my_callback, 1)

```

Warning: While the main loop will try to keep to the schedule as requested, there is some uncertainty as to when exactly a scheduled callback will be called. Sometimes another callback or some other task in the application will take longer than anticipated and thus the timing can be a little off.

In the latter solution to the repetitive callback problem, the next iteration will be called at least one second after the last iteration ends. With `schedule_interval()` however, the callback is called every second.

20.2.3 Trigger events

Sometimes you may want to schedule a function to be called only once for the next frame, preventing duplicate calls. You might be tempted to achieve that like so:

```

# First, schedule once.
event = Clock.schedule_once(my_callback, 0)

# Then, in another place you will have to unschedule first
# to avoid duplicate call. Then you can schedule again.

```

(continues on next page)

```
Clock.unschedule(event)
event = Clock.schedule_once(my_callback, 0)
```

This way of programming a trigger is expensive, since you'll always call unschedule, even if the event has already completed. In addition, a new event is created every time. Use a trigger instead:

```
trigger = Clock.create_trigger(my_callback)
# later
trigger()
```

Each time you call trigger(), it will schedule a single call of your callback. If it was already scheduled, it will not be rescheduled.

20.3 Widget events

A widget has 2 default types of events:

- Property event: if your widget changes its position or size, an event is fired.
- Widget-defined event: e.g. an event will be fired for a Button when it's pressed or released.

For a discussion on how widget touch events are managed and propagated, please refer to the [Widget touch event bubbling](#) section.

20.4 Creating custom events

To create an event dispatcher with custom events, you need to register the name of the event in the class and then create a method of the same name.

See the following example:

```
class MyEventDispatcher(EventDispatcher):
    def __init__(self, **kwargs):
        self.register_event_type('on_test')
        super(MyEventDispatcher, self).__init__(**kwargs)

    def do_something(self, value):
        # when do_something is called, the 'on_test' event will be
        # dispatched with the value
        self.dispatch('on_test', value)

    def on_test(self, *args):
        print("I am dispatched", args)
```

20.5 Attaching callbacks

To use events, you have to bind callbacks to them. When the event is dispatched, your callbacks will be called with the parameters relevant to that specific event.

A callback can be any python callable, but you need to ensure it accepts the arguments that the event emits. For this, it's usually safest to accept the `*args` argument, which will catch all arguments in the `args` list.

Example:

```
def my_callback(value, *args):
    print("Hello, I got an event!", args)

ev = MyEventDispatcher()
ev.bind(on_test=my_callback)
ev.do_something('test')
```

Please refer to the `kivy.event.EventDispatcher.bind()` method documentation for more examples on how to attach callbacks.

20.6 Introduction to Properties

Properties are an awesome way to define events and bind to them. Essentially, they produce events such that when an attribute of your object changes, all properties that reference that attribute are automatically updated.

There are different kinds of properties to describe the type of data you want to handle.

- `StringProperty`
- `NumericProperty`
- `BoundedNumericProperty`
- `ObjectProperty`
- `DictProperty`
- `ListProperty`
- `OptionProperty`
- `AliasProperty`
- `BooleanProperty`
- `ReferenceListProperty`

20.7 Declaration of a Property

To declare properties, you must declare them at the class level. The class will then do the work to instantiate the real attributes when your object is created. These properties are not attributes: they are mechanisms for creating events based on your attributes:

```
class MyWidget(Widget):
    text = StringProperty('')
```

When overriding `__init__`, always accept `**kwargs` and use `super()` to call the parent's `__init__` method, passing in your class instance:

```
def __init__(self, **kwargs):
    super(MyWidget, self).__init__(**kwargs)
```

20.8 Dispatching a Property event

Kivy properties, by default, provide an `on_<property_name>` event. This event is called when the value of the property is changed.

Note: If the new value for the property is equal to the current value, then the `on_<property_name>` event will not be called.

For example, consider the following code:

```
1  class CustomBtn(Widget):
2
3      pressed = ListProperty([0, 0])
4
5      def on_touch_down(self, touch):
6          if self.collide_point(*touch.pos):
7              self.pressed = touch.pos
8              return True
9      return super(CustomBtn, self).on_touch_down(touch)
10
11     def on_pressed(self, instance, pos):
12         print('pressed at {}'.format(pos=pos))
```

In the code above at line 3:

```
pressed = ListProperty([0, 0])
```

We define the `pressed` Property of type `ListProperty`, giving it a default value of `[0, 0]`. From this point forward, the `on_pressed` event will be called whenever the value of this property is changed.

At Line 5:

```
def on_touch_down(self, touch):
    if self.collide_point(*touch.pos):
        self.pressed = touch.pos
        return True
    return super(CustomBtn, self).on_touch_down(touch)
```

We override the `on_touch_down()` method of the Widget class. Here, we check for collision of the `touch` with our widget.

If the touch falls inside of our widget, we change the value of `pressed` to `touch.pos` and return True, indicating that we have consumed the touch and don't want it to propagate any further.

Finally, if the touch falls outside our widget, we call the original event using `super(...)` and return the result. This allows the touch event propagation to continue as it would normally have occurred.

Finally on line 11:

```
def on_pressed(self, instance, pos):
    print('pressed at {}'.format(pos=pos))
```

We define an `on_pressed` function that will be called by the property whenever the property value is changed.

Note: This `on-<prop_name>` event is called within the class where the property is defined. To monitor/observe any change to a property outside of the class where it's defined, you should bind to the property as shown below.

Binding to the property

How to monitor changes to a property when all you have access to is a widget instance? You *bind* to the property:

```
your_widget_instance.bind(property_name=function_name)
```

For example, consider the following code:

```
1  class RootWidget(BoxLayout):
2
3      def __init__(self, **kwargs):
4          super(RootWidget, self).__init__(**kwargs)
5          self.add_widget(Button(text='btn 1'))
6          cb = CustomBtn()
7          cb.bind(pressed=self.btn_pressed)
8          self.add_widget(cb)
9          self.add_widget(Button(text='btn 2'))
10
11     def btn_pressed(self, instance, pos):
12         print('pos: printed from root widget: {}'.format(pos=pos))
```

If you run the code as is, you will notice two print statements in the console. One from the `on_pressed` event that is called inside the `CustomBtn` class and another from the `btn_pressed` function that we bind to the property change.

The reason that both functions are called is simple. Binding doesn't mean overriding. Having both of these functions is redundant and you should generally only use one of the methods of listening/reacting to property changes.

You should also take note of the parameters that are passed to the `on-<property_name>` event or the function bound to the property.

```
def btn_pressed(self, instance, pos):
```

The first parameter is `self`, which is the instance of the class where this function is defined. You can use an in-line function as follows:

```

1 cb = CustomBtn()
2
3 def _local_func(instance, pos):
4     print('pos: printed from root widget: {}'.format(pos=pos))
5
6 cb.bind(pressed=_local_func)
7 self.add_widget(cb)

```

The first parameter would be the *instance* of the class the property is defined.

The second parameter would be the *value*, which is the new value of the property.

Here is the complete example, derived from the snippets above, that you can use to copy and paste into an editor to experiment.

```

1 from kivy.app import App
2 from kivy.uix.widget import Widget
3 from kivy.uix.button import Button
4 from kivy.uix.boxlayout import BoxLayout
5 from kivy.properties import ListProperty
6
7 class RootWidget(BoxLayout):
8
9     def __init__(self, **kwargs):
10         super(RootWidget, self).__init__(**kwargs)
11         self.add_widget(Button(text='btn 1'))
12         cb = CustomBtn()
13         cb.bind(pressed=self.btn_pressed)
14         self.add_widget(cb)
15         self.add_widget(Button(text='btn 2'))
16
17     def btn_pressed(self, instance, pos):
18         print('pos: printed from root widget: {}'.format(pos=pos))
19
20 class CustomBtn(Widget):
21
22     pressed = ListProperty([0, 0])
23
24     def on_touch_down(self, touch):
25         if self.collide_point(*touch.pos):
26             self.pressed = touch.pos
27             # we consumed the touch. return False here to propagate
28             # the touch further to the children.
29             return True
30     return super(CustomBtn, self).on_touch_down(touch)
31
32     def on_pressed(self, instance, pos):
33         print('pressed at {}'.format(pos=pos))
34
35 class TestApp(App):
36
37     def build(self):
38         return RootWidget()
39

```

(continues on next page)

```
41 if __name__ == '__main__':
42     TestApp().run()
```

Running the code above will give you the following output:



Our CustomBtn has no visual representation and thus appears black. You can touch/click on the black area to see the output on your console.

20.9 Compound Properties

When defining an *AliasProperty*, you normally define a getter and a setter function yourself. Here, it falls on to you to define when the getter and the setter functions are called using the *bind* argument.

Consider the following code.

```
1 cursor_pos = AliasProperty(_get_cursor_pos, None,
2                             bind=('cursor', 'padding', 'pos', 'size',
3                                   'focus', 'scroll_x', 'scroll_y',
4                                   'line_height', 'line_spacing'),
5                             cache=True)
6 '''Current position of the cursor, in (x, y).
7
8 :attr:`cursor_pos` is an :class:`~kivy.properties.AliasProperty`,
9 read-only.
10'''
```

Here *cursor_pos* is a *AliasProperty* which uses the *getter _get_cursor_pos* with the *setter* part set to *None*, implying this is a read only Property.

The *bind* argument at the end defines that *on_cursor_pos* event is dispatched when any of the properties used in the *bind=* argument change.

INPUT MANAGEMENT

21.1 Input architecture

Kivy is able to handle most types of input: mouse, touchscreen, accelerometer, gyroscope, etc. It handles the native multitouch protocols on the following platforms: Tuio, WM_Touch, MacMultitouchSupport, MT Protocol A/B and Android.

The global architecture can be viewed as:

```
Input providers -> Motion event -> Post processing -> Dispatch to Window
```

The class of all input events is the *MotionEvent*. It generates 2 kinds of events:

- Touch events: a motion event that contains at least an X and Y position. All the touch events are dispatched across the Widget tree.
- No-touch events: all the rest. For example, the accelerometer is a continuous event, without position. It never starts or stops. These events are not dispatched across the Widget tree.

A Motion event is generated by an *Input Provider*. An Input Provider is responsible for reading the input event from the operating system, the network or even from another application. Several input providers exist, such as:

- *TuioMotionEventProvider*: create a UDP server and listen for TUIO/OSC messages.
- *WM_MotionEventProvider*: use the windows API for reading multitouch information and sending it to Kivy.
- *ProbeSysfsHardwareProbe*: In Linux, iterate over all the hardware connected to the computer, and attaches a multitouch input provider for each multitouch device found.
- and much more!

When you write an application, you don't need to create an input provider. Kivy tries to automatically detect available hardware. However, if you want to support custom hardware, you will need to configure kivy to make it work.

Before the newly-created Motion Event is passed to the user, Kivy applies post-processing to the input. Every motion event is analyzed to detect and correct faulty input, as well as make meaningful interpretations like:

- Double/triple-tap detection, according to a distance and time threshold
- Making events more accurate when the hardware is not accurate
- Reducing the amount of generated events if the native touch hardware is sending events with nearly the same position

After processing, the motion event is dispatched to the Window. As explained previously, not all events are dispatched to the whole widget tree: the window filters them. For a given event:

- if it's only a motion event, it will be dispatched to `on_motion()`
- if it's a touch event, the (x,y) position of the touch (0-1 range) will be scaled to the Window size (width/height), and dispatched to:
 - `on_touch_down()`
 - `on_touch_move()`
 - `on_touch_up()`

21.2 Motion event profiles

Depending on your hardware and the input providers used, more information may be made available to you. For example, a touch input has an (x,y) position, but might also have pressure information, blob size, an acceleration vector, etc.

A profile is a string that indicates what features are available inside the motion event. Let's imagine that you are in an `on_touch_move` method:

```
def on_touch_move(self, touch):
    print(touch.profile)
    return super(..., self).on_touch_move(touch)
```

The print could output:

```
['pos', 'angle']
```

Warning: Many people mix up the profile's name and the name of the corresponding property. Just because 'angle' is in the available profile doesn't mean that the touch event object will have an `angle` property.

For the 'pos' profile, the properties `pos`, `x`, and `y` will be available. With the 'angle' profile, the property `a` will be available. As we said, for touch events 'pos' is a mandatory profile, but not 'angle'. You can extend your interaction by checking if the 'angle' profile exists:

```
def on_touch_move(self, touch):
    print('The touch is at position', touch.pos)
    if 'angle' in touch.profile:
        print('The touch angle is', touch.a)
```

You can find a list of available profiles in the [motionevent](#) documentation.

21.3 Touch events

A touch event is a specialized `MotionEvent` where the property `is_touch` evaluates to True. For all touch events, you automatically have the X and Y positions available, scaled to the Window width and height. In other words, all touch events have the 'pos' profile.

21.3.1 Touch event basics

By default, touch events are dispatched to all currently displayed widgets. This means widgets receive the touch event whether it occurs within their physical area or not.

This can be counter intuitive if you have experience with other GUI toolkits. These typically divide the screen into geometric areas and only dispatch touch or mouse events to the widget if the coordinate lies within the widgets area.

This requirement becomes very restrictive when working with touch input. Swipes, pinches and long presses may well originate from outside of the widget that wants to know about them and react to them.

In order to provide the maximum flexibility, Kivy dispatches the events to all the widgets and lets them decide how to react to them. If you only want to respond to touch events inside the widget, you simply check:

```
def on_touch_down(self, touch):
    if self.collide_point(*touch.pos):
        # The touch has occurred inside the widgets area. Do stuff!
        pass
```

21.3.2 Coordinates

You must take care of matrix transformation in your touch as soon as you use a widget with matrix transformation. Some widgets such as `Scatter` have their own matrix transformation, meaning the touch must be multiplied by the scatter matrix to be able to correctly dispatch touch positions to the Scatter's children.

- Get coordinate from parent space to local space: `to_local()`
- Get coordinate from local space to parent space: `to_parent()`
- Get coordinate from local space to window space: `to_window()`
- Get coordinate from window space to local space: `to_widget()`

You must use one of them to scale coordinates correctly to the context. Let's look the scatter implementation:

```
def on_touch_down(self, touch):
    # push the current coordinate, to be able to restore it later
    touch.push()

    # transform the touch coordinate to local space
    touch.apply_transform_2d(self.to_local)

    # dispatch the touch as usual to children
    # the coordinate in the touch is now in local space
    ret = super(..., self).on_touch_down(touch)

    # whatever the result, don't forget to pop your transformation
    # after the call, so the coordinate will be back in parent space
    touch.pop()

    # return the result (depending what you want.)
    return ret
```

21.3.3 Touch shapes

If the touch has a shape, it will be reflected in the ‘shape’ property. Right now, only a `ShapeRect` can be exposed:

```
from kivy.input.shape import ShapeRect

def on_touch_move(self, touch):
    if isinstance(touch.shape, ShapeRect):
        print('My touch have a rectangle shape of size',
              (touch.shape.width, touch.shape.height))
    # ...
```

21.3.4 Double tap

A double tap is the action of tapping twice within a time and a distance. It’s calculated by the doubletap post-processing module. You can test if the current touch is one of a double tap or not:

```
def on_touch_down(self, touch):
    if touch.is_double_tap:
        print('Touch is a double tap !')
        print(' - interval is', touch.double_tap_time)
        print(' - distance between previous is', touch.double_tap_distance)
    # ...
```

21.3.5 Triple tap

A triple tap is the action of tapping thrice within a time and a distance. It’s calculated by the tripletap post-processing module. You can test if the current touch is one of a triple tap or not:

```
def on_touch_down(self, touch):
    if touch.is_triple_tap:
        print('Touch is a triple tap !')
        print(' - interval is', touch.triple_tap_time)
        print(' - distance between previous is', touch.triple_tap_distance)
    # ...
```

21.3.6 Grabbing touch events

It’s possible for the parent widget to dispatch a touch event to a child widget from within `on_touch_down`, but not from `on_touch_move` or `on_touch_up`. This can happen in certain scenarios, like when a touch movement is outside the bounding box of the parent, so the parent decides not to notify its children of the movement.

But you might want to do something in `on_touch_up`. Say you started something in the `on_touch_down` event, like playing a sound, and you’d like to finish things on the `on_touch_up` event. Grabbing is what you need.

When you grab a touch, you will always receive the move and up event. But there are some limitations to grabbing:

- You will receive the event at least twice: one time from your parent (the normal event), and one time from the window (grab).

- You might receive an event with a grabbed touch, but not from you: it can be because the parent has sent the touch to its children while it was in the grabbed state.

Here is an example of how to use grabbing:

```
def on_touch_down(self, touch):
    if self.collide_point(*touch.pos):

        # if the touch collides with our widget, let's grab it
        touch.grab(self)

        # and accept the touch.
        return True

def on_touch_up(self, touch):
    # here, you don't check if the touch collides or things like that.
    # you just need to check if it's a grabbed touch event
    if touch.grab_current is self:

        # ok, the current touch is dispatched for us.
        # do something interesting here
        print('Hello world!')

        # don't forget to ungrab ourself, or you might have side effects
        touch.ungrab(self)

        # and accept the last up
        return True
```

21.3.7 Touch Event Management

In order to see how touch events are controlled and propagated between widgets, please refer to the [Widget touch event bubbling](#) section.

21.4 Joystick events

A joystick input represents raw values received directly from physical or virtual controllers through the SDL2 provider via these events:

- `SDL_JOYAXISMOTION`
- `SDL_JOYHATMOTION`
- `SDL_JOYBALLMOTION`
- `SDL_JOYBUTTONDOWN`
- `SDL_JOYBUTTONUP`

Every motion event has a minimum, maximum and default value which can reach:

Event	Minimum	Maximum	Default
<code>on_joy_axis</code>	-32767	32767	0
<code>on_joy_hat</code>	(-1, -1)	(1, 1)	(0, 0)
<code>on_joy_ball</code>	Unknown	Unknown	Unknown

Button events, on the other hand represent basically only a state of each button i.e. *up* and *down*, therefore no such values are present.

- `on_joy_button_up`
- `on_joy_button_down`

21.4.1 Joystick event basics

Unlike touch events, joystick events are dispatched directly to the Window, which means there's only a single value passed for e.g. a specified axis, not multiple ones. This makes things harder if you want to separate input to different widgets, yet not impossible. You can use [Multiple dropfile example](#) as an inspiration.

To get a joystick event, you first need to bind some function to the Window joystick event like this:

```
Window.bind(on_joy_axis=self.on_joy_axis)
```

Then you need to fetch the parameters specified in `Window` for each event you use, for example:

```
def on_joy_axis(self, win, stickid, axisid, value):
    print(win, stickid, axisid, value)
```

A variable `stickid` is an id of a controller that sent the value, `axisid` is an id of an axis to which the value belongs.

21.4.2 Joystick input

Kivy should be able to fetch input from any device specified as `gamepad`, `joystick` or basically any other type of game controller recognized by the SDL2 provider. To make things easier, here are layouts of some common controllers together with ids for each part.

Xbox 360



#	ID	#	ID
1	axis 1	2	axis 0
3	hat Y	4	hat X
5	axis 4	6	axis 3
7	axis 2	8	axis 5
9	button 4	10	button 5
X	button 2	Y	button 3
A	button 0	B	button 1
back	button 6	start	button 7
center	button 10		

21.4.3 Joystick debugging

Mostly you'd want to debug your application with multiple controllers, or test it against `_other_` types of controllers (e.g. different brands). As an alternative you might want to use some of the available controller emulators, such as [vJoy](#).

WIDGETS

22.1 Introduction to Widget

A **Widget** is the base building block of GUI interfaces in Kivy. It provides a **Canvas** that can be used to draw on screen. It receives events and reacts to them. For a in-depth explanation about the **Widget** class, look at the module documentation.

22.2 Manipulating the Widget tree

Widgets in Kivy are organized in trees. Your application has a *root widget*, which usually has **children** that can have **children** of their own. Children of a widget are represented as the **children** attribute, a Kivy **ListProperty**.

The widget tree can be manipulated with the following methods:

- **add_widget()**: add a widget as a child
- **remove_widget()**: remove a widget from the children list
- **clear_widgets()**: remove all children from a widget

For example, if you want to add a button inside a BoxLayout, you can do:

```
layout = BoxLayout(padding=10)
button = Button(text='My first button')
layout.add_widget(button)
```

The button is added to layout: the button's parent property will be set to layout; the layout will have the button added to its children list. To remove the button from the layout:

```
layout.remove_widget(button)
```

With removal, the button's parent property will be set to None, and the layout will have button removed from its children list.

If you want to clear all the children inside a widget, use **clear_widgets()** method:

```
layout.clear_widgets()
```

Warning: Never manipulate the children list yourself, unless you really know what you are doing. The widget tree is associated with a graphic tree. For example, if you add a widget into the

children list without adding its canvas to the graphics tree, the widget will be a child, yes, but nothing will be drawn on the screen. Moreover, you might have issues on further calls of add_widget, remove_widget and clear_widgets.

22.3 Traversing the Tree

The Widget class instance's `children` list property contains all the children. You can easily traverse the tree by doing:

```
root = BoxLayout()  
# ... add widgets to root ...  
for child in root.children:  
    print(child)
```

However, this must be used carefully. If you intend to modify the children list with one of the methods shown in the previous section, you must use a copy of the list like this:

```
for child in root.children[:]:  
    # manipulate the tree. For example here, remove all widgets that have a  
    # width < 100  
    if child.width < 100:  
        root.remove_widget(child)
```

Widgets don't influence the size/pos of their children by default. The `pos` attribute is the absolute position in screen co-ordinates (unless, you use the `relativelayout`. More on that later) and `size`, is an absolute size.

22.4 Widgets Z Index

The order of widget drawing is based on the widget's position in the widget tree. The `add_widget` method takes an `index` parameter which can be used to specify its position in the widget tree:

```
root.add_widget(widget, index)
```

The lower indexed widgets will be drawn above those with a higher index. Keep in mind that the default for `index` is 0, so widgets added later are drawn on top of the others unless specified otherwise.

22.5 Organize with Layouts

`layout` is a special kind of widget that controls the size and position of its children. There are different kinds of layouts, allowing for different automatic organization of their children. Layouts use `size_hint` and `pos_hint` properties to determine the `size` and `pos` of their `children`.

Box Layout

vertical

vertical

Grid Layout

cols = 3	cols = 3	cols = 3
cols = 3	cols = 3	cols = 3
cols = 3	cols = 3	cols = 3
cols = 3	cols = 3	

Stack Layout

bt-rl

bt-rl

bt-rl

bt-rl

bt-rl

bt-rl



BoxLayout: Arranges widgets in an adjacent manner (either vertically or horizontally) manner, to fill all the space. The `size_hint` property of children can be used to change proportions allowed to each child, or set fixed size for some of them.

GridLayout: Arranges widgets in a grid. You must specify at least one dimension of the grid so kivy can compute the size of the elements and how to arrange them.

StackLayout: Arranges widgets adjacent to one another, but with a set size in one of the dimensions, without trying to make them fit within the entire space. This is useful to display children of the same predefined size.

AnchorLayout: A simple layout only caring about children positions. It allows putting the children at a position relative to a border of the layout. `size_hint` is not honored.

FloatLayout: Allows placing children with arbitrary locations and size, either absolute or relative to the layout size. Default `size_hint` (1, 1) will make every child the same size as the whole layout, so you probably want to change this value if you have more than one child. You can set `size_hint` to (None, None) to use absolute size with `size`. This widget honors `pos_hint` also, which as a dict setting position relative to layout position.

RelativeLayout: Behaves just like FloatLayout, except children positions are relative to layout position, not the screen.

Examine the documentation of the individual layouts for a more in-depth understanding.

size_hint and *pos_hint*:

- *floatlayout*
- *boxlayout*
- *gridlayout*
- *stacklayout*
- *relativelayout*
- *anchorlayout*

size_hint is a *ReferenceListProperty* of *size_hint_x* and *size_hint_y*. It accepts values from 0 to 1 or *None* and defaults to (1, 1). This signifies that if the widget is in a layout, the layout will allocate it as much place as possible in both directions (relative to the layouts size).

Setting *size_hint* to (0.5, 0.8), for example, will make the widget 50% the width and 80% the height of available size for the *Widget* inside a *layout*.


Consider the following example:

```
BoxLayout:  
    Button:  
        text: 'Button 1'  
        # default size_hint is 1, 1, we don't need to specify it explicitly  
        # however it's provided here to make things clear  
        size_hint: 1, 1
```

Now load kivy catalog by typing the following, but replacing \$KIVYDIR with the directory of your installation (discoverable via `os.path.dirname(kivy.__file__)`):


```
cd $KIVYDIR/examples/demo/kivycatalog  
python main.py
```

A new window will appear. Click in the area below the 'Welcome' *Spinner* on the left and replace the text there with your kv code from above.




As you can see from the image above, the *Button* takes up 100% of the layout *size*.

Changing the *size_hint_x*/*size_hint_y* to .5 will make the *Widget* take 50% of the *layout width/height*.




You can see here that, although we specify `size_hint_x` and `size_hint_y` both to be .5, only `size_hint_y` seems to be honored. That is because `boxlayout` controls the `size_hint_y` when `orientation` is `vertical` and `size_hint_x` when `orientation` is 'horizontal'. The controlled dimension's size is calculated depending upon the total no. of `children` in the `boxlayout`. In this example, one child has `size_hint_y` controlled ($.5/.5 = 1$). Thus, the widget takes 100% of the parent layout's height.

Let's add another `Button` to the `layout` and see what happens.



boxlayout by its very nature divides the available space between its *children* equally. In our example, the proportion is 50-50, because we have two *children*. Let's use *size_hint* on one of the children and see the results.



If a child specifies `size_hint`, this specifies how much space the `Widget` will take out of the `size` given to it by the `boxlayout`. In our example, the first `Button` specifies .5 for `size_hint_x`. The space for the widget is calculated like so:

```
first child's size_hint divided by
first child's size_hint + second child's size_hint + ...n(no of children)

.5/(.5+1) = .333...
```

The rest of the BoxLayout's `width` is divided among the rest of the `children`. In our example, this means the second `Button` takes up 66.66% of the `layout width`.

Experiment with `size_hint` to get comfortable with it.

If you want to control the absolute `size` of a `Widget`, you can set `size_hint_x`/`size_hint_y` or both to `None` so that the widget's `width` and or `height` attributes will be honored.

`pos_hint` is a dict, which defaults to empty. As for `size_hint`, layouts honor `pos_hint` differently, but generally you can add values to any of the `pos` attributes (`x, y, right, top, center_x, center_y`) to have the `Widget` positioned relative to its `parent`.

Let's experiment with the following code in kivycatalog to understand `pos_hint` visually:

```
FloatLayout:
    Button:
        text: "We Will"
        pos: 100, 100
        size_hint: .2, .4
    Button:
```


(continues on next page)

(continued from previous page)

```
text: "Wee Wiill"
pos: 200, 200
size_hint: .4, .2

Button:
    text: "ROCK YOU!!"
    pos_hint: {'x': .3, 'y': .6}
    size_hint: .5, .2
```

This gives us:



As with `size_hint`, you should experiment with `pos_hint` to understand the effect it has on the widget positions.

22.6 Adding a Background to a Layout

One of the frequently asked questions about layouts is::

"How to add a background image/color/video/... to a Layout"

Layouts by their nature have no visual representation: they have no canvas instructions by default. However you can add canvas instructions to a layout instance easily, as with adding a colored background:

In Python:

```

from kivy.graphics import Color, Rectangle

with layout_instance.canvas.before:
    Color(0, 1, 0, 1) # green; colors range from 0-1 instead of 0-255
    self.rect = Rectangle(size=layout_instance.size,
                          pos=layout_instance.pos)

```

Unfortunately, this will only draw a rectangle at the layout's initial position and size. To make sure the rect is drawn inside the layout, when the layout size/pos changes, we need to listen to any changes and update the rectangles size and pos. We can do that as follows:

```

with layout_instance.canvas.before:
    Color(0, 1, 0, 1) # green; colors range from 0-1 instead of 0-255
    self.rect = Rectangle(size=layout_instance.size,
                          pos=layout_instance.pos)

def update_rect(instance, value):
    instance.rect.pos = instance.pos
    instance.rect.size = instance.size

# listen to size and position changes
layout_instance.bind(pos=update_rect, size=update_rect)

```

In kv:

```

FloatLayout:
    canvas.before:
        Color:
            rgba: 0, 1, 0, 1
        Rectangle:
            # self here refers to the widget i.e FloatLayout
            pos: self.pos
            size: self.size

```

The kv declaration sets an implicit binding: the last two kv lines ensure that the `pos` and `size` values of the rectangle will update when the `pos` of the `floatlayout` changes.

Now we put the snippets above into the shell of Kivy App.

Pure Python way:

```

from kivy.app import App
from kivy.graphics import Color, Rectangle
from kivy.uix.floatlayout import FloatLayout
from kivy.uix.button import Button

class RootWidget(FloatLayout):

    def __init__(self, **kwargs):
        # make sure we aren't overriding any important functionality
        super(RootWidget, self).__init__(**kwargs)

        # let's add a Widget to this layout
        self.add_widget(
            Button(

```

(continues on next page)

(continued from previous page)

```
        text="Hello World",
        size_hint=(.5, .5),
        pos_hint={'center_x': .5, 'center_y': .5}))
```



```
class MainApp(App):

    def build(self):
        self.root = root = RootWidget()
        root.bind(size=self._update_rect, pos=self._update_rect)

        with root.canvas.before:
            Color(0, 1, 0, 1) # green; colors range from 0-1 not 0-255
            self.rect = Rectangle(size=root.size, pos=root.pos)
        return root

    def _update_rect(self, instance, value):
        self.rect.pos = instance.pos
        self.rect.size = instance.size

if __name__ == '__main__':
    MainApp().run()
```

Using the kv Language:

```
from kivy.app import App
from kivy.lang import Builder



root = Builder.load_string('''
FloatLayout:
    canvas.before:
        Color:
            rgba: 0, 1, 0, 1
        Rectangle:
            # self here refers to the widget i.e FloatLayout
            pos: self.pos
            size: self.size
    Button:
        text: 'Hello World!!!'
        size_hint: .5, .5
        pos_hint: {'center_x':.5, 'center_y': .5}
''')

class MainApp(App):

    def build(self):
        return root

if __name__ == '__main__':
    MainApp().run()
```

Both of the Apps should look something like this:



22.6.1 Add a color to the background of a **custom layouts rule/class**

The way we add background to the layout's instance can quickly become cumbersome if we need to use multiple layouts. To help with this, you can subclass the Layout and create your own layout that adds a background.

Using Python:

```
from kivy.app import App
from kivy.graphics import Color, Rectangle
from kivy.uix.boxlayout import BoxLayout
from kivy.uix.floatlayout import FloatLayout
from kivy.uix.image import AsyncImage

class RootWidget(BoxLayout):
    pass

class CustomLayout(FloatLayout):

    def __init__(self, **kwargs):
        # make sure we aren't overriding any important functionality
        super(CustomLayout, self).__init__(**kwargs)
```

(continues on next page)

(continued from previous page)

```
with self.canvas.before:
    Color(0, 1, 0, 1) # green; colors range from 0-1 instead of 0-
→255
    self.rect = Rectangle(size=self.size, pos=self.pos)

    self.bind(size=self._update_rect, pos=self._update_rect)

def _update_rect(self, instance, value):
    self.rect.pos = instance.pos
    self.rect.size = instance.size

class MainApp(App):

    def build(self):
        root = RootWidget()
        c = CustomLayout()
        root.add_widget(c)
        c.add_widget(
            AsyncImage(
                source="http://www.everythingzoomer.com/wp-content/uploads/
→2013/01/Monday-joke-289x277.jpg",
                size_hint= (1, .5),
                pos_hint={'center_x':.5, 'center_y':.5}))
        root.add_widget(AsyncImage(source='http://www.stuffistumbledupon.
→com/wp-content/uploads/2012/05/Have-you-seen-this-dog-because-its-
→awesome-meme-puppy-doggy.jpg'))
        c = CustomLayout()
        c.add_widget(
            AsyncImage(
                source="http://www.stuffistumbledupon.com/wp-content/
→uploads/2012/04/Get-a-Girlfriend-Meme-empty-wallet.jpg",
                size_hint= (1, .5),
                pos_hint={'center_x':.5, 'center_y':.5}))
        root.add_widget(c)
        return root

if __name__ == '__main__':
    MainApp().run()
```

Using the kv Language:

```
from kivy.app import App
from kivy.uix.floatlayout import FloatLayout
from kivy.uix.boxlayout import BoxLayout
from kivy.lang import Builder

Builder.load_string('''
<CustomLayout>
    canvas.before:
        Color:
            rgba: 0, 1, 0, 1
```

(continues on next page)

```

Rectangle:
    pos: self.pos
    size: self.size

<RootWidget>
    CustomLayout:
        AsyncImage:
            source: 'http://www.everythingzoomer.com/wp-content/uploads/
→2013/01/Monday-joke-289x277.jpg'
            size_hint: 1, .5
            pos_hint: {'center_x':.5, 'center_y': .5}
        AsyncImage:
            source: 'http://www.stuffistumbledupon.com/wp-content/uploads/2012/
→05/Have-you-seen-this-dog-because-its-awesome-meme-puppy-doggy.jpg'
        CustomLayout
            AsyncImage:
                source: 'http://www.stuffistumbledupon.com/wp-content/uploads/
→2012/04/Get-a-Girlfriend-Meme-empty-wallet.jpg'
                size_hint: 1, .5
                pos_hint: {'center_x':.5, 'center_y': .5}
    ...)

class RootWidget(BoxLayout):
    pass

class CustomLayout(FloatLayout):
    pass


class MainApp(App):

    def build(self):
        return RootWidget()

if __name__ == '__main__':
    MainApp().run()

```

Both of the Apps should look something like this:



Defining the background in the custom layout class, assures that it will be used in every instance of CustomLayout.

Now, to add an image or color to the background of a built-in Kivy layout, **globally**, we need to override the kv rule for the layout in question. Consider GridLayout:

```
<GridLayout>
    canvas.before:
        Color:
            rgba: 0, 1, 0, 1
        BorderImage:
            source: '../examples/widgets/sequenced_images/data/images/
        ↪button_white.png'
            pos: self.pos
            size: self.size
```

Then, when we put this snippet into a Kivy app:

```
from kivy.app import App
from kivy.uix.floatlayout import FloatLayout
from kivy.lang import Builder

Builder.load_string('''
<GridLayout>
    canvas.before:
        BorderImage:
            # BorderImage behaves like the CSS BorderImage
```

(continues on next page)

(continued from previous page)

```
        border: 10, 10, 10, 10
        source: '../examples/widgets/sequenced_images/data/images/
↳button_white.png'
        pos: self.pos
        size: self.size

<RootWidget>
    GridLayout:
        size_hint: .9, .9
        pos_hint: {'center_x': .5, 'center_y': .5}
        rows:1
        Label:
            text: "I don't suffer from insanity, I enjoy every minute of it
        -->
            text_size: self.width-20, self.height-20
            valign: 'top'
        Label:
            text: "When I was born I was so surprised; I didn't speak for_
↳a year and a half."
            text_size: self.width-20, self.height-20
            valign: 'middle'
            halign: 'center'
        Label:
            text: "A consultant is someone who takes a subject you_
↳understand and makes it sound confusing"
            text_size: self.width-20, self.height-20
            valign: 'bottom'
            halign: 'justify'
    ...)


class RootWidget(FloatLayout):
    pass

class MainApp(App):

    def build(self):
        return RootWidget()

if __name__ == '__main__':
    MainApp().run()
```

The result should look something like this:



As we are overriding the rule of the class GridLayout, any use of this class in our app will display that image.

How about an **Animated background**?

You can set the drawing instructions like Rectangle/BorderImage/Ellipse/... to use a particular texture:

```
Rectangle:  
    texture: reference to a texture
```

We use this to display an animated background:

```
from kivy.app import App  
from kivy.uix.floatlayout import FloatLayout  
from kivy.uix.gridlayout import GridLayout  
from kivy.uix.image import Image  
from kivy.properties import ObjectProperty  
from kivy.lang import Builder  
  
Builder.load_string(''  
<CustomLayout>  
    canvas.before:  
        BorderImage:  
            # BorderImage behaves like the CSS BorderImage  
            border: 10, 10, 10, 10
```

(continues on next page)

```

        texture: self.background_image.texture
        pos: self.pos
        size: self.size

<RootWidget>
    CustomLayout:
        size_hint: .9, .9
        pos_hint: {'center_x': .5, 'center_y': .5}
        rows:1
        Label:
            text: "I don't suffer from insanity, I enjoy every minute of it"
        -->
        text_size: self.width-20, self.height-20
        valign: 'top'
        Label:
            text: "When I was born I was so surprised; I didn't speak for_
→ a year and a half."
        text_size: self.width-20, self.height-20
        valign: 'middle'
        halign: 'center'
        Label:
            text: "A consultant is someone who takes a subject you_
→ understand and makes it sound confusing"
        text_size: self.width-20, self.height-20
        valign: 'bottom'
        halign: 'justify'
    ...)

class CustomLayout(GridLayout):
    background_image = ObjectProperty(
        Image(
            source='../../examples/widgets/sequenced_images/data/images/
→button_white_animated.zip',
            anim_delay=.1))

class RootWidget(FloatLayout):
    pass

class MainApp(App):
    def build(self):
        return RootWidget()

    if __name__ == '__main__':
        MainApp().run()

```

To try to understand what is happening here, start from line 13:

```
texture: self.background_image.texture
```

This specifies that the *texture* property of *BorderImage* will be updated whenever the *texture* property of *background_image* updates. We define the *background_image* property at line 40:

```
background_image = ObjectProperty(...)
```

This sets up *background_image* as an *ObjectProperty* in which we add an *Image* widget. An image widget has a *texture* property; where you see *self.background_image.texture*, this sets a reference, *texture*, to this property. The *Image* widget supports animation: the texture of the image is updated whenever the animation changes, and the texture of *BorderImage* instruction is updated in the process.

You can also just blit custom data to the texture. For details, look at the documentation of *Texture*.

22.7 Nesting Layouts

Yes! It is quite fun to see how extensible the process can be.

22.8 Size and position metrics

Kivy's default unit for length is the pixel, all sizes and positions are expressed in it by default. You can express them in other units, which is useful to achieve better consistency across devices (they get converted to the size in pixels automatically).

Available units are *pt*, *mm*, *cm*, *inch*, *dp* and *sp*. You can learn about their usage in the *metrics* documentation.

You can also experiment with the *screen* usage to simulate various devices screens for your application.

22.9 Screen Separation with Screen Manager

If your application is composed of various screens, you likely want an easy way to navigate from one *Screen* to another. Fortunately, there is the *ScreenManager* class, that allows you to define screens separately, and to set the *TransitionBase* from one to another.

GRAPHICS

23.1 Introduction to Canvas

A Widgets graphical representation is rendered using a canvas, which you can see as both an unlimited drawing board or as a set of drawing instructions. There are numerous instructions you can apply (add) to your canvas, but there are two main variations:

- *context instructions*
- *vertex instructions*

Context instructions don't draw anything, but they change the results of the vertex instructions.

Canvasses can contain two subsets of instructions. They are the *canvas.before* and the *canvas.after* instruction groups. The instructions in these groups will be executed before and after the *canvas* group respectively. This means that they will appear under (be executed before) and above (be executed after) them. Those groups are not created until the user accesses them.

To add a canvas instruction to a widget, you use the canvas context:

```
class MyWidget(Widget):
    def __init__(self, **kwargs):
        super(MyWidget, self).__init__(**kwargs)
        with self.canvas:
            # add your instruction for main canvas here

        with self.canvas.before:
            # you can use this to add instructions rendered before

        with self.canvas.after:
            # you can use this to add instructions rendered after
```

23.2 Context instructions

Context instructions manipulate the opengl context. You can rotate, translate, and scale your canvas. You can also attach a texture or change the drawing color. This one is the most commonly used, but others are really useful too:

```
with self.canvas.before:
    Color(1, 0, .4, mode='rgb')
```

23.3 Drawing instructions

Drawing instructions range from very simple ones, like drawing a line or a polygon, to more complex ones, like meshes or bezier curves:

```
with self.canvas:  
    # draw a line using the default color  
    Line(points=(x1, y1, x2, y2, x3, y3))  
  
    # lets draw a semi-transparent red square  
    Color(1, 0, 0, .5, mode='rgba')  
    Rectangle(pos=self.pos, size=self.size)
```

23.4 Manipulating instructions

Sometimes you want to update or remove the instructions you have added to a canvas. This can be done in various ways depending on your needs:

You can keep a reference to your instructions and update them:

```
class MyWidget(Widget):  
    def __init__(self, **kwargs):  
        super(MyWidget, self).__init__(**kwargs)  
        with self.canvas:  
            self.rect = Rectangle(pos=self.pos, size=self.size)  
  
            self.bind(pos=self.update_rect)  
            self.bind(size=self.update_rect)  
  
    def update_rect(self, *args):  
        self.rect.pos = self.pos  
        self.rect.size = self.size
```

Or you can clean your canvas and start fresh:

```
class MyWidget(Widget):  
    def __init__(self, **kwargs):  
        super(MyWidget, self).__init__(**kwargs)  
        self.draw_my_stuff()  
  
        self.bind(pos=self.draw_my_stuff)  
        self.bind(size=self.draw_my_stuff)  
  
    def draw_my_stuff(self, *args):  
        self.canvas.clear()  
  
        with self.canvas:  
            self.rect = Rectangle(pos=self.pos, size=self.size)
```

Note that updating the instructions is considered the best practice as it involves less overhead and avoids creating new instructions.

KV LANGUAGE

24.1 Concept behind the language

As your application grows more complex, it's common that the construction of widget trees and explicit declaration of bindings becomes verbose and hard to maintain. The *KV Language* is an attempt to overcome these shortcomings.

The *KV language*, sometimes called *kvlang* or the *kivy language*, allows you to create your widget tree in a declarative way and to bind widget properties to each other or to callbacks in a natural manner. It allows for very fast prototypes and agile changes to your UI. It also facilitates separating the logic of your application and its User Interface.

24.2 How to load KV

There are two ways to load Kv code into your application:

- By name convention:

Kivy looks for a Kv file with the same name as your App class in lowercase, minus "App" if it ends with 'App' e.g:

```
MyApp -> my.kv
```

If this file defines a *Root Widget* it will be attached to the App's *root* attribute and used as the base of the application widget tree.

- **Builder:** You can tell Kivy to directly load a string or a file. If this string or file defines a root widget, it will be returned by the method:

```
Builder.load_file('path/to/file.kv')
```

or:

```
Builder.load_string(kv_string)
```

24.3 Rule context

A Kv source constitutes of *rules* which are used to describe the content of a Widget. You can have one *root* rule, and any number of *class* or *template* rules.

The *root* rule is declared by declaring the class of your root widget, without any indentation, followed by : and will be set as the *root* attribute of the App instance:

```
Widget:
```

A *class* rule, declared by the name of a widget class between <> and followed by :, defines the appearance and behavior of any instance of that class:

```
<MyWidget>:
```

Rules use indentation for delimitation, like Python. Indentation should be four spaces per level, like the Python style guide [recommends](#).

There are three keywords specific to the Kv language:

- *app*: always refers to the instance of your application.
- *root*: refers to the base widget/template in the current rule
- *self*: always refer to the current widget

24.4 Special syntax

There is a special syntax to define values for the whole Kv context.

To access Python modules and classes from kv, use #:import

```
#:import name x.y.z
#:import isdir os.path.isdir
#:import np numpy
```

is equivalent to:

```
from x.y import z as name
from os.path import isdir
import numpy as np
```

in Python.

To set a global value, use #:set

```
#:set name value
```

is equivalent to:

```
name = value
```

in Python.

24.5 Instantiate children

To declare a widget instance of some class as a child widget, just declare that child inside the rule:

```
MyWidget:  
    BoxLayout:  
        Button:  
        Button:
```

The example above defines that our root widget, an instance of *MyWidget*, has a child that is an instance of the *BoxLayout*, and that BoxLayout further has two children, instances of the *Button* class.

The Python equivalent of this code might be:

```
root = MyWidget()  
box = BoxLayout()  
box.add_widget(Button())  
box.add_widget(Button())  
root.add_widget(box)
```

Which you may find less nice, both to read and to write.

Of course, in Python, you can pass keyword arguments to your widgets at creation to specify their behaviour. For example, to set the number of columns of a *GridLayout*, we would do:

```
grid = GridLayout(cols=3)
```

To do the same thing in kv, you can set properties of the child widget directly in the rule:

```
GridLayout:  
    cols: 3
```

The value is evaluated as a Python expression, and all the properties used in the expression will be observed, that means that if you had something like this in Python (this assume *self* is a widget with a *data ListProperty*):

```
grid = GridLayout(cols=len(self.data))  
self.bind(data=grid.setter('cols'))
```

To have your display updated when your data change, you can now have just:

```
GridLayout:  
    cols: len(root.data)
```

Note: Widget names should start with upper case letters while property names should start with lower case ones. Following the [PEP8 Naming Conventions](#) is encouraged.

24.6 Event Bindings

You can bind to events in Kv using the ":" syntax, that is, associating a callback to an event:

```
Widget:  
    on_size: my_callback()
```

You can pass the values dispatched by the signal using the *args* keyword:

```
TextInput:  
    on_text: app.search(args[1])
```

More complex expressions can be used, like:

```
pos: self.center_x - self.texture_size[0] / 2., self.center_y - self.  
    ↴ texture_size[1] / 2.
```

This expression listens for a change in `center_x`, `center_y`, and `texture_size`. If one of them changes, the expression will be re-evaluated to update the `pos` field.

You can also handle `on_` events inside your kv language. For example the `TextInput` class has a `focus` property whose auto-generated `on_focus` event can be accessed inside the kv language like so:

```
TextInput:  
    on_focus: print(args)
```

24.7 Extend canvas

Kv lang can be used to define the canvas instructions of your widget like this:

```
MyWidget:  
    canvas:  
        Color:  
            rgba: 1, .3, .8, .5  
        Line:  
            points: zip(self.data.x, self.data.y)
```

And they get updated when properties values change.

Of course you can use `canvas.before` and `canvas.after`.

24.8 Referencing Widgets

In a widget tree there is often a need to access/reference other widgets. The Kv Language provides a way to do this using id's. Think of them as class level variables that can only be used in the Kv language. Consider the following:

```
<MyFirstWidget>:  
    Button:  
        id: f_but  
    TextInput:  
        text: f_but.state
```

(continues on next page)

```
<MySecondWidget>:
    Button:
        id: s_but
    TextInput:
        text: s_but.state
```

An `id` is limited in scope to the rule it is declared in, so in the code above `s_but` can not be accessed outside the `<MySecondWidget>` rule.

Warning: When assigning a value to `id`, remember that the value isn't a string. There are no quotes:
good -> `id: value`, bad -> `id: 'value'`

An `id` is a `weakref` to the widget and not the widget itself. As a consequence, storing the `id` is not sufficient to keep the widget from being garbage collected. To demonstrate:

```
<MyWidget>:
    label_widget: label_widget
    Button:
        text: 'Add Button'
        on_press: root.add_widget(label_widget)
    Button:
        text: 'Remove Button'
        on_press: root.remove_widget(label_widget)
    Label:
        id: label_widget
        text: 'widget'
```

Although a reference to `label_widget` is stored in `MyWidget`, it is not sufficient to keep the object alive once other references have been removed because it's only a `weakref`. Therefore, after the remove button is clicked (which removes any direct reference to the widget) and the window is resized (which calls the garbage collector resulting in the deletion of `label_widget`), when the add button is clicked to add the widget back, a `ReferenceError: weakly-referenced object no longer exists` will be thrown.

To keep the widget alive, a direct reference to the `label_widget` widget must be kept. This is achieved using `id.__self__` or `label_widget.__self__` in this case. The correct way to do this would be:

```
<MyWidget>:
    label_widget: label_widget.__self__
```

24.9 Accessing Widgets defined inside Kv lang in your Python code

Consider the code below in `my.kv`:

```
<MyFirstWidget>:
    # both these variables can be the same name and this doesn't lead to
    # an issue with uniqueness as the id is only accessible in kv.
    txt_inpt: txt_inpt
    Button:
        id: f_but
    TextInput:
```

(continues on next page)

(continued from previous page)

```
    id: txt_inpt
    text: f_but.state
    on_text: root.check_status(f_but)
```

In myapp.py:

```
...
class MyFirstWidget(BoxLayout):
    txt_inpt = ObjectProperty(None)

    def check_status(self, btn):
        print('button state is: {}'.format(state=btn.state))
        print('text input text is: {}'.format(txt=self.txt_inpt))
...

```

txt_inpt is defined as a *ObjectProperty* initialized to *None* inside the Class.

```
txt_inpt = ObjectProperty(None)
```

At this point *self.txt_inpt* is *None*. In Kv lang this property is updated to hold the instance of the *TextInput* referenced by the id *txt_inpt*:

```
txt_inpt: txt_inpt
```

From this point onwards, *self.txt_inpt* holds a reference to the widget identified by the id *txt_input* and can be used anywhere in the class, as in the function *check_status*. In contrast to this method you could also just pass the *id* to the function that needs to use it, like in case of *f_but* in the code above.

There is a simpler way to access objects with *id* tags in Kv using the *ids* lookup object. You can do this as follows:

```
<Marvel>
    Label:
        id: loki
        text: 'loki: I AM YOUR GOD!'
    Button:
        id: hulk
        text: "press to smash loki"
        on_release: root.hulk_smash()
```

In your Python code:

```
class Marvel(BoxLayout):
    def hulk_smash(self):
        self.ids.hulk.text = "hulk: puny god!"
        self.ids["loki"].text = "loki: >_<!!!"
            # alternative syntax
```

When your kv file is parsed, kivy collects all the widgets tagged with *id*'s and places them in this *self.ids* dictionary type property. That means you can also iterate over these widgets and access them dictionary style:

```
for key, val in self.ids.items():
    print("key={0}, val={1}".format(key, val))
```

Note: Although the `self.ids` method is very concise, it is generally regarded as ‘best practice’ to use the `ObjectProperty`. This creates a direct reference, provides faster access and is more explicit.

24.10 Dynamic Classes

Consider the code below:

```
<MyWidget>:  
    Button:  
        text: "Hello world, watch this text wrap inside the button"  
        text_size: self.size  
        font_size: '25sp'  
        markup: True  
    Button:  
        text: "Even absolute is relative to itself"  
        text_size: self.size  
        font_size: '25sp'  
        markup: True  
    Button:  
        text: "Repeating the same thing over and over in a comp = fail"  
        text_size: self.size  
        font_size: '25sp'  
        markup: True  
    Button:
```

Instead of having to repeat the same values for every button, we can just use a template instead, like so:

```
<MyBigButton@Button>:  
    text_size: self.size  
    font_size: '25sp'  
    markup: True  
  
<MyWidget>:  
    MyBigButton:  
        text: "Hello world, watch this text wrap inside the button"  
    MyBigButton:  
        text: "Even absolute is relative to itself"  
    MyBigButton:  
        text: "repeating the same thing over and over in a comp = fail"  
    MyBigButton:
```

This class, created just by the declaration of this rule, inherits from the `Button` class and allows us to change default values and create bindings for all its instances without adding any new code on the Python side.

24.11 Re-using styles in multiple widgets

Consider the code below in my.kv:

```
<MyFirstWidget>:  
    Button:  
        on_press: root.text(txt_inpt.text)  
    TextInput:  
        id: txt_inpt  
  
<MySecondWidget>:  
    Button:  
        on_press: root.text(txt_inpt.text)  
    TextInput:  
        id: txt_inpt
```

In myapp.py:

```
class MyFirstWidget(BoxLayout):  
  
    def text(self, val):  
        print('text input text is: {}'.format(txt=val))  
  
class MySecondWidget(BoxLayout):  
  
    writing = StringProperty('')  
  
    def text(self, val):  
        self.writing = val
```

Because both classes share the same .kv style, this design can be simplified if we reuse that style for both widgets. You can do this in .kv as follows. In my.kv:

```
<MyFirstWidget,MySecondWidget>:  
    Button:  
        on_press: root.text(txt_inpt.text)  
    TextInput:  
        id: txt_inpt
```

By separating the class names with a comma, all the classes listed in the declaration will have the same kv properties.

24.12 Designing with the Kivy Language

One of the aims of the Kivy language is to **separate the concerns** of presentation and logic. The presentation (layout) side is addressed by your .kv file and the logic by your .py file.

24.12.1 The code goes in py files

Let's start with a little example: a Python file named *main.py*:

```
import kivy
kivy.require('1.0.5')

from kivy.uix.floatlayout import FloatLayout
from kivy.app import App
from kivy.properties import ObjectProperty, StringProperty

class Controller(FloatLayout):
    '''Create a controller that receives a custom widget from the kv lang_
    file.

    Add an action to be called from the kv lang file.
    '''

    label_wid = ObjectProperty()
    info = StringProperty()

    def do_action(self):
        self.label_wid.text = 'My label after button press'
        self.info = 'New info text'

class ControllerApp(App):

    def build(self):
        return Controller(info='Hello world')

if __name__ == '__main__':
    ControllerApp().run()
```

In this example, we are creating a Controller class with 2 properties:

- `info` for receiving some text
- `label_wid` for receiving the label widget

In addition, we are creating a `do_action()` method that will use both of these properties. It will change the `info` text and change text in the `label_wid` widget.

24.12.2 The layout goes in controller.kv

Executing this application without a corresponding *.kv* file will work, but nothing will be shown on the screen. This is expected, because the `Controller` class has no widgets in it, it's just a `FloatLayout`. We can create the UI around the `Controller` class in a file named `controller.kv`, which will be loaded when we run the `ControllerApp`. How this is done and what files are loaded is described in the `kivy.app.App.load_kv()` method.

```
#:kivy 1.0

<Controller>:
    label_wid: my_custom_label

    BoxLayout:
        orientation: 'vertical'
        padding: 20

        Button:
            text: 'My controller info is: ' + root.info
            on_press: root.do_action()

        Label:
            id: my_custom_label
            text: 'My label before button press'
```

One label and one button in a vertical `BoxLayout`. Seems very simple. There are 3 things going on here:

1. Using data from the `Controller`. As soon as the `info` property is changed in the controller, the expression `text: 'My controller info is: ' + root.info` will automatically be re-evaluated, changing the text in the `Button`.
2. Giving data to the `Controller`. The expression `id: my_custom_label` is assigning the created `Label` the id of `my_custom_label`. Then, using `my_custom_label` in the expression `label_wid: my_custom_label` gives the instance of that `Label` widget to your `Controller`.
3. Creating a custom callback in the `Button` using the `Controller`'s `on_press` method.
 - `root` and `self` are reserved keywords, usable anywhere. `root` represents the top widget in the rule and `self` represents the current widget.
 - You can use any id declared in the rule the same as `root` and `self`. For example, you could do this in the `on_press()`:

```
Button:
    on_press: root.do_action(); my_custom_label.font_size = 18
```

And that's that. Now when we run `main.py`, `controller.kv` will be loaded so that the `Button` and `Label` will show up and respond to our touch events.

24.13 More documentation

For a full description of the different components of the *KV* language, advanced usage and limitations, see the documentation for [*lang*](#)

INTEGRATING WITH OTHER FRAMEWORKS

New in version 1.0.8.

25.1 Using Twisted inside Kivy

Note: You can use the `kivy.support.install_twisted_reactor` function to install a twisted reactor that will run inside the kivy event loop.

Any arguments or keyword arguments passed to this function will be passed on the threadedselect reactors `interleave` function. These are the arguments one would usually pass to twisted's `reactor.startRunning`

Warning: Unlike the default twisted reactor, the installed reactor will not handle any signals unless you set the 'installSignalHandlers' keyword argument to 1 explicitly. This is done to allow kivy to handle the signals as usual, unless you specifically want the twisted reactor to handle the signals (e.g. SIGINT).

The kivy examples include a small example of a twisted server and client. The server app has a simple twisted server running and logs any messages. The client app can send messages to the server and will print its message and the response it got. The examples are based mostly on the simple Echo example from the twisted docs, which you can find here:

- <https://twistedmatrix.com/documents/current/core/examples/>

To try the example, run `echo_server_app.py` first, and then launch `echo_client_app.py`. The server will reply with simple echo messages to anything the client app sends when you hit enter after typing something in the textbox.

25.1.1 Server App

```
# install_twisted_reactor must be called before importing and using the reactor
from kivy.support import install_twisted_reactor

install_twisted_reactor()

from twisted.internet import reactor
from twisted.internet import protocol

class EchoServer(protocol.Protocol):
    def dataReceived(self, data):
        response = self.factory.app.handle_message(data)
        if response:
            self.transport.write(response)

class EchoServerFactory(protocol.Factory):
    protocol = EchoServer

    def __init__(self, app):
        self.app = app

from kivy.app import App
from kivy.uix.label import Label

class TwistedServerApp(App):
    label = None

    def build(self):
        self.label = Label(text="server started\n")
        reactor.listenTCP(8000, EchoServerFactory(self))
        return self.label

    def handle_message(self, msg):
        msg = msg.decode('utf-8')
        self.label.text = "received: {}\n".format(msg)

        if msg == "ping":
            msg = "Pong"
        if msg == "plop":
            msg = "Kivy Rocks!!!"
        self.label.text += "responded: {}\n".format(msg)
        return msg.encode('utf-8')

if __name__ == '__main__':
    TwistedServerApp().run()
```

25.1.2 Client App

```
# install_twisted_reactor must be called before importing the reactor
from __future__ import unicode_literals

from kivy.support import install_twisted_reactor

install_twisted_reactor()

# A Simple Client that send messages to the Echo Server
from twisted.internet import reactor, protocol

class EchoClient(protocol.Protocol):
    def connectionMade(self):
        self.factory.app.on_connection(self.transport)

    def dataReceived(self, data):
        self.factory.app.print_message(data.decode('utf-8'))


class EchoClientFactory(protocol.ClientFactory):
    protocol = EchoClient

    def __init__(self, app):
        self.app = app

    def startedConnecting(self, connector):
        self.app.print_message('Started to connect.')

    def clientConnectionLost(self, connector, reason):
        self.app.print_message('Lost connection.')

    def clientConnectionFailed(self, connector, reason):
        self.app.print_message('Connection failed.')

from kivy.app import App
from kivy.uix.label import Label
from kivy.uix.textinput import TextInput
from kivy.uix.boxlayout import BoxLayout

# A simple kivy App, with a textbox to enter messages, and
# a large label to display all the messages received from
# the server
class TwistedClientApp(App):
    connection = None
    textbox = None
    label = None

    def build(self):
        root = self.setup_gui()
        self.connect_to_server()
```

(continues on next page)

```
return root

def setup_gui(self):
    self.textbox = TextInput(size_hint_y=.1, multiline=False)
    self.textbox.bind(on_text_validate=self.send_message)
    self.label = Label(text='connecting...\n')
    layout = BoxLayout(orientation='vertical')
    layout.add_widget(self.label)
    layout.add_widget(self.textbox)
    return layout

def connect_to_server(self):
    reactor.connectTCP('localhost', 8000, EchoClientFactory(self))

def on_connection(self, connection):
    self.print_message("Connected successfully!")
    self.connection = connection

def send_message(self, *args):
    msg = self.textbox.text
    if msg and self.connection:
        self.connection.write(msg.encode('utf-8'))
    self.textbox.text = ""

def print_message(self, msg):
    self.label.text += "{}\n".format(msg)

if __name__ == '__main__':
    TwistedClientApp().run()
```

PACKAGING YOUR APPLICATION

26.1 Create a package for Windows

Note: This document only applies for kivy 1.9.1 and greater.

Packaging your application for the Windows platform can only be done inside the Windows OS. The following process has been tested on Windows with the Kivy **wheels** installation, see at the end for alternate installations.

The package will be either 32 or 64 bits depending on which version of Python you ran it with.

26.1.1 Requirements

- Latest Kivy (installed as described in `installation_windows`).
- PyInstaller 3.1+ (`pip install --upgrade pyinstaller`).

26.1.2 PyInstaller default hook

This section applies to PyInstaller (>= 3.1) that includes the kivy hooks. To overwrite the default hook the following examples need to be slightly modified. See [Overwriting the default hook](#).

26.1.3 Packaging a simple app

For this example, we'll package the **touchtracer** example project and embed a custom icon. The location of the kivy examples is, when using the wheels, installed to `python\share\kivy-examples` and when using the github source code installed as `kivy\examples`. We'll just refer to the full path leading to the examples as `examples-path`. The touchtracer example is in `examples-path\demo\touchtracer` and the main file is named `main.py`.

1. Open your command line shell and ensure that python is on the path (i.e. `python` works).
2. Create a folder into which the packaged app will be created. For example create a `TouchApp` folder and [change to that directory](#) with e.g. `cd TouchApp`. Then type:

```
python -m PyInstaller --name touchtracer examples-path\demo\
    ↵touchtracer\main.py
```

You can also add an `icon.ico` file to the application folder in order to create an icon for the executable. If you don't have a .ico file available, you can convert your `icon.png` file to ico using the web app [ConvertICO](#). Save the `icon.ico` in the `touchtracer` directory and type:

```
python -m PyInstaller --name touchtracer --icon examples-path\demo\
    ↪touchtracer\icon.ico examples-path\demo\touchtracer\main.py
```

For more options, please consult the [PyInstaller Manual](#).

3. The spec file will be `touchtracer.spec` located in `TouchApp`. Now we need to edit the spec file to add the dependencies hooks to correctly build the exe. Open the spec file with your favorite editor and add these lines at the beginning of the spec (assuming `sdl2` is used, the default now):

```
from kivy_deps import sdl2, glew
```

Then, find `COLLECT()` and add the data for `touchtracer` (`touchtracer.kv`, `particle.png`, ...): Change the line to add a `Tree()` object, e.g. `Tree('examples-path\\demo\\touchtracer\\')`. This Tree will search and add every file found in the `touchtracer` directory to your final package.

To add the dependencies, before the first keyword argument in `COLLECT` add a `Tree` object for every path of the dependencies. E.g. `*[Tree(p) for p in (sdl2.dep_bins + glew.dep_bins)]` so it'll look something like:

```
coll = COLLECT(exe, Tree('examples-path\\demo\\touchtracer\\'),
                 a.binaries,
                 a.zipfiles,
                 a.datas,
                 *[Tree(p) for p in (sdl2.dep_bins + glew.dep_bins)],
                 strip=False,
                 upx=True,
                 name='touchtracer')
```

4. Now we build the spec file in `TouchApp` with:

```
python -m PyInstaller touchtracer.spec
```

5. The compiled package will be in the `TouchApp\dist\touchtracer` directory.

26.1.4 Single File Application

Next, we will modify the example above to package the `touchtracer` example project as a single file application. Following the same steps as above, instead issue the following command:

```
python -m PyInstaller --onefile --name touchtracer examples-path\demo\
    ↪touchtracer\main.py
```

1. As before, this will generate `touchtracer.spec`, which we will edit to add the dependencies. In this instance, edit the arguments to the `EXE` command so that it will look something like this:

```
exe = EXE(pyz, Tree('examples-path\\demo\\touchtracer\\'),
           a.scripts,
           a.binaries,
           a.zipfiles,
           a.datas,
           *[Tree(p) for p in (sdl2.dep_bins + glew.dep_bins)],
           upx=True,
           name='touchtracer')
```

2. Now you can build the spec file as before with:

```
python -m PyInstaller touchtracer.spec
```

3. The compiled package will be in the *TouchApp\dist* directory and will consist of a single executable file.

26.1.5 Bundling Data Files

We will again modify the previous example to include bundled data files. PyInstaller allows inclusion of outside data files (such as images, databases, etc) that the project needs to run. When running an app on Windows, the executable extracts to a temporary folder which the Kivy project doesn't know about, so it can't locate these data files. We can fix that with a few lines.

1. First, follow PyInstaller documentation on how to include data files in your application.
2. Modify your main python code to include the following imports (if it doesn't have them already):

```
import os, sys
from kivy.resources import resource_add_path, resource_find
```

3. Modify your main python code to include the following (using the **touchtracer** app as an example):

```
if __name__ == '__main__':
    if hasattr(sys, '_MEIPASS'):
        resource_add_path(os.path.join(sys._MEIPASS))
    TouchtracerApp().run()
```

4. Finally, follow the steps for bundling your application above.

26.1.6 Packaging a video app with gstreamer

Following we'll slightly modify the example above to package a app that uses gstreamer for video. We'll use the `videoplayer` example found at `examples-path\widgets\videoplayer.py`. Create a folder somewhere called `VideoPlayer` and on the command line change your current directory to that folder and do:

```
python -m PyInstaller --name gstvideo examples-path\widgets\videoplayer.py
```

to create the `gstvideo.spec` file. Edit as above and this time include the gstreamer dependency as well:

```
from kivy_deps import sdl2, glew, gstreamer
```

and add the `Tree()` to include the video files, e.g. `Tree('examples-path\\widgets')` as well as the gstreamer dependencies so it should look something like:

```
coll = COLLECT(exe, Tree('examples-path\\widgets'),
                a.binaries,
                a.zipfiles,
                a.datas,
                *[Tree(p) for p in (sdl2.dep_bins + glew.dep_bins +
                                     gstreamer.dep_bins)],
                strip=False,
                upx=True,
                name='gstvideo')
```

Then build the spec file in `VideoPlayer` with:

```
python -m PyInstaller gstvideo.spec
```

and you should find `gstvideo.exe` in `VideoPlayer\dist\gstvideo`, which when run will play a video.

Note: If you're using Pygame and need PyGame in your packaging app, you'll have to add the following code to your spec file due to kivy issue #1638. After the imports add the following:

```
def getResource(identifier, *args, **kwargs):
    if identifier == 'pygame_icon.tiff':
        raise IOError()
    return _original_getResource(identifier, *args, **kwargs)

import pygame.pkgdata
_original_getResource = pygame.pkgdata.getResource
pygame.pkgdata.getResource = getResource
```

26.1.7 Overwriting the default hook

26.1.8 Including/excluding video and audio and reducing app size

PyInstaller includes a hook for kivy that by default adds **all** the core modules used by kivy, e.g. audio, video, spelling etc (you still need to package the gstreamer dlls manually with `Tree()` - see the example above) and their dependencies. If the hook is not installed or to reduce app size some of these modules may be excluded, e.g. if no audio/video is used, with an alternative hook.

Kivy provides the alternate hook at `hookspath()`. In addition, if and only if PyInstaller doesn't have the default hooks `runtime_hooks()` must also be provided. When overwriting the hook, the latter one typically is not required to be overwritten.

The alternate `hookspath()` hook does not include any of the kivy providers. To add them, they have to be added with `get_deps_minimal()` or `get_deps_all()`. See their documentation and `pyinstaller_hooks` for more details. But essentially, `get_deps_all()` add all the providers like in the default hook while `get_deps_minimal()` only adds those that are loaded when the app is run. Each method provides a list of hidden kivy imports and excluded imports that can be passed on to `Analysis`.

One can also generate a alternate hook which literally lists every kivy provider module and those not required can be commented out. See `pyinstaller_hooks`.

To use the the alternate hooks with the examples above modify as following to add the hooks with `hookspath()` and `runtime_hooks` (if required) and `**get_deps_minimal()` or `**get_deps_all()` to specify the providers.

For example, add the import statement:

```
from kivy.tools.packaging.pyinstaller_hooks import get_deps_minimal, get_
deps_all, hookspath, runtime_hooks
```

and then modify `Analysis` as follows:

```
a = Analysis(['examples-path\\demo\\touchtracer\\main.py'],
            ...)
```

(continues on next page)

(continued from previous page)

```
hookspath=hookspath(),
runtime_hooks=runtime_hooks(),
...
**get_deps_all()
```

to include everything like the default hook. Or:

```
a = Analysis(['examples-path\\demo\\touchtracer\\main.py'],
...
hookspath=hookspath(),
runtime_hooks=runtime_hooks(),
...
**get_deps_minimal(video=None, audio=None))
```

e.g. to exclude the audio and video providers and for the other core modules only use those loaded.

The key points is to provide the alternate `hookspath()` which does not list by default all the kivy providers and instead manually to hiddenimports add the required providers while removing the undesired ones (audio and video in this example) with `get_deps_minimal()`.

26.1.9 Alternate installations

The previous examples used e.g. `*[Tree(p) for p in (sdl2.dep_bins + glew.dep_bins + gstreamer.dep_bins)]`, to make PyInstaller add all the dlls used by these dependencies. If kivy was not installed using the wheels method these commands will not work and e.g. `Kivy_deps.sdl2` will fail to import. Instead, one must find the location of these dlls and manually pass them to the Tree class in a similar fashion as the example.

26.2 Create a package for Android

You can create a package for android using the [python-for-android](#) project. This page explains how to download and use it directly on your own machine (see Packaging your application into APK or AAB) or use the [Buildozer](#) tool to automate the entire process. You can also see [Packaging your application for the Kivy Launcher](#) to run kivy programs without compiling them.

For new users, we recommend using [Buildozer](#) as the easiest way to make a full APK or AAB. You can also run your Kivy app without a compilation step with the [Kivy Launcher](#) app.

Kivy applications can be [released on an Android market](#) such as the Play store, with a few extra steps to create a fully signed AAB (Android App Bundle).

The Kivy project includes tools for accessing Android APIs to accomplish vibration, sensor access, text-ing etc. These, along with information on debugging on the device, are documented at the [main Android page](#).

26.2.1 Buildozer

Buildozer is a tool that automates the entire build process. It downloads and sets up all the prerequisites for python-for-android, including the android SDK and NDK, then builds an apk that can be automatically pushed to the device.

Buildozer currently works only in Linux and macOS (You can still use it on Windows via WSL), and can significantly simplify the apk build.

You can get buildozer at <https://github.com/kivy/buildozer>:

```
git clone https://github.com/kivy/buildozer.git  
cd buildozer  
sudo python setup.py install
```

This will install buildozer in your system. Afterwards, navigate to your project directory and run:

```
buildozer init
```

This creates a *buildozer.spec* file controlling your build configuration. You should edit it appropriately with your app name etc. You can set variables to control most or all of the parameters passed to python-for-android.

Install buildozer's [dependencies](#).

Finally, plug in your android device and run:

```
buildozer android debug deploy run
```

to build, push and automatically run the apk on your device.

Buildozer has many available options and tools to help you, the steps above are just the simplest way to build and run your APK. The full documentation is available [here](#). You can also check the Buildozer README at <https://github.com/kivy/buildozer>.

26.2.2 Packaging with python-for-android

You can also package directly with python-for-android, which can give you more control but requires you to manually download parts of the Android toolchain.

See the [python-for-android documentation](#) for full details.

26.2.3 Packaging your application for the Kivy Launcher

The Kivy launcher is an Android application that runs any Kivy examples stored on your SD Card. To install the Kivy launcher, you must:

1. Go on Google Play Store and search for *Kivy Launcher* from *kivy org*
2. Click on Install
3. Select your phone... And you're done!

If you don't have access to the Google Play Store on your phone/tablet, you can download and install the APK manually from <https://github.com/kivy/kivy-launcher/releases>

Once the Kivy launcher is installed, you can put your Kivy applications in the Kivy directory in your external storage directory (often available at `/sdcard` even in devices where this memory is internal), e.g.

```
/sdcard/kivy/<yourapplication>
```

<yourapplication> should be a directory containing:

```
# Your main application file:  
main.py  
# Some info Kivy requires about your app on android:  
android.txt
```

The file *android.txt* must contain:

```
title=<Application Title>  
author=<Your Name>  
orientation=<portrait|landscape>
```

These options are just a very basic configuration. If you create your own APK using the tools above, you can choose many other settings.

Installation of Examples

Kivy comes with many examples, and these can be a great place to start trying the Kivy launcher. You can run them as below:

```
#. Download the `Kivy demos for Android <https://storage.googleapis.com/google-code-archive-downloads/v2/code.google.com/kivy/kivydemo-for-android.zip>`_  
#. Unzip the contents and go to the folder `kivydemo-for-android`  
#. Copy all the subfolders here to
```

/sdcard/kivy

1. Run the launcher and select one of the Pictures, Showcase, Touchtracer, Cymunk or other demos...

26.2.4 Release on the market

If you have built your own APK with Buildozer or with python-for-android, you can create a release version that may be released on the Play store or other Android markets.

To do this, you must run Buildozer with the `release` parameter (e.g. `buildozer android release`), or if using python-for-android use the `--release` option to build.py. This creates a release AAB in the `bin` directory, which you must properly sign and zipalign. The procedure for doing this is described in the Android documentation at <https://developer.android.com/studio/publish/app-signing.html#signing-manually> - all the necessary tools come with the Android SDK.

26.2.5 Targeting Android

Kivy is designed to operate identically across platforms and as a result, makes some clear design decisions. It includes its own set of widgets and by default, builds an APK or AAB with all the required core dependencies and libraries.

It is possible to target specific Android features, both directly and in a (somewhat) cross-platform way. See the *Using Android APIs* section of the [Kivy on Android documentation](#) for more details.

26.3 Kivy on Android

You can run Kivy applications on Android, on (more or less) any device with OpenGL ES 2.0 (Android 2.2 minimum). This is standard on modern devices; Google reports the requirement is met by [99.9% of devices](#).

Kivy APKs are normal Android apps that you can distribute like any other, including on stores like the Google Play Store. They behave properly when paused or restarted, may utilise Android services and have access to most of the normal java API as described below.

Follow the instructions below to learn how to [package your app for Android](#), [debug your code on the device](#), and [use Android APIs](#) such as for vibration and reading sensors.

26.3.1 Package for Android

The Kivy project provides all the necessary tools to package your app on Android, including building your own standalone APK or AAB that may be distributed on a market like the Google Play Store. This is covered fully in the [Create a package for Android](#) documentation.

26.3.2 Debugging your application on the Android platform

You can view the normal output of your code (stdout, stderr), as well as the normal Kivy logs, through the Android logcat stream. This is accessed through adb, provided by the [Android SDK](#). You may need to enable adb in your device's developer options, then connect your device to your computer and run:

```
adb logcat
```

You'll see all the logs including your stdout/stderr and Kivy logger.

If you packaged your app with Buildozer, the *adb* tool may not be in your \$PATH and the above command may not work. You can instead run:

```
buildozer android logcat
```

to run the version installed by Buildozer, or find the SDK tools at \$HOME/.buildozer/android/platform.

You can also run and debug your application using the Kivy Launcher. If you run your application this way, you will find log files inside the “*./kivy/logs*” sub-folder within your application folder.

26.3.3 Using Android APIs

Although Kivy is a Python framework, the Kivy project maintains tools to easily use the normal java APIs, for everything from vibration to sensors to sending messages through SMS or email.

For new users, we recommend using [Plyer](#). For more advanced access or for APIs not currently wrapped, you can use [Pyjnius](#) directly. Kivy also supplies an [android module](#) for basic Android functionality.

User contributed Android code and examples are available on the [Kivy wiki](#).

Plyer

[Plyer](#) is a pythonic, platform-independent API to use features commonly found on various platforms, particularly mobile ones. The idea is that your app can call simply call a Plyer function, such as to present a notification to the user, and Plyer will take care of doing so in the right way regardless of the platform or operating system. Internally, Plyer uses Pyjnius (on Android), Pyobjus (on iOS) and some platform specific APIs on desktop platforms.

For instance, the following code would make your Android device vibrate, or raise a NotImplementedException that you can handle appropriately on other platforms such as desktops that don't have appropriate hardware::

```
from plyer import vibrator
vibrator.vibrate(10) # vibrate for 10 seconds
```

Plyer's list of supported APIs is growing quite quickly, you can see the full list in the Plyer [README](#).

Pyjnius

Pyjnius is a Python module that lets you access java classes directly from Python, automatically converting arguments to the right type, and letting you easily convert the java results to Python.

Pyjnius can be obtained from [github](#), and has its [own documentation](#).

Here is a simple example showing Pyjnius' ability to access the normal Android vibration API, the same result of the plyer code above:

```
# 'autoclass' takes a java class and gives it a Python wrapper
from jnius import autoclass

# Context is a normal java class in the Android API
Context = autoclass('android.content.Context')

# PythonActivity is provided by the Kivy bootstrap app in python-for-
# android
PythonActivity = autoclass('org.renpy.android.PythonActivity')

# The PythonActivity stores a reference to the currently running activity
# We need this to access the vibrator service
activity = PythonActivity.mActivity

# This is almost identical to the java code for the vibrator
vibrator = activity.getSystemService(Context.VIBRATOR_SERVICE)

vibrator.vibrate(10000) # The value is in milliseconds - this is 10s
```

This code directly follows the java API functions to call the vibrator, with Pyjnius automatically translating the api to Python code and our calls back to the equivalent java. It is much more verbose and java-like than Plyer's version, for no benefit in this case, though Plyer does not wrap every API available to Pyjnius.

Pyjnius also has powerful abilities to implement java interfaces, which is important for wrapping some APIs, but these are not documented here - you can see Pyjnius' [own documentation](#).

Android module

Python-for-android includes a python module (actually cython wrapping java) to access a limited set of Android APIs. This has been largely superseded by the more flexible Pyjnius and Plyer as above, but may still occasionally be useful. The available functions are given in the [python-for-android documentation](#).

This includes code for billing/IAP and creating/accessing Android services, which is not yet available in the other tools above.

26.3.4 Status of the Project and Tested Devices

These sections previously described the existence of Kivy's Android build tools, with their limitations and some devices that were known to work.

The Android tools are now quite stable, and should work with practically any device; our minimum requirements are OpenGL ES 2.0 and Android 2.2. These are very common now - Kivy has even been run on an Android smartwatch!

As Kivy works fine on most devices, the list of supported phones/tablets has been retired - all Android devices are likely to work if they meet the conditions above.

26.4 Creating packages for macOS

Note: This guide describes multiple ways for packaging Kivy applications. Packaging using the Kivy SDK is recommended for general use.

26.4.1 Using the Kivy SDK

Note: These instructions apply only from Kivy v2.0.0 onwards.

Note: Kivy.app is built with `MACOSX_DEPLOYMENT_TARGET=10.9`.

We provide a Kivy DMG with all dependencies bundled in a **virtual environment**, including a Python interpreter that can be used as a base to package kivy apps.

This is the safest approach because it packages the binaries without references to any binaries on the system on which the app is packaged. Because all references are to frameworks included in the dmg or to binaries with the dmg. As opposed to e.g. pyinstaller which copies binaries from your local python installation.

You can find complete instructions to build and package apps with Kivy.app, starting either with Kivy.app or building from scratch, in the readme of the [kivy-sdk-packager repo](#).

26.4.2 Using Buildozer

```
pip install git+http://github.com/kivy/buildozer cd /to/where/I/Want/to/package buildozer init
```

Edit the buildozer.spec and add the details for your app. Dependencies can be added to the *requirements*= section.

By default the kivy version specified in the requirements is ignored.

If you have a Kivy.app at /Applications/Kivy.app then that is used, for packaging. Otherwise the latest build from kivy.org using Kivy master will be downloaded and used.

When you're ready to package your macOS app just run:

```
buildozer osx debug
```

Once the app is packaged, you might want to remove unneeded packages, just reduce the package to its minimal state that is needed for the app to run.

That's it. Enjoy!

Buildozer right now uses the Kivy SDK to package your app. If you want to control more details about your app than buildozer currently offers then you can use the SDK directly, as detailed in the section below.

26.4.3 Using PyInstaller and Homebrew

Note: Package your app on the oldest macOS version you want to support.

Complete guide

1. Install [Homebrew](#)
2. Install Python:

```
$ brew install python
```

Note: To use Python 3, `brew install python3` and replace `pip` with `pip3` in the guide below.

3. (Re)install your dependencies with `--build-from-source` to make sure they can be used on other machines:

```
$ brew reinstall --build-from-source sdl2 sdl2_image sdl2_ttf sdl2_mixer
```

Note: If your project depends on GStreamer or other additional libraries (re)install them with `--build-from-source` as described [below](#).

4. Install Cython and Kivy:

```
$ pip install Cython==0.29.28
$ pip install -U kivy
```

5. Install PyInstaller:

```
$ pip install -U pyinstaller
```

6. Package your app using the path to your main.py:

```
$ pyinstaller -y --clean --windowed --name touchtracer \
--exclude-module _tkinter \
--exclude-module Tkinter \
--exclude-module enchant \
--exclude-module twisted \
/usr/local/share/kivy-examples/demo/touchtracer/main.py
```

Note: This will not yet copy additional image or sound files. You would need to adapt the created .spec file for that.

Editing the spec file

The specs file is named *touchtracer.spec* and is located in the directory where you ran the pyinstaller command.

You need to change the *COLLECT()* call to add the data of touchtracer (*touchtracer.kv*, *particle.png*, ...). Change the line to add a *Tree()* object. This Tree will search and add every file found in the touchtracer directory to your final package. Your COLLECT section should look something like this:

```
coll = COLLECT(exe, Tree('/usr/local/share/kivy-examples/demo/touchtracer/
˓→'),
                a.binaries,
                a.zipfiles,
                a.datas,
                strip=None,
                upx=True,
                name='touchtracer')
```

This will add the required hooks so that PyInstaller gets the required Kivy files. We are done. Your spec is ready to be executed.

Build the spec and create a DMG

1. Open a console.
2. Go to the PyInstaller directory, and build the spec:

```
$ pyinstaller -y --clean --windowed touchtracer.spec
```

3. Run:

```
$ pushd dist
$ hdiutil create ./Touchtracer.dmg -srcfolder touchtracer.app -ov
$ popd
```

4. You will now have a Touchtracer.dmg available in the *dist* directory.

Additional Libraries

GStreamer

If your project depends on GStreamer:

```
$ brew reinstall --build-from-source gstreamer gst-plugins-{base,good,bad,  
→ugly}
```

Note: If your Project needs Ogg Vorbis support be sure to add the `--with-libvorbis` option to the command above.

If you are using Python from Homebrew you will also need the following step until [this pull request](#) gets merged:

```
$ brew reinstall --with-python --build-from-source https://github.com/  
→cbenhagen/homebrew/raw/patch-3/Library/Formula/gst-python.rb
```

26.4.4 Using PyInstaller without Homebrew

First install Kivy and its dependencies without using Homebrew as mentioned here <http://kivy.org/docs/installation/installation.html#development-version>.

Once you have kivy and its deps installed, you need to install PyInstaller.

Let's assume we use a folder like *testpackaging*:

```
cd testpackaging  
git clone http://github.com/pyinstaller/pyinstaller
```

Create a file named *touchtracer.spec* in this directory and add the following code to it:

```
# -*- mode: python -*-  
  
block_cipher = None  
from kivy.tools.packaging.pyinstaller_hooks import get_deps_all, hookspath,  
→ runtime_hooks  
  
a = Analysis(['/path/to/yout/folder/containing/examples/demo/touchtracer/  
→main.py'],  
            pathex=['/path/to/yout/folder/containing/testpackaging'],  
            binaries=None,  
            win_no_prefer_redirects=False,  
            win_private_assemblies=False,  
            cipher=block_cipher,  
            hookspath=hookspath(),  
            runtime_hooks=runtime_hooks(),  
            **get_deps_all())  
pyz = PYZ(a.pure, a.zipped_data,  
          cipher=block_cipher)  
exe = EXE(pyz,
```

(continues on next page)

(continued from previous page)

```
a.scripts,
exclude_binaries=True,
name='touchtracer',
debug=False,
strip=False,
upx=True,
console=False )
coll = COLLECT(exe, Tree('../kivy/examples/demo/touchtracer/'),
                Tree('/Library/Frameworks/SDL2_ttf.framework/Versions/A/
→Frameworks/FreeType.framework'),
                a.binaries,
                a.zipfiles,
                a.datas,
                strip=False,
                upx=True,
                name='touchtracer')
app = BUNDLE(coll,
              name='touchtracer.app',
              icon=None,
              bundle_identifier=None)
```

Change the paths with your relevant paths:

```
a = Analysis(['/path/to/yout/folder/containing/examples/demo/touchtracer/
→main.py'],
             pathex=['/path/to/yout/folder/containing/testpackaging'],
...
...
coll = COLLECT(exe, Tree('../kivy/examples/demo/touchtracer/'),
```

Then run the following command:

```
pyinstaller/pyinstaller.py touchtracer.spec
```

Replace *touchtracer* with your app where appropriate. This will give you a <yourapp>.app in the dist/ folder.

26.5 iOS Prerequisites

The following guide assumes:

- Xcode 13.2.1 or above
- macOS 11.6 or above

Your experience may vary with different versions.

26.5.1 Getting started

In order to submit any application to the iTunes store, you will need an [iOS Developer License](#). For testing, you can use a physical device or the Xcode iOS emulator.

Please note that in order to test on the device, you need to register these devices and install your “provisioning profile” on them. Please refer to the Apple’s [Getting started](#) guide for more information.

26.5.2 Homebrew

We use the [Homebrew](#) package manager for macOS to install some of the dependencies and tools used by Kivy. It’s a really helpful tool and is an Open Source project hosted on [Github](#).

Due to the nature of package management (complications with versions and Operating Systems), this process can be error prone and cause failures in the build process. The **Missing requirement: <pkg> is not installed!** message is typically such an error.

The first thing is to ensure you have run the following commands:

```
$ brew install autoconf automake libtool pkg-config  
$ brew link libtool  
$ pip install Cython==0.29.28
```

If you still receive build errors, check your Homebrew is in a healthy state:

```
brew doctor
```

For further help, please refer to the [Homebrew docs](#).

The last, final and desperate step to get things working might be to remove Homebrew altogether, get the latest version, install that and then re-install the dependencies.

[How do I uninstall Homebrew?](#)

26.6 Create a package for iOS

The overall process for creating a package for iOS can be explained in 4 steps:

1. [Compile the distribution](#) (python + modules for iOS)
2. [Create an Xcode project](#) (and link your source code)
3. [Update the Xcode project](#)
4. [Customize the Xcode project](#)

26.6.1 Prerequisites

You need to install some dependencies, like Cython, autotools, etc. We encourage you to use [Homebrew](#) to install those dependencies:

```
$ brew install autoconf automake libtool pkg-config  
$ brew link libtool  
$ pip install Cython==0.29.28
```

For more detail, see [iOS Prerequisites](#). Just ensure that everything is ok before starting the second step!

26.6.2 Compile the distribution

Open a terminal, and type:

```
$ pip install kivy-ios  
$ toolchain build kivy
```

If you experience any issues, please refer to our [user group](#) or the [kivy-ios project page](#).

26.6.3 Create an Xcode project

Before proceeding to the next step, ensure your application entry point is a file named *main.py*.

We provide a script that creates an initial Xcode project to start with. In the command line below, replace *title* with your project name. It must be a name without any spaces or illegal characters:

```
$ toolchain create <title> <app_directory>  
$ toolchain create Touchtracer ~/code/kivy/examples/demo/touchtracer
```

Note: You must use a fully qualified path to your application directory.

A directory named *<title>-ios* will be created, with an Xcode project in it. You can open the Xcode project:

```
$ open touchtracer-ios/touchtracer.xcodeproj
```

Then click on *Play*, and enjoy.

Note: Everytime you press *Play*, your application directory will be synced to the *<title>-ios/YourApp* directory. Don't make changes in the -ios directory directly.

26.6.4 Update the Xcode project

Let's say you want to add numpy to your project but you did not compile it prior to creating your XCode project. First, ensure it is built:

```
$ toolchain build numpy
```

Then, update your Xcode project:

```
$ toolchain update touchtracer-ios
```

All the libraries / frameworks necessary to run all the compiled recipes will be added to your Xcode project.

26.6.5 Customize the Xcode project

There are various ways to customize and configure your app. Please refer to the [kivy-ios](#) documentation for more information.

26.6.6 Known issues

All known issues with packaging for iOS are currently tracked on our [issues](#) page. If you encounter an issue specific to packaging for iOS that isn't listed there, please feel free to file a new issue, and we will get back to you on it.

While most are too technical to be written here, one important known issue is that removing some libraries (e.g. `SDL_Mixer` for audio) is currently not possible because the kivy project requires it. We will fix this and others in future versions.

26.6.7 FAQ

Application quit abnormally!

In debug mode, all the print statements are sent to the Xcode console. Looking and grep'ing these logs is highly encouraged. You'll probably find that you missed to build/install a required dependency. Not your case? Feel free to ask on our Discord [support](#) channels.

How can Apple accept a python app?

We managed to merge the app binary with all the libraries into a single binary, called `libpython`. This means all binary modules are loaded beforehand, so nothing is dynamically loaded.

Have you already submitted a Kivy application to the App store?

Yes, absolutely. [Kivy Apps in the Apple App Store](#).

PACKAGE LICENSING

Warning: This is not a legally authoritative guide! The Kivy organisation, authors and contributors take no responsibility for any lack of knowledge, information or advice presented here. The guide is merely informative and is meant to protect inexperienced users.

Your code alone may not require including licensing information or copyright notices of other included software, but binaries are something else. When a binary (.exe, .app, .apk, ...) is created, it includes Kivy, its dependencies and other packages that your application uses.

Some of them are licensed in a way that requires including a copyright notice somewhere in your app (or more). Before distributing any of the binaries, please **check all the created files** that don't belong to your source (.dll, .pyd, .so, ...) and include the appropriate copyright notices if required by the license the files belong to. This way you may satisfy licensing requirements of the Kivy deps.

27.1 Dependencies

All of the dependencies will be used at least partially on each platform Kivy supports. You therefore need to comply to their licenses, which mostly requires only pasting a copyright notice in your app and not pretending you wrote the code.

- [docutils](#)
- [`pygments https://github.com/pygments/pygments/blob/master/LICENSE`](https://github.com/pygments/pygments/blob/master/LICENSE)
- [sdl2](#)
- [glew](#)
- [gstreamer](#) (if used)
- image & audio libraries(e.g. [SDL_mixer has them](#))

You'll probably need to check image and audio libraries manually (most begin with lib). The LICENSE* files that belong to them should be included by PyInstaller, but are not included by python-for-android and you need to find them.

27.2 Windows (PyInstaller)

To access some Windows API features, Kivy uses the [pypiwin32](#) package. This package is released under the [PSF license](#).

27.2.1 Visual Studio Redistributables

Python compiled with Visual Studio (official) includes files from Microsoft and you are only allowed to redistribute them under specific conditions listed in the CRTlicense. You need to include the names of the files and a reworded version of [Py2 CRT license](#) or [Py3 CRT license](#) (depending which interpreter you use) and present these to the end-user of your application in order to satisfy their requirements.

- [List of redistributables](#)

27.2.2 Other libraries

- [zlib](#)

Note: Please add the attributions for other libraries that you *don't use directly* but are present after packaging with e.g. PyInstaller on Windows.

27.3 Linux

Linux has many distributions which means there's no correct guide for all of the distributions. This applies to the RPi too. However, it can be simplified in two ways depending on how you create a package (also with PyInstaller): with or without including binaries.

If the binaries are included, you should check every file (e.g. `.so`) that's not your source and find the license it belongs to. According to that license, you'll probably need to put an attribution into your application or possibly more, depending on the requirements of that license.

If the binaries are not included (which allows packaging your app as e.g. a `.deb` package), there's a [*situation bad for your user*](#). It's up to you to decide whether you satisfy the conditions of other licenses and, for example, include copyright attributions into your app or not.

27.4 Android

As APK or AAB are just an archive of files: you can extract files from them and (as in Windows redistributables) check all the files.

`private.tar` contains all the included files. Most of them are related to Kivy, Python or your source, but those that aren't need checking.

`apk: APK/assets/private.tar`

`aab: AAB/base/assets/private.tar`

There are other included libraries, included either by Kivy directly or through SDL2, that are located in `APK/lib/*` or `AAB/base/lib/*`. Most of them are related to dependencies or are produced by python-for-android and are part of its source (and licensing).

Warning: `libpybundle.so` is actually a tarball that contains python modules and site-packages. You'll probably want to inspect it for licensing purposes via `tar -xvf libpybundle.so`.

27.5 macOS

Missing.

27.6 iOS

Missing.

27.7 Avoiding binaries

There might be a way how to avoid this licensing process by avoiding creating a distribution with third-party stuff completely. With Python you can create a module, which is only your code with `__main__.py + setup.py` that only lists required dependencies.

This way, you can still distribute your app - your *code* - and you might not need to care about other licenses. The combination of your code and the dependencies could be specified as a "usage" rather than a "distribution". The responsibility of satisfying licenses, however, most likely transfers to your user, who needs to assemble the environment to even run the module. If you care about your users, you might want to slow down a little and read more about the [consequences](#).


Part IV
TUTORIALS

PONG GAME TUTORIAL

28.1 Introduction

Welcome to the Pong tutorial

This tutorial will teach you how to write pong using Kivy. We'll start with a basic application like the one described in the [Create an application](#) and turn it into a playable pong game, describing each step along the way.



Here is a check list before starting this tutorial:

- You have a working Kivy installation. See the [Installing Kivy](#) section for detailed descriptions
- You know how to run a basic Kivy application. See [Create an application](#) if you don't.

If you have read the programming guide, and understand both basic Widget concepts ([A Simple Paint App](#)) and basic concepts of the kv language ([Kv language](#)), you can probably skip the first 2 steps and go straight to step 3.

Note: You can find the entire source code, and source code files for each step in the Kivy examples directory under *tutorials/pong/*

Ready? Sweet, let's get started!

28.2 Getting Started

Getting Started

Let's start by getting a really simple Kivy app up and running. Create a directory for the game and a file named *main.py*

```
1 from kivy.app import App
2 from kivy.uix.widget import Widget
3
4
5 class PongGame(Widget):
6     pass
7
8
9 class PongApp(App):
10     def build(self):
11         return PongGame()
12
13
14 if __name__ == '__main__':
15     PongApp().run()
```

Go ahead and run the application. It should just show a black window at this point. What we've done is create a very simple Kivy *App*, which creates an instance of our *PongGame* Widget class and returns it as the root element for the applications UI, which you should imagine at this point as a hierarchical tree of Widgets. Kivy places this widget-tree in the default Window. In the next step, we will draw the Pong background and scores by defining how the *PongGame* widget looks.

28.3 Add Simple Graphics

Creation of pong.kv

We will use a .kv file to define the look and feel of the *PongGame* class. Since our *App* class is called *PongApp*, we can simply create a file called *pong.kv* in the same directory that will be automatically loaded when the application is run. So create a new file called ``*pong.kv*`` and add the following contents.

```
1 #:kivy 1.0.9
2
3 <PongGame>:
4     canvas:
5         Rectangle:
6             pos: self.center_x - 5, 0
7             size: 10, self.height
```

(continues on next page)

```

9  Label:
10    font_size: 70
11    center_x: root.width / 4
12    top: root.top - 50
13    text: "0"
14
15 Label:
16    font_size: 70
17    center_x: root.width * 3 / 4
18    top: root.top - 50
19    text: "0"

```

Note: COMMON ERROR: The name of the kv file, e.g. pong.kv, must match the name of the app, e.g. PongApp (the part before the App ending).

If you run the app now, you should see a vertical bar in the middle, and two zeros where the player scores will be displayed.

28.3.1 Explaining the Kv File Syntax

Before going on to the next step, you might want to take a closer look at the contents of the kv file we just created and figure out what is going on. If you understand what's happening, you can probably skip ahead to the next step.

On the very first line we have:

```
#:kivy 1.0.9
```

This first line is required in every kv file. It should start with `#:kivy` followed by a space and the Kivy version it is intended for (so Kivy can make sure you have at least the required version, or handle backwards compatibility later on).

After that, we begin defining rules that are applied to all `PongGame` instances:

```
<PongGame>:
    ...
```

Like Python, kv files use indentation to define nested blocks. A block defined with a class name inside the `<` and `>` characters is a `Widget` rule. It will be applied to any instance of the named class. If you replaced `PongGame` with `Widget` in our example, all `Widget` instances would have the vertical line and the two `Label` widgets inside them because it would define these rules for all `Widget` instances.

Inside a rule section, you can add various blocks to define the style and contents of the widgets they will be applied to. You can:

- set property values
- add child widgets
- define a `canvas` section in which you can add Graphics instructions that define how the widget is rendered.

The first block inside the `<PongGame>` rule we have is a `canvas` block:

```

1 <PongGame>:
2     canvas:
3         Rectangle:
4             pos: self.center_x - 5, 0
5             size: 10, self.height

```

So this canvas block says that the `PongGame` widget should draw some graphics primitives. In this case, we add a rectangle to the canvas. We set the pos of the rectangle to be 5 pixels left of the horizontal center of the widget, and 0 for y. The size of the rectangle is set to 10 pixels in width, and the widget's height in height. The nice thing about defining the graphics like this, is that the rendered rectangle will be automatically updated when the properties of any widgets used in the value expression change.

Note: Try to resize the application window and notice what happens. That's right, the entire UI resizes automatically. The standard behaviour of the `Window` is to resize an element based on its property `size_hint`. The default widget `size_hint` is (1,1), meaning it will be stretched 100% in both x-direction and y-direction and hence fill the available space. Since the pos and size of the rectangle and `center_x` and `top` of the score labels were defined within the context of the `PongGame` class, these properties will automatically update when the corresponding widget properties change. Using the Kv language gives you automatic property binding. :)

The last two sections we add look pretty similar. Each of them adds a `Label` widget as a child widget to the `PongGame` widget. For now, the text on both of them is just set to "0". We'll hook that up to the actual score once we have the logic implemented, but the labels already look good since we set a bigger `font_size`, and positioned them relatively to the root widget. The `root` keyword can be used inside the child block to refer back to the parent/root widget the rule applies to (`PongGame` in this case):

```

1 <PongGame>:
2     # ...
3
4     Label:
5         font_size: 70
6         center_x: root.width / 4
7         top: root.top - 50
8         text: "0"
9
10    Label:
11        font_size: 70
12        center_x: root.width * 3 / 4
13        top: root.top - 50
14        text: "0"

```

28.4 Add the Ball

Add the Ball

Ok, so we have a basic pong arena to play in, but we still need the players and a ball to hit around. Let's start with the ball. We'll add a new `PongBall` class to create a widget that will be our ball and make it bounce around.

28.4.1 PongBall Class

Here is the Python code for the PongBall class:

```
1  class PongBall(Widget):
2
3      # velocity of the ball on x and y axis
4      velocity_x = NumericProperty(0)
5      velocity_y = NumericProperty(0)
6
7      # reference list property so we can use ball.velocity as
8      # a shorthand, just like e.g. w.pos for w.x and w.y
9      velocity = ReferenceListProperty(velocity_x, velocity_y)
10
11     # ``move`` function will move the ball one step. This
12     # will be called in equal intervals to animate the ball
13     def move(self):
14         self.pos = Vector(*self.velocity) + self.pos
```

And here is the kv rule used to draw the ball as a white circle:

```
1 <PongBall>:
2     size: 50, 50
3     canvas:
4         Ellipse:
5             pos: self.pos
6             size: self.size
```

To make it all work, you also have to add the imports for the *Properties* Property classes used and the *Vector*.

Here is the entire updated python code and kv file for this step:

main.py:

```
1  from kivy.app import App
2  from kivy.uix.widget import Widget
3  from kivy.properties import NumericProperty, ReferenceListProperty
4  from kivy.vector import Vector
5
6
7  class PongBall(Widget):
8      velocity_x = NumericProperty(0)
9      velocity_y = NumericProperty(0)
10     velocity = ReferenceListProperty(velocity_x, velocity_y)
11
12     def move(self):
13         self.pos = Vector(*self.velocity) + self.pos
14
15
16 class PongGame(Widget):
17     pass
18
19
20 class PongApp(App):
21     def build(self):
```

(continues on next page)

(continued from previous page)

```
22     return PongGame()
23
24
25 if __name__ == '__main__':
26     PongApp().run()
```

pong.kv:

```
1 #:kivy 1.0.9
2
3 <PongBall>:
4     size: 50, 50
5     canvas:
6         Ellipse:
7             pos: self.pos
8             size: self.size
9
10 <PongGame>:
11     canvas:
12         Rectangle:
13             pos: self.center_x - 5, 0
14             size: 10, self.height
15
16     Label:
17         font_size: 70
18         center_x: root.width / 4
19         top: root.top - 50
20         text: "0"
21
22     Label:
23         font_size: 70
24         center_x: root.width * 3 / 4
25         top: root.top - 50
26         text: "0"
27
28     PongBall:
29         center: self.parent.center
```

Note that not only a `<PongBall>` widget rule has been added, but also a child widget `PongBall` in the `<PongGame>` widget rule.

28.5 Adding Ball Animation

Making the ball move

Cool, so now we have a ball, and it even has a `move` function... but it's not moving yet. Let's fix that.

28.5.1 Scheduling Functions on the Clock

We need the `move` method of our ball to be called regularly. Luckily, Kivy makes this pretty easy by letting us schedule any function we want using the `Clock` and specifying the interval:

```
Clock.schedule_interval(game.update, 1.0/60.0)
```

This line for example, would cause the `update` function of the `game` object to be called once every 60th of a second (60 times per second).

28.5.2 Object Properties/References

We have another problem though. We'd like to make sure the `PongBall` has its `move` function called regularly, but in our code we don't have any references to the ball object since we just added it via the `kv` file inside the `kv` rule for the `PongGame` class. The only reference to our game is the one we return in the applications build method.

Since we're going to have to do more than just move the ball (e.g. bounce it off the walls and later the players racket), we'll probably need an `update` method for our `PongGame` class anyway. Furthermore, given that we have a reference to the `game` object already, we can easily schedule its new `update` method when the application gets built:

```
1 class PongGame(Widget):
2
3     def update(self, dt):
4         # call ball.move and other stuff
5         pass
6
7 class PongApp(App):
8
9     def build(self):
10        game = PongGame()
11        Clock.schedule_interval(game.update, 1.0/60.0)
12        return game
```

However, that still doesn't change the fact that we don't have a reference to the `PongBall` child widget created by the `kv` rule. To fix this, we can add an `ObjectProperty` to the `PongGame` class, and hook it up to the widget created in the `kv` rule. Once that's done, we can easily reference the `ball` property inside the `update` method and even make it bounce off the edges:

```
1 class PongGame(Widget):
2     ball = ObjectProperty(None)
3
4     def update(self, dt):
5         self.ball.move()
6
7         # bounce off top and bottom
8         if (self.ball.y < 0) or (self.ball.top > self.height):
```

(continues on next page)

(continued from previous page)

```
9     self.ball.velocity_y *= -1
10
11    # bounce off left and right
12    if (self.ball.x < 0) or (self.ball.right > self.width):
13        self.ball.velocity_x *= -1
```

Don't forget to hook it up in the kv file, by giving the child widget an id and setting the PongGame's ball ObjectProperty to that id:

```
1 <PongGame>:
2     ball: pong_ball
3
4     # ... (canvas and Labels)
5
6     PongBall:
7         id: pong_ball
8         center: self.parent.center
```

Note: At this point everything is hooked up for the ball to bounce around. If you're coding along as we go, you might be wondering why the ball isn't moving anywhere. The ball's velocity is set to 0 on both x and y. In the code listing below, a `serve_ball` method is added to the `PongGame` class and called in the app's `build` method. It sets a random x and y velocity for the ball, and also resets the position, so we can use it later to reset the ball when a player has scored a point.

Here is the entire code for this step:

`main.py`:

```
1  from kivy.app import App
2  from kivy.uix.widget import Widget
3  from kivy.properties import (
4      NumericProperty, ReferenceListProperty, ObjectProperty
5  )
6  from kivy.vector import Vector
7  from kivy.clock import Clock
8  from random import randint
9
10
11 class PongBall(Widget):
12     velocity_x = NumericProperty(0)
13     velocity_y = NumericProperty(0)
14     velocity = ReferenceListProperty(velocity_x, velocity_y)
15
16     def move(self):
17         self.pos = Vector(*self.velocity) + self.pos
18
19
20 class PongGame(Widget):
21     ball = ObjectProperty(None)
22
23     def serve_ball(self):
24         self.ball.center = self.center
25         self.ball.velocity = Vector(4, 0).rotate(randint(0, 360))
```

(continues on next page)

(continued from previous page)

```
26
27     def update(self, dt):
28         self.ball.move()
29
30         # bounce off top and bottom
31         if (self.ball.y < 0) or (self.ball.top > self.height):
32             self.ball.velocity_y *= -1
33
34         # bounce off left and right
35         if (self.ball.x < 0) or (self.ball.right > self.width):
36             self.ball.velocity_x *= -1
37
38
39 class PongApp(App):
40     def build(self):
41         game = PongGame()
42         game.serve_ball()
43         Clock.schedule_interval(game.update, 1.0 / 60.0)
44         return game
45
46
47 if __name__ == '__main__':
48     PongApp().run()
```

pong.kv:

```
1 #:kivy 1.0.9
2
3 <PongBall>:
4     size: 50, 50
5     canvas:
6         Ellipse:
7             pos: self.pos
8             size: self.size
9
10 <PongGame>:
11     ball: pong_ball
12
13     canvas:
14         Rectangle:
15             pos: self.center_x - 5, 0
16             size: 10, self.height
17
18     Label:
19         font_size: 70
20         center_x: root.width / 4
21         top: root.top - 50
22         text: "0"
23
24     Label:
25         font_size: 70
26         center_x: root.width * 3 / 4
27         top: root.top - 50
```

(continues on next page)

(continued from previous page)

```
28     text: "0"
29
30     PongBall:
31         id: pong_ball
32         center: self.parent.center
33
```

28.6 Connect Input Events

Adding Players and reacting to touch input

Sweet, our ball is bouncing around. The only things missing now are the movable player rackets and keeping track of the score. We won't go over all the details of creating the class and kv rules again, since those concepts were already covered in the previous steps. Instead, let's focus on how to move the Player widgets in response to user input. You can get the whole code and kv rules for the `PongPaddle` class at the end of this section.

In Kivy, a widget can react to input by implementing the `on_touch_down`, the `on_touch_move` and the `on_touch_up` methods. By default, the Widget class implements these methods by just calling the corresponding method on all its child widgets to pass on the event until one of the children returns True.

Pong is pretty simple. The rackets just need to move up and down. In fact it's so simple, we don't even really need to have the player widgets handle the events themselves. We'll just implement the `on_touch_move` function for the `PongGame` class and have it set the position of the left or right player based on whether the touch occurred on the left or right side of the screen.

Check the `on_touch_move` handler:

```
1 def on_touch_move(self, touch):
2     if touch.x < self.width/3:
3         self.player1.center_y = touch.y
4     if touch.x > self.width - self.width/3:
5         self.player2.center_y = touch.y
```

We'll keep the score for each player in a `NumericProperty`. The score labels of the `PongGame` are kept updated by changing the `NumericProperty` `score`, which in turn updates the `PongGame` child labels `text` property. This binding occurs because Kivy `properties` automatically bind to any references in their corresponding kv files. When the ball escapes out of the sides, we'll update the score and serve the ball again by changing the `update` method in the `PongGame` class. The `PongPaddle` class also implements a `bounce_ball` method, so that the ball bounces differently based on where it hits the racket. Here is the code for the `PongPaddle` class:

```
1 class PongPaddle(Widget):
2
3     score = NumericProperty(0)
4
5     def bounce_ball(self, ball):
6         if self.collide_widget(ball):
7             speedup = 1.1
8             offset = 0.02 * Vector(0, ball.center_y-self.center_y)
9             ball.velocity = speedup * (offset - ball.velocity)
```

Note: This algorithm for ball bouncing is very simple, but will have strange behavior if the ball hits the paddle from the side or bottom...this is something you could try to fix yourself if you like.

And here it is in context. Pretty much done:

main.py:

```
1  from kivy.app import App
2  from kivy.uix.widget import Widget
3  from kivy.properties import (
4      NumericProperty, ReferenceListProperty, ObjectProperty
5  )
6  from kivy.vector import Vector
7  from kivy.clock import Clock
8
9
10 class PongPaddle(Widget):
11     score = NumericProperty(0)
12
13     def bounce_ball(self, ball):
14         if self.collide_widget(ball):
15             vx, vy = ball.velocity
16             offset = (ball.center_y - self.center_y) / (self.height / ↴2)
17             bounced = Vector(-1 * vx, vy)
18             vel = bounced * 1.1
19             ball.velocity = vel.x, vel.y + offset
20
21
22 class PongBall(Widget):
23     velocity_x = NumericProperty(0)
24     velocity_y = NumericProperty(0)
25     velocity = ReferenceListProperty(velocity_x, velocity_y)
26
27     def move(self):
28         self.pos = Vector(*self.velocity) + self.pos
29
30
31 class PongGame(Widget):
32     ball = ObjectProperty(None)
33     player1 = ObjectProperty(None)
34     player2 = ObjectProperty(None)
35
36     def serve_ball(self, vel=(4, 0)):
37         self.ball.center = self.center
38         self.ball.velocity = vel
39
40     def update(self, dt):
41         self.ball.move()
42
43         # bounce of paddles
44         self.player1.bounce_ball(self.ball)
45         self.player2.bounce_ball(self.ball)
```

(continues on next page)

(continued from previous page)

```
47     # bounce ball off bottom or top
48     if (self.ball.y < self.y) or (self.ball.top > self.top):
49         self.ball.velocity_y *= -1
50
51     # went off to a side to score point?
52     if self.ball.x < self.x:
53         self.player2.score += 1
54         self.serve_ball(vel=(4, 0))
55     if self.ball.right > self.width:
56         self.player1.score += 1
57         self.serve_ball(vel=(-4, 0))
58
59     def on_touch_move(self, touch):
60         if touch.x < self.width / 3:
61             self.player1.center_y = touch.y
62         if touch.x > self.width - self.width / 3:
63             self.player2.center_y = touch.y
64
65
66 class PongApp(App):
67     def build(self):
68         game = PongGame()
69         game.serve_ball()
70         Clock.schedule_interval(game.update, 1.0 / 60.0)
71         return game
72
73
74 if __name__ == '__main__':
75     PongApp().run()
```

pong.kv:

```
1 #:kivy 1.0.9
2
3 <PongBall>:
4     size: 50, 50
5     canvas:
6         Ellipse:
7             pos: self.pos
8             size: self.size
9
10 <PongPaddle>:
11     size: 25, 200
12     canvas:
13         Rectangle:
14             pos: self.pos
15             size: self.size
16
17 <PongGame>:
18     ball: pong_ball
19     player1: player_left
20     player2: player_right
```

(continues on next page)

```

22 canvas:
23     Rectangle:
24         pos: self.center_x - 5, 0
25         size: 10, self.height
26
27 Label:
28     font_size: 70
29     center_x: root.width / 4
30     top: root.top - 50
31     text: str(root.player1.score)
32
33 Label:
34     font_size: 70
35     center_x: root.width * 3 / 4
36     top: root.top - 50
37     text: str(root.player2.score)
38
39 PongBall:
40     id: pong_ball
41     center: self.parent.center
42
43 PongPaddle:
44     id: player_left
45     x: root.x
46     center_y: root.center_y
47
48 PongPaddle:
49     id: player_right
50     x: root.width - self.width
51     center_y: root.center_y
52

```

28.7 Where To Go Now?

Have some fun

Well, the pong game is pretty much complete. If you understood all of the things that are covered in this tutorial, give yourself a pat on the back and think about how you could improve the game. Here are a few ideas of things you could do:

- Add some nicer graphics / images. (Hint: check out the `source` property on the graphics instructions like `circle` or `Rectangle`, to set an image as the texture.)
- Make the game end after a certain score. Maybe once a player has 10 points, you can display a large “PLAYER 1 WINS” label and/or add a main menu to start, pause and reset the game. (Hint: check out the `Button` and `Label` classes, and figure out how to use their `add_widget` and `remove_widget` functions to add or remove widgets dynamically.)
- Make it a 4 player Pong Game. Most tablets have Multi-Touch support, so wouldn’t it be cool to have a player on each side and have four people play at the same time?
- Fix the simplistic collision check so hitting the ball with an end of the paddle results in a more realistic bounce.

Note: You can find the entire source code and source code files for each step in the Kivy examples directory under tutorials/pong/

A SIMPLE PAINT APP

In the following tutorial, you will be guided through the creation of your first widget. This provides powerful and important knowledge when programming Kivy applications, as it lets you create completely new user interfaces with custom elements for your specific purpose.

29.1 Basic Considerations

When creating an application, you have to ask yourself three important questions:

- What data does my application process?
- How do I visually represent that data?
- How does the user interact with that data?

If you want to write a very simple line drawing application for example, you most likely want the user to just draw on the screen with his/her fingers. That's how the user *interacts* with your application. While doing so, your application would memorize the positions where the user's finger were, so that you can later draw lines between those positions. So the points where the fingers were would be your *data* and the lines that you draw between them would be your *visual representation*.

In Kivy, an application's user interface is composed of Widgets. Everything that you see on the screen is somehow drawn by a widget. Often you would like to be able to reuse code that you already wrote in a different context, which is why widgets typically represent one specific instance that answers the three questions above. A widget encapsulates data, defines the user's interaction with that data and draws its visual representation. You can build anything from simple to complex user interfaces by nesting widgets. There are many widgets built in, such as buttons, sliders and other common stuff. In many cases, however, you need a custom widget that is beyond the scope of what is shipped with Kivy (e.g. a medical visualization widget).

So keep these three questions in mind when you design your widgets. Try to write them in a minimal and reusable manner (i.e. a widget does exactly what its supposed to do and nothing more. If you need more, write more widgets or compose other widgets of smaller widgets. We try to adhere to the [Single Responsibility Principle](#)).

29.2 Paint Widget

We're sure one of your childhood dreams has always been creating your own multitouch paint program. Allow us to help you achieve that. In the following sections you will successively learn how to write a program like that using Kivy. Make sure that you have read and understood [Create an application](#). You have? Great! Let's get started!

29.2.1 Initial Structure

Let's start by writing the very basic code structure that we need. By the way, all the different pieces of code that are used in this section are also available in the `examples/guide/firstwidget` directory that comes with Kivy, so you don't need to copy & paste it all the time. Here is the basic code skeleton that we will need:

```
1  from kivy.app import App
2  from kivy.uix.widget import Widget
3
4
5  class MyPaintWidget(Widget):
6      pass
7
8
9  class MyPaintApp(App):
10     def build(self):
11         return MyPaintWidget()
12
13
14 if __name__ == '__main__':
15     MyPaintApp().run()
```

This is actually really simple. Save it as `paint.py`. If you run it, you should only see a black screen. As you can see, instead of using a built-in widget such as a Button (see [Create an application](#)), we are going to write our own widget to do the drawing. We do that by creating a class that inherits from `Widget` (line 5-6) and although that class does nothing yet, we can still treat it like a normal Kivy widget (line 11). The `if __name__ == '__main__':` construct (line 14) is a Python mechanism that prevents you from executing the code in the if-statement when importing from the file, i.e. if you write `import paint`, it won't do something unexpected but just nicely provide the classes defined in the file.

Note: You may be wondering why you have to import `App` and `Widget` separately, instead of doing something like `from kivy import *`. While shorter, this would have the disadvantage of [polluting your namespace](#) and make the start of the application potentially much slower. It can also introduce ambiguity into class and variable naming, so is generally frowned upon in the Python community. The way we do it is faster and cleaner.

29.2.2 Adding Behaviour


Let's now add some actual behaviour to the widget, i.e. make it react to user input. Change the code like so:

```
1 from kivy.app import App
2 from kivy.uix.widget import Widget
3
4
5 class MyPaintWidget(Widget):
6     def on_touch_down(self, touch):
7         print(touch)
8
9
10 class MyPaintApp(App):
11     def build(self):
12         return MyPaintWidget()
13
14
15 if __name__ == '__main__':
16     MyPaintApp().run()
```

This is just to show how easy it is to react to user input. When a *MotionEvent* (i.e. a touch, click, etc.) occurs, we simply print the information about the touch object to the console. You won't see anything on the screen, but if you observe the command-line from which you are running the program, you will see a message for every touch. This also demonstrates that a widget does not have to have a visual representation.

Now that's not really an overwhelming user experience. Let's add some code that actually draws something into our window:

```
1 from kivy.app import App
2 from kivy.uix.widget import Widget
3 from kivy.graphics import Color, Ellipse
4
5
6 class MyPaintWidget(Widget):
7
8     def on_touch_down(self, touch):
9         with self.canvas:
10             Color(1, 1, 0)
11             d = 30.
12             Ellipse(pos=(touch.x - d / 2, touch.y - d / 2), size=(d, d))
13
14
15 class MyPaintApp(App):
16
17     def build(self):
18         return MyPaintWidget()
19
20
21 if __name__ == '__main__':
22     MyPaintApp().run()
```



If you run your code with these modifications, you will see that every time you touch, there will be a small yellow circle drawn where you touched. How does it work?

- Line 9: We use Python's `with` statement with the widget's `Canvas` object. This is like an area in which the widget can draw things to represent itself on the screen. By using the `with` statement with it, all successive drawing commands that are properly indented will modify this canvas. The `with` statement also makes sure that after our drawing, internal state can be cleaned up properly.
- Line 10: You might have guessed it already: This sets the `Color` for successive drawing operations to yellow (default color format is RGB, so `(1, 1, 0)` is yellow). This is true until another `Color` is set. Think of this as dipping your brushes in that color, which you can then use to draw on a canvas until you dip the brushes into another color.
- Line 11: We specify the diameter for the circle that we are about to draw. Using a variable for that is preferable since we need to refer to that value multiple times and we don't want to have to change it in several places if we want the circle bigger or smaller.
- Line 12: To draw a circle, we simply draw an `Ellipse` with equal width and height. Since we want the circle to be drawn where the user touches, we pass the touch's position to the ellipse. Note that we need to shift the ellipse by `-d/2` in the x and y directions (i.e. left and downwards) because the position specifies the bottom left corner of the ellipse's bounding box, and we want it to be centered around our touch.

That was easy, wasn't it? It gets better! Update the code to look like this:


```
1 from kivy.app import App
2 from kivy.uix.widget import Widget
3 from kivy.graphics import Color, Ellipse, Line
4
5
6 class MyPaintWidget(Widget):
7
8     def on_touch_down(self, touch):
9         with self.canvas:
10             Color(1, 1, 0)
11             d = 30.
12             Ellipse(pos=(touch.x - d / 2, touch.y - d / 2), size=(d, d))
13             touch.ud['line'] = Line(points=(touch.x, touch.y))
```

(continues on next page)

```

14
15     def on_touch_move(self, touch):
16         touch.ud['line'].points += [touch.x, touch.y]
17
18
19 class MyPaintApp(App):
20
21     def build(self):
22         return MyPaintWidget()
23
24
25 if __name__ == '__main__':
26     MyPaintApp().run()

```




This is what has changed:

- Line 3: We now not only import the `Ellipse` drawing instruction, but also the `Line` drawing instruction. If you look at the documentation for `Line`, you will see that it accepts a `points` argument that has to be a list of 2D point coordinates, like `(x1, y1, x2, y2, ..., xN, yN)`.
- Line 13: This is where it gets interesting. `touch.ud` is a Python dictionary (type `<dict>`) that allows us to store *custom attributes* for a touch.
- Line 13: We make use of the `Line` instruction that we imported and set a `Line` up for drawing. Since this is done in `on_touch_down`, there will be a new line for every new touch. By creating the line inside the `with` block, the canvas automatically knows about the line and will draw it. We just want to modify the line later, so we store a reference to it in the `touch.ud` dictionary under the arbitrarily chosen but aptly named key '`'line'`'. We pass the line that we're creating the initial touch position because that's where our line will begin.
- Lines 15: We add a new method to our widget. This is similar to the `on_touch_down` method, but instead of being called when a *new* touch occurs, this method is being called when an *existing* touch (for which `on_touch_down` was already called) moves, i.e. its position changes. Note that this is the **same** `MotionEvent` object with updated attributes. This is something we found incredibly handy and you will shortly see why.
- Line 16: Remember: This is the same touch object that we got in `on_touch_down`, so we can

simply access the data we stored away in the `touch.ud` dictionary! To the line we set up for this touch earlier, we now add the current position of the touch as a new point. We know that we need to extend the line because this happens in `on_touch_move`, which is only called when the touch has moved, which is exactly why we want to update the line. Storing the line in the `touch.ud` makes it a whole lot easier for us as we don't have to maintain our own touch-to-line bookkeeping.

So far so good. This isn't exactly beautiful yet, though. It looks a bit like spaghetti bolognese. How about giving each touch its own color? Great, let's do it:

```
1  from random import random
2  from kivy.app import App
3  from kivy.uix.widget import Widget
4  from kivy.graphics import Color, Ellipse, Line
5
6
7  class MyPaintWidget(Widget):
8
9      def on_touch_down(self, touch):
10         color = (random(), random(), random())
11         with self.canvas:
12             Color(*color)
13             d = 30.
14             Ellipse(pos=(touch.x - d / 2, touch.y - d / 2), size=(d, d))
15             touch.ud['line'] = Line(points=(touch.x, touch.y))
16
17     def on_touch_move(self, touch):
18         touch.ud['line'].points += [touch.x, touch.y]
19
20
21 class MyPaintApp(App):
22
23     def build(self):
24         return MyPaintWidget()
25
26
27 if __name__ == '__main__':
28     MyPaintApp().run()
```



Here are the changes:

- Line 1: We import Python's random() function that will give us random values in the range of [0., 1.).
- Line 10: In this case we simply create a new tuple of 3 random float values that will represent a random RGB color. Since we do this in `on_touch_down`, every new touch will get its own color. Don't get confused by the use of **tuples**. We're just binding the tuple to `color` for use as a shortcut within this method because we're lazy.
- Line 12: As before, we set the color for the canvas. Only this time we use the random values we generated and feed them to the color class using Python's tuple unpacking syntax (since the Color class expects three individual color components instead of just 1. If we were to pass the tuple directly, that would be just 1 value being passed, regardless of the fact that the tuple itself contains 3 values).

This looks a lot nicer already! With a lot of skill and patience, you might even be able to create a nice little drawing!

Note: Since by default the `Color` instructions assume RGB mode and we're feeding a tuple with three random float values to it, it might very well happen that we end up with a lot of dark or even black colors if we are unlucky. That would be bad because by default the background color is dark as well, so you wouldn't be able to (easily) see the lines you draw. There is a nice trick to prevent this: Instead of creating a tuple with three random values, create a tuple like this: `(random(), 1., 1.)`. Then, when passing it to the color instruction, set the mode to HSV color space: `Color(*color, mode='hsv')`. This way you will have a smaller number of possible colors, but the colors that you get will always be equally bright: only the hue changes.

29.2.3 Bonus Points

At this point, we could say we are done. The widget does what it's supposed to do: it traces the touches and draws lines. It even draws circles at the positions where a line begins.

But what if the user wants to start a new drawing? With the current code, the only way to clear the window would be to restart the entire application. Luckily, we can do better. Let us add a *Clear* button that erases all the lines and circles that have been drawn so far. There are two options now:


- We could either create the button as a child of our widget. That would imply that if you create more than one widget, every widget gets its own button. If you're not careful, this will also allow users to draw on top of the button, which might not be what you want.
- Or we set up the button only once, initially, in our app class and when it's pressed we clear the widget.

For our simple example, it doesn't really matter that much. For larger applications you should give some thought to who does what in your app. We'll go with the second option here so that you see how you can build up your application's widget tree in your app class's *build()* method. We'll also change to the HSV color space (see preceding note):

```
1  from random import random
2  from kivy.app import App
3  from kivy.uix.widget import Widget
4  from kivy.uix.button import Button
5  from kivy.graphics import Color, Ellipse, Line
6
7
8  class MyPaintWidget(Widget):
9
10     def on_touch_down(self, touch):
11         color = (random(), 1, 1)
12         with self.canvas:
13             Color(*color, mode='hsv')
14             d = 30.
15             Ellipse(pos=(touch.x - d / 2, touch.y - d / 2), size=(d, d))
16             touch.ud['line'] = Line(points=(touch.x, touch.y))
17
18     def on_touch_move(self, touch):
19         touch.ud['line'].points += [touch.x, touch.y]
20
21
22 class MyPaintApp(App):
23
24     def build(self):
25         parent = Widget()
26         self.painter = MyPaintWidget()
27         clearbtn = Button(text='Clear')
28         clearbtn.bind(on_release=self.clear_canvas)
29         parent.add_widget(self.painter)
30         parent.add_widget(clearbtn)
31         return parent
32
33     def clear_canvas(self, obj):
34         self.painter.canvas.clear()
```

(continues on next page)

```
37 if __name__ == '__main__':
38     MyPaintApp().run()
```



Here's what happens:

- Line 4: We added an import statement to be able to use the `Button` class.
- Line 25: We create a dummy `Widget()` object as a parent for both our painting widget and the button we're about to add. This is just a poor-man's approach to setting up a widget tree hierarchy. We could just as well use a layout or do some other fancy stuff. Again: this widget does absolutely nothing except holding the two widgets we will now add to it as children.
- Line 26: We create our `MyPaintWidget()` as usual, only this time we don't return it directly but bind it to a variable name.
- Line 27: We create a button widget. It will have a label on it that displays the text 'Clear'.
- Line 28: We then bind the button's `on_release` event (which is fired when the button is pressed and then released) to the `callback function` `clear_canvas` defined on below on Lines 33 & 34.
- Line 29 & 30: We set up the widget hierarchy by making both the painter and the clearbtn children of the dummy parent widget. That means `painter` and `clearbtn` are now siblings in the usual computer science tree terminology.
- Line 33 & 34: Up to now, the button did nothing. It was there, visible, and you could press it, but nothing would happen. We change that here: we create a small, throw-away function that is going to be our `callback function` when the button is pressed. The function just clears the painter's canvas' contents, making it black again.

Note: The Kivy Widget class, by design, is kept simple. There are no general properties such as background color and border color. Instead, the examples and documentation illustrate how to easily handle such simple things yourself, as we have done here, setting the color for the canvas, and drawing the shape. From a simple start, you can move to more elaborate customization. Higher-level built-in widgets, deriving from Widget, such as Button, do have convenience properties such as `background_color`, but these vary by widget. Use the API docs to see what is offered by a widget, and subclass if you need to add more functionality.

Congratulations! You've written your first Kivy widget. Obviously this was just a quick introduction.

There is much more to discover. We suggest taking a short break to let what you just learned sink in. Maybe draw some nice pictures to relax? If you feel like you've understood everything and are ready for more, we encourage you to read on.

CRASH COURSE

The Kivy Crash Course is a series of YouTube video tutorials by Kivy core developer [inclement](#). They provide a simple walkthrough in Kivy for users who know how to code in Python and is friendly to Python beginners. After the Pong and Paint tutorials, this set of videos covers basic features and techniques that can be used to create your app quicker, keeping your code elegant and eye-friendly.

30.1 Basic Info

The Crash Course primarily consists of a series of YouTube videos, each roughly 10 minutes long. There are also articles describing some of the videos and the code used in the videos.

30.1.1 Topics covered by the Crash Course include:

- Use of the basic Kivy widgets such as the Label, Button, Scatter and TextInput
- Building an app for android with python-for-android's [old toolchain](#)
- Binding functions to events
- Using changes in variables on the go
- Smart user interface ([Kv language](#))
- Properties
- Canvas and drawing
- Label with scrolling
- Positioning and layouts
- Animation and Clock
- Accessing android API ([pyjnius](#), [plyer](#))
- Settings panel (and building your own options)
- ScreenManager

30.1.2 Links:

- Videos
- Articles
- Code

Part V

API REFERENCE

The API reference is a lexicographic list of all the different classes, methods and features that Kivy offers.

KIVY FRAMEWORK

Kivy is an open source library for developing multi-touch applications. It is cross-platform (Linux/OSX/Windows/Android/iOS) and released under the terms of the [MIT License](#).

It comes with native support for many multi-touch input devices, a growing library of multi-touch aware widgets and hardware accelerated OpenGL drawing. Kivy is designed to let you focus on building custom and highly interactive applications as quickly and easily as possible.

With Kivy, you can take full advantage of the dynamic nature of Python. There are thousands of high-quality, free libraries that can be integrated in your application. At the same time, performance-critical parts are implemented using [Cython](#).

See <http://kivy.org> for more information.

```
kivy.kivy_base_dir = '/home/docs/checkouts/readthedocs.org/user_builds/
kivy/envs/latest/lib/python3.7/site-packages/kivy'
    Kivy directory

kivy.kivy_config_fn = ''
    Kivy configuration filename

kivy.kivy_configure()
    Call post-configuration of Kivy. This function must be called if you create the window yourself.

kivy.kivy_data_dir = '/home/docs/checkouts/readthedocs.org/user_builds/
kivy/envs/latest/lib/python3.7/site-packages/kivy/data'
    Kivy data directory

kivy.kivy_examples_dir = '/home/docs/checkouts/readthedocs.org/user_builds/
kivy/envs/latest/share/kivy-examples'
    Kivy examples directory

kivy.kivy_home_dir = ''
    Kivy user-home storage directory

kivy.kivy_icons_dir = '/home/docs/checkouts/readthedocs.org/user_builds/
kivy/envs/latest/lib/python3.7/site-packages/kivy/data/icons/'
    Kivy icons config path (don't remove the last '')

kivy.kivy_options = {'audio': ('gstplayer', 'pygame', 'ffpyplayer',
'sdl2', 'avplayer'), 'camera': ('opencv', 'gi', 'avfoundation', 'android',
'picamera'), 'clipboard': ('android', 'winctypes', 'xsel', 'xclip',
'dbusclipper', 'nspaste', 'sdl2', 'pygame', 'dummy', 'gtk3'), 'image':
('tex', 'imageio', 'dds', 'sdl2', 'pygame', 'pil', 'ffpy', 'gif'),
'spelling': ('enchant', 'osxappkit'), 'text': ('pil', 'sdl2', 'pygame',
'sdlttf'), 'video': ('gstplayer', 'ffmpeg', 'ffpyplayer', 'null'),
>window': ('egl_rpi', 'sdl2', 'pygame', 'sdl', 'x11')}

    Global settings options for kivy
```

```
kivy.kivy_register_post_configuration(callback)
```

Register a function to be called when kivy_configure() is called.

Warning: Internal use only.

```
kivy.kivy_shader_dir = '/home/docs/checkouts/readthedocs.org/user_builds/kivy/envs/latest/lib/python3.7/site-packages/kivy/data/gls'
```

Kivy glsl shader directory

```
kivy.kivy_usermodules_dir = ''
```

Kivy user modules directory

```
kivy.parse_kivy_version(version)
```

Parses the kivy version as described in [require\(\)](#) into a 3-tuple of ([x, y, z], 'rc | a | b | dev | post', 'N') where N is the tag revision. The last two elements may be None.

```
kivy.require(version)
```

Require can be used to check the minimum version required to run a Kivy application. For example, you can start your application code like this:

```
import kivy  
kivy.require('1.0.1')
```

If a user attempts to run your application with a version of Kivy that is older than the specified version, an Exception is raised.

The Kivy version string is built like this:

```
X.Y.Z[tag[tagrevision]]  
  
X is the major version  
Y is the minor version  
Z is the bugfixes revision
```

The tag is optional, but may be one of '.dev', '.post', 'a', 'b', or 'rc'. The tagrevision is the revision number of the tag.

Warning: You must not ask for a version with a tag, except -dev. Asking for a 'dev' version will just warn the user if the current Kivy version is not a -dev, but it will never raise an exception. You must not ask for a version with a tagrevision.

31.1 NO DOCUMENTATION (module kivy.uix.recycleview)

31.2 Animation

[Animation](#) and [AnimationTransition](#) are used to animate [Widget](#) properties. You must specify at least a property name and target value. To use an Animation, follow these steps:

- Setup an Animation object
- Use the Animation object on a Widget

31.2.1 Simple animation

To animate a Widget's x or y position, simply specify the target x/y values where you want the widget positioned at the end of the animation:

```
anim = Animation(x=100, y=100)
anim.start(widget)
```

The animation will last for 1 second unless `duration` is specified. When `anim.start()` is called, the Widget will move smoothly from the current x/y position to (100, 100).

31.2.2 Multiple properties and transitions

You can animate multiple properties and use built-in or custom transition functions using `transition` (or the `t=` shortcut). For example, to animate the position and size using the 'in_quad' transition:

```
anim = Animation(x=50, size=(80, 80), t='in_quad')
anim.start(widget)
```

Note that the `t=` parameter can be the string name of a method in the `AnimationTransition` class or your own animation function.

31.2.3 Sequential animation

To join animations sequentially, use the '+' operator. The following example will animate to x=50 over 1 second, then animate the size to (80, 80) over the next two seconds:

```
anim = Animation(x=50) + Animation(size=(80, 80), duration=2.)
anim.start(widget)
```

31.2.4 Parallel animation

To join animations in parallel, use the '&' operator. The following example will animate the position to (80, 10) over 1 second, whilst in parallel animating the size to (800, 800):

```
anim = Animation(pos=(80, 10))
anim &= Animation(size=(800, 800), duration=2.)
anim.start(widget)
```

Keep in mind that creating overlapping animations on the same property may have unexpected results. If you want to apply multiple animations to the same property, you should either schedule them sequentially (via the '+' operator or using the `on_complete` callback) or cancel previous animations using the `cancel_all` method.

31.2.5 Repeating animation

New in version 1.8.0.

Note: This is currently only implemented for ‘Sequence’ animations.

To set an animation to repeat, simply set the `Sequence.repeat` property to `True`:

```
anim = Animation(...) + Animation(...)  
anim.repeat = True  
anim.start(widget)
```

For flow control of animations such as stopping and cancelling, use the methods already in place in the animation module.

class `kivy.animation.Animation(**kw)`
Bases: `kivy.event.EventDispatcher`

Create an animation definition that can be used to animate a Widget.

Parameters

duration or d: float, defaults to 1. Duration of the animation, in seconds.

transition or t: str or func Transition function for animate properties. It can be the name of a method from `AnimationTransition`.

step or s: float Step in milliseconds of the animation. Defaults to 0, which means the animation is updated for every frame.

To update the animation less often, set the step value to a float. For example, if you want to animate at 30 FPS, use `s=1/30`.

Events

on_start: animation, widget Fired when the animation is started on a widget.

on_complete: animation, widget Fired when the animation is completed or stopped on a widget.

on_progress: animation, widget, progression Fired when the progression of the animation is changing.

Changed in version 1.4.0: Added `s/step` parameter.

Changed in version 1.10.0: The default value of the step parameter was changed from `1/60.` to `0.`

property `animated_properties`

Return the properties used to animate.

`cancel(widget)`

Cancel the animation previously applied to a widget. Same effect as `stop`, except the `on_complete` event will *not* be triggered!

New in version 1.4.0.

`static cancel_all(widget, *largs)`

Cancel all animations that concern a specific widget / list of properties. See `cancel`.

Example:

```
anim = Animation(x=50)  
anim.start(widget)
```

(continues on next page)

```
# and later
Animation.cancel_all(widget, 'x')
```

New in version 1.4.0.

Changed in version 2.1.0: If the parameter `widget` is `None`, all animated widgets will be the target and cancelled. If `largs` is also given, animation of these properties will be canceled for all animated widgets.

cancel_property(*widget, prop*)

Even if an animation is running, remove a property. It will not be animated further. If it was the only/last property being animated, the animation will be canceled (see `cancel`)

New in version 1.4.0.

property duration

Return the duration of the animation.

have_properties_to_animate(*widget*)

Return True if a widget still has properties to animate.

New in version 1.8.0.

start(*widget*)

Start the animation on a widget.

stop(*widget*)

Stop the animation previously applied to a widget, triggering the `on_complete` event.

static stop_all(*widget, *largs*)

Stop all animations that concern a specific widget / list of properties.

Example:

```
anim = Animation(x=50)
anim.start(widget)

# and later
Animation.stop_all(widget, 'x')
```

stop_property(*widget, prop*)

Even if an animation is running, remove a property. It will not be animated further. If it was the only/last property being animated, the animation will be stopped (see `stop`).

property transition

Return the transition of the animation.


class kivy.animation.AnimationTransition

Bases: `builtins.object`


Collection of animation functions to be used with the `Animation` object. Easing Functions ported to Kivy from the Clutter Project <https://developer.gnome.org/clutter/stable/ClutterAlpha.html>

The `progress` parameter in each animation function is in the range 0-1.


static in_back(progress)




static in_bounce(progress)




static in_circ(progress)




static in_cubic(progress)




static in_elastic(progress)




static in_expo(progress)



```
static in_out_back(progress)
```




```
static in_out_bounce(progress)
```



```
static in_out_circ(progress)
```




```
static in_out_cubic(progress)
```



```
static in_out_elastic(progress)
```




```
static in_out_expo(progress)
```




static in_out_quad(progress)



static in_out_quart(progress)




static in_out_quint(progress)




static in_out_sine(progress)




static in_quad(progress)




static in_quart(progress)




static in_quint(progress)




static in_sine(progress)




static linear(progress)




static out_back(progress)




static out_bounce(progress)



static out_circ(progress)




static out_cubic(progress)




static out_elastic(progress)



static out_expo(progress)




static out_quad(progress)



static out_quart(progress)



static out_quint(progress)



```
static out_sine(progress)
```



31.3 Application

The `App` class is the base for creating Kivy applications. Think of it as your main entry point into the Kivy run loop. In most cases, you subclass this class and make your own app. You create an instance of your specific app class and then, when you are ready to start the application's life cycle, you call your instance's `App.run()` method.

31.3.1 Creating an Application

Method using `build()` override

To initialize your app with a widget tree, override the `build()` method in your app class and return the widget tree you constructed.

Here's an example of a very simple application that just shows a button:

```
...
Application example using build() + return
=====

An application can be built if you return a widget on build(), or if you_
→set
self.root.
...

import kivy
kivy.require('1.0.7')

from kivy.app import App
from kivy.uix.button import Button

class TestApp(App):

    def build(self):
        # return a Button() as a root widget
        return Button(text='hello world')

if __name__ == '__main__':
    TestApp().run()
```

The file is also available in the examples folder at `kivy/examples/application/app_with_build.py`.

Here, no widget tree was constructed (or if you will, a tree with only the root node).

Method using kv file

You can also use the *Kivy Language* for creating applications. The .kv can contain rules and root widget definitions at the same time. Here is the same example as the Button one in a kv file.

Contents of ‘test.kv’:

```
#:kivy 1.0

Button:
    text: 'Hello from test.kv'
```

Contents of ‘main.py’:

```
...
Application built from a .kv file
=====

This shows how to implicitly use a .kv file for your application. You should see a full screen button labelled "Hello from test.kv".

After Kivy instantiates a subclass of App, it implicitly searches for a .kv file. The file test.kv is selected because the name of the subclass of App is
TestApp, which implies that kivy should try to load "test.kv". That file contains a root Widget.
...

import kivy
kivy.require('1.0.7')

from kivy.app import App

class TestApp(App):
    pass

if __name__ == '__main__':
    TestApp().run()
```

See `kivy/examples/application/app_with_kv.py`.

The relationship between main.py and test.kv is explained in [App.load_kv\(\)](#).

31.3.2 Application configuration

Use the configuration file

Your application might need its own configuration file. The `App` class handles ‘ini’ files automatically if you add the section key-value pair to the `App.build_config()` method using the `config` parameter (an instance of `ConfigParser`):

```
class TestApp(App):
    def build_config(self, config):
        config.setdefault('section1', {
            'key1': 'value1',
            'key2': '42'
        })
```

As soon as you add one section to the config, a file is created on the disk (see `get_application_config` for its location) and named based your class name. “TestApp” will give a config file named “test.ini” with the content:

```
[section1]
key1 = value1
key2 = 42
```


The “test.ini” will be automatically loaded at runtime and you can access the configuration in your `App.build()` method:

```
class TestApp(App):
    def build_config(self, config):
        config.setdefault('section1', {
            'key1': 'value1',
            'key2': '42'
        })

    def build(self):
        config = self.config
        return Label(text='key1 is %s and key2 is %d' % (
            config.get('section1', 'key1'),
            config.getint('section1', 'key2')))
```

Create a settings panel

Your application can have a settings panel to let your user configure some of your config tokens. Here is an example done in the KinectViewer example (available in the examples directory):



You can add your own panels of settings by extending the `App.build_settings()` method. Check the [Settings](#) about how to create a panel, because you need a JSON file / data first.

Let's take as an example the previous snippet of TestApp with custom config. We could create a JSON like this:

```
[ { "type": "title",
  "title": "Test application" },

{ "type": "options",
  "title": "My first key",
  "desc": "Description of my first key",
  "section": "section1",
  "key": "key1",
  "options": ["value1", "value2", "another value"] },

{ "type": "numeric",
  "title": "My second key",
  "desc": "Description of my second key",
  "section": "section1",
  "key": "key2" }
]
```

Then, we can create a panel using this JSON to automatically create all the options and link them to our `App.config` ConfigParser instance:

```
class TestApp(App):
    # ...
    def build_settings(self, settings):
        jsondata = """... put the json data here ..."""
        settings.add_json_panel('Test application',
                               self.config, data=jsondata)
```

That's all! Now you can press F1 (default keystroke) to toggle the settings panel or press the "settings" key on your android device. You can manually call `App.open_settings()` and `App.close_settings()` if you want to handle this manually. Every change in the panel is automatically saved in the config file.

You can also use `App.build_settings()` to modify properties of the settings panel. For instance, the default panel has a sidebar for switching between json panels whose width defaults to 200dp. If you'd prefer this to be narrower, you could add:

```
settings.interface.menu.width = dp(100)
```

to your `build_settings()` method.

You might want to know when a config value has been changed by the user in order to adapt or reload your UI. You can then overload the `on_config_change()` method:

```
class TestApp(App):
    # ...
    def on_config_change(self, config, section, key, value):
        if config is self.config:
            token = (section, key)
            if token == ('section1', 'key1'):
                print('Our key1 has been changed to', value)
            elif token == ('section1', 'key2'):
                print('Our key2 has been changed to', value)
```

The Kivy configuration panel is added by default to the settings instance. If you don't want this panel, you can declare your Application as follows:

```
class TestApp(App):
    use_kivy_settings = False
    # ...
```

This only removes the Kivy panel but does not stop the settings instance from appearing. If you want to prevent the settings instance from appearing altogether, you can do this:

```
class TestApp(App):
    def open_settings(self, *largs):
        pass
```

New in version 1.0.7.

31.3.3 Profiling with on_start and on_stop

It is often useful to profile python code in order to discover locations to optimise. The standard library profilers (<http://docs.python.org/2/library/profile.html>) provides multiple options for profiling code. For profiling the entire program, the natural approaches of using `profile` as a module or `profile's run` method does not work with Kivy. It is however, possible to use `App.on_start()` and `App.on_stop()` methods:

```
import cProfile

class MyApp(App):
    def on_start(self):
        self.profile = cProfile.Profile()
        self.profile.enable()

    def on_stop(self):
        self.profile.disable()
        self.profile.dump_stats('myapp.profile')
```

This will create a file called `myapp.profile` when you exit your app.

31.3.4 Customising layout

You can choose different settings widget layouts by setting `App.settings_cls`. By default, this is a `Settings` class which provides the pictured sidebar layout, but you could set it to any of the other layouts provided in `kivy.uix.settings` or create your own. See the module documentation for `kivy.uix.settings` for more information.

You can customise how the settings panel is displayed by overriding `App.display_settings()` which is called before displaying the settings panel on the screen. By default, it simply draws the panel on top of the window, but you could modify it to (for instance) show the settings in a `Popup` or add it to your app's `ScreenManager` if you are using one. If you do so, you should also modify `App.close_settings()` to exit the panel appropriately. For instance, to have the settings panel appear in a popup you can do:

```
def display_settings(self, settings):
    try:
        p = self.settings_popup
    except AttributeError:
        self.settings_popup = Popup(content=settings,
                                      title='Settings',
                                      size_hint=(0.8, 0.8))
        p = self.settings_popup
    if p.content is not settings:
        p.content = settings
    p.open()

def close_settings(self, *args):
    try:
        p = self.settings_popup
        p.dismiss()
    except AttributeError:
        pass # Settings popup doesn't exist
```

Finally, if you want to replace the current settings panel widget, you can remove the internal references to it using `App.destroy_settings()`. If you have modified `App.display_settings()`, you should be careful to detect if the settings panel has been replaced.

31.3.5 Pause mode

New in version 1.1.0.

On tablets and phones, the user can switch at any moment to another application. By default, your application will close and the `App.on_stop()` event will be fired.

If you support Pause mode, when switching to another application, your application will wait indefinitely until the user switches back to your application. There is an issue with OpenGL on Android devices: it is not guaranteed that the OpenGL ES Context will be restored when your app resumes. The mechanism for restoring all the OpenGL data is not yet implemented in Kivy.

The currently implemented Pause mechanism is:

1. Kivy checks every frame if Pause mode is activated by the Operating System due to the user switching to another application, a phone shutdown or any other reason.
2. `App.on_pause()` is called:
3. If False is returned, then `App.on_stop()` is called.
4. If True is returned (default case), the application will sleep until the OS resumes our App.

5. When the app is resumed, `App.on_resume()` is called.
6. If our app memory has been reclaimed by the OS, then nothing will be called.

Here is a simple example of how `on_pause()` should be used:

```
class TestApp(App):

    def on_pause(self):
        # Here you can save data if needed
        return True

    def on_resume(self):
        # Here you can check if any data needs replacing (usually nothing)
        pass
```

Warning: Both `on_pause` and `on_stop` must save important data because after `on_pause` is called, `on_resume` may not be called at all.

31.3.6 Asynchronous app

In addition to running an app normally, Kivy can be run within an async event loop such as provided by the standard library `asyncio` package or the `trio` package (highly recommended).

Background

Normally, when a Kivy app is run, it blocks the thread that runs it until the app exits. Internally, at each clock iteration it executes all the app callbacks, handles graphics and input, and idles by sleeping for any remaining time.

To be able to run asynchronously, the Kivy app may not sleep, but instead must release control of the running context to the asynchronous event loop running the Kivy app. We do this when idling by calling the appropriate functions of the `async` package being used instead of sleeping.

Async configuration

To run a Kivy app asynchronously, either the `async_runTouchApp()` or `App.async_run()` coroutine must be scheduled to run in the event loop of the `async` library being used.

The environmental variable `KIVY_EVENTLOOP` or the `async_lib` parameter in `async_runTouchApp()` and `App.async_run()` set the `async` library that Kivy uses internally when the app is run with `async_runTouchApp()` and `App.async_run()`. It can be set to one of “`asyncio`” when the standard library `asyncio` is used, or “`trio`” if the `trio` library is used. If the environment variable is not set and `async_lib` is not provided, the stdlib `asyncio` is used.

`init_async_lib()` can also be directly called to set the `async` library to use, but it may only be called before the app has begun running with `async_runTouchApp()` or `App.async_run()`.

To run the app asynchronously, one schedules `async_runTouchApp()` or `App.async_run()` to run within the given library’s `async` event loop as in the examples shown below. Kivy is then treated as just another coroutine that the given library runs in its event loop. Internally, Kivy will use the specified `async` library’s API, so `KIVY_EVENTLOOP` or `async_lib` must match the `async` library that is running Kivy.

For a fuller basic and more advanced examples, see the demo apps in `examples/async`.

Asyncio example ~~~~~

```
import asyncio

from kivy.app import async_runTouchApp
from kivy.uix.label import Label

loop = asyncio.get_event_loop()
loop.run_until_complete(
    async_runTouchApp(Label(text='Hello, World!'), async_lib='asyncio'))
loop.close()
```

Trio example ~~~~~

```
import trio

from kivy.app import async_runTouchApp
from kivy.uix.label import Label

from functools import partial

# use functools.partial() to pass keyword arguments:
async_runTouchApp_func = partial(async_runTouchApp, async_lib='trio')

trio.run(async_runTouchApp_func, Label(text='Hello, World!'))
```

31.3.7 Interacting with Kivy app from other coroutines

It is fully safe to interact with any kivy object from other coroutines running within the same async event loop. This is because they are all running from the same thread and the other coroutines are only executed when Kivy is idling.

Similarly, the kivy callbacks may safely interact with objects from other coroutines running in the same event loop. Normal single threaded rules apply to both case.

New in version 2.0.0.

```
class kivy.app.App(**kwargs)
    Bases: kivy.event.Dispatcher
```

Application class, see module documentation for more information.

Events

on_start: Fired when the application is being started (before the *runTouchApp()* call).

on_stop: Fired when the application stops.

on_pause: Fired when the application is paused by the OS.

on_resume: Fired when the application is resumed from pause by the OS. Beware: you have no guarantee that this event will be fired after the *on_pause* event has been called.

Changed in version 1.7.0: Parameter *kv_file* added.

Changed in version 1.8.0: Parameters *kv_file* and *kv_directory* are now properties of App.

async async_run(*async_lib=None*)

Identical to [run\(\)](#), but is a coroutine and can be scheduled in a running async event loop.

See [kivy.app](#) for example usage.

New in version 2.0.0.

build()

Initializes the application; it will be called only once. If this method returns a widget (tree), it will be used as the root widget and added to the window.

Returns None or a root [Widget](#) instance if no self.root exists.

build_config(*config*)

New in version 1.0.7.

This method is called before the application is initialized to construct your [ConfigParser](#) object. This is where you can put any default section / key / value for your config. If anything is set, the configuration will be automatically saved in the file returned by [get_application_config\(\)](#).

Parameters

config: [ConfigParser](#) Use this to add default section / key / value items

build_settings(*settings*)

New in version 1.0.7.

This method is called when the user (or you) want to show the application settings. It is called once when the settings panel is first opened, after which the panel is cached. It may be called again if the cached settings panel is removed by [destroy_settings\(\)](#).

You can use this method to add settings panels and to customise the settings widget e.g. by changing the sidebar width. See the module documentation for full details.

Parameters

settings: [Settings](#) Settings instance for adding panels

close_settings(args*)**

Close the previously opened settings panel.

Returns True if the settings has been closed.

config

Returns an instance of the [ConfigParser](#) for the application configuration. You can use this to query some config tokens in the [build\(\)](#) method.

create_settings()

Create the settings panel. This method will normally be called only one time per application life-time and the result is cached internally, but it may be called again if the cached panel is removed by [destroy_settings\(\)](#).

By default, it will build a settings panel according to [settings_cls](#), call [build_settings\(\)](#), add a Kivy panel if [use_kivy_settings](#) is True, and bind to on_close/on_config_change.

If you want to plug your own way of doing settings, without the Kivy panel or close/config change events, this is the method you want to overload.

New in version 1.8.0.

destroy_settings()

New in version 1.8.0.

Dereferences the current settings panel if one exists. This means that when [App.open_settings\(\)](#) is next run, a new panel will be created and displayed. It doesn't affect

any of the contents of the panel, but lets you (for instance) refresh the settings panel layout if you have changed the settings widget in response to a screen size change.

If you have modified `open_settings()` or `display_settings()`, you should be careful to correctly detect if the previous settings widget has been destroyed.

property directory

New in version 1.0.7.

Return the directory where the application lives.

display_settings(*settings*)

New in version 1.8.0.

Display the settings panel. By default, the panel is drawn directly on top of the window. You can define other behaviour by overriding this method, such as adding it to a ScreenManager or Popup.

You should return True if the display is successful, otherwise False.

Parameters

settings: **Settings** You can modify this object in order to modify the settings display.

get_application_config(*defaultpath*='%(appdir)s%(appname)s.ini')

Return the filename of your application configuration. Depending on the platform, the application file will be stored in different locations:

- on iOS: <appdir>/Documents/<appname>.ini
- on Android: <user_data_dir>/<appname>.ini
- otherwise: <appdir>/<appname>.ini

When you are distributing your application on Desktops, please note that if the application is meant to be installed system-wide, the user might not have write-access to the application directory. If you want to store user settings, you should overload this method and change the default behavior to save the configuration file in the user directory.

```
class TestApp(App):
    def get_application_config(self):
        return super(TestApp, self).get_application_config(
            '~/.%(appname)s.ini')
```

Some notes:

- The tilda ‘~’ will be expanded to the user directory.
- %(appdir)s will be replaced with the application **directory**
- %(appname)s will be replaced with the application **name**

New in version 1.0.7.

Changed in version 1.4.0: Customized the defaultpath for iOS and Android platforms. Added a defaultpath parameter for desktop OS's (not applicable to iOS and Android.)

Changed in version 1.11.0: Changed the Android version to make use of the **user_data_dir** and added a missing dot to the iOS config file name.

get_application_icon()

Return the icon of the application.

get_application_name()

Return the name of the application.

static get_running_app()

Return the currently running application instance.

New in version 1.1.0.

icon

Icon of your application. The icon can be located in the same directory as your main file. You can set this as follows:

```
class MyApp(App):
    def build(self):
        self.icon = 'myicon.png'
```

New in version 1.0.5.

Changed in version 1.8.0: *icon* is now a *StringProperty*. Don't set the icon in the class as previously stated in the documentation.

Note: For Kivy prior to 1.8.0, you need to set this as follows:

```
class MyApp(App):
    icon = 'customicon.png'
```

Recommended 256x256 or 1024x1024? for GNU/Linux and Mac OSX 32x32 for Windows7 or less. <= 256x256 for windows 8 256x256 does work (on Windows 8 at least), but is scaled down and doesn't look as good as a 32x32 icon.

kv_directory

Path of the directory where application kv is stored, defaults to None

New in version 1.8.0.

If a kv_directory is set, it will be used to get the initial kv file. By default, the file is assumed to be in the same directory as the current App definition file.

kv_file

Filename of the Kv file to load, defaults to None.

New in version 1.8.0.

If a kv_file is set, it will be loaded when the application starts. The loading of the "default" kv file will be prevented.

load_config()

(internal) This function is used for returning a ConfigParser with the application configuration. It's doing 3 things:

1. Creating an instance of a ConfigParser
2. Loading the default configuration by calling *build_config()*, then
3. If it exists, it loads the application configuration file, otherwise it creates one.

Returns *ConfigParser* instance

load_kv(*filename=None*)

This method is invoked the first time the app is being run if no widget tree has been constructed before for this app. This method then looks for a matching kv file in the same directory as the file that contains the application class.

For example, say you have a file named main.py that contains:

```
class ShowcaseApp(App):
    pass
```

This method will search for a file named *showcase.kv* in the directory that contains *main.py*. The name of the kv file has to be the lowercase name of the class, without the 'App' postfix at the end if it exists.

You can define rules and a root widget in your kv file:

```
<ClassName>: # this is a rule
    ...
ClassName: # this is a root widget
    ...
```

There must be only one root widget. See the [Kivy Language](#) documentation for more information on how to create kv files. If your kv file contains a root widget, it will be used as `self.root`, the root widget for the application.

Note: This function is called from `run()`, therefore, any widget whose styling is defined in this kv file and is created before `run()` is called (e.g. in `__init__`), won't have its styling applied. Note that `build()` is called after `load_kv` has been called.

property name

New in version 1.0.7.

Return the name of the application based on the class name.

on_config_change(config, section, key, value)

Event handler fired when a configuration token has been changed by the settings page.

Changed in version 1.10.1: Added corresponding `on_config_change` event.

on_pause()

Event handler called when Pause mode is requested. You should return True if your app can go into Pause mode, otherwise return False and your application will be stopped.

You cannot control when the application is going to go into this mode. It's determined by the Operating System and mostly used for mobile devices (android/ios) and for resizing.

The default return value is True.

New in version 1.1.0.

Changed in version 1.10.0: The default return value is now True.

on_resume()

Event handler called when your application is resuming from the Pause mode.

New in version 1.1.0.

Warning: When resuming, the OpenGL Context might have been damaged / freed. This is where you can reconstruct some of your OpenGL state e.g. FBO content.

on_start()

Event handler for the `on_start` event which is fired after initialization (after `build()` has been called) but before the application has started running.

on_stop()

Event handler for the *on_stop* event which is fired when the application has finished running (i.e. the window is about to be closed).

open_settings(*args)

Open the application settings panel. It will be created the very first time, or recreated if the previously cached panel has been removed by *destroy_settings()*. The settings panel will be displayed with the *display_settings()* method, which by default adds the settings panel to the Window attached to your application. You should override that method if you want to display the settings panel differently.

Returns True if the settings has been opened.

options

Options passed to the *__init__* of the App

root

The *root* widget returned by the *build()* method or by the *load_kv()* method if the kv file contains a root widget.

property root_window

New in version 1.9.0.

Returns the root window instance used by *run()*.

run()

Launches the app in standalone mode.

settings_cls

New in version 1.8.0.

The class used to construct the settings panel and the instance passed to *build_config()*. You should use either *Settings* or one of the provided subclasses with different layouts (*SettingsWithSidebar*, *SettingsWithSpinner*, *SettingsWithTabbedPanel*, *SettingsWithNoMenu*). You can also create your own Settings subclass. See the documentation of *Settings* for more information.

settings_cls is an *ObjectProperty* and defaults to *SettingsWithSpinner* which displays settings panels with a spinner to switch between them. If you set a string, the *Factory* will be used to resolve the class.

stop(*args)

Stop the application.

If you use this method, the whole application will stop by issuing a call to *stopTouchApp()*.

title

Title of your application. You can set this as follows:

```
class MyApp(App):
    def build(self):
        self.title = 'Hello world'
```

New in version 1.0.5.

Changed in version 1.8.0: *title* is now a *StringProperty*. Don't set the title in the class as previously stated in the documentation.

Note: For Kivy < 1.8.0, you can set this as follows:

```
class MyApp(App):
    title = 'Custom title'
```

If you want to dynamically change the title, you can do:

```
from kivy.base import EventLoop  
EventLoop.window.title = 'New title'
```

use_kivy_settings = True

New in version 1.0.7.

If True, the application settings will also include the Kivy settings. If you don't want the user to change any kivy settings from your settings UI, change this to False.

property user_data_dir

New in version 1.7.0.

Returns the path to the directory in the users file system which the application can use to store additional data.

Different platforms have different conventions with regards to where the user can store data such as preferences, saved games and settings. This function implements these conventions. The <app_name> directory is created when the property is called, unless it already exists.

On iOS, *~/Documents/<app_name>* is returned (which is inside the app's sandbox).

On Windows, *%APPDATA%/<app_name>* is returned.

On OS X, *~/Library/Application Support/<app_name>* is returned.

On Linux, *\$XDG_CONFIG_HOME/<app_name>* is returned.

On Android, *Context.GetFilesDir* is returned.

Changed in version 1.11.0: On Android, this function previously returned */sd-card/<app_name>*. This folder became read-only by default in Android API 26 and the user_data_dir has therefore been moved to a writeable location.

async kivy.app.async_runTouchApp(widget=None, embedded=False, async_lib=None)

Identical to *runTouchApp()* but instead it is a coroutine that can be run in an existing async event loop.

async_lib is the async library to use. See *kivy.app* for details and example usage.

New in version 2.0.0.

kivy.app.runTouchApp(widget=None, embedded=False)

Static main function that starts the application loop. You can access some magic via the following arguments:

See *kivy.app* for example usage.

Parameters

<empty> To make dispatching work, you need at least one input listener. If not, application will leave. (MTWindow act as an input listener)

widget If you pass only a widget, a MTWindow will be created and your widget will be added to the window as the root widget.

embedded No event dispatching is done. This will be your job.

widget + embedded No event dispatching is done. This will be your job but we try to get the window (must be created by you beforehand) and add the widget to it. Very useful for embedding Kivy in another toolkit. (like Qt, check kivy-designed)

```
kivy.app.stopTouchApp()  
Stop the current application by leaving the main loop.  
See kivy.app for example usage.
```

31.4 Asynchronous data loader

This is the Asynchronous Loader. You can use it to load an image and use it, even if data are not yet available. You must specify a default loading image when using the loader:

```
from kivy.loader import Loader  
image = Loader.image('mysprite.png')
```

You can also load an image from a url:

```
image = Loader.image('http://mysite.com/test.png')
```

If you want to change the default loading image, you can do:

```
Loader.loading_image = Image('another_loading.png')
```

31.4.1 Tweaking the asynchronous loader

New in version 1.6.0.

You can tweak the loader to provide a better user experience or more performance, depending of the images you are going to load. Take a look at the parameters:

- `Loader.num_workers` - define the number of threads to start for loading images.
- `Loader.max_upload_per_frame` - define the maximum image uploads in GPU to do per frame.

```
class kivy.loader.LoaderBase  
Bases: builtins.object
```

Common base for the Loader and specific implementations. By default, the Loader will be the best available loader implementation.

The `_update()` function is called every 1 / 25.s or each frame if we have less than 25 FPS.

property error_image

Image used for error. You can change it by doing:

```
Loader.error_image = 'error.png'
```

Changed in version 1.6.0: Not readonly anymore.

image(filename, load_callback=None, post_callback=None, **kwargs)

Load a image using the Loader. A ProxyImage is returned with a loading image. You can use it as follows:

```
from kivy.app import App  
from kivy.uix.image import Image  
from kivy.loader import Loader  
  
class TestApp(App):  
    def _image_loaded(self, proxyImage):
```

(continues on next page)

```

if proxyImage.image.texture:
    self.image.texture = proxyImage.image.texture

def build(self):
    proxyImage = Loader.image("myPic.jpg")
    proxyImage.bind(on_load=self._image_loaded)
    self.image = Image()
    return self.image

TestApp().run()

```

In order to cancel all background loading, call `Loader.stop()`.

property loading_image

Image used for loading. You can change it by doing:

```
Loader.loading_image = 'loading.png'
```

Changed in version 1.6.0: Not readonly anymore.

property max_upload_per_frame

The number of images to upload per frame. By default, we'll upload only 2 images to the GPU per frame. If you are uploading many small images, you can easily increase this parameter to 10 or more. If you are loading multiple full HD images, the upload time may have consequences and block the application. If you want a smooth experience, use the default.

As a matter of fact, a Full-HD RGB image will take ~6MB in memory, so it may take time. If you have activated `mipmap=True` too, then the GPU must calculate the mipmap of these big images too, in real time. Then it may be best to reduce the `max_upload_per_frame` to 1 or 2. If you want to get rid of that (or reduce it a lot), take a look at the DDS format.

New in version 1.6.0.

property num_workers

Number of workers to use while loading (used only if the loader implementation supports it). This setting impacts the loader only on initialization. Once the loader is started, the setting has no impact:

```
from kivy.loader import Loader
Loader.num_workers = 4
```

The default value is 2 for giving a smooth user experience. You could increase the number of workers, then all the images will be loaded faster, but the user will not be able to use the application while loading. Prior to 1.6.0, the default number was 20, and loading many full-hd images was completely blocking the application.

New in version 1.6.0.

pause()

Pause the loader, can be useful during interactions.

New in version 1.6.0.

resume()

Resume the loader, after a `pause()`.

New in version 1.6.0.

run(*args)

Main loop for the loader.

```

start()
    Start the loader thread/process.

stop()
    Stop the loader thread/process.

class kivy.loader.ProxyImage(arg, **kwargs)
    Bases: kivy.core.image.Image
        Image returned by the Loader.image() function.

Properties

    loaded: bool, defaults to False This value may be True if the image is already
        cached.

Events

    on_load Fired when the image is loaded or changed.

    on_error Fired when the image cannot be loaded. error: Exception data that oc-
        curred

```

31.5 Atlas

New in version 1.1.0.

Atlas manages texture atlases: packing multiple textures into one. With it, you reduce the number of images loaded and speedup the application loading. This module contains both the `Atlas` class and command line processing for creating an atlas from a set of individual PNG files. The command line section requires the Pillow library, or the defunct Python Imaging Library (PIL), to be installed.

An Atlas is composed of 2 or more files:

- a json file (.atlas) that contains the image file names and texture locations of the atlas.
- one or multiple image files containing textures referenced by the .atlas file.

31.5.1 Definition of .atlas files

A file with `<basename>.atlas` is a json file formatted like this:

```
{
    "<basename>-<index>.png": {
        "id1": [ <x>, <y>, <width>, <height> ],
        "id2": [ <x>, <y>, <width>, <height> ],
        # ...
    },
    # ...
}
```

Example from the Kivy `data/images/defaulttheme.atlas`:

```
{
    "defaulttheme-0.png": {
        "progressbar_background": [431, 224, 59, 24],
        "image-missing": [253, 344, 48, 48],
        "filechooser_selected": [1, 207, 118, 118],
        "bubble_btn": [83, 174, 32, 32],
    }
}
```

(continues on next page)

(continued from previous page)

```
# ... and more ...
}
```

In this example, “defaulttheme-0.png” is a large image, with the pixels in the rectangle from (431, 224) to (431 + 59, 224 + 24) usable as `atlas://data/images/defaulttheme/progressbar_background` in any image parameter.

31.5.2 How to create an Atlas

Warning: The atlas creation requires the Pillow library (or the defunct Imaging/PIL library). This requirement will be removed in the future when the Kivy core Image is able to support loading, blitting, and saving operations.

You can directly use this module to create atlas files with this command:

```
$ python -m kivy.atlas <basename> <size> <list of images...>
```

Let’s say you have a list of images that you want to put into an Atlas. The directory is named `images` with lots of 64x64 png files inside:

```
$ ls
images
$ cd images
$ ls
bubble.png bubble-red.png button.png button-down.png
```

You can combine all the png’s into one and generate the atlas file with:

```
$ python -m kivy.atlas myatlas 256x256 *.png
Atlas created at myatlas.atlas
1 image has been created
$ ls
bubble.png bubble-red.png button.png button-down.png myatlas.atlas
myatlas-0.png
```

As you can see, we get 2 new files: `myatlas.atlas` and `myatlas-0.png`. `myatlas-0.png` is a new 256x256 .png composed of all your images. If the size you specify is not large enough to fit all of the source images, more atlas images will be created as required e.g. `myatlas-1.png`, `myatlas-2.png` etc.

Note: When using this script, the ids referenced in the atlas are the base names of the images without the extension. So, if you are going to name a file `../images/button.png`, the id for this image will be `button`.

If you need path information included, you should include `use_path` as follows:

```
$ python -m kivy.atlas --use_path myatlas 256 *.png
```

In which case the id for `../images/button.png` will be `images_button`

31.5.3 How to use an Atlas

Usually, you would specify the images by supplying the path:

```
a = Button(background_normal='images/button.png',
            background_down='images/button_down.png')
```

In our previous example, we have created the atlas containing both images and put them in `images/myatlas.atlas`. You can use url notation to reference them:

```
a = Button(background_normal='atlas://images/myatlas/button',
            background_down='atlas://images/myatlas/button_down')
```

In other words, the path to the images is replaced by:

```
atlas://path/to/myatlas/id
# will search for the ``path/to/myatlas.atlas`` and get the image ``id``
```

Note: In the atlas url, there is no need to add the `.atlas` extension. It will be automatically append to the filename.

31.5.4 Manual usage of the Atlas

```
>>> from kivy.atlas import Atlas
>>> atlas = Atlas('path/to/myatlas.atlas')
>>> print(atlas.textures.keys())
['bubble', 'bubble-red', 'button', 'button-down']
>>> print(atlas['button'])
<kivy.graphics.texture.TextureRegion object at 0x2404d10>
```

class `kivy.atlas.Atlas(filename)`
Bases: `kivy.event.EventDispatcher`

Manage texture atlas. See module documentation for more information.

static create(outname, filenames, size, padding=2, use_path=False)

This method can be used to create an atlas manually from a set of images.

Parameters

outname: str Basename to use for `.atlas` creation and `-<idx>.png` associated images.

filenames: list List of filenames to put in the atlas.

size: int or list (width, height) Size of the atlas image. If the size is not large enough to fit all of the source images, more atlas images will be created as required.

padding: int, defaults to 2 Padding to put around each image.

Be careful. If you're using a padding < 2, you might have issues with the borders of the images. Because of the OpenGL linearization, it might use the pixels of the adjacent image.

If you're using a padding ≥ 2 , we'll automatically generate a "border" of 1px around your image. If you look at the result, don't be scared if the image inside is not exactly the same as yours :).

use_path: bool, defaults to False If True, the relative path of the source png file names will be included in the atlas ids rather than just in the file names. Leading dots and slashes will be excluded and all other slashes in the path will be replaced with underscores. For example, if *use_path* is False (the default) and the file name is `../data/tiles/green_grass.png`, the id will be `green_grass`. If *use_path* is True, it will be `data_tiles_green_grass`.

Changed in version 1.8.0: Parameter *use_path* added

filename

Filename of the current Atlas.

filename is an *AliasProperty* and defaults to None.

original_textures

List of original atlas textures (which contain the *textures*).

original_textures is a *ListProperty* and defaults to [].

New in version 1.9.1.

textures

List of available textures within the atlas.

textures is a *DictProperty* and defaults to {}.

31.6 Cache manager

The cache manager can be used to store python objects attached to a unique key. The cache can be controlled in two ways: with a object limit or a timeout.

For example, we can create a new cache with a limit of 10 objects and a timeout of 5 seconds:

```
# register a new Cache
Cache.register('mycache', limit=10, timeout=5)

# create an object + id
key = 'objectid'
instance = Label(text=text)
Cache.append('mycache', key, instance)

# retrieve the cached object
instance = Cache.get('mycache', key)
```

If the instance is NULL, the cache may have trashed it because you've not used the label for 5 seconds and you've reach the limit.

class kivy.cache.Cache
Bases: `builtins.object`

See module documentation for more information.

static append(*category*, *key*, *obj*, *timeout=None*)
Add a new object to the cache.

Parameters

category: str Identifier of the category.

key: str Unique identifier of the object to store.

obj: object Object to store in cache.

timeout: double (optional) Time after which to delete the object if it has not been used. If None, no timeout is applied.

Raises *ValueError*: If *None* is used as *key*.

Changed in version 2.0.0: Raises *ValueError* if *None* is used as *key*.

static get(*category*, *key*, *default=None*)

Get a object from the cache.

Parameters

category: str Identifier of the category.

key: str Unique identifier of the object in the store.

default: anything, defaults to None Default value to be returned if the key is not found.

static get_lastaccess(*category*, *key*, *default=None*)

Get the objects last access time in the cache.

Parameters

category: str Identifier of the category.

key: str Unique identifier of the object in the store.

default: anything, defaults to None Default value to be returned if the key is not found.

static get_timestamp(*category*, *key*, *default=None*)

Get the object timestamp in the cache.

Parameters

category: str Identifier of the category.

key: str Unique identifier of the object in the store.

default: anything, defaults to None Default value to be returned if the key is not found.

static print_usage()

Print the cache usage to the console.

static register(*category*, *limit=None*, *timeout=None*)

Register a new category in the cache with the specified limit.

Parameters

category: str Identifier of the category.

limit: int (optional) Maximum number of objects allowed in the cache. If None, no limit is applied.

timeout: double (optional) Time after which to delete the object if it has not been used. If None, no timeout is applied.

static remove(*category*, *key=None*)

Purge the cache.

Parameters

category: str Identifier of the category.

key: str (optional) Unique identifier of the object in the store. If this argument is not supplied, the entire category will be purged.

31.7 Clock object

The `Clock` object allows you to schedule a function call in the future; once or repeatedly at specified intervals. You can get the time elapsed between the scheduling and the calling of the callback via the `dt` argument:

```
# dt means delta-time
def my_callback(dt):
    pass

# call my_callback every 0.5 seconds
Clock.schedule_interval(my_callback, 0.5)

# call my_callback in 5 seconds
Clock.schedule_once(my_callback, 5)

# call my_callback as soon as possible (usually next frame.)
Clock.schedule_once(my_callback)
```

Note: If the callback returns False, the schedule will be canceled and won't repeat.

If you want to schedule a function to call with default arguments, you can use the `functools.partial` python module:

```
from functools import partial

def my_callback(value, key, *largs):
    pass

Clock.schedule_interval(partial(my_callback, 'my value', 'my key'), 0.5)
```

Conversely, if you want to schedule a function that doesn't accept the `dt` argument, you can use a `lambda` expression to write a short function that does accept `dt`. For Example:

```
def no_args_func():
    print("I accept no arguments, so don't schedule me in the clock")

Clock.schedule_once(lambda dt: no_args_func(), 0.5)
```

Note: You cannot unschedule an anonymous function unless you keep a reference to it. It's better to add `*args` to your function definition so that it can be called with an arbitrary number of parameters.

Important: The class method `callback` is weak-referenced: you are responsible for keeping a reference to your original object/callback. If you don't keep a reference, the `ClockBase` will never execute your callback. For example:

```
class Foo(object):
    def start(self):
        Clock.schedule_interval(self.callback, 0.5)

    def callback(self, dt):
```

(continues on next page)

```

print('In callback')

# A Foo object is created and the method start is called.
# Because no reference is kept to the instance returned from Foo(),
# the object will be collected by the Python Garbage Collector and
# your callback will be never called.
Foo().start()

# So you should do the following and keep a reference to the instance
# of foo until you don't need it anymore!
foo = Foo()
foo.start()

```

31.7.1 Schedule before frame

New in version 1.0.5.

Sometimes you need to schedule a callback BEFORE the next frame. Starting from 1.0.5, you can use a timeout of -1:

```

Clock.schedule_once(my_callback, 0) # call after the next frame
Clock.schedule_once(my_callback, -1) # call before the next frame

```

The Clock will execute all the callbacks with a timeout of -1 before the next frame even if you add a new callback with -1 from a running callback. However, **Clock** has an iteration limit for these callbacks: it defaults to 10.

If you schedule a callback that schedules a callback that schedules a ... etc more than 10 times, it will leave the loop and send a warning to the console, then continue after the next frame. This is implemented to prevent bugs from hanging or crashing the application.

If you need to increase the limit, set the `max_iteration` property:

```

from kivy.clock import Clock
Clock.max_iteration = 20

```

31.7.2 Triggered Events

New in version 1.0.5.

CyClockBase.create_trigger() is an advanced method way to defer a callback. It functions exactly like **CyClockBase.schedule_once()** and **CyClockBase.schedule_interval()** except that it doesn't immediately schedule the callback. Instead, one schedules the callback using the **ClockEvent** returned by it. This ensures that you can call the event multiple times but it won't be scheduled more than once. This is not the case with **CyClockBase.schedule_once()**:

```

# will run the callback twice before the next frame
Clock.schedule_once(my_callback)
Clock.schedule_once(my_callback)

# will run the callback once before the next frame
event = Clock.create_trigger(my_callback)
event()

```

(continues on next page)

(continued from previous page)

```
event()

# will also run the callback only once before the next frame
event = Clock.schedule_once(my_callback) # now it's already scheduled
event() # won't be scheduled again
event()
```

In addition, it is more convenient to create and bind to the triggered event than using `CyClockBase.schedule_once()` in a function:

```
from kivy.clock import Clock
from kivy.uix.widget import Widget

class Sample(Widget):
    def __init__(self, **kwargs):
        self._trigger = Clock.create_trigger(self.cb)
        super(Sample, self).__init__(**kwargs)
        self.bind(x=self._trigger, y=self._trigger)

    def cb(self, *largs):
        pass
```

Even if x and y changes within one frame, the callback is only run once.

31.7.3 Unscheduling

An event scheduled with `CyClockBase.schedule_once()`, `CyClockBase.schedule_interval()`, or with `CyClockBase.create_trigger()` and then triggered can be unscheduled in multiple ways. E.g:

```
def my_callback(dt):
    pass

# call my_callback every 0.5 seconds
event = Clock.schedule_interval(my_callback, 0.5)

# call my_callback in 5 seconds
event2 = Clock.schedule_once(my_callback, 5)

event_trig = Clock.create_trigger(my_callback, 5)
event_trig()

# unschedule using cancel
event.cancel()

# unschedule using Clock.unschedule
Clock.unschedule(event2)

# unschedule using Clock.unschedule with the callback
# NOT RECOMMENDED
Clock.unschedule(my_callback)
```

The best way to unschedule a callback is with `ClockEvent.cancel()`. `CyClockBase.unschedule()` is mainly an alias for that for that function. However, if the original callback itself

is passed to `CyClockBase.unschedule()`, it'll unschedule all instances of that callback (provided `all` is True, the default, otherwise only the first match is removed).

Calling `CyClockBase.unschedule()` on the original callback is highly discouraged because it's significantly slower than when using the event.

31.7.4 Clock Lifecycle

Kivy's clock has a lifecycle. By default, scheduling a callback after the Clock has ended will not raise an error, even though the callback may never be called. That's because most callbacks are like services, e.g. responding to a user button press - if the app is running the callbacks need to service the app and respond to the input, but once the app has stopped or is stopping, we can safely not process these events.

Other events always need to be processed. E.g. another thread may request a callback in kivy's thread and then process some result. If the event is not processed in Kivy's thread because the app stopped, the second thread may block forever hanging the application as it exits.

Consequently, we provide a API (`CyClockBase.create_lifecycle_aware_trigger()`) for scheduling callbacks that raise a `ClockNotRunningError` if the clock has stopped. If the scheduling succeeded it guarantees that one of its callbacks will be called. I.e. the new `CyClockBase.create_lifecycle_aware_trigger()` accepts an additional `clock_ended_callback` parameter. Normally, `callback` will be called when the event is processed. But, if the clock is stopped before it can be processed, if the application exited normally (and the app was started) and the event wasn't canceled, and the callbacks are not garbage collected, then `clock_ended_callback` will be called instead when the clock is stopped.

That is, given these conditions, if `ClockNotRunningError` was not raised when the event was scheduled, then one of these callbacks will be called - either `callback` if the event executed normally, or `clock_ended_callback` if the clock is stopped while the event is scheduled.

By default, events can be scheduled before the clock is started because it is assumed the clock will eventually be started when the app starts. I.e. calling `CyClockBase.create_lifecycle_aware_trigger()` before the clock and application starts will succeed. But if the app never actually starts, then neither of the callbacks may be executed.

New in version 2.0.0: The lifecycle was added in 2.0.0

31.7.5 Exception Handling

Kivy provides a exception handling manager, `ExceptionManager`, to handle its internal exceptions including exceptions raised by clock callbacks, without crashing the application. By default when an exception is raised, the app will crash. But, if a handler is registered with the exception manager and the handler handles the exception, the app will not crash and will continue as normal.:

```
from kivy.base import ExceptionHandler, ExceptionManager
class MyHandler(ExceptionHandler):
    def handle_exception(self, inst):
        if isinstance(inst, ValueError):
            Logger.exception('ValueError caught by MyHandler')
            return ExceptionManager.PASS
        return ExceptionManager.RAISE

ExceptionManager.add_handler(MyHandler())
```

Then, all `ValueError` exceptions will be logged to the console and ignored. Similarly, if a scheduled clock callback raises a `ValueError`, other clock events will still be processed normally.

If an event's callback raises an exception, before the exception handler is executed, the callback is immediately canceled.

It still is possible for the app to be corrupted if kivy itself is the source of the exception. I.e. even with a handler that ignores exceptions and doesn't crash, the app may be in a corrupted state if the error originates from within Kivy itself. However, the exception handler can help protect the app from crashing and can help protect against user callbacks crashing the app.

Changed in version 2.0.0: Prior to Kivy 2.0.0, an exception raised in a event's callback would cause the clock to crash and subsequent events may or may not be executed. Even if the exception was handled by an *ExceptionHandler*, there was no guarantee that some scheduled events would not be skipped.

From 2.0.0 onward, if a event's exception is handled by an *ExceptionHandler*, other events will be shielded from the exception and will execute normally.

31.7.6 Scheduling from `__del__`

It is not safe to schedule Clock events from a object's `__del__` or `__dealloc__` method. If you must schedule a Clock call from this method, use `CyClockBase.schedule_del_safe()` or `CyClockBase.schedule_lifecycle_aware_del_safe()` instead.

31.7.7 Threading and Callback Order

Beginning with 1.10.0, all the events scheduled for the same frame, e.g. all the events scheduled in the same frame with a `timeout` of 0, will be executed in the order they were scheduled.

Also, all the scheduling and canceling methods are fully thread safe and can be safely used from external threads.

As a consequence, calling `CyClockBase.unschedule()` with the original callback is now significantly slower and highly discouraged. Instead, the returned events should be used to cancel. As a tradeoff, all the other methods are now significantly faster than before.

31.7.8 Advanced Clock Details

The following section goes into the internal kivy clock details as well as the various clock options. It is meant only for advanced users.

Fundamentally, the Kivy clock attempts to execute any scheduled callback rhythmically as determined by the specified fps (frame per second, see `maxfps` in [config](#)). That is, ideally, given e.g. a desired fps of 30, the clock will execute the callbacks at intervals of 1 / 30 seconds, or every 33.33 ms. All the callbacks in a frame are given the same timestamp, i.e. the `dt` passed to the callback are all the same and it's the difference in time between the start of this and the previous frame.

Because of inherent indeterminism, the frames do not actually occur exactly at intervals of the fps and `dt` may be under or over the desired fps. Also, once the timeout is "close enough" to the desired timeout, as determined internally, Kivy will execute the callback in the current frame even when the "actual time" has not elapsed the `timeout` amount.

Kivy offers now, since 1.10.0, multiple clocks with different behaviors.

Default Clock

The default clock (`default`) behaves as described above. When a callback with a timeout of zero or non-zero is scheduled, they are executed at the frame that is near the timeout, which is a function of the fps. So a timeout of zero would still result in a delay of one frame or about $1 / \text{fps}$, typically a bit less but sometimes more depending on the CPU usage of the other events scheduled for that frame.

In a test using a fps of 30, a callback with a timeout of 0, 0.001, and 0.05, resulted in a mean callback delay of 0.02487, 0.02488, and 0.05011 seconds, respectively. When tested with a fps of 600 the delay for 0.05 was similar, except the standard deviation was reduced resulting in overall better accuracy.

Interruptible Clock

The default clock suffers from the quantization problem, as frames occur only on intervals and any scheduled timeouts will not be able to occur during an interval. For example, with the timeout of 0.05, while the mean was 0.05011, its values ranged between 0.02548 - 0.07348 and a standard deviation of 0.002. Also, there's the minimum timeout of about 0.02487.

The interruptible clock (`interrupt`) will execute timeouts even during a frame. So a timeout of zero will execute as quickly as possible and similarly a non-zero timeout will be executed even during the interval.

This clock, and all the clocks described after this have an option, `ClockBaseInterruptBehavior.interrupt_next_only`. When True, any of the behavior new behavior will only apply to the callbacks with a timeout of zero. Non-zero timeouts will behave like in the default clock. E.g. for this clock when True, only zero timeouts will execute during the the interval.

In a test using a fps of 30, a callback with a timeout of 0, 0.001, and 0.05, resulted in a mean callback delay of 0.00013, 0.00013, and 0.04120 seconds, respectively when `ClockBaseInterruptBehavior.interrupt_next_only` was False. Also, compared to the default clock the standard deviation was reduced. When `ClockBaseInterruptBehavior.interrupt_next_only` was True, the values were 0.00010, 0.02414, and 0.05034, respectively.

Free Clock

The interruptible clock may not be ideal for all cases because all the events are executed during the intervals and events are not executed anymore rhythmically as multiples of the fps. For example, there may not be any benefit for the graphics to update in a sub-interval, so the additional accuracy wastes CPU.

The Free clock (`free_all`) solves this by having `Clock.xxx_free` versions of all the Clock scheduling methods. By free, we mean the event is free from the fps because it's not fps limited. E.g. `CyClockBaseFree.create_trigger_free()` corresponds to `CyClockBase.create_trigger()`. Only when an event scheduled using the `Clock.xxx_free` methods is present will the clock interrupt and execute the events during the interval. So, if no `free` event is present the clock behaves like the `default` clock, otherwise it behaves like the `interrupt` clock.

In a test using a fps of 30, a callback with a timeout of 0s, 0.001s, and 0.05s, resulted in a mean callback delay of 0.00012s, 0.00017s, and 0.04121s seconds, respectively when it was a free event and 0.02403s, 0.02405s, and 0.04829s, respectively when it wasn't.

Free Only Clock

The Free clock executes all events when a free event was scheduled. This results in normal events also being execute in the middle of the interval when a free event is scheduled. For example, above, when a free event was absent, a normal event with a 0.001s timeout was delayed for 0.02405s. However, if a free event happened to be also scheduled, the normal event was only delayed 0.00014s, which may be undesirable.

The Free only clock (`free_only`) solves it by only executing free events during the interval and normal events are always executed like with the default clock. For example, in the presence of a free event, a normal event with a timeout of 0.001s still had a delay of 0.02406. So this clock, treats free and normal events independently, with normal events always being fps limited, but never the free events.

Summary

The kivy clock type to use can be set with the `kivy_clock` option the [config](#). If KIVY_CLOCK is present in the environment it overwrites the config selection. Its possible values are as follows:

- When `kivy_clock` is `default`, the normal clock, `ClockBase`, which limits callbacks to the maxfps quantization - is used.
- When `kivy_clock` is `interrupt`, a interruptible clock, `ClockBaseInterrupt`, which doesn't limit any callbacks to the maxfps - is used. Callbacks will be executed at any time.
- When `kivy_clock` is `free_all`, a interruptible clock, `ClockBaseFreeInterruptAll`, which doesn't limit any callbacks to the maxfps in the presence of free events, but in their absence it limits events to the fps quantization interval - is used.
- When `kivy_clock` is `free_only`, a interruptible clock, `ClockBaseFreeInterruptAll`, which treats free and normal events independently; normal events are fps limited while free events are not - is used.

31.7.9 Async clock support

New in version 2.0.0.

Experimental async support has been added in 2.0.0. The Clock now has a `ClockBaseBehavior`, `async_tick()` and `ClockBaseBehavior.async_idle()` coroutine method which is used by the kivy EventLoop when the kivy EventLoop is executed in a asynchronous manner. When used, the kivy clock does not block while idling.

The async library to use is selected with the `KIVY_EVENTLOOP` environmental variable or by calling `init_async_lib()` directly. The library can be one of “`asyncio`” when the standard library `asyncio` should be used, or “`trio`” if the trio library should be used. If not set it defaults to “`asyncio`”.

See [app](#) for example usage.

`kivy.clock.Clock: kivy.clock.ClockBase = None`

The kivy Clock instance. See module documentation for details.

`class kivy.clock.ClockBase(**kwargs)`

Bases: `kivy.clock.ClockBaseBehavior`, `kivy._clock.CyClockBase`

The default kivy clock. See module for details.

`usleep(microseconds)`

Sleeps for the number of microseconds.

`class kivy.clock.ClockBaseBehavior(async_lib='asyncio', **kwargs)`

Bases: `builtins.object`

The base of the kivy clock.

Parameters

async_lib: string The async library to use when the clock is run asynchronously.
Can be one of, “*asyncio*” when the standard library *asyncio* should be used, or
“*trio*” if the *trio* library should be used.

It defaults to ‘*asyncio*’ or the value in the environmental variable
KIVY_EVENTLOOP if set. *init_async_lib()* can also be called directly to
set the library.

MIN_SLEEP = 0.005

The minimum time to sleep. If the remaining time is less than this, the event loop will con-tinue.

async async_idle()

(internal) async version of *idle()*.

async async_tick()

async version of *tick()*.

property frames

Number of internal frames (not necessarily drawn) from the start of the clock.

New in version 1.8.0.

property frames_displayed

Number of displayed frames from the start of the clock.

property frametime

Time spent between the last frame and the current frame (in seconds).

New in version 1.8.0.

get_boottime()

Get the time in seconds from the application start.

get_fps()

Get the current average FPS calculated by the clock.

get_rfps()

Get the current “real” FPS calculated by the clock. This counter reflects the real framerate displayed on the screen.

In contrast to *get_fps()*, this function returns a counter of the number of frames, not the average of frames per second.

get_time()

Get the last tick made by the clock.

idle()

(internal) waits here until the next frame.

init_async_lib(lib)

Manually sets the async library to use internally, when running in a asynchronous manner.

This can be called anytime before the kivy event loop has started, but not once the kivy App is running.

Parameters

lib: string The async library to use when the clock is run asynchronously. Can be one of, “*asyncio*” when the standard library *asyncio* should be used, or “*trio*” if the *trio* library should be used.

post_idle(ts, current)
Called after `idle()` by `tick()`.

pre_idle()
Called before `idle()` by `tick()`.

tick()
Advance the clock to the next step. Must be called every frame. The default clock has a `tick()` function called by the core Kivy framework.

tick_draw()
Tick the drawing counter.

static time()
Proxy method for `clock()`.

usleep(microseconds)
Sleeps for the number of microseconds.

class kivy.clock.ClockBaseFreeInterruptAll(kwargs)**
Bases: `kivy.clock.ClockBaseInterruptFreeBehavior`, `kivy._clock.CyClockBaseFree`
The `free_all` kivy clock. See module for details.

class kivy.clock.ClockBaseFreeInterruptOnly(kwargs)**
Bases: `kivy.clock.ClockBaseInterruptFreeBehavior`, `kivy._clock.CyClockBaseFree`
The `free_only` kivy clock. See module for details.

async async_idle()
(internal) async version of `idle()`.

idle()
(internal) waits here until the next frame.

class kivy.clock.ClockBaseInterrupt(interrupt_next_only=False, **kwargs)
Bases: `kivy.clock.ClockBaseInterruptBehavior`, `kivy._clock.CyClockBase`
The `interrupt` kivy clock. See module for details.

class kivy.clock.ClockBaseInterruptBehavior(interrupt_next_only=False, **kwargs)
Bases: `kivy.clock.ClockBaseBehavior`
A kivy clock which can be interrupted during a frame to execute events.

async async_idle()
(internal) async version of `idle()`.

idle()
(internal) waits here until the next frame.

init_async_lib(lib)
Manually sets the async library to use internally, when running in a asynchronous manner.
This can be called anytime before the kivy event loop has started, but not once the kivy App is running.

Parameters

lib: string The async library to use when the clock is run asynchronously. Can be one of, “`asyncio`” when the standard library `asyncio` should be used, or “`trio`” if the `trio` library should be used.

usleep(microseconds)
Sleeps for the number of microseconds.

```
class kivy.clock.ClockBaseInterruptFreeBehavior(**kwargs)
    Bases: kivy.clock.ClockBaseInterruptBehavior
```

A base class for the clock that interrupts the sleep interval for free events.

```
class kivy.clock.ClockEvent(CyClockBase clock, int loop, callback, double timeout, double starttime,
                             cid=None, int trigger=False, clock_ended_callback=None,
                             release_ref=True, **kwargs)
```

Bases: `builtins.object`

This class is never created by the user; instead, kivy creates and returns an instance of this class when scheduling a callback.

An event can be triggered (scheduled) by calling it. If it's already scheduled, nothing will happen, otherwise it'll be scheduled. E.g.:

```
event = Clock.schedule_once(my_callback, .5)
event() # nothing will happen since it's already scheduled.
event.cancel() # cancel it
event() # now it's scheduled again.
```

callback

callback: object

cancel()

Cancels the callback if it was scheduled to be called. If not scheduled, nothing happens.

cid

cid: object

clock

clock: kivy._clock.CyClockBase The [CyClockBase](#) instance associated with the event.

clock_ended_callback

clock_ended_callback: object A Optional callback for this event, which if provided is called by the clock

when the clock is stopped and the event was not ticked.

get_callback()

Returns the callback associated with the event. Callbacks get stored with a indirect ref so that it doesn't keep objects alive. If the callback is dead, None is returned.

get_clock_ended_callback()

Returns the clock_ended_callback associated with the event. Callbacks get stored with a indirect ref so that it doesn't keep objects alive. If the callback is dead or wasn't provided, None is returned.

is_triggered

Returns whether the event is scheduled to have its callback executed by the kivy thread.

loop

loop: 'int' Whether this event repeats at intervals of [timeout](#).

next

next: kivy._clock.ClockEvent The next [ClockEvent](#) in order they were scheduled.

prev

prev: kivy._clock.ClockEvent The previous [ClockEvent](#) in order they were scheduled.

release()

(internal method) Converts the callback into a indirect ref.

release_ref

release_ref: 'int' If True, the event should never release the reference to the callbacks.

If False, a weakref may be created instead.

tick(double curtime)

(internal method) Processes the event for the kivy thread.

timeout

timeout: 'double' The duration after scheduling when the callback should be executed.

weak_callback

weak_callback: object

weak_clock_ended_callback

weak_clock_ended_callback: object

exception kivy.clock.ClockNotRunningError

Bases: RuntimeError

Raised by the kivy Clock when scheduling an event if the Kivy Clock has already finished ([stop_clock](#) was called).

class kivy.clock.CyClockBase(kwargs)**

Bases: builtins.object

clock_resolution

clock_resolution: 'double' If the remaining time until the event timeout is less than [clock_resolution](#),

the clock will execute the callback even if it hasn't exactly timed out.

If -1, the default, the resolution will be computed from config's maxfps. Otherwise, the provided value is used. Defaults to -1.

create_lifecycle_aware_trigger(callback, clock_ended_callback, timeout=0, interval=False, release_ref=True) → ClockEvent

Create a Trigger event similarly to [create_trigger\(\)](#), but the event is sensitive to the clock's state.

If this event is triggered after the clock has stopped ([stop_clock\(\)](#)), then a [ClockNotRunningError](#) will be raised. If the error is not raised, then either `callback` or `clock_ended_callback` will be called. `callback` will be called when the event is normally executed. If the clock is stopped before it can be executed, provided the app exited normally without crashing and the event wasn't manually canceled, and the callbacks are not garbage collected then `clock_ended_callback` will be called instead when the clock is stopped.

Parameters

callback: callable The callback to execute from kivy. It takes a single parameter
- the current elapsed kivy time.

clock_ended_callback: callable A callback that will be called if the clock is stopped while the event is still scheduled to be called. The callback takes a single parameter - the event object. When the event is successfully scheduled, if the app exited normally and the event wasn't canceled, and the callbacks are not garbage collected - it is guaranteed that either `callback` or `clock_ended_callback` would have been called.

timeout: float How long to wait before calling the callback.

interval: bool Whether the callback should be called once (False) or repeatedly with a period of `timeout` (True) like [schedule_interval\(\)](#).

release_ref: bool If True, the default, then if `callback` or `clock_ended_callback` is a class method and the object has no references to it, then the object may be garbage collected and the callbacks won't be called. If False, the clock keeps a reference to the object preventing it from being garbage collected - so it will be called.

Returns A `ClockEvent` instance. To schedule the callback of this instance, you can call it.

New in version 2.0.0.

`create_trigger(callback, timeout=0, interval=False, release_ref=True) → ClockEvent`

Create a Trigger event. It is thread safe but not `__del__` or `__dealloc__` safe (see `schedule_del_safe()`). Check module documentation for more information.

To cancel the event before it is executed, call `ClockEvent.cancel()` on the returned event. To schedule it again, simply call the event (`event()`) and it'll be safely rescheduled if it isn't already scheduled.

Parameters

callback: callable The callback to execute from kivy. It takes a single parameter - the current elapsed kivy time.

timeout: float How long to wait before calling the callback.

interval: bool Whether the callback should be called once (False) or repeatedly with a period of `timeout` (True) like `schedule_interval()`.

release_ref: bool If True, the default, then if `callback` is a class method and the object has no references to it, then the object may be garbage collected and the callbacks won't be called. If False, the clock keeps a reference to the object preventing it from being garbage collected - so it will be called.

Returns A `ClockEvent` instance. To schedule the callback of this instance, you can call it.

New in version 1.0.5.

Changed in version 1.10.0: `interval` has been added.

Changed in version 2.0.0: `release_ref` has been added.

`get_before_frame_events()`

Returns the list of `ClockEvent` instances that are scheduled to be called before the next frame (-1 timeout).

New in version 2.1.0.

`get_events()`

Returns the list of `ClockEvent` instances currently scheduled.

`get_min_timeout()`

Returns the remaining time since the start of the current frame for the event with the smallest timeout.

`get_resolution()`

Returns the minimum resolution the clock has. It's a function of `clock_resolution` and `maxfps` provided at the config.

`handle_exception(e)`

Provides an opportunity to handle an event's exception.

If desired, the exception is handled, otherwise it should be raised again. By default it is raised again.

Parameters `e` – The exception to be handled.

New in version 2.0.0.

has-ended

`has-ended: 'int'`

has-started

`has-started: 'int'`

max_iteration

`max_iteration: 'int'` The maximum number of callback iterations at the end of the frame, before the next

frame. If more iterations occur, a warning is issued.

on_schedule(event)

Function that is called internally every time an event is triggered for this clock. It takes the event as a parameter.

The order of `on_schedule` calls are not guaranteed to be in the same order that the events are scheduled. Similarly, it is possible that the event being scheduled was canceled before this is called on the event. That's because `on_schedule()` may be called from different threads.

schedule_del_safe(callback)

Schedule a callback that is thread safe and `__del__` or `__dealloc__` safe.

It's unsafe to call various kinds of code from `__del__` or `__dealloc__` methods because they can be executed at any time. Most Kivy's Clock methods are unsafe to call the Clock from these methods. Instead, use this method, which is thread safe and `__del__` or `__dealloc__` safe, to schedule the callback in the kivy thread. It'll be executed in order after the normal events are processed.

Parameters

`callback: Callable` The callback the execute from kivy. It takes no parameters and cannot be canceled.

New in version 1.11.0.

schedule_interval(callback, timeout) → ClockEvent

Schedule an event to be called every `<timeout>` seconds. See `create_trigger()` for advanced scheduling and more details.

To cancel the event before it is executed, call `ClockEvent.cancel()` on the returned event. If the callback is a class method, a weakref to the object is created and it may be garbage collected if there's no other reference to the object.

Returns A `ClockEvent` instance. As opposed to `create_trigger()` which only creates the trigger event, this method also schedules it.

schedule_lifecycle_aware_del_safe(callback, clock_ended_callback)

Schedule a callback that is thread safe and `__del__` or `__dealloc__` safe similarly to `schedule_del_safe()`, but the callback is sensitive to the clock's state.

If this event is triggered after the clock has stopped (`stop_clock()`), then a `ClockNotRunningError` will be raised. If the error is not raised, then either `callback` or `clock_ended_callback` will be called. `callback` will be called when the callback is normally executed. If the clock is stopped before it can be executed, provided the app exited normally without crashing then `clock_ended_callback` will be called instead when the clock is stopped.

Parameters

callback: Callable The callback to execute from kivy. It takes no parameters and cannot be canceled.

clock_ended_callback: callable A callback that will be called if the clock is stopped while the callback is still scheduled to be called. The callback takes a single parameter - the callback. If the app exited normally, it is guaranteed that either `callback` or `clock_ended_callback` would have been called.

New in version 2.0.0.

schedule_once(callback, timeout=0) → ClockEvent

Schedule an event in `<timeout>` seconds. If `<timeout>` is unspecified or 0, the callback will be called after the next frame is rendered. See [create_trigger\(\)](#) for advanced scheduling and more details.

To cancel the event before it is executed, call [`ClockEvent.cancel\(\)`](#) on the returned event. If the callback is a class method, a weakref to the object is created and it may be garbage collected if there's no other reference to the object.

Returns A [`ClockEvent`](#) instance. As opposed to [`create_trigger\(\)`](#) which only creates the trigger event, this method also schedules it.

Changed in version 1.0.5: If the timeout is -1, the callback will be called before the next frame (`at tick_draw()`).

start_clock()

Must be called to start the clock.

Once [`stop_clock\(\)`](#) is called, it cannot be started again.

stop_clock()

Stops the clock and cleans up.

This must be called to process the lifecycle_aware callbacks etc.

unschedule(callback, all=True)

Remove a previously scheduled event.

An [`ClockEvent`](#) can also be canceled directly by calling [`ClockEvent.cancel\(\)`](#).

Parameters

callback: ClockEvent or a callable. If it's a [`ClockEvent`](#) instance, then the callback associated with this event will be canceled if it is scheduled.

If it's a callable, then the callable will be unscheduled if it was scheduled.

Warning: Passing the callback function rather than the returned [`ClockEvent`](#) will result in a significantly slower unscheduling.

all: bool If True and if `callback` is a callable, all instances of this callable will be unscheduled (i.e. if this callable was scheduled multiple times). Defaults to `True`.

Changed in version 1.9.0: The `all` parameter was added. Before, it behaved as if `all` was `True`.

class kivy.clock.CyClockBaseFree

Bases: `kivy._clock.CyClockBase`

A clock class that supports scheduling free events in addition to normal events.

Each of the [`create_trigger\(\)`](#), [`schedule_once\(\)`](#), and [`schedule_interval\(\)`](#) methods, which create a normal event, have a corresponding method for creating a free event.

```
create_lifecycle_aware_trigger(callback, clock_ended_callback, timeout=0, interval=False, release_ref=True) → FreeClockEvent
```

```
create_lifecycle_aware_trigger_free(callback, clock_ended_callback, timeout=0, interval=False, release_ref=True) → FreeClockEvent
```

Similar to `create_lifecycle_aware_trigger()`, but instead creates a free event.

```
create_trigger(callback, timeout=0, interval=False, release_ref=True) → FreeClockEvent
```

```
create_trigger_free(callback, timeout=0, interval=False, release_ref=True) → FreeClockEvent
```

Similar to `create_trigger()`, but instead creates a free event.

```
get_min_free_timeout()
```

Returns the remaining time since the start of the current frame for the *free* event with the smallest timeout.

```
schedule_interval(callback, timeout) → FreeClockEvent
```

```
schedule_interval_free(callback, timeout) → FreeClockEvent
```

Similar to `schedule_interval()`, but instead creates a free event.

```
schedule_once(callback, timeout=0) → FreeClockEvent
```

```
schedule_once_free(callback, timeout=0) → FreeClockEvent
```

Similar to `schedule_once()`, but instead creates a free event.

```
class kivy.clock.FreeClockEvent(free, *args, **kwargs)
```

Bases: `kivy._clock.ClockEvent`

CyClockBaseFree. It stores whether the event was scheduled as a free event.

```
free
```

free: 'int' Whether this event was scheduled as a free event.

```
kivy.clock.mainthread(func)
```

Decorator that will schedule the call of the function for the next available frame in the mainthread. It can be useful when you use `UrlRequest` or when you do Thread programming: you cannot do any OpenGL-related work in a thread.

Please note that this method will return directly and no result can be returned:

```
@mainthread
def callback(self, *args):
    print('The request succeeded!',
          'This callback is called in the main thread.')

self.req = UrlRequest(url='http://...', on_success=callback)
```

New in version 1.8.0.

```
kivy.clock.triggered(timeout=0, interval=False)
```

Decorator that will trigger the call of the function at the specified timeout, through the method `CyClockBase.create_trigger()`. Subsequent calls to the decorated function (while the timeout is active) are ignored.

It can be helpful when an expensive function (i.e. call to a server) can be triggered by different methods. Setting a proper timeout will delay the calling and only one of them will be triggered.

```
@triggered(timeout, interval=False) def callback(id):
```

```
    print('The callback has been called with id=%d' % id)
```

```
>> callback(id=1) >> callback(id=2) The callback has been called with id=2
```

The decorated callback can also be unscheduled using:

```
>> callback.cancel()
```

New in version 1.10.1.

31.8 Compatibility module for Python 2.7 and >= 3.4

This module provides a set of utility types and functions for optimization and to aid in writing Python 2/3 compatible code.

kivy.compat.PY2 = False

False, because we don't support Python 2 anymore.

kivy.compat.clock() → float

A clock with the highest available resolution on your current Operating System.

kivy.compat.isclose(a, b, *, rel_tol=1e-09, abs_tol=0.0)

Determine whether two floating point numbers are close in value.

rel_tol maximum difference for being considered "close", relative to the magnitude of the input values

abs_tol maximum difference for being considered "close", regardless of the magnitude of the input values

Return True if a is close in value to b, and False otherwise.

For the values to be considered close, the difference between them must be smaller than at least one of the tolerances.

-inf, inf and NaN behave similarly to the IEEE 754 Standard. That is, NaN is not close to anything, even itself. inf and -inf are only close to themselves.

kivy.compat.string_types

A utility type for detecting string in a Python 2/3 friendly way. For example:

```
if isinstance(s, string_types):
    print("It's a string or unicode type")
else:
    print("It's something else.")
```

31.9 Configuration object

The **Config** object is an instance of a modified Python ConfigParser. See the [ConfigParser documentation](#) for more information.

Kivy has a configuration file which determines the default settings. In order to change these settings, you can alter this file manually or use the Config object. Please see the [Configure Kivy](#) section for more information.

31.9.1 Applying configurations

Configuration options control the initialization of the [App](#). In order to avoid situations where the config settings do not work or are not applied before window creation (like setting an initial window size), [`Config.set`](#) should be used before importing any other Kivy modules. Ideally, this means setting them right at the start of your main.py script.

Alternatively, you can save these settings permanently using [`Config.set`](#) then [`Config.write`](#). In this case, you will need to restart the app for the changes to take effect. Note that this approach will effect all Kivy apps system wide.

Please note that no underscores (_) are allowed in the section name.

31.9.2 Usage of the Config object

To read a configuration token from a particular section:

```
>>> from kivy.config import Config  
>>> Config.getint('kivy', 'show_fps')  
0
```

Change the configuration and save it:

```
>>> Config.set('postproc', 'retain_time', '50')  
>>> Config.write()
```

For information on configuring your [App](#), please see the [Application configuration](#) section.

Changed in version 1.7.1: The ConfigParser should work correctly with utf-8 now. The values are converted from ascii to unicode only when needed. The method get() returns utf-8 strings.

31.9.3 Changing configuration with environment variables

Since 1.11.0, it is now possible to change the configuration using environment variables. They take precedence on the loaded config.ini. The format is:

```
KCFG_<section>_<key> = <value>
```

For example:

```
KCFG_GRAPHICS_FULLSCREEN=auto ... KCFG_KIVY_LOG_LEVEL=warning ...
```

Or in your file before any kivy import:

```
import os  
os.environ["KCFG_KIVY_LOG_LEVEL"] = "warning"
```

If you don't want to map any environment variables, you can disable the behavior:

```
os.environ["KIVY_NO_ENV_CONFIG"] = "1"
```

31.9.4 Available configuration tokens

kivy

default_font: list Default fonts used for widgets displaying any text. It defaults to ['Roboto', 'data/fonts/Roboto-Regular.ttf', 'data/fonts/Roboto-Italic.ttf', 'data/fonts/Roboto-Bold.ttf', 'data/fonts/Roboto-BoldItalic.ttf'].

desktop: int, 0 or 1 This option controls desktop OS specific features, such as enabling drag-able scroll-bar in scroll views, disabling of bubbles in TextInput etc. 0 is disabled, 1 is enabled.

exit_on_escape: int, 0 or 1 Enables exiting kivy when escape is pressed. 0 is disabled, 1 is enabled.

pause_on_minimize: int, 0 or 1 If set to 1, the main loop is paused and the *on_pause* event is dispatched when the window is minimized. This option is intended for desktop use only. Defaults to 0.

keyboard_layout: string Identifier of the layout to use.

keyboard_mode: string Specifies the keyboard mode to use. If can be one of the following:

- '' - Let Kivy choose the best option for your current platform.
- 'system' - real keyboard.
- 'dock' - one virtual keyboard docked to a screen side.
- 'multi' - one virtual keyboard for every widget request.
- 'systemanddock' - virtual docked keyboard plus input from real keyboard.
- 'systemandmulti' - analogous.

kivy_clock: one of default, interrupt, free_all, free_only The clock type to use with kivy. See [kivy.clock](#).

log_dir: string Path of log directory.

log_enable: int, 0 or 1 Activate file logging. 0 is disabled, 1 is enabled.

log_level: string, one of 'trace', 'debug', 'info', 'warning', 'error' or 'critical' Set the minimum log level to use.

log_name: string Format string to use for the filename of log file.

log_maxfiles: int Keep log_maxfiles recent logfiles while purging the log directory. Set 'log_maxfiles' to -1 to disable logfile purging (eg keep all logfiles).

Note: You end up with 'log_maxfiles + 1' logfiles because the logger adds a new one after purging.

window_icon: string Path of the window icon. Use this if you want to replace the default pygame icon.

postproc

double_tap_distance: float Maximum distance allowed for a double tap, normalized inside the range 0 - 1000.

double_tap_time: int Time allowed for the detection of double tap, in milliseconds.

ignore: list of tuples List of regions where new touches are ignored. This configuration token can be used to resolve hotspot problems with DIY hardware. The format of the list must be:

```
ignore = [(xmin, ymin, xmax, ymax), ...]
```

All the values must be inside the range 0 - 1.

jitter_distance: int Maximum distance for jitter detection, normalized inside the range 0 - 1000.

jitter_ignore_devices: string, separated with commas List of devices to ignore from jitter detection.

retain_distance: int If the touch moves more than is indicated by retain_distance, it will not be retained. Argument should be an int between 0 and 1000.

retain_time: int Time allowed for a retain touch, in milliseconds.

triple_tap_distance: float Maximum distance allowed for a triple tap, normalized inside the range 0 - 1000.

triple_tap_time: int Time allowed for the detection of triple tap, in milliseconds.

graphics

borderless: int, one of 0 or 1 If set to 1, removes the window border/decoration. Window resizing must also be disabled to hide the resizing border.

custom_titlebar: int, one of 0 or 1 If set to 1, removes the window border and allows user to set a Widget as a titlebar see [set_custom_titlebar\(\)](#) for detailed usage

custom_titlebar_border: int, defaults to 5 sets the how many pixels off the border should be used as the rezising frame

window_state: string, one of 'visible', 'hidden', 'maximized'
or 'minimized'

Sets the window state, defaults to 'visible'. This option is available only for the SDL2 window provider and it should be used on desktop OSes.

fbo: string, one of 'hardware', 'software' or 'force-hardware' Selects the FBO backend to use.

fullscreen: int or string, one of 0, 1, 'fake' or 'auto' Activate fullscreen. If set to 1, a resolution of *width* times *height* pixels will be used. If set to *auto*, your current display's resolution will be used instead. This is most likely what you want. If you want to place the window in another display, use *fake*, or set the *borderless* option from the graphics section, then adjust *width*, *height*, *top* and *left*.

height: int Height of the Window, not used if *fullscreen* is set to *auto*.

left: int Left position of the Window.

maxfps: int, defaults to 60 Maximum FPS allowed.

Warning: Setting maxfps to 0 will lead to max CPU usage.

'multisamples': int, defaults to 2 Sets the [MultiSample Anti-Aliasing \(MSAA\)](#) level. Increasing this value results in smoother graphics but at the cost of processing time.

Note: This feature is limited by device hardware support and will have no effect on devices which do not support the level of MSAA requested.

position: string, one of ‘auto’ or ‘custom’ Position of the window on your display. If *auto* is used, you have no control of the initial position: *top* and *left* are ignored.

show_cursor: int, one of 0 or 1 Set whether or not the cursor is shown on the window.

top: int Top position of the Window.

resizable: int, one of 0 or 1 If 0, the window will have a fixed size. If 1, the window will be resizable.

rotation: int, one of 0, 90, 180 or 270 Rotation of the Window.

width: int Width of the Window, not used if *fullscreen* is set to *auto*.

minimum_width: int Minimum width to restrict the window to. (sdl2 only)

minimum_height: int Minimum height to restrict the window to. (sdl2 only)

min_state_time: float, defaults to .035 Minimum time for widgets to display a given visual state. This attrib is currently used by widgets like *DropDown* & *ButtonBehavior* to make sure they display their current visual state for the given time.

allow_screensaver: int, one of 0 or 1, defaults to 1 Allow the device to show a screen saver, or to go to sleep on mobile devices. Only works for the sdl2 window provider.

vsync: none, empty value, or integers Whether vsync is enabled, currently only used with sdl2 window. Possible values are *none* or empty value – leaves it unchanged, 0 – disables vsync, 1 or larger – sets vsync interval, -1 sets adaptive vsync. It falls back to 1 if setting to 2+ or -1 failed. See `SDL_GL_SetSwapInterval`.

verify_gl_main_thread: int, 1 or 0, defaults to 1 Whether to check if code that changes any gl instructions is running outside the main thread and then raise an error.

input You can create new input devices using this syntax:

```
# example of input provider instance
yourid = providerid,parameters

# example for tuio provider
default = tuio,127.0.0.1:3333
mytable = tuio,192.168.0.1:3334
```

See also:

Check the providers in `kivy.input.providers` for the syntax to use inside the configuration file.

widgets

scroll_distance: int Default value of the `scroll_distance` property used by the *ScrollView* widget. Check the widget documentation for more information.

scroll_friction: float Default value of the `scroll_friction` property used by the *ScrollView* widget. Check the widget documentation for more information.

Deprecated since version 1.7.0: Please use `effect_cls` instead.

scroll_timeout: int Default value of the `scroll_timeout` property used by the *ScrollView* widget. Check the widget documentation for more information.

`scroll_stoptime: int` Default value of the `scroll_stoptime` property used by the `ScrollView` widget. Check the widget documentation for more information.

Deprecated since version 1.7.0: Please use `effect_cls` instead.

`scroll_moves: int` Default value of the `scroll_moves` property used by the `ScrollView` widget. Check the widget documentation for more information.

Deprecated since version 1.7.0: Please use `effect_cls` instead.

modules You can activate modules with this syntax:

```
modulename =
```

Anything after the `=` will be passed to the module as arguments. Check the specific module's documentation for a list of accepted arguments.

Changed in version 2.1.0: `vsync` has been added to the `graphics` section. `verify_gl_main_thread` has been added to the `graphics` section.

Changed in version 1.10.0: `min_state_time` and `allow_screensaver` have been added to the `graphics` section. `kivy_clock` has been added to the `kivy` section. `default_font` has been added to the `kivy` section.

Changed in version 1.9.0: `borderless` and `window_state` have been added to the `graphics` section. The `fake` setting of the `fullscreen` option has been deprecated, use the `borderless` option instead. `pause_on_minimize` has been added to the `kivy` section.

Changed in version 1.8.0: `systemanddock` and `systemandmulti` has been added as possible values for `keyboard_mode` in the `kivy` section. `exit_on_escape` has been added to the `kivy` section.

Changed in version 1.2.0: `resizable` has been added to `graphics` section.

Changed in version 1.1.0: tuio no longer listens by default. Window icons are not copied to user directory anymore. You can still set a new window icon by using the `window_icon` config setting.

Changed in version 1.0.8: `scroll_timeout`, `scroll_distance` and `scroll_friction` have been added. `list_friction`, `list_trigger_distance` and `list_friction_bound` have been removed. `keyboard_type` and `keyboard_layout` have been removed from the `widget`. `keyboard_mode` and `keyboard_layout` have been added to the `kivy` section.

`kivy.config.Config = None`

The default Kivy configuration object. This is a `ConfigParser` instance with the `name` set to 'kivy'.

```
Config = ConfigParser(name='kivy')
```

class kivy.config.ConfigParser(name='', **kwargs)
Bases: `configparser.RawConfigParser, builtins.object`

Enhanced ConfigParser class that supports the addition of default sections and default values.

By default, the kivy ConfigParser instance, `Config`, is named 'kivy' and the ConfigParser instance used by the `App.build_settings` method is named 'app'.

Parameters

`name: string` The name of the instance. See `name`. Defaults to ''.

Changed in version 1.9.0: Each ConfigParser can now be `named`. You can get the ConfigParser associated with a name using `get_configparser()`. In addition, you can now control the config values with `ConfigParserProperty`.

New in version 1.0.7.

`add_callback(callback, section=None, key=None)`

Add a callback to be called when a specific section or key has changed. If you don't specify a section or key, it will call the callback for all section/key changes.

Callbacks will receive 3 arguments: the section, key and value.

New in version 1.4.1.

`adddefaultsection(section)`

Add a section if the section is missing.

`get(section, option, **kwargs)`

Get an option value for a given section.

If `vars` is provided, it must be a dictionary. The option is looked up in `vars` (if provided), `section`, and in `DEFAULTSECT` in that order. If the key is not found and `fallback` is provided, it is used as a fallback value. `None` can be provided as a `fallback` value.

If interpolation is enabled and the optional argument `raw` is False, all interpolations are expanded in the return values.

Arguments `raw`, `vars`, and `fallback` are keyword only.

The section DEFAULT is special.

`static get_configparser(name)`

Returns the *ConfigParser* instance whose name is *name*, or None if not found.

Parameters

name: string The name of the *ConfigParser* instance to return.

`getdefault(section, option, defaultvalue)`

Get the value of an option in the specified section. If not found, it will return the default value.

`getdefaultint(section, option, defaultvalue)`

Get the value of an option in the specified section. If not found, it will return the default value. The value will always be returned as an integer.

New in version 1.6.0.

`property name`

The name associated with this ConfigParser instance, if not ``. Defaults to ``. It can be safely changed dynamically or set to ``.

When a ConfigParser is given a name, that config object can be retrieved using `get_configparser()`. In addition, that config instance can also be used with a *ConfigParserProperty* instance that set its *config* value to this name.

Setting more than one ConfigParser with the same name will raise a *ValueError*.

`read(filename)`

Read only one filename. In contrast to the original ConfigParser of Python, this one is able to read only one file at a time. The last read file will be used for the `write()` method.

Changed in version 1.9.0: `read()` now calls the callbacks if read changed any values.

`remove_callback(callback, section=None, key=None)`

Removes a callback added with `add_callback()`. `remove_callback()` must be called with the same parameters as `add_callback()`.

Raises a *ValueError* if not found.

New in version 1.9.0.

set(*section, option, value*)

Functions similarly to PythonConfigParser’s set method, except that the value is implicitly converted to a string.

setall(*section, keyvalues*)

Sets multiple key-value pairs in a section. keyvalues should be a dictionary containing the key-value pairs to be set.

setdefault(*section, option, value*)

Set the default value for an option in the specified section.

setdefaults(*section, keyvalues*)

Set multiple key-value defaults in a section. keyvalues should be a dictionary containing the new key-value defaults.

update_config(*filename, overwrite=False*)

Upgrade the configuration based on a new default config file. Overwrite any existing values if overwrite is True.

write()

Write the configuration to the last file opened using the *read()* method.

Return True if the write finished successfully, False otherwise.

31.10 Context

New in version 1.8.0.

Warning: This is experimental and subject to change as long as this warning notice is present.

Kivy has a few “global” instances that are used directly by many pieces of the framework: *Cache*, *Builder*, *Clock*.

TODO: document this module.

class kivy.context.Context(*init=False*)

Bases: *builtins.dict*

pop(*k[, d]*) → *v*, remove specified key and return the corresponding value.

If key is not found, *d* is returned if given, otherwise *KeyError* is raised

kivy.context.get_current_context()

Return the current context.

kivy.context.register_context(*name, cls, *args, **kwargs*)

Register a new context.

31.11 Event dispatcher

All objects that produce events in Kivy implement the *EventDispatcher* which provides a consistent interface for registering and manipulating event handlers.

Changed in version 1.0.9: Property discovery and methods have been moved from the *Widget* to the *EventDispatcher*.

class kivy.event.EventDispatcher(***kwargs*)

Bases: *kivy.event.ObjectWithUid*

See the module docstring for usage.

apply_property(kwargs)**

Adds properties at runtime to the class. The function accepts keyword arguments of the form *prop_name*=*prop*, where *prop* is a `Property` instance and *prop_name* is the name of the attribute of the property.

New in version 1.9.1.

Warning: This method is not recommended for common usage because you should declare the properties in your class instead of using this method.

For example:

```
>>> print(wid.property('sticks', quiet=True))
None
>>> wid.apply_property(sticks=ObjectProperty(55, max=10))
>>> print(wid.property('sticks', quiet=True))
<kivy.properties.ObjectProperty object at 0x04303130>
```

bind(kwargs)**

Bind an event type or a property to a callback.

Usage:

```
# With properties
def my_x_callback(obj, value):
    print('on object', obj, 'x changed to', value)
def my_width_callback(obj, value):
    print('on object', obj, 'width changed to', value)
self.bind(x=my_x_callback, width=my_width_callback)

# With event
def my_press_callback(obj):
    print('event on object', obj)
self.bind(on_press=my_press_callback)
```

In general, property callbacks are called with 2 arguments (the object and the property's new value) and event callbacks with one argument (the object). The example above illustrates this.

The following example demonstrates various ways of using the bind function in a complete application:

```
from kivy.uix.boxlayout import BoxLayout
from kivy.app import App
from kivy.uix.button import Button
from functools import partial

class DemoBox(BoxLayout):
    """
        This class demonstrates various techniques that can be used_
        for binding to
        events. Although parts could me made more optimal, advanced_
        Python concepts
    """

    pass
```

(continues on next page)

(continued from previous page)

```
are avoided for the sake of readability and clarity.  
"""  
def __init__(self, **kwargs):  
    super(DemoBox, self).__init__(**kwargs)  
    self.orientation = "vertical"  
  
    # We start with binding to a normal event. The only  
    ↪argument  
    # passed to the callback is the object which we have bound  
    ↪to.  
    btn = Button(text="Normal binding to event")  
    btn.bind(on_press=self.on_event)  
  
    # Next, we bind to a standard property change event. This  
    ↪typically  
    # passes 2 arguments: the object and the value  
    btn2 = Button(text="Normal binding to a property change")  
    btn2.bind(state=self.on_property)  
  
    # Here we use anonymous functions (a.k.a lambdas) to  
    ↪perform binding.  
    # Their advantage is that you can avoid declaring new  
    ↪functions i.e.  
    # they offer a concise way to "redirect" callbacks.  
    btn3 = Button(text="Using anonymous functions.")  
    btn3.bind(on_press=lambda x: self.on_event(None))  
  
    # You can also declare a function that accepts a variable  
    ↪number of  
    # positional and keyword arguments and use introspection  
    ↪to determine  
    # what is being passed in. This is very handy for  
    ↪debugging as well  
    # as function re-use. Here, we use standard event binding  
    ↪to a function  
    # that accepts optional positional and keyword arguments.  
    btn4 = Button(text="Use a flexible function")  
    btn4.bind(on_press=self.on_anything)  
  
    # Lastly, we show how to use partial functions. They are  
    ↪sometimes  
    # difficult to grasp, but provide a very flexible and  
    ↪powerful way to  
    # reuse functions.  
    btn5 = Button(text="Using partial functions. For hardcores."  
    ↪")  
    btn5.bind(on_press=partial(self.on_anything, "1", "2",  
    ↪monthly="python"))  
  
    for but in [btn, btn2, btn3, btn4, btn5]:  
        self.add_widget(but)  
  
def on_event(self, obj):
```

(continues on next page)

```

        print("Typical event from", obj)

    def on_property(self, obj, value):
        print("Typical property change from", obj, "to", value)

    def on_anything(self, *args, **kwargs):
        print('The flexible function has *args of', str(args),
              "and **kwargs of", str(kwargs))

class DemoApp(App):
    def build(self):
        return DemoBox()

if __name__ == "__main__":
    DemoApp().run()

```

If a callback has already been bound to a given event or property, it won't be added again.

When binding a method to an event or property, a `kivy.weakmethod.WeakMethod` of the callback is saved. That is, rather than storing a regular reference, it stores both a weak reference to the instance (see Python's `weakref`).

This has two consequences.

The first is that the binding will not prevent garbage collection of the method's object. The client must maintain a reference to the instance for the desired lifetime. The callback reference is silently removed if it becomes invalid.

The second is that when using a decorated method e.g.:

```

@my_decorator
def callback(self, *args):
    pass

```

the decorator (`my_decorator` here) must use `wraps` internally.

create_property(*unicode name*, *value=None*, *default_value=True*, **largs*, ***kwargs*)
Create a new property at runtime.

New in version 1.0.9.

Changed in version 1.8.0: *value* parameter added, can be used to set the default value of the property. Also, the type of the value is used to specialize the created property.

Changed in version 1.9.0: In the past, if *value* was of type `bool`, a `NumericProperty` would be created, now a `BooleanProperty` is created.

Also, now and positional and keyword arguments are passed to the property when created.

Changed in version 2.0.0: `default_value` has been added.

Warning: This function is designed for the Kivy language, don't use it in your code. You should declare the property in your class instead of using this method.

Parameters

name: string Name of the property

value: object, optional Default value of the property. Type is also used for creating more appropriate property types. Defaults to None.

default_value: bool, True by default If True, *value* will be the default for the property. Otherwise, the property will be initialized with the the property type's normal default value, and subsequently set to *value*.

```
>>> mywidget = Widget()
>>> mywidget.create_property('custom')
>>> mywidget.custom = True
>>> print(mywidget.custom)
True
```

dispatch(event_type, *largs, **kwargs)

Dispatch an event across all the handlers added in bind/fbind(). As soon as a handler returns True, the dispatching stops.

The function collects all the positional and keyword arguments and passes them on to the handlers.

Note: The handlers are called in reverse order than they were registered with *bind()*.

Parameters

event_type: str the event name to dispatch.

Changed in version 1.9.0: Keyword arguments collection and forwarding was added. Before, only positional arguments would be collected and forwarded.

dispatch_children(event_type, *largs, **kwargs)

dispatch_generic(event_type, *largs, **kwargs)

events()

Return all the events in the class. Can be used for introspection.

New in version 1.8.0.

fbind(name, func, *largs, **kwargs)

A method for advanced, and typically faster binding. This method is different than *bind()* and is meant for more advanced users and internal usage. It can be used as long as the following points are heeded.

1. As opposed to *bind()*, it does not check that this function and largs/kwags has not been bound before to this name. So binding the same callback multiple times will just keep adding it.
2. Although *bind()* creates a **WeakMethod** of the callback when binding to an event or property, this method stores the callback directly, unless a keyword argument *ref* with value True is provided and then a **WeakMethod** is saved. This is useful when there's no risk of a memory leak by storing the callback directly.
3. This method returns a unique positive number if *name* was found and bound, and 0, otherwise. It does not raise an exception, like *bind()* if the property *name* is not found. If not zero, the uid returned is unique to this *name* and callback and can be used with *unbind_uid()* for unbinding.

When binding a callback with largs and/or kwargs, *funbind()* must be used for unbinding. If no largs and kwargs are provided, *unbind()* may be used as well. *unbind_uid()* can be used in either case.

This method passes on any caught positional and/or keyword arguments to the callback, removing the need to call partial. When calling the callback the expended largs are passed on followed by instance/value (just instance for kwargs) followed by expended kwargs.

Following is an example of usage similar to the example in [bind\(\)](#):

```
class DemoBox(BoxLayout):

    def __init__(self, **kwargs):
        super(DemoBox, self).__init__(**kwargs)
        self.orientation = "vertical"

        btn = Button(text="Normal binding to event")
        btn.fbind('on_press', self.on_event)

        btn2 = Button(text="Normal binding to a property change")
        btn2.fbind('state', self.on_property)

        btn3 = Button(text="A: Using function with args.")
        btn3.fbind('on_press', self.on_event_with_args, 'right',
                   tree='birch', food='apple')

        btn4 = Button(text="Unbind A.")
        btn4.fbind('on_press', self.unbind_a, btn3)

        btn5 = Button(text="Use a flexible function")
        btn5.fbind('on_press', self.on_anything)

        btn6 = Button(text="B: Using flexible functions with args.\nFor hardcores.")
        btn6.fbind('on_press', self.on_anything, "1", "2", monthy=
                   "python")

        btn7 = Button(text="Force dispatch B with different params")
        btn7.fbind('on_press', btn6.dispatch, 'on_press', 6, 7,
                   monthy="other python")

        for but in [btn, btn2, btn3, btn4, btn5, btn6, btn7]:
            self.add_widget(but)

    def on_event(self, obj):
        print("Typical event from", obj)

    def on_event_with_args(self, side, obj, tree=None, food=None):
        print("Event with args", obj, side, tree, food)

    def on_property(self, obj, value):
        print("Typical property change from", obj, "to", value)

    def on_anything(self, *args, **kwargs):
        print('The flexible function has *args of', str(args),
              "and **kwargs of", str(kwargs))
        return True
```

(continues on next page)

(continued from previous page)

```
def unbind_a(self, btn, event):
    btn.funbind('on_press', self.on_event_with_args, 'right',
                tree='birch', food='apple')
```

Note: Since the kv lang uses this method to bind, one has to implement this method, instead of `bind()` when creating a non `EventDispatcher` based class used with the kv lang. See `Observable` for an example.

New in version 1.9.0.

Changed in version 1.9.1: The `ref` keyword argument has been added.

funbind(*name, func, *largs, **kwargs*)
Similar to `fbind()`.

When unbinding, `unbind()` will unbind all callbacks that match the callback, while this method will only unbind the first.

To unbind, the same positional and keyword arguments passed to `fbind()` must be passed on to funbind.

Note: It is safe to use `funbind()` to unbind a function bound with `bind()` as long as no keyword and positional arguments are provided to `funbind()`.

New in version 1.9.0.

get_property_observers(*name, args=False*)

Returns a list of methods that are bound to the property/event passed as the *name* argument:

```
widget_instance.get_property_observers('on_release')
```

Parameters

name: str The name of the event or property.

args: bool Whether to return the bound args. To keep compatibility, only the callback functions and not their provided args will be returned in the list when *args* is False.

If True, each element in the list is a 5-tuple of (*callback, largs, kwargs, is_ref, uid*), where *is_ref* indicates whether *callback* is a weakref, and *uid* is the uid given by `fbind()`, or None if `bind()` was used. Defaults to *False*.

Returns The list of bound callbacks. See *args* for details.

New in version 1.8.0.

Changed in version 1.9.0: *args* has been added.

getter(*name*)

Return the getter of a property.

New in version 1.0.9.

is_event_type(*event_type*)

Return True if the event_type is already registered.

New in version 1.0.4.

properties() → dict

Return all the properties in the class in a dictionary of key/property class. Can be used for introspection.

New in version 1.0.9.

property(*name*, *quiet=False*)

Get a property instance from the property name. If quiet is True, None is returned instead of raising an exception when *name* is not a property. Defaults to *False*.

New in version 1.0.9.

Returns A *Property* derived instance corresponding to the name.

Changed in version 1.9.0: quiet was added.

proxy_ref

Returns a *WeakProxy* reference to the *EventDispatcher*.

New in version 1.9.0.

Changed in version 2.0.0: Previously it just returned itself, now it actually returns a *WeakProxy*.

register_event_type(*event_type*)

Register an event type with the dispatcher.

Registering event types allows the dispatcher to validate event handler names as they are attached and to search attached objects for suitable handlers. Each event type declaration must:

1. start with the prefix *on_*.
2. have a default handler in the class.

Example of creating a custom event:

```
class MyWidget(Widget):  
    def __init__(self, **kwargs):  
        super(MyWidget, self).__init__(**kwargs)  
        self.register_event_type('on_swipe')  
  
    def on_swipe(self):  
        pass  
  
    def on_swipe_callback(*largs):  
        print('my swipe is called', largs)  
w = MyWidget()  
w.dispatch('on_swipe')
```

setter(*name*)

Return the setter of a property. Use: `instance.setter('name')`. The setter is a convenient callback function useful if you want to directly bind one property to another. It returns a partial function that will accept (obj, value) args and results in the property 'name' of instance being set to value.

New in version 1.0.9.

For example, to bind number2 to number1 in python you would do:

```
class ExampleWidget(Widget):  
    number1 = NumericProperty(None)  
    number2 = NumericProperty(None)
```

(continues on next page)

```
def __init__(self, **kwargs):
    super(ExampleWidget, self).__init__(**kwargs)
    self.bind(number1=self.setter('number2'))
```

This is equivalent to kv binding:

```
<ExampleWidget>:
    number2: self.number1
```

unbind(kwargs)**

Unbind properties from callback functions with similar usage as `bind()`.

If a callback has been bound to a given event or property multiple times, only the first occurrence will be unbound.

Note: It is safe to use `unbind()` on a function bound with `fbind()` as long as that function was originally bound without any keyword and positional arguments. Otherwise, the function will fail to be unbound and you should use `funbind()` instead.

unbind_uid(name, uid)

Uses the uid returned by `fbind()` to unbind the callback.

This method is much more efficient than `funbind()`. If `uid` evaluates to False (e.g. 0) a `ValueError` is raised. Also, only callbacks bound with `fbind()` can be unbound with this method.

Since each call to `fbind()` will generate a unique `uid`, only one callback will be removed. If `uid` is not found among the callbacks, no error is raised.

E.g.:

```
btn6 = Button(text="B: Using flexible functions with args. For_
    ↴hardcores.")
uid = btn6.fbind('on_press', self.on_anything, "1", "2", monthly=
    ↴"python")
if not uid:
    raise Exception('Binding failed').
...
btn6.unbind_uid('on_press', uid)
```

New in version 1.9.0.

unregister_event_type(event_type)

Unregister an event type in the dispatcher.

Changed in version 2.1.0: Method renamed from `unregister_event_types` to `unregister_event_type`.

unregister_event_types(self, event_type)

class kivy.event.ObjectWithUid

Bases: `builtins.object`

(internal) This class assists in providing unique identifiers for class instances. It is not intended for direct usage.

class kivy.event.Observable

Bases: `kivy.event.ObjectWithUid`

`Observable` is a stub class defining the methods required for binding. `EventDispatcher` is (the) one example of a class that implements the binding interface. See `EventDispatcher` for details.

New in version 1.9.0.

`bind(**kwargs)`

`fbind(name, func, *largs, **kwargs)`

See `EventDispatcher.fbind()`.

Note: To keep backward compatibility with derived classes which may have inherited from `Observable` before, the `fbind()` method was added. The default implementation of `fbind()` is to create a partial function that it passes to bind while saving the uid and largs/kwargs. However, `funbind()` (and `unbind_uid()`) are fairly inefficient since we have to first lookup this partial function using the largs/kwargs or uid and then call `unbind()` on the returned function. It is recommended to overwrite these methods in derived classes to bind directly for better performance.

Similarly to `EventDispatcher.fbind()`, this method returns 0 on failure and a positive unique uid on success. This uid can be used with `unbind_uid()`.

`funbind(name, func, *largs, **kwargs)`

See `fbind()` and `EventDispatcher.funbind()`.

`unbind(**kwargs)`

`unbind_uid(name, uid)`

See `fbind()` and `EventDispatcher.unbind_uid()`.

31.12 Factory object

The factory can be used to automatically register any class or module and instantiate classes from it anywhere in your project. It is an implementation of the [Factory Pattern](#).

The class list and available modules are automatically generated by `setup.py`.

Example for registering a class/module:

```
>>> from kivy.factory import Factory
>>> Factory.register('Widget', module='kivy.uix.widget')
>>> Factory.register('Vector', module='kivy.vector')
```

Example of using the Factory:

```
>>> from kivy.factory import Factory
>>> widget = Factory.Widget(pos=(456,456))
>>> vector = Factory.Vector(9, 2)
```

Example using a class name:

```
>>> from kivy.factory import Factory
>>> Factory.register('MyWidget', cls=MyWidget)
```

By default, the first classname you register via the factory is permanent. If you wish to change the registered class, you need to unregister the classname before you re-assign it:

```

>>> from kivy.factory import Factory
>>> Factory.register('MyWidget', cls=MyWidget)
>>> widget = Factory.MyWidget()
>>> Factory.unregister('MyWidget')
>>> Factory.register('MyWidget', cls=CustomWidget)
>>> customWidget = Factory.MyWidget()

```

kivy.factory.Factory: kivy.factory.FactoryBase = <kivy.factory.FactoryBase object>

Factory instance to use for getting new classes

exception kivy.factory.FactoryException

Bases: Exception

31.13 Geometry utilities

This module contains some helper functions for geometric calculations.

kivy.geometry.circumcircle(a, b, c)

Computes the circumcircle of a triangle defined by a, b, c. See: http://en.wikipedia.org/wiki/Circumscribed_circle

Parameters

a: iterable containing at least 2 values (for x and y) The 1st point of the triangle.

b: iterable containing at least 2 values (for x and y) The 2nd point of the triangle.

c: iterable containing at least 2 values (for x and y) The 3rd point of the triangle.

Return

A tuple that defines the circle :

- The first element in the returned tuple is the center as (x, y)
- The second is the radius (float)

kivy.geometry.minimum_bounding_circle(points)

Returns the minimum bounding circle for a set of points.

For a description of the problem being solved, see the [Smallest Circle Problem](#).

The function uses Applet's Algorithm, the runtime is $O(h^3 * n)$, where h is the number of points in the convex hull of the set of points. But it runs in linear time in almost all real world cases. See: <http://tinyurl.com/6e4n5yb>

Parameters

points: iterable A list of points (2 tuple with x,y coordinates)

Return

A tuple that defines the circle:

- The first element in the returned tuple is the center (x, y)
- The second the radius (float)

31.14 Gesture recognition

This class allows you to easily create new gestures and compare them:

```
from kivy.gesture import Gesture, GestureDatabase

# Create a gesture
g = Gesture()
g.add_stroke(point_list=[(1,1), (3,4), (2,1)])
g.normalize()

# Add it to the database
gdb = GestureDatabase()
gdb.add_gesture(g)

# And for the next gesture, try to find it!
g2 = Gesture()
# ...
gdb.find(g2)
```

Warning: You don't really want to do this: it's more of an example of how to construct gestures dynamically. Typically, you would need a lot more points, so it's better to record gestures in a file and reload them to compare later. Look in the examples/gestures directory for an example of how to do that.

class `kivy.gesture.Gesture`(*tolerance=None*)

Bases: `builtins.object`

A python implementation of a gesture recognition algorithm by Oleg Dopertchouk: <http://www.gamedev.net/reference/articles/article2039.asp>

Implemented by Jeiel Aranal (chemikhazi@gmail.com), released into the public domain.

add_stroke(*point_list=None*)

Adds a stroke to the gesture and returns the Stroke instance. Optional point_list argument is a list of the mouse points for the stroke.

dot_product(*comparison_gesture*)

Calculates the dot product of the gesture with another gesture.

get_rigid_rotation(*dstpts*)

Extract the rotation to apply to a group of points to minimize the distance to a second group of points. The two groups of points are assumed to be centered. This is a simple version that just picks an angle based on the first point of the gesture.

get_score(*comparison_gesture*, *rotation_invariant=True*)

Returns the matching score of the gesture against another gesture.

normalize(*stroke_samples=32*)

Runs the gesture normalization algorithm and calculates the dot product with self.

class `kivy.gesture.GestureDatabase`

Bases: `builtins.object`

Class to handle a gesture database.

add_gesture(*gesture*)

Add a new gesture to the database.

```

find(gesture, minscore=0.9, rotation_invariant=True)
    Find a matching gesture in the database.

gesture_to_str(gesture)
    Convert a gesture into a unique string.

str_to_gesture(data)
    Convert a unique string to a gesture.

class kivy.gesture.GestureStroke
    Bases: builtins.object

    Gestures can be made up of multiple strokes.

    add_point(x=x_pos, y=y_pos)
        Adds a point to the stroke.

    center_stroke(offset_x, offset_y)
        Centers the stroke by offsetting the points.

    normalize_stroke(sample_points=32)
        Normalizes strokes so that every stroke has a standard number of points. Returns True if stroke is normalized, False if it can't be normalized. sample_points controls the resolution of the stroke.

    points_distance(point1=GesturePoint, point2=GesturePoint)
        Returns the distance between two GesturePoints.

    scale_stroke(scale_factor=float)
        Scales the stroke down by scale_factor.

    stroke_length(point_list=None)
        Finds the length of the stroke. If a point list is given, finds the length of that list.

```

31.15 Interactive launcher

New in version 1.3.0.

Deprecated since version 1.10.0: The interactive launcher has been deprecated.

The [InteractiveLauncher](#) provides a user-friendly python shell interface to an App so that it can be prototyped and debugged interactively.

Note: The Kivy API intends for some functions to only be run once or before the main EventLoop has started. Methods that can normally be called during the course of an application will work as intended, but specifically overriding methods such as `on_touch()` dynamically leads to trouble.

31.15.1 Creating an InteractiveLauncher

Take your existing subclass of App (this can be production code) and pass an instance to the [InteractiveLauncher](#) constructor.

```

from kivy.interactive import InteractiveLauncher
from kivy.app import App
from kivy.uix.button import Button

class MyApp(App):

```

(continues on next page)

```

def build(self):
    return Button(text='Hello Shell')

launcher = InteractiveLauncher(MyApp())
launcher.run()

```

After pressing *enter*, the script will return. This allows the interpreter to continue running. Inspection or modification of the App can be done safely through the InteractiveLauncher instance or the provided *SafeMembrane* class instances.

Note: If you want to test this example, start Python without any file to have already an interpreter, and copy/paste all the lines. You'll still have the interpreter at the end + the kivy application running.

31.15.2 Interactive Development

IPython provides a fast way to learn the Kivy API. The App instance and all of its attributes, including methods and the entire widget tree, can be quickly listed by using the '.' operator and pressing 'tab'. Try this code in an Ipython shell.

```

from kivy.interactive import InteractiveLauncher
from kivy.app import App
from kivy.uix.widget import Widget
from kivy.graphics import Color, Ellipse

class MyPaintWidget(Widget):
    def on_touch_down(self, touch):
        with self.canvas:
            Color(1, 1, 0)
            d = 30.
            Ellipse(pos=(touch.x - d/2, touch.y - d/2), size=(d, d))

class TestApp(App):
    def build(self):
        return Widget()

i = InteractiveLauncher(TestApp())
i.run()
i.      # press 'tab' to list attributes of the app
i.root. # press 'tab' to list attributes of the root widget

# App is boring. Attach a new widget!
i.root.add_widget(MyPaintWidget())

i.safeIn()
# The application is now blocked.
# Click on the screen several times.
i.safeOut()
# The clicks will show up now

```

```
# Erase artwork and start over
i.root.canvas.clear()
```

Note: All of the proxies used in the module store their referent in the `_ref` attribute, which can be accessed directly if needed, such as for getting doc strings. `help()` and `type()` will access the proxy, not its referent.

31.15.3 Directly Pausing the Application

Both the `InteractiveLauncher` and `SafeMembrane` hold internal references to the EventLoop's 'safe' and 'confirmed' `threading.Event` objects. You can use their safing methods to control the application manually.

`SafeMembrane.safeIn()` will cause the application to pause and `SafeMembrane.safeOut()` will allow a paused application to continue running. This is potentially useful for scripting actions into functions that need the screen to update etc.

Note: The pausing is implemented via the `Clocks` schedule_once()` method and occurs before the start of each frame.

31.15.4 Adding Attributes Dynamically

Note: This module uses threading and object proxies to encapsulate the running App. Deadlocks and memory corruption can occur if making direct references inside the thread without going through the provided proxy(s).

The `InteractiveLauncher` can have attributes added to it exactly like a normal object and if these were created from outside the membrane, they will not be threadsafe because the external references to them in the python interpreter do not go through InteractiveLauncher's membrane behavior, inherited from `SafeMembrane`.

To threadsafe these external references, simply assign them to `SafeMembrane` instances of themselves like so:

```
from kivy.interactive import SafeMembrane

interactiveLauncher.attribute = myNewObject
# myNewObject is unsafe
myNewObject = SafeMembrane(myNewObject)
# myNewObject is now safe. Call at will.
myNewObject.method()
```

TODO

Unit tests, examples, and a better explanation of which methods are safe in a running application would be nice. All three would be excellent.

Could be re-written with a context-manager style i.e.

```
with safe:  
    foo()
```

Any use cases besides compacting code?

class kivy.interactive.InteractiveLauncher(*app=None, *args, **kwargs*)
Bases: *kivy.interactive.SafeMembrane*

Proxy to an application instance that launches it in a thread and then returns and acts as a proxy to the application in the thread.

class kivy.interactive.SafeMembrane(*ob, *args, **kwargs*)
Bases: *builtins.object*

This help is for a proxy object. Did you want help on the proxy's referent instead? Try using `help(<instance>._ref)`

The SafeMembrane is a threadsafe proxy that also returns attributes as new thread-safe objects and makes thread-safe method calls, preventing thread-unsafe objects from leaking into the user's environment.

safeIn()

Provides a thread-safe entry point for interactive launching.

safeOut()

Provides a thread-safe exit point for interactive launching.

31.16 Kivy Base

This module contains the Kivy core functionality and is not intended for end users. Feel free to look through it, but bare in mind that calling any of these methods directly may result in an unpredictable behavior as the calls access directly the event loop of an application.

kivy.base.EventLoop = <kivy.base.EventLoopBase object>

EventLoop instance

class kivy.base.EventLoopBase
Bases: *kivy.event.EventDispatcher*

Main event loop. This loop handles the updating of input and dispatching events.

add_event_listener(*listener*)

Add a new event listener for getting touch events.

add_input_provider(*provider, auto_remove=False*)

Add a new input provider to listen for touch events.

add_postproc_module(*mod*)

Add a postproc input module (DoubleTap, TripleTap, DeJitter RetainTouch are defaults).

async async_idle()

Identical to *idle()*, but instead used when running within an async event loop.

close()

Exit from the main loop and stop all configured input providers.

dispatch_input()

Called by [EventLoopBase.idle\(\)](#) to read events from input providers, pass events to postproc, and dispatch final events.

ensure_window()

Ensure that we have a window.

exit()

Close the main loop and close the window.

idle()

This function is called after every frame. By default:

- it “ticks” the clock to the next frame.
- it reads all input and dispatches events.
- it dispatches *on_update*, *on_draw* and *on_flip* events to the window.

on_pause()

Event handler for *on_pause* which will be fired when the event loop is paused.

on_start()

Event handler for *on_start* which will be fired right after all input providers have been started.

on_stop()

Event handler for *on_stop* events which will be fired right after all input providers have been stopped.

post_dispatch_input(etype, me)

This function is called by [EventLoopBase.dispatch_input\(\)](#) when we want to dispatch an input event. The event is dispatched to all listeners and if grabbed, it's dispatched to grabbed widgets.

remove_android_splash(*args)

Remove android presplash in SDL2 bootstrap.

remove_event_listener(listener)

Remove an event listener from the list.

remove_input_provider(provider)

Remove an input provider.

Changed in version 2.1.0: Provider will be also removed if it exist in auto-remove list.

remove_postproc_module(mod)

Remove a postproc module.

run()

Main loop

set_window(window)

Set the window used for the event loop.

start()

Must be called before [EventLoopBase.run\(\)](#). This starts all configured input providers.

Changed in version 2.1.0: Method can be called multiple times, but event loop will start only once.

stop()

Stop all input providers and call callbacks registered using [EventLoop.add_stop_callback\(\)](#).

Changed in version 2.1.0: Method can be called multiple times, but event loop will stop only once.

property touches

Return the list of all touches currently in down or move states.

class kivy.base.ExceptionHandler

Bases: `builtins.object`

Base handler that catches exceptions in `runTouchApp()`. You can subclass and extend it as follows:

```
class E(ExceptionHandler):
    def handle_exception(self, inst):
        Logger.exception('Exception caught by ExceptionHandler')
        return ExceptionManager.PASS

ExceptionManager.add_handler(E())
```

Then, all exceptions will be set to PASS, and logged to the console!

handle_exception(exception)

Called by `ExceptionManagerBase` to handle a exception.

Defaults to returning `ExceptionManager.RAISE` that re-raises the exception. Return `ExceptionManager.PASS` to indicate that the exception was handled and should be ignored.

This may be called multiple times with the same exception, if `ExceptionManager.RAISE` is returned as the exception bubbles through multiple kivy exception handling levels.

kivy.base.ExceptionManager: `kivy.base.ExceptionManagerBase` = <kivy.base.ExceptionManagerBase object>

The `ExceptionManagerBase` instance that handles kivy exceptions.

class kivy.base.ExceptionManagerBase

Bases: `builtins.object`

ExceptionManager manages exceptions handlers.

PASS = 1

The exception should be ignored as it was handled by the handler.

RAISE = 0

The exception should be re-raised.

add_handler(cls)

Add a new exception handler to the stack.

handle_exception(inst)

Called when an exception occurred in the `runTouchApp()` main loop.

remove_handler(cls)

Remove the exception handler from the stack.

async kivy.base.async_runTouchApp(widget=None, embedded=False, async_lib=None)

Identical to `runTouchApp()` but instead it is a coroutine that can be run in an existing async event loop.

`async_lib` is the async library to use. See `kivy.app` for details and example usage.

New in version 2.0.0.

kivy.base.runTouchApp(widget=None, embedded=False)

Static main function that starts the application loop. You can access some magic via the following arguments:

See `kivy.app` for example usage.

Parameters

<empty> To make dispatching work, you need at least one input listener. If not, application will leave. (MTWindow act as an input listener)

widget If you pass only a widget, a MTWindow will be created and your widget will be added to the window as the root widget.

embedded No event dispatching is done. This will be your job.

widget + embedded No event dispatching is done. This will be your job but we try to get the window (must be created by you beforehand) and add the widget to it. Very useful for embedding Kivy in another toolkit. (like Qt, check kivy-designed)

`kivy.base.stopTouchApp()`

Stop the current application by leaving the main loop.

See [kivy.app](#) for example usage.

31.17 Logger object

The Kivy *Logger* class provides a singleton logger instance. This instance exposes a standard Python [logger](#) object but adds some convenient features.

All the standard logging levels are available : *trace, debug, info, warning, error* and *critical*.

31.17.1 Example Usage

Use the *Logger* as you would a standard Python logger.

```
from kivy.logger import Logger

Logger.info('title: This is a info message.')
Logger.debug('title: This is a debug message.')

try:
    raise Exception('bleh')
except Exception:
    Logger.exception('Something happened!')
```

The message passed to the logger is split into two parts separated by a colon (:). The first part is used as a title and the second part is used as the message. This way, you can “categorize” your messages easily.

```
Logger.info('Application: This is a test')

# will appear as

[INFO    ] [Application] This is a test
```

You can change the logging level at any time using the *setLevel* method.

```
from kivy.logger import Logger, LOG_LEVELS

Logger.setLevel(LOG_LEVELS["debug"])
```

31.17.2 Features

Although you are free to use standard python loggers, the Kivy *Logger* offers some solid benefits and useful features. These include:

- simplified usage (single instance, simple configuration, works by default)
- color-coded output
- output to *stdout* by default
- message categorization via colon separation
- access to log history even if logging is disabled
- built-in handling of various cross-platform considerations

Kivys' logger was designed to be used with kivy apps and makes logging from Kivy apps more convenient.

31.17.3 Logger Configuration

The Logger can be controlled via the Kivy configuration file:

```
[kivy]
log_level = info
log_enable = 1
log_dir = logs
log_name = kivy_%y-%m-%d_.txt
log_maxfiles = 100
```

More information about the allowed values are described in the [kivy.config](#) module.

31.17.4 Logger History

Even if the logger is not enabled, you still have access to the last 100 messages:

```
from kivy.logger import LoggerHistory
print(LoggerHistory.history)
```

kivy.logger.Logger = <Logger kivy (WARNING)>

Kivy default logger instance

class kivy.logger.LoggerHistory(level=0)

Bases: `logging.Handler`

emit(message)

Do whatever it takes to actually log the specified logging record.

This version is intended to be implemented by subclasses and so raises a `NotImplementedError`.

flush()

Ensure all logging output has been flushed.

This version does nothing and is intended to be implemented by subclasses.

31.18 Low level Metrics

31.19 Metrics

New in version 1.5.0.

A screen is defined by its physical size, density and resolution. These factors are essential for creating UI's with correct size everywhere.

In Kivy, all the graphics pipelines work with pixels. But using pixels as a measurement unit is problematic because sizes change according to the screen.

31.19.1 Dimensions

If you want to design your UI for different screen sizes, you will want better measurement units to work with. Kivy provides some more scalable alternatives.

Units

pt Points - 1/72 of an inch based on the physical size of the screen. Prefer to use **sp** instead of **pt**.

mm Millimeters - Based on the physical size of the screen.

cm Centimeters - Based on the physical size of the screen.

in Inches - Based on the physical size of the screen.

dp Density-independent Pixels - An abstract unit that is based on the physical density of the screen. With a **density** of 1, 1dp is equal to 1px. When running on a higher density screen, the number of pixels used to draw 1dp is scaled up a factor appropriate to the screen's dpi, and the inverse for a lower dpi. The ratio of dp-to-pixels will change with the screen density, but not necessarily in direct proportion. Using the **dp** unit is a simple solution to making the view dimensions in your layout resize properly for different screen densities. In other words, it provides consistency for the real-world size of your UI across different devices.

sp Scale-independent Pixels - This is like the **dp** unit, but it is also scaled by the user's font size preference. We recommend you use this unit when specifying font sizes, so the font size will be adjusted to both the screen density and the user's preference.

31.19.2 Examples

Here is an example of creating a label with a **sp** font_size and setting the height manually with a 10dp margin:

```
#:kivy 1.5.0
<MyWidget>:
    Label:
        text: 'Hello world'
        font_size: '15sp'
        size_hint_y: None
        height: self.texture_size[1] + dp(10)
```

31.19.3 Manual control of metrics

The metrics cannot be changed at runtime. Once a value has been converted to pixels, you can't retrieve the original value anymore. This stems from the fact that the DPI and density of a device cannot be changed at runtime.

We provide some environment variables to control metrics:

- `KIVY_METRICS_DENSITY`: if set, this value will be used for `density` instead of the systems one. On android, the value varies between 0.75, 1, 1.5 and 2.
- `KIVY_METRICS_FONTSIZE`: if set, this value will be used for `fontscale` instead of the systems one. On android, the value varies between 0.8 and 1.2.
- `KIVY_DPI`: if set, this value will be used for `dpi`. Please note that setting the DPI will not impact the dp/sp notation because these are based on the screen density.

For example, if you want to simulate a high-density screen (like the HTC One X):

```
KIVY_DPI=320 KIVY_METRICS_DENSITY=2 python main.py --size 1280x720
```

Or a medium-density (like Motorola Droid 2):

```
KIVY_DPI=240 KIVY_METRICS_DENSITY=1.5 python main.py --size 854x480
```

You can also simulate an alternative user preference for fontscale as follows:

```
KIVY_METRICS_FONTSIZE=1.2 python main.py
```

`kivy.metrics.Metrics: kivy.metrics.MetricsBase = <kivy.metrics.MetricsBase object>`

The metrics object storing the window scaling factors.

New in version 1.7.0.

Changed in version 2.1.0: `Metrics` is now a Context registered variable (like e.g. `Clock`).

`class kivy.metrics.MetricsBase(**kwargs)`
Bases: `kivy.event.EventDispatcher`

Class that contains the default attributes for Metrics. Don't use this class directly, but use the `Metrics` instance.

cm: float

The scaling factor that converts from centimeters to pixels.

`cm` is a `AliasProperty` containing the factor. E.g in KV: `width: self.texture_size[0] + 10 * Metrics.cm` will update width when `cm` changes from a screen configuration change.

density: float

The density of the screen.

This value is 1 by default on desktops but varies on android depending on the screen.

`density` is a `AliasProperty` and can be set to change the value. But, the `density` is reloaded and reset if we got it from the Window and the Window `density` changed.

dp: float

The scaling factor that converts from density-independent pixels to pixels.

`dp` is a `AliasProperty` containing the factor. E.g in KV: `width: self.texture_size[0] + 10 * Metrics.dp` will update width when `dp` changes from a screen configuration change.

dpi: float

The DPI of the screen.

Depending on the platform, the DPI can be taken from the Window provider (Desktop mainly) or from a platform-specific module (like android/ios).

dpi is a *AliasProperty* and can be set to change the value. But, the *density* is reloaded and reset if we got it from the Window and the Window *dpi* changed.

dpi_rounded: int

Return the *dpi* of the screen, rounded to the nearest of 120, 160, 240 or 320.

dpi_rounded is a *AliasProperty* and updates when *dpi* changes.

fontscale: float

The fontscale user preference.

This value is 1 by default but can vary between 0.8 and 1.2.

fontscale is a *AliasProperty* and can be set to change the value.

inch: float

The scaling factor that converts from inches to pixels.

inch is a *AliasProperty* containing the factor. E.g in KV: `width: self.texture_size[0] + 10 * Metrics.inch` will update width when *inch* changes from a screen configuration change.

mm: float

The scaling factor that converts from millimeters to pixels.

mm is a *AliasProperty* containing the factor. E.g in KV: `width: self.texture_size[0] + 10 * Metrics.mm` will update width when *mm* changes from a screen configuration change.

pt: float

The scaling factor that converts from points to pixels.

pt is a *AliasProperty* containing the factor. E.g in KV: `width: self.texture_size[0] + 10 * Metrics.pt` will update width when *pt* changes from a screen configuration change.

reset_dpi(*args)

Resets the dpi (and possibly density) to the platform values, overwriting any manually set values.

reset_metrics()

Resets the dpi/density/fontscale to the platform values, overwriting any manually set values.

sp: float

The scaling factor that converts from scale-independent pixels to pixels.

sp is a *AliasProperty* containing the factor. E.g in KV: `width: self.texture_size[0] + 10 * Metrics.sp` will update width when *sp* changes from a screen configuration change.

kivy.metrics.cm(value) → float

Convert from centimeters to pixels

kivy.metrics.dp(value) → float

Convert from density-independent pixels to pixels

kivy.metrics.dpi2px(value, unicode ext) → float

Converts the value according to the ext.

```
kivy.metrics.inch(value) → float  
    Convert from inches to pixels  
  
kivy.metrics.mm(value) → float  
    Convert from millimeters to pixels  
  
kivy.metrics.pt(value) → float  
    Convert from points to pixels  
  
kivy.metrics.sp(value) → float  
    Convert from scale-independent pixels to pixels
```

31.20 Multistroke gesture recognizer

New in version 1.9.0.

Warning: This is experimental and subject to change as long as this warning notice is present.

See `kivy/examples/demo/multistroke/main.py` for a complete application example.

31.20.1 Conceptual Overview

This module implements the Protractor gesture recognition algorithm.

`Recognizer` is the search/database API similar to `GestureDatabase`. It maintains a list of `MultistrokeGesture` objects and allows you to search for a user-input gestures among them.

`ProgressTracker` tracks the progress of a `Recognizer.recognize()` call. It can be used to interact with the running recognizer task, for example forcing it to stop half-way, or analyzing results as they arrive.

`MultistrokeGesture` represents a gesture in the gesture database (`Recognizer.db`). It is a container for `UnistrokeTemplate` objects, and implements the heap permute algorithm to automatically generate all possible stroke orders (if desired).

`UnistrokeTemplate` represents a single stroke path. It's typically instantiated automatically by `MultistrokeGesture`, but sometimes you may need to create them manually.

`Candidate` represents a user-input gesture that is used to search the gesture database for matches. It is normally instantiated automatically by calling `Recognizer.recognize()`.

31.20.2 Usage examples

See `kivy/examples/demo/multistroke/main.py` for a complete application example.

You can bind to events on `Recognizer` to track the state of all calls to `Recognizer.recognize()`. The callback function will receive an instance of `ProgressTracker` that can be used to analyze and control various aspects of the recognition process

```
from kivy.vector import Vector  
from kivy.multistroke import Recognizer  
  
gdb = Recognizer()  
  
def search_start(gdb, pt):
```

(continues on next page)

(continued from previous page)

```
print("A search is starting with %d tasks" % (pt.tasks))

def search_stop(gdb, pt):
    # This will call max() on the result dictionary, so it's best to store
    # it instead of calling it 3 times consecutively
    best = pt.best
    print("Search ended (%s). Best is %s (score %f, distance %f)" % (
        pt.status, best['name'], best['score'], best['dist']))

# Bind your callbacks to track all matching operations
gdb.bind(on_search_start=search_start)
gdb.bind(on_search_complete=search_stop)

# The format below is referred to as 'strokes', a list of stroke paths.
# Note that each path shown here consists of two points, ie a straight
# line; if you plot them it looks like a T, hence the name.
gdb.add_gesture('T', [
    [Vector(30, 7), Vector(103, 7)],
    [Vector(66, 7), Vector(66, 87)]])

# Now you can search for the 'T' gesture using similar data (user input).
# This will trigger both of the callbacks bound above.
gdb.recognize([
    [Vector(45, 8), Vector(110, 12)],
    [Vector(88, 9), Vector(85, 95)])
```

On the next *Clock* tick, the matching process starts (and, in this case, completes).

To track individual calls to *Recognizer.recognize()*, use the return value (also a *ProgressTracker* instance)

```
# Same as above, but keep track of progress using returned value
progress = gdb.recognize([
    [Vector(45, 8), Vector(110, 12)],
    [Vector(88, 9), Vector(85, 95)])]

progress.bind(on_progress=my_other_callback)
print(progress.progress) # = 0

# [ assuming a kivy.clock.Clock.tick() here ]

print(result.progress) # = 1
```

31.20.3 Algorithm details

For more information about the matching algorithm, see:

“Protractor: A fast and accurate gesture recognizer” by Yang Li <http://yangli.org/pdf/protractor-chi2010.pdf>

“\$N-Protractor” by Lisa Anthony and Jacob O. Wobbrock <http://depts.washington.edu/aimgroup/proj/dollar/ndollar-protractor.pdf>

Some of the code is derived from the JavaScript implementation here: <http://depts.washington.edu/aimgroup/proj/dollar/ndollar.html>

```
class kivy.multistroke.Candidate(strokes=None, numpoints=16, **kwargs)
Bases: builtins.object
```

Represents a set of unistroke paths of user input, ie data to be matched against a *UnistrokeTemplate* object using the Protractor algorithm. By default, data is precomputed to match both rotation bounded and fully invariant *UnistrokeTemplate* objects.

Arguments

strokes See `MultistrokeGesture.strokes` for format example. The Candidate strokes are simply combined to a unistroke in the order given. The idea is that this will match one of the unistroke permutations in *MultistrokeGesture.templates*.

numpoints The Candidate's default N; this is only for a fallback, it is not normally used since n is driven by the *UnistrokeTemplate* we are being compared to.

skip_bound If True, do not generate/store rotation bounded vectors

skip_invariant If True, do not generate/store rotation invariant vectors

Note that you WILL get errors if you set a skip-flag and then attempt to retrieve the data.

add_stroke(stroke)

Add a stroke to the candidate; this will invalidate all previously computed vectors

get_angle_similarity(tpl, **kwargs)

(Internal use only) Compute the angle similarity between this Candidate and a *UnistrokeTemplate* object. Returns a number that represents the angle similarity (lower is more similar).

get_protractor_vector(numpoints, orientation_sens)

(Internal use only) Return vector for comparing to a *UnistrokeTemplate* with Protractor

get_start_unit_vector(numpoints, orientation_sens)

(Internal use only) Get the start vector for this Candidate, with the path resampled to *numpoints* points. This is the first step in the matching process. It is compared to a *UnistrokeTemplate* object's start vector to determine angle similarity.

prepare(numpoints=None)

Prepare the Candidate vectors. `self.strokes` is combined to a single unistroke (connected end-to-end), resampled to *numpoints* points, and then the vectors are calculated and stored in `self.db` (for use by `get_distance` and `get_angle_similarity`)

```
class kivy.multistroke.MultistrokeGesture(name, strokes=None, **kwargs)
```

Bases: builtins.object

MultistrokeGesture represents a gesture. It maintains a set of *strokes* and generates unistroke (ie *UnistrokeTemplate*) permutations that are used for evaluating candidates against this gesture later.

Arguments

name Identifies the name of the gesture - it is returned to you in the results of a *Recognizer.recognize()* search. You can have any number of *MultistrokeGesture* objects with the same name; many definitions of one gesture. The same name is given to all the generated unistroke permutations. Required, no default.

strokes A list of paths that represents the gesture. A path is a list of Vector objects:

```
gesture = MultistrokeGesture('my_gesture', strokes=[  
    [Vector(x1, y1), Vector(x2, y2), ..... ], # stroke 1  
    [Vector(), Vector(), Vector(), Vector()] # stroke 2
```

(continues on next page)

(continued from previous page)

```
#, [stroke 3], [stroke 4], ...  
])
```

For template matching purposes, all the strokes are combined to a single list (unistroke). You should still specify the strokes individually, and set *stroke_sensitive* True (whenever possible).

Once you do this, unistroke permutations are immediately generated and stored in *self.templates* for later, unless you set the *permute* flag to False.

priority Determines when *Recognizer.recognize()* will attempt to match this template, lower priorities are evaluated first (only if a priority filter is used). You should use lower priority on gestures that are more likely to match. For example, set user templates at lower number than generic templates. Default is 100.

numpoints Determines the number of points this gesture should be resampled to (for matching purposes). The default is 16.

stroke_sensitive Determines if the number of strokes (paths) in this gesture is required to be the same in the candidate (user input) gesture during matching. If this is False, candidates will always be evaluated, disregarding the number of strokes. Default is True.

orientation_sensitive Determines if this gesture is orientation sensitive. If True, aligns the indicative orientation with the one of eight base orientations that requires least rotation. Default is True.

angle_similarity This is used by the *Recognizer.recognize()* function when a candidate is evaluated against this gesture. If the angles between them are too far off, the template is considered a non-match. Default is 30.0 (degrees)

permute If False, do not use Heap Permute algorithm to generate different stroke orders when instantiated. If you set this to False, a single UnistrokeTemplate built from *strokes* is used.

add_stroke(stroke, permute=False)

Add a stroke to the *self.strokes* list. If *permute* is True, the *permute()* method is called to generate new unistroke templates

get_distance(cand, tpl, numpoints=None)

Compute the distance from this Candidate to a UnistrokeTemplate. Returns the Cosine distance between the stroke paths.

numpoints will prepare both the UnistrokeTemplate and Candidate path to n points (when necessary), you probably don't want to do this.

match_candidate(cand, **kwargs)

Match a given candidate against this MultistrokeGesture object. Will test against all templates and report results as a list of four items:

index 0 Best matching template's index (in *self.templates*)

index 1 Computed distance from the template to the candidate path

index 2 List of distances for all templates. The list index corresponds to a *UnistrokeTemplate* index in *self.templates*.

index 3 Counter for the number of performed matching operations, ie templates matched against the candidate

permute()

Generate all possible unistroke permutations from self.strokes and save the resulting list of UnistrokeTemplate objects in self.templates.

Quote from <http://faculty.washington.edu/wobbrock/pubs/gi-10.2.pdf>

We use Heap Permute [16] (p. 179) to generate all stroke orders in a multistroke gesture. Then, to generate stroke directions for each order, we treat each component stroke as a dichotomous [0,1] variable. There are 2^N combinations for N strokes, so we convert the decimal values 0 to 2^N-1 , inclusive, to binary representations and regard each bit as indicating forward (0) or reverse (1). This algorithm is often used to generate truth tables in propositional logic.

See section 4.1: “\$N Algorithm” of the linked paper for details.

Warning: Using heap permute for gestures with more than 3 strokes can result in very large number of templates (a 9-stroke gesture = 38 million templates). If you are dealing with these types of gestures, you should manually compose all the desired stroke orders.

class kivy.multistroke.ProgressTracker(candidate, tasks, **kwargs)

Bases: [kivy.event.EventDispatcher](#)

Represents an ongoing (or completed) search operation. Instantiated and returned by the [Recognizer.recognize\(\)](#) method when it is called. The *results* attribute is a dictionary that is updated as the recognition operation progresses.

Note: You do not need to instantiate this class.

Arguments

candidate [Candidate](#) object to be evaluated

tasks Total number of gestures in tasklist (to test against)

Events

on_progress Fired for every gesture that is processed

on_result Fired when a new result is added, and it is the first match for the *name* so far, or a consecutive match with better score.

on_complete Fired when the search is completed, for whatever reason. (use *ProgressTracker.status* to find out)

Attributes

results A dictionary of all results (so far). The key is the name of the gesture (ie [UnistrokeTemplate.name](#) usually inherited from [MultistrokeGesture](#)). Each item in the dictionary is a dict with the following entries:

name Name of the matched template (redundant)

score Computed score from 1.0 (perfect match) to 0.0

dist Cosine distance from candidate to template (low=closer)

gesture The [MultistrokeGesture](#) object that was matched

best_template Index of the best matching template (in `MultistrokeGesture.templates`)

template_results List of distances for all templates. The list index corresponds to a `UnistrokeTemplate` index in `gesture.templates`.

status

search Currently working

stop Was stopped by the user (`stop()` called)

timeout A timeout occurred (specified as `timeout=` to `recognize()`)

goodscore The search was stopped early because a gesture with a high enough score was found (specified as `goodscore=` to `recognize()`)

complete The search is complete (all gestures matching filters were tested)

property best

Return the best match found by `recognize()` so far. It returns a dictionary with three keys, 'name', 'dist' and 'score' representing the template's name, distance (from candidate path) and the computed score value. This is a Python property.

property progress

Returns the progress as a float, 0 is 0% done, 1 is 100%. This is a Python property.

stop()

Raises a stop flag that is checked by the search process. It will be stopped on the next clock tick (if it is still running).

class `kivy.multistroke.Recognizer(**kwargs)`

Bases: `kivy.event.EventDispatcher`

`Recognizer` provides a gesture database with matching facilities.

Events

on_search_start Fired when a new search is started using this Recognizer.

on_search_complete Fired when a running search ends, for whatever reason. (use `ProgressTracker.status` to find out)

Properties

db A `ListProperty` that contains the available `MultistrokeGesture` objects.

db is a `ListProperty` and defaults to []

add_gesture(name, strokes, **kwargs)

Add a new gesture to the database. This will instantiate a new `MultistrokeGesture` with `strokes` and append it to `self.db`.

Note: If you already have instantiated a `MultistrokeGesture` object and wish to add it, append it to `Recognizer.db` manually.

export_gesture(filename=None, **kwargs)

Export a list of `MultistrokeGesture` objects. Outputs a base64-encoded string that can be decoded to a Python list with the `parse_gesture()` function or imported directly to `self.db` using `Recognizer.import_gesture()`. If `filename` is specified, the output is written to disk, otherwise returned.

This method accepts optional `Recognizer.filter()` arguments.

```
filter(**kwargs)
```

`filter()` returns a subset of objects in `self.db`, according to given criteria. This is used by many other methods of the `Recognizer`; the arguments below can for example be used when calling `Recognizer.recognize()` or `Recognizer.export_gesture()`. You normally don't need to call this directly.

Arguments

`name` Limits the returned list to gestures where `MultistrokeGesture.name` matches given regular expression(s). If `re.match(name, MultistrokeGesture.name)` tests true, the gesture is included in the returned list. Can be a string or an array of strings

```
gdb = Recognizer()

# Will match all names that start with a capital N
# (ie Next, New, N, Nebraska etc, but not "n" or "next")
gdb.filter(name='N')

# exactly 'N'
gdb.filter(name='N$')

# Nebraska, teletubbies, France, fraggle, N, n, etc
gdb.filter(name=['[Nn]', '(?i)T', '(?i)F'])
```

`priority` Limits the returned list to gestures with certain `MultistrokeGesture.priority` values. If specified as an integer, only gestures with a lower priority are returned. If specified as a list (min/max)

```
# Max priority 50
gdb.filter(priority=50)

# Max priority 50 (same result as above)
gdb.filter(priority=[0, 50])

# Min priority 50, max 100
gdb.filter(priority=[50, 100])
```

When this option is used, `Recognizer.db` is automatically sorted according to priority, incurring extra cost. You can use `force_priority_sort` to override this behavior if your gestures are already sorted according to priority.

`orientation_sensitive` Limits the returned list to gestures that are orientation sensitive (True), gestures that are not orientation sensitive (False) or None (ignore template sensitivity, this is the default).

`numstrokes` Limits the returned list to gestures that have the specified number of strokes (in `MultistrokeGesture.strokes`). Can be a single integer or a list of integers.

`numpoints` Limits the returned list to gestures that have specific `MultistrokeGesture.numpoints` values. This is provided for flexibility, do not use it unless you understand what it does. Can be a single integer or a list of integers.

`force_priority_sort` Can be used to override the default sort behavior. Normally `MultistrokeGesture` objects are returned in priority order if the `priority`

option is used. Setting this to True will return gestures sorted in priority order, False will return in the order gestures were added. None means decide automatically (the default).

Note: For improved performance, you can load your gesture database in priority order and set this to False when calling `Recognizer.recognize()`

db Can be set if you want to filter a different list of objects than `Recognizer`.
db. You probably don't want to do this; it is used internally by `import_gesture()`.

`import_gesture(data=None, filename=None, **kwargs)`

Import a list of gestures as formatted by `export_gesture()`. One of `data` or `filename` must be specified.

This method accepts optional `Recognizer.filter()` arguments, if none are specified then all gestures in specified data are imported.

`parse_gesture(data)`

Parse data formatted by `export_gesture()`. Returns a list of `MultistrokeGesture` objects. This is used internally by `import_gesture()`, you normally don't need to call this directly.

`prepare_templates(**kwargs)`

This method is used to prepare `UnistrokeTemplate` objects within the gestures in self.db. This is useful if you want to minimize punishment of lazy resampling by preparing all vectors in advance. If you do this before a call to `Recognizer.export_gesture()`, you will have the vectors computed when you load the data later.

This method accepts optional `Recognizer.filter()` arguments.

`force_numpoints`, if specified, will prepare all templates to the given number of points (instead of each template's preferred n; ie `UnistrokeTemplate.numpoints`). You normally don't want to do this.

`recognize(strokes, goodscore=None, timeout=0, delay=0, **kwargs)`

Search for gestures matching `strokes`. Returns a `ProgressTracker` instance.

This method accepts optional `Recognizer.filter()` arguments.

Arguments

`strokes` A list of stroke paths (list of lists of `Vector` objects) that will be matched against gestures in the database. Can also be a `Candidate` instance.

Warning: If you manually supply a `Candidate` that has a skip-flag, make sure that the correct filter arguments are set. Otherwise the system will attempt to load vectors that have not been computed. For example, if you set `skip_bounded` and do not set `orientation_sensitive` to False, it will raise an exception if an orientation_sensitive `UnistrokeTemplate` is encountered.

`goodscore` If this is set (between 0.0 - 1.0) and a gesture score is equal to or higher than the specified value, the search is immediately halted and the `on_search_complete` event is fired (+ the `on_complete` event of the associated `ProgressTracker` instance). Default is None (disabled).

`timeout` Specifies a timeout (in seconds) for when the search is aborted and the results returned. This option applies only when `max_gpf` is not 0. Default value is 0, meaning all gestures in the database will be tested, no matter how long it takes.

max_gpf Specifies the maximum number of *MultistrokeGesture* objects that can be processed per frame. When exceeded, will cause the search to halt and resume work in the next frame. Setting to 0 will complete the search immediately (and block the UI).

Warning: This does not limit the number of *UnistrokeTemplate* objects matched! If a single gesture has a million templates, they will all be processed in a single frame with *max_gpf*=1!

delay Sets an optional delay between each run of the recognizer loop. Normally, a run is scheduled for the next frame until the tasklist is exhausted. If you set this, there will be an additional delay between each run (specified in seconds). Default is 0, resume in the next frame.

force_numpoints forces all templates (and candidate) to be prepared to a certain number of points. This can be useful for example if you are evaluating templates for optimal n (do not use this unless you understand what it does).

`transfer_gesture(tgt, **kwargs)`

Transfers *MultistrokeGesture* objects from *Recognizer.db* to another *Recognizer* instance *tgt*.

This method accepts optional *Recognizer.filter()* arguments.

`class kivy.multistroke.UnistrokeTemplate(name, points=None, **kwargs)`

Bases: *builtins.object*

Represents a (uni)stroke path as a list of Vectors. Normally, this class is instantiated by *MultistrokeGesture* and not by the programmer directly. However, it is possible to manually compose *UnistrokeTemplate* objects.

Arguments

name Identifies the name of the gesture. This is normally inherited from the parent *MultistrokeGesture* object when a template is generated.

points A list of points that represents a unistroke path. This is normally one of the possible stroke order permutations from a *MultistrokeGesture*.

numpoints The number of points this template should (ideally) be resampled to before the matching process. The default is 16, but you can use a template-specific settings if that improves results.

orientation_sensitive Determines if this template is orientation sensitive (True) or fully rotation invariant (False). The default is True.

Note: You will get an exception if you set a skip-flag and then attempt to retrieve those vectors.

`add_point(p)`

Add a point to the unistroke/path. This invalidates all previously computed vectors.

`prepare(numpoints=None)`

This function prepares the *UnistrokeTemplate* for matching given a target number of points (for resample). 16 is optimal.

31.21 Parser utilities

Helper functions used for CSS parsing.

kivy.parser.parse_bool(*text*)

Parse a string to a boolean, ignoring case. “true”/“1” is True, “false”/“0” is False. Anything else throws an exception.

kivy.parser.parse_color(*text*)

Parse a string to a kivy color. Supported formats:

- `rgb(r, g, b)`
- `rgba(r, g, b, a)`
- `rgb`
- `rgba`
- `rrggbb`
- `rrggbbaa`

For hexdecimal values, you can also use:

- `#rgb`
- `#rgba`
- `#rrggbb`
- `#rrggbbaa`

kivy.parser.parse_filename(*filename*)

Parse a filename and search for it using `resource_find()`. If found, the resource path is returned, otherwise return the unmodified filename (as specified by the caller).

kivy.parser.parse_float

alias of `float`

kivy.parser.parse_float4(*text*)

Parse a string to a list of exactly 4 floats.

```
>>> parse_float4('54 87. 35 0')
54, 87., 35, 0
```

kivy.parser.parse_int

alias of `int`

kivy.parser.parse_int2(*text*)

Parse a string to a list of exactly 2 integers.

```
>>> print(parse_int2("12 54"))
12, 54
```

kivy.parser.parse_string(*text*)

Parse a string to a string (removing single and double quotes).

31.22 Properties

The *Properties* classes are used when you create an *EventDispatcher*.

Warning: Kivy's Properties are **not to be confused** with Python's properties (i.e. the @property decorator and the <property> type).

Kivy's property classes support:

Value Checking / Validation When you assign a new value to a property, the value is checked against validation constraints. For example, validation for an *OptionProperty* will make sure that the value is in a predefined list of possibilities. Validation for a *NumericProperty* will check that your value is a numeric type. This prevents many errors early on.

Observer Pattern You can specify what should happen when a property's value changes. You can bind your own function as a callback to changes of a *Property*. If, for example, you want a piece of code to be called when a widget's *pos* property changes, you can *bind* a function to it.

Better Memory Management The same instance of a property is shared across multiple widget instances.

31.22.1 Comparison Python vs. Kivy

Basic example

Let's compare Python and Kivy properties by creating a Python class with 'a' as a float property:

```
class MyClass(object):
    def __init__(self, a=1.0):
        super(MyClass, self).__init__()
        self.a = a
```

With Kivy, you can do:

```
class MyClass(EventDispatcher):
    a = NumericProperty(1.0)
```

Depth being tracked

Only the "top level" of a nested object is being tracked. For example:

```
my_list_prop = ListProperty([1, {'hi': 0}])
# Changing a top level element will trigger all `on_my_list_prop` callbacks
my_list_prop[0] = 4
# Changing a deeper element will be ignored by all `on_my_list_prop` callbacks
my_list_prop[1]['hi'] = 4
```

The same holds true for all container-type kivy properties.

Value checking

If you wanted to add a check for a minimum / maximum value allowed for a property, here is a possible implementation in Python:

```
class MyClass(object):
    def __init__(self, a=1):
        super(MyClass, self).__init__()
        self.a_min = 0
        self.a_max = 100
        self.a = a

    def _get_a(self):
        return self._a
    def _set_a(self, value):
        if value < self.a_min or value > self.a_max:
            raise ValueError('a out of bounds')
        self._a = value
    a = property(_get_a, _set_a)
```

The disadvantage is you have to do that work yourself. And it becomes laborious and complex if you have many properties. With Kivy, you can simplify the process:

```
class MyClass(EventDispatcher):
    a = BoundedNumericProperty(1, min=0, max=100)
```

That's all!

Error Handling

If setting a value would otherwise raise a `ValueError`, you have two options to handle the error gracefully within the property. The first option is to use an `errorvalue` parameter. An `errorvalue` is a substitute for the invalid value:

```
# simply returns 0 if the value exceeds the bounds
bnp = BoundedNumericProperty(0, min=-500, max=500, errorvalue=0)
```

The second option is to use an `errorhandler` parameter. An `errorhandler` is a callable (single argument function or lambda) which can return a valid substitute:

```
# returns the boundary value when exceeded
bnp = BoundedNumericProperty(0, min=-500, max=500,
    errorhandler=lambda x: 500 if x > 500 else -500)
```

Keyword arguments and `__init__()`

When working with inheritance, namely with the `__init__()` of an object that inherits from `EventDispatcher` e.g. a `Widget`, the properties protect you from a Python 3 object error. This error occurs when passing `kwargs` to the `object` instance through a `super()` call:

```
class MyClass(EventDispatcher):
    def __init__(self, **kwargs):
        super(MyClass, self).__init__(**kwargs)
        self.my_string = kwargs.get('my_string')
```

(continues on next page)

```
print(MyClass(my_string='value').my_string)
```

While this error is silenced in Python 2, it will stop the application in Python 3 with:

```
TypeError: object.__init__() takes no parameters
```

Logically, to fix that you'd either put *my_string* directly in the `__init__()` definition as a required argument or as an optional keyword argument with a default value i.e.:

```
class MyClass(EventDispatcher):
    def __init__(self, my_string, **kwargs):
        super(MyClass, self).__init__(**kwargs)
        self.my_string = my_string
```

or:

```
class MyClass(EventDispatcher):
    def __init__(self, my_string='default', **kwargs):
        super(MyClass, self).__init__(**kwargs)
        self.my_string = my_string
```

Alternatively, you could pop the key-value pair from the *kwargs* dictionary before calling *super()*:

```
class MyClass(EventDispatcher):
    def __init__(self, **kwargs):
        self.my_string = kwargs.pop('my_string')
        super(MyClass, self).__init__(**kwargs)
```

Kivy properties are more flexible and do the required *kwargs.pop()* in the background automatically (within the *super()* call to *EventDispatcher*) to prevent this distraction:

```
class MyClass(EventDispatcher):
    my_string = StringProperty('default')
    def __init__(self, **kwargs):
        super(MyClass, self).__init__(**kwargs)

print(MyClass(my_string='value').my_string)
```

Conclusion

Kivy properties are easier to use than the standard ones. See the next chapter for examples of how to use them :)

31.22.2 Observe Property changes

As we said in the beginning, Kivy's Properties implement the [Observer pattern](#). That means you can [`bind\(\)`](#) to a property and have your own function called when the value changes.

There are multiple ways to observe the changes.

Observe using bind()

You can observe a property change by using the `bind()` method outside of the class:

```
class MyClass(EventDispatcher):
    a = NumericProperty(1)

    def callback(instance, value):
        print('My callback is call from', instance)
        print('and the a value changed to', value)

    ins = MyClass()
    ins.bind(a=callback)

# At this point, any change to the a property will call your callback.
ins.a = 5      # callback called
ins.a = 5      # callback not called, because the value did not change
ins.a = -1     # callback called
```

Note: Property objects live at the class level and manage the values attached to instances. Re-assigning at class level will remove the Property. For example, continuing with the code above, `MyClass.a = 5` replaces the property object with a simple int.

Observe using 'on_<propname>'

If you defined the class yourself, you can use the 'on_<propname>' callback:

```
class MyClass(EventDispatcher):
    a = NumericProperty(1)

    def on_a(self, instance, value):
        print('My property a changed to', value)
```

Warning: Be careful with 'on_<propname>'. If you are creating such a callback on a property you are inheriting, you must not forget to call the superclass function too.

31.22.3 Binding to properties of properties.

When binding to a property of a property, for example binding to a numeric property of an object saved in a object property, updating the object property to point to a new object will not re-bind the numeric property to the new object. For example:

```
<MyWidget>:  
    Label:  
        id: first  
        text: 'First label'  
    Label:  
        id: second  
        text: 'Second label'  
    Button:  
        label: first  
        text: self.label.text  
        on_press: self.label = second
```

When clicking on the button, although the label object property has changed to the second widget, the button text will not change because it is bound to the text property of the first label directly.

In 1.9.0, the `rebind` option has been introduced that will allow the automatic updating of the `text` when `label` is changed, provided it was enabled. See [ObjectProperty](#).

```
class kivy.properties.AliasProperty(getter, setter=None, rebind=False,  
                                    watch_before_use=True, **kwargs)  
Bases: kivy.properties.Property
```

If you don't find a Property class that fits to your needs, you can make your own by creating custom Python getter and setter methods.

Example from `kivy/uix/widget.py` where `x` and `width` are instances of [NumericProperty](#):

```
def get_right(self):  
    return self.x + self.width  
def set_right(self, value):  
    self.x = value - self.width  
right = AliasProperty(get_right, set_right, bind=['x', 'width'])
```

If `x` were a non Kivy property then you have to return `True` from setter to dispatch new value of `right`:

```
def set_right(self, value):  
    self.x = value - self.width  
    return True
```

Usually `bind` list should contain all Kivy properties used in getter method. If you return `True` it will cause a dispatch which one should do when the property value has changed, but keep in mind that the property could already have dispatched the changed value if a kivy property the alias property is bound was set in the setter, causing a second dispatch if the setter returns `True`.

If you want to cache the value returned by getter then pass `cache=True`. This way getter will only be called if new value is set or one of the binded properties changes. In both cases new value of alias property will be cached again.

To make property readonly pass `None` as setter. This way `AttributeError` will be raised on every set attempt:

```
right = AliasProperty(get_right, None, bind=['x', 'width'], cache=True)
```

Parameters

getter: function Function to use as a property getter.

setter: function Function to use as a property setter. Callbacks bound to the alias property won't be called when the property is set (e.g. `right = 10`), unless the setter returns `True`.

bind: list/tuple Properties to observe for changes as property name strings. Changing values of this properties will dispatch value of the alias property.

cache: boolean If `True`, the value will be cached until one of the binded elements changes or if setter returns `True`.

rebind: bool, defaults to False See [ObjectProperty](#) for details.

watch_before_use: bool, defaults to True Whether the `bind` properties are tracked (bound) before this property is used in any way.

By default, the getter is called if the `bind` properties update or if the property value (unless cached) is read. As an optimization to speed up widget creation, when `watch_before_use` is `False`, we only track the bound properties once this property is used in any way (i.e. it is bound, it was set/read, etc).

The property value read/set/bound will be correct as expected in both cases. The difference is only that when `False`, any side effects from the `getter` would not occur until this property is interacted with in any way because the `getter` won't be called early.

Changed in version 1.9.0: `rebind` has been introduced.

Changed in version 1.4.0: Parameter `cache` added.

get(EventDispatcher obj)

link_deps(EventDispatcher obj, unicode name)

link_eagerly(EventDispatcher obj) → PropertyStorage

rebind

rebind: 'int'

set(EventDispatcher obj, value)

trigger_change(EventDispatcher obj, value)

class kivy.properties.BooleanProperty(defaultvalue=True, **kw)

Bases: [kivy.properties.Property](#)

Parameters

defaultvalue: boolean Specifies the default value of the property.

class kivy.properties.BoundedNumericProperty(*largs, **kw)

Bases: [kivy.properties.Property](#)

maximum bound – within a numeric range.

Parameters

default: numeric Specifies the default value of the property.

****kwargs: a list of keyword arguments** If a *min* parameter is included, this specifies the minimum numeric value that will be accepted. If a *max* parameter is included, this specifies the maximum numeric value that will be accepted.

bounds

Return min/max of the value.

New in version 1.0.9.

get_max(EventDispatcher obj)

Return the maximum value acceptable for the BoundedNumericProperty in *obj*. Return None if no maximum value is set. Check [get_min](#) for a usage example.

New in version 1.1.0.

get_min(EventDispatcher obj)

Return the minimum value acceptable for the BoundedNumericProperty in *obj*. Return None if no minimum value is set:

```
class MyWidget(Widget):
    number = BoundedNumericProperty(0, min=-5, max=5)

widget = MyWidget()
print(widget.property('number').get_min(widget))
# will output -5
```

New in version 1.1.0.

set_max(EventDispatcher obj, value)

Change the maximum value acceptable for the BoundedNumericProperty, only for the *obj* instance. Set to None if you want to disable it. Check [set_min](#) for a usage example.

Warning: Changing the bounds doesn't revalidate the current value.

New in version 1.1.0.

set_min(EventDispatcher obj, value)

Change the minimum value acceptable for the BoundedNumericProperty, only for the *obj* instance. Set to None if you want to disable it:

```
class MyWidget(Widget):
    number = BoundedNumericProperty(0, min=-5, max=5)

widget = MyWidget()
# change the minimum to -10
widget.property('number').set_min(widget, -10)
# or disable the minimum check
widget.property('number').set_min(widget, None)
```

Warning: Changing the bounds doesn't revalidate the current value.

New in version 1.1.0.

class kivy.properties.ColorProperty(defaultvalue=0, **kw) Bases: [kivy.properties.Property](#)

- a collection of 3 or 4 float values between 0-1 (kivy default)

- a string in the format #rrggb or #rrggbbaa
- a string representing color name (eg. 'red', 'yellow', 'green')

Object `colormap` is used to retrieve color from color name and names definitions can be found at this [link](#). Color can be assigned in different formats, but it will be returned as `ObservableList` of 4 float elements with values between 0-1.

Parameters

`defaultvalue: list or string, defaults to [1.0, 1.0, 1.0, 1.0]` Specifies the default value of the property.

New in version 1.10.0.

Changed in version 2.0.0: Color value will be dispatched when set through indexing or slicing, but when setting with slice you must ensure that slice has 4 components with float values between 0-1. Assigning color name as value is now supported. Value `None` is allowed as default value for property.

`class kivy.properties.ConfigParserProperty(defaultvalue, section, key, config, **kw)`
Bases: [kivy.properties.Property](#)

of a [ConfigParser](#) as well as to bind the ConfigParser values to other properties.

A ConfigParser is composed of sections, where each section has a number of keys and values associated with these keys. ConfigParserProperty lets you automatically listen to and change the values of specified keys based on other kivy properties.

For example, say we want to have a TextInput automatically write its value, represented as an int, in the `info` section of a ConfigParser. Also, the textinputs should update its values from the ConfigParser's fields. Finally, their values should be displayed in a label. In py:

```
class Info(Label):
    number = ConfigParserProperty(0, 'info', 'number', 'example',
                                  val_type=int, errorvalue=41)

    def __init__(self, **kw):
        super(Info, self).__init__(**kw)
        config = ConfigParser(name='example')
```

The above code creates a property that is connected to the `number` key in the `info` section of the ConfigParser named `example`. Initially, this ConfigParser doesn't exist. Then, in `__init__`, a ConfigParser is created with name `example`, which is then automatically linked with this property. then in kv:

```
BoxLayout:
    TextInput:
        id: number
        text: str(info.number)
    Info:
        id: info
        number: number.text
        text: 'Number: {}'.format(self.number)
```

You'll notice that we have to do `text: str(info.number)`, this is because the value of this property is always an int, because we specified `int` as the `val_type`. However, we can assign anything to the property, e.g. `number: number.text` which assigns a string, because it is instantly converted with the `val_type` callback.

Note: If a file has been opened for this ConfigParser using `read()`, then `write()` will be called every property change, keeping the file updated.

Warning: It is recommended that the config parser object be assigned to the property after the kv tree has been constructed (e.g. schedule on next frame from init). This is because the kv tree and its properties, when constructed, are evaluated on its own order, therefore, any initial values in the parser might be overwritten by objects it's bound to. So in the example above, the TextInput might be initially empty, and if `number: number.text` is evaluated before `text: str(info.number)`, the config value will be overwritten with the (empty) text value.

Parameters

default: object type Specifies the default value for the key. If the parser associated with this property doesn't have this section or key, it'll be created with the current value, which is the default value initially.

section: string type The section in the ConfigParser where the key / value will be written. Must be provided. If the section doesn't exist, it'll be created.

key: string type The key in section `section` where the value will be written to. Must be provided. If the key doesn't exist, it'll be created and the current value written to it, otherwise its value will be used.

config: string or ConfigParser instance. The ConfigParser instance to associate with this property if not None. If it's a string, the ConfigParser instance whose `name` is the value of `config` will be used. If no such parser exists yet, whenever a ConfigParser with this name is created, it will automatically be linked to this property.

Whenever a ConfigParser becomes linked with a property, if the section or key doesn't exist, the current property value will be used to create that key, otherwise, the existing key value will be used for the property value; overwriting its current value. You can change the ConfigParser associated with this property if a string was used here, by changing the `name` of an existing or new ConfigParser instance. Or through `set_config()`.

****kwargs: a list of keyword arguments**

val_type: a callable object The key values are saved in the ConfigParser as strings. When the ConfigParser value is read internally and assigned to the property or when the user changes the property value directly, if `val_type` is not None, it will be called with the new value as input and it should return the value converted to the proper type accepted by this property. For example, if the property represents ints, `val_type` can simply be `int`.

If the `val_type` callback raises a `ValueError`, `errorvalue` or `errorhandler` will be used if provided. Tip: the `getboolean` function of the ConfigParser might also be useful here to convert to a boolean type.

verify: a callable object Can be used to restrict the allowable values of the property. For every value assigned to the property, if this is specified, `verify` is called with the new value, and if it returns `True` the value is accepted, otherwise, `errorvalue` or `errorhandler` will be used if provided or a `ValueError` is raised.

New in version 1.9.0.

link_deps(EventDispatcher obj, unicode name)

set(EventDispatcher obj, value)

set_config(config)

Sets the ConfigParser object to be used by this property. Normally, the ConfigParser is set when initializing the Property using the *config* parameter.

Parameters

config: A **ConfigParser** instance. The instance to use for listening to and saving property value changes. If None, it disconnects the currently used ConfigParser.

```
class MyWidget(Widget):
    username = ConfigParserProperty('', 'info', 'name', None)

widget = MyWidget()
widget.property('username').set_config(ConfigParser())
```

class kivy.properties.DictProperty(*defaultvalue=0, rebind=False, **kw*)

Bases: *kivy.properties.Property*

Parameters

defaultvalue: dict, defaults to {} Specifies the default value of the property.

rebind: bool, defaults to False See *ObjectProperty* for details.

Changed in version 1.9.0: *rebind* has been introduced.

Warning: Similar to *ListProperty*, when assigning a dict to a *DictProperty*, the dict stored in the property is a shallow copy of the dict and not the original dict. See *ListProperty* for details.

link(EventDispatcher obj, unicode name) → PropertyStorage

rebind

rebind: 'int'

set(EventDispatcher obj, value)

class kivy.properties.ListProperty(*defaultvalue=0, **kw*)

Bases: *kivy.properties.Property*

Parameters

defaultvalue: list, defaults to [] Specifies the default value of the property.

Warning: When assigning a list to a *ListProperty*, the list stored in the property is a shallow copy of the list and not the original list. This can be demonstrated with the following example:

```
>>> class MyWidget(Widget):
>>>     my_list = ListProperty([])

>>> widget = MyWidget()
>>> my_list = [1, 5, {'hi': 'hello'}]
>>> widget.my_list = my_list
>>> print(my_list is widget.my_list)
False
```

```
>>> my_list.append(10)
>>> print(my_list, widget.my_list)
[1, 5, {'hi': 'hello'}, 10] [1, 5, {'hi': 'hello'}]
```

However, changes to nested levels will affect the property as well, since the property uses a shallow copy of my_list.

```
>>> my_list[2]['hi'] = 'bye'
>>> print(my_list, widget.my_list)
[1, 5, {'hi': 'bye'}, 10] [1, 5, {'hi': 'bye'}]
```

link(*EventDispatcher obj, unicode name*) → *PropertyStorage*
set(*EventDispatcher obj, value*)
class *kivy.properties.NumericProperty*(*defaultvalue=0, **kw*)
Bases: *kivy.properties.Property*

It only accepts the int or float numeric data type or a string that can be converted to a number as shown below. For other numeric types use ObjectProperty or use errorhandler to convert it to an int/float.

It does not support numpy numbers so they must be manually converted to int/float. E.g. `widget.num = np.arange(4)[0]` will raise an exception. Numpy arrays are not supported at all, even by ObjectProperty because their comparision does not return a bool. But if you must use a Kivy property, use a ObjectProperty with comparator set to `np.array_equal`. E.g.:

```
>>> class A(EventDispatcher):
...     data = ObjectProperty(comparator=np.array_equal)
>>> a = A()
>>> a.bind(data=print)
>>> a.data = np.arange(2)
<__main__.A object at 0x000001C839B50208> [0 1]
>>> a.data = np.arange(3)
<__main__.A object at 0x000001C839B50208> [0 1 2]
```

Parameters

defaultvalue: int or float, defaults to 0 Specifies the default value of the property.

```
>>> wid = Widget()
>>> wid.x = 42
>>> print(wid.x)
42
>>> wid.x = "plop"
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
  File "properties.pyx", line 93, in kivy.properties.Property.__set__
  File "properties.pyx", line 111, in kivy.properties.Property.set
  File "properties.pyx", line 159, in kivy.properties.NumericProperty.
    ↴check
ValueError: NumericProperty accept only int/float
```

Changed in version 1.4.1: NumericProperty can now accept custom text and tuple value to indicate a type, like “in”, “pt”, “px”, “cm”, “mm”, in the format: ‘10pt’ or (10, ‘pt’).

get_format(*EventDispatcher obj*)

Return the format used for Numeric calculation. Default is px (mean the value have not been changed at all). Otherwise, it can be one of ‘in’, ‘pt’, ‘cm’, ‘mm’.

class kivy.properties.ObjectProperty(*defaultvalue=None, rebind=False, **kw*)
Bases: *kivy.properties.Property*

Parameters

defaultvalue: object type Specifies the default value of the property.

rebind: bool, defaults to False Whether kv rules using this object as an intermediate attribute in a kv rule, will update the bound property when this object changes.

That is the standard behavior is that if there’s a kv rule `text: self.a.b.c.d`, where `a`, `b`, and `c` are properties with `rebind False` and `d` is a **StringProperty**. Then when the rule is applied, `text` becomes bound only to `d`. If `a`, `b`, or `c` change, `text` still remains bound to `d`. Furthermore, if any of them were `None` when the rule was initially evaluated, e.g. `b` was `None`; then `text` is bound to `b` and will not become bound to `d` even when `b` is changed to not be `None`.

By setting `rebind` to `True`, however, the rule will be re-evaluated and all the properties rebound when that intermediate property changes. E.g. in the example above, whenever `b` changes or becomes not `None` if it was `None` before, `text` is evaluated again and becomes rebound to `d`. The overall result is that `text` is now bound to all the properties among `a`, `b`, or `c` that have `rebind` set to `True`.

****kwargs: a list of keyword arguments**

baseclass If `kwargs` includes a `baseclass` argument, this value will be used for validation: `isinstance(value, kwargs['baseclass'])`.

Warning: To mark the property as changed, you must reassign a new python object.

Changed in version 1.9.0: `rebind` has been introduced.

Changed in version 1.7.0: `baseclass` parameter added.

rebind

`rebind: 'int'`

class kivy.properties.OptionProperty(**largs, **kw*)
Bases: *kivy.properties.Property*

`options`.

If the string set in the property is not in the list of valid options (passed at property creation time), a `ValueError` exception will be raised.

Parameters

default: any valid type in the list of options Specifies the default value of the property.

****kwargs: a list of keyword arguments** Should include an `options` parameter specifying a list (not tuple) of valid options.

For example:

```
class MyWidget(Widget):
    state = OptionProperty("None", options=["On", "Off", "None"])
```

options

Return the options available.

New in version 1.0.9.

```
class kivy.properties.Property(defaultvalue, **kw)
Bases: builtins.object
```

This class handles all the basic setters and getters, None type handling, the observer list and storage initialisation. This class should not be directly instantiated.

By default, a *Property* always takes a default value:

```
class MyObject(Widget):

    hello = Property('Hello world')
```

The default value must be a value that agrees with the Property type. For example, you can't set a list to a *StringProperty* because the StringProperty will check the default value.

None is a special case: you can set the default value of a Property to None, but you can't set None to a property afterward. If you really want to do that, you must declare the Property with *allownone=True*:

```
class MyObject(Widget):

    hello = ObjectProperty(None, allownone=True)

# then later
a = MyObject()
a.hello = 'bleh' # working
a.hello = None # working too, because allownone is True.
```

Parameters

default: Specifies the default value for the property.

***kwargs*: If the parameters include *errorhandler*, this should be a callable which must take a single argument and return a valid substitute value.

If the parameters include *errorvalue*, this should be an object. If set, it will replace an invalid property value (overrides errorhandler).

If the parameters include *force_dispatch*, it should be a boolean. If True, no value comparison will be done, so the property event will be dispatched even if the new value matches the old value (by default identical values are not dispatched to avoid infinite recursion in two-way binds). Be careful, this is for advanced use only.

comparator: **callable or None** When not None, it's called with two values to be compared. The function returns whether they are considered the same.

deprecated: **bool** When True, a warning will be logged if the property is accessed or set. Defaults to False.

Changed in version 1.4.2: Parameters *errorhandler* and *errorvalue* added

Changed in version 1.9.0: Parameter *force_dispatch* added

Changed in version 1.11.0: Parameter deprecated added

bind(*EventDispatcher obj, observer*)

Add a new observer to be called only when the value is changed.

defaultvalue

defaultvalue: object

dispatch(*EventDispatcher obj*)

Dispatch the value change to all observers.

Changed in version 1.1.0: The method is now accessible from Python.

This can be used to force the dispatch of the property, even if the value didn't change:

```
button = Button()
# get the Property class instance
prop = button.property('text')
# dispatch this property on the button instance
prop.dispatch(button)
```

Property.fbind(EventDispatcher obj, observer, int ref, tuple largs=

Similar to bind, except it doesn't check if the observer already exists. It also expands and forwards largs and kwargs to the callback. funbind or unbind_uid should be called when unbinding. It returns a unique positive uid to be used with unbind_uid.

Property.funbind(EventDispatcher obj, observer, tuple largs=

Remove the observer from our widget observer list bound with fbind. It removes the first match it finds, as opposed to unbind which searches for all matches.

get(*EventDispatcher obj*)

Return the value of the property.

link(*EventDispatcher obj, unicode name*) → *PropertyStorage*

Link the instance with its real name.

Warning: Internal usage only.

When a widget is defined and uses a **Property** class, the creation of the property object happens, but the instance doesn't know anything about its name in the widget class:

```
class MyWidget(Widget):
    uid = NumericProperty(0)
```

In this example, the uid will be a NumericProperty() instance, but the property instance doesn't know its name. That's why **link()** is used in *Widget.__new__*. The link function is also used to create the storage space of the property for this specific widget instance.

link_deps(*EventDispatcher obj, unicode name*)

link_eagerly(*EventDispatcher obj*) → *PropertyStorage*

set(*EventDispatcher obj, value*)

Set a new value for the property.

set_name(*EventDispatcher obj, unicode name*)

unbind(*EventDispatcher obj, observer, int stop_on_first=0*)

Remove the observer from our widget observer list.

unbind_uid(*EventDispatcher obj, uid*)

Remove the observer from our widget observer list bound with fbind using the uid.

```
class kivy.properties.ReferenceListProperty(*args, **kw)
Bases: kivy.properties.Property
```

For example, if *x* and *y* are *NumericProperty*s, we can create a *ReferenceListProperty* for the *pos*. If you change the value of *pos*, it will automatically change the values of *x* and *y* accordingly. If you read the value of *pos*, it will return a tuple with the values of *x* and *y*.

For example:

```
class MyWidget(EventDispatcher):
    x = NumericProperty(0)
    y = NumericProperty(0)
    pos = ReferenceListProperty(x, y)
```

```
get(EventDispatcher obj)
link(EventDispatcher obj, unicode name) → PropertyStorage
link_deps(EventDispatcher obj, unicode name)
set(EventDispatcher obj, _value)
setitem(EventDispatcher obj, key, value)
trigger_change(EventDispatcher obj, value)
class kivy.properties.StringProperty(defaultvalue='', **kw)
Bases: kivy.properties.Property
```

Parameters

defaultvalue: string, defaults to '' Specifies the default value of the property.

```
class kivy.properties.VariableListProperty(defaultvalue=None, length=4, **kw)
Bases: kivy.properties.Property
```

list items and to expand them to the desired list size.

For example, GridLayout's padding used to just accept one numeric value which was applied equally to the left, top, right and bottom of the GridLayout. Now padding can be given one, two or four values, which are expanded into a length four list [left, top, right, bottom] and stored in the property.

Parameters

default: a default list of values Specifies the default values for the list.

length: int, one of 2 or 4. Specifies the length of the final list. The *default* list will be expanded to match a list of this length.

***kwargs*: a list of keyword arguments Not currently used.

Keeping in mind that the *default* list is expanded to a list of length 4, here are some examples of how VariableListProperty is handled.

- VariableListProperty([1]) represents [1, 1, 1, 1].
- VariableListProperty([1, 2]) represents [1, 2, 1, 2].
- VariableListProperty(['1px', (2, 'px'), 3, 4.0]) represents [1, 2, 3, 4.0].
- VariableListProperty(5) represents [5, 5, 5, 5].
- VariableListProperty(3, length=2) represents [3, 3].

New in version 1.7.0.

length

length: 'int'

link(*EventDispatcher obj, unicode name*) → PropertyStorage

31.23 Resources management

Resource management can be a pain if you have multiple paths and projects. Kivy offers 2 functions for searching for specific resources across a list of paths.

31.23.1 Resource lookup

When Kivy looks for a resource e.g. an image or a kv file, it searches through a predetermined set of folders. You can modify this folder list using the `resource_add_path()` and `resource_remove_path()` functions.

31.23.2 Customizing Kivy

These functions can also be helpful if you want to replace standard Kivy resources with your own. For example, if you wish to customize or re-style Kivy, you can force your `style.kv` or `data/defaulttheme-0.png` files to be used in preference to the defaults simply by adding the path to your preferred alternatives via the `resource_add_path()` method.

As almost all Kivy resources are looked up using the `resource_find()`, so you can use this approach to add fonts and keyboard layouts and to replace images and icons.

kivy.resources.resource_add_path(path)

Add a custom path to search in.

kivy.resources.resource_find(filename, use_cache=False)

Search for a resource in the list of paths. Use `resource_add_path` to add a custom path to the search. By default, results are cached for 60 seconds. This can be disabled using `use_cache=False`.

Changed in version 2.1.0: `use_cache` parameter added and made True by default.

kivy.resources.resource_remove_path(path)

Remove a search path.

New in version 1.0.8.

31.24 Support

Activate other frameworks/toolkits inside the kivy event loop.

kivy.support.install_android()

Install hooks for the android platform.

- Automatically sleep when the device is paused.
- Automatically kill the application when the return key is pressed.

kivy.support.install_gobject_iteration()

Import and install gobject context iteration inside our event loop. This is used as soon as gobject is used (like gstreamer).

kivy.support.install_twisted_reactor(kwargs)**

Installs a threaded twisted reactor, which will schedule one reactor iteration before the next frame only when twisted needs to do some work.

Any arguments or keyword arguments passed to this function will be passed on to the threaded-select reactors interleave function. These are the arguments one would usually pass to twisted's reactor.startRunning.

Unlike the default twisted reactor, the installed reactor will not handle any signals unless you set the 'installSignalHandlers' keyword argument to 1 explicitly. This is done to allow kivy to handle the signals as usual unless you specifically want the twisted reactor to handle the signals (e.g. SIGINT).

Note: Twisted is not included in iOS build by default. To use it on iOS, put the twisted distribution (and zope.interface dependency) in your application directory.

`kivy.support.uninstall_twisted_reactor()`

Uninstalls the Kivy's threaded Twisted Reactor. No more Twisted tasks will run after this got called. Use this to clean the *twisted.internet.reactor*.

New in version 1.9.0.

31.25 Utils

The Utils module provides a selection of general utility functions and classes that may be useful for various applications. These include maths, color, algebraic and platform functions.

Changed in version 1.6.0: The OrderedDict class has been removed. Use collections.OrderedDict instead.

`class kivy.utils.QueryDict`

Bases: `builtins.dict`

QueryDict is a dict() that can be queried with dot.

```
d = QueryDict()  
# create a key named toto, with the value 1  
d.toto = 1  
# it's the same as  
d['toto'] = 1
```

New in version 1.0.4.

`class kivy.utils.SafeList(*args, **kwargs)`

Bases: `builtins.list`

List with a clear() method.

Warning: Usage of the iterate() function will decrease your performance.

`clear()`

Remove all items from list.

`kivy.utils.boundary(value, minvalue, maxvalue)`

Limit a value between a minvalue and maxvalue.

`kivy.utils.deprecated(func=None, msg='')`

This is a decorator which can be used to mark functions as deprecated. It will result in a warning being emitted the first time the function is used.

`kivy.utils.difference(set1, set2)`

Return the difference between 2 lists.

`kivy.utils.escape_markup(text)`

Escape markup characters found in the text. Intended to be used when markup text is activated on the Label:

```
untrusted_text = escape_markup('Look at the example [1]')
text = '[color=ff0000]' + untrusted_text + '[/color]'
w = Label(text=text, markup=True)
```

New in version 1.3.0.

`kivy.utils.get_color_from_hex(s)`

Transform a hex string color to a kivy `Color`.

`kivy.utils.get_hex_from_color(color)`

Transform a kivy `Color` to a hex value:

```
>>> get_hex_from_color((0, 1, 0))
'#00ff00'
>>> get_hex_from_color((.25, .77, .90, .5))
'#3fc4e57f'
```

New in version 1.5.0.

`kivy.utils.get_random_color(alpha=1.0)`

Returns a random color (4 tuple).

Parameters

`alpha: float, defaults to 1.0` If alpha == 'random', a random alpha value is generated.

`kivy.utils.interpolate(value_from, value_to, step=10)`

Interpolate between two values. This can be useful for smoothing some transitions. For example:

```
# instead of setting directly
self.pos = pos

# use interpolate, and you'll have a nicer transition
self.pos = interpolate(self.pos, new_pos)
```

Warning: These interpolations work only on lists/tuples/doubles with the same dimensions.
No test is done to check the dimensions are the same.

`kivy.utils.intersection(set1, set2)`

Return the intersection of 2 lists.

`kivy.utils.is_color_transparent(c)`

Return True if the alpha channel is 0.

`kivy.utils.platform = 'linux'`

A string identifying the current operating system. It is one of: 'win', 'linux', 'android', 'macosx', 'ios' or 'unknown'. You can use it as follows:

```
from kivy.utils import platform
if platform == 'linux':
    do_linux_things()
```

New in version 1.3.0.

Changed in version 1.8.0: platform is now a variable instead of a function.

```
class kivy.utils.reify(func)
Bases: builtins.object
```

Put the result of a method which uses this (non-data) descriptor decorator in the instance dict after the first call, effectively replacing the decorator with an instance variable.

It acts like `@property`, except that the function is only ever called once; after that, the value is cached as a regular attribute. This gives you lazy attribute creation on objects that are meant to be immutable.

Taken from the [Pyramid project](#).

To use this as a decorator:

```
@reify
def lazy(self):
    ...
    return hard_to_compute_int
first_time = self.lazy  # lazy is reify obj, reify.__get__() runs
second_time = self.lazy # lazy is hard_to_compute_int
```

kivy.utils.rgb(s, *args)

Return a Kivy color (4 value from 0-1 range) from either a hex string or a list of 0-255 values.

New in version 1.10.0.

kivy.utils.strptime(s)

Convert a tuple string into a tuple with some security checks. Designed to be used with the eval() function:

```
a = (12, 54, 68)
b = str(a)          # return '(12, 54, 68)'
c = strtotuple(b)  # return (12, 54, 68)
```

31.26 Vector

The **Vector** represents a 2D vector (x, y). Our implementation is built on top of a Python list.

An example of constructing a Vector:

```
>>> # Construct a point at 82,34
>>> v = Vector(82, 34)
>>> v[0]
82
>>> v.x
82
>>> v[1]
34
>>> v.y
34

>>> # Construct by giving a list of 2 values
>>> pos = (93, 45)
>>> v = Vector(pos)
```

(continues on next page)

(continued from previous page)

```
>>> v[0]
93
>>> v.x
93
>>> v[1]
45
>>> v.y
45
```

31.26.1 Optimized usage

Most of the time, you can use a list for arguments instead of using a Vector. For example, if you want to calculate the distance between 2 points:

```
a = (10, 10)
b = (87, 34)

# optimized method
print('distance between a and b:', Vector(a).distance(b))

# non-optimized method
va = Vector(a)
vb = Vector(b)
print('distance between a and b:', va.distance(vb))
```

31.26.2 Vector operators

The `Vector` supports some numeric operators such as `+`, `-`, `/`:

```
>>> Vector(1, 1) + Vector(9, 5)
[10, 6]

>>> Vector(9, 5) - Vector(5, 5)
[4, 0]

>>> Vector(10, 10) / Vector(2., 4.)
[5.0, 2.5]

>>> Vector(10, 10) / 5.
[2.0, 2.0]
```

You can also use in-place operators:

```
>>> v = Vector(1, 1)
>>> v += 2
>>> v
[3, 3]
>>> v *= 5
[15, 15]
>>> v /= 2.
[7.5, 7.5]
```

```
class kivy.vector.Vector(*args)
```

Bases: builtins.list

Vector class. See module documentation for more information.

angle(a)

Computes the angle between a and b, and returns the angle in degrees.

```
>>> Vector(100, 0).angle((0, 100))  
-90.0  
>>> Vector(87, 23).angle((-77, 10))  
-157.7920283010705
```

distance(to)

Returns the distance between two points.

```
>>> Vector(10, 10).distance((5, 10))  
5.  
>>> a = (90, 33)  
>>> b = (76, 34)  
>>> Vector(a).distance(b)  
14.035668847618199
```

distance2(to)

Returns the distance between two points squared.

```
>>> Vector(10, 10).distance2((5, 10))  
25
```

dot(a)

Computes the dot product of a and b.

```
>>> Vector(2, 4).dot((2, 2))  
12
```

static in_bbox(point, a, b)

Return True if *point* is in the bounding box defined by *a* and *b*.

```
>>> bmin = (0, 0)  
>>> bmax = (100, 100)  
>>> Vector.in_bbox((50, 50), bmin, bmax)  
True  
>>> Vector.in_bbox((647, -10), bmin, bmax)  
False
```

length()

Returns the length of a vector.

```
>>> Vector(10, 10).length()  
14.142135623730951  
>>> pos = (10, 10)  
>>> Vector(pos).length()  
14.142135623730951
```

length2()

Returns the length of a vector squared.

```
>>> Vector(10, 10).length2()
200
>>> pos = (10, 10)
>>> Vector(pos).length2()
200
```

static line_intersection(*v1, v2, v3, v4*)

Finds the intersection point between the lines (1)v1->v2 and (2)v3->v4 and returns it as a vector object.

```
>>> a = (98, 28)
>>> b = (72, 33)
>>> c = (10, -5)
>>> d = (20, 88)
>>> Vector.line_intersection(a, b, c, d)
[15.25931928687196, 43.911669367909241]
```

Warning: This is a line intersection method, not a segment intersection.

For math see: http://en.wikipedia.org/wiki/Line-line_intersection

normalize()

Returns a new vector that has the same direction as vec, but has a length of one.

```
>>> v = Vector(88, 33).normalize()
>>> v
[0.9363291775690444, 0.3511234415883917]
>>> v.length()
1.0
```

rotate(*angle*)

Rotate the vector with an angle in degrees.

```
>>> v = Vector(100, 0)
>>> v.rotate(45)
[70.71067811865476, 70.71067811865474]
```

static segment_intersection(*v1, v2, v3, v4*)

Finds the intersection point between segments (1)v1->v2 and (2)v3->v4 and returns it as a vector object.

```
>>> a = (98, 28)
>>> b = (72, 33)
>>> c = (10, -5)
>>> d = (20, 88)
>>> Vector.segment_intersection(a, b, c, d)
None
```

```
>>> a = (0, 0)
>>> b = (10, 10)
>>> c = (0, 10)
>>> d = (10, 0)
>>> Vector.segment_intersection(a, b, c, d)
[5, 5]
```

property x

x represents the first element in the list.

```
>>> v = Vector(12, 23)
>>> v[0]
12
>>> v.x
12
```

property y

y represents the second element in the list.

```
>>> v = Vector(12, 23)
>>> v[1]
23
>>> v.y
23
```

31.27 Weak Method

The **WeakMethod** is used by the **Clock** class to allow references to a bound method that permits the associated object to be garbage collected. Please refer to *examples/core/clock_method.py* for more information.

This WeakMethod class is taken from the recipe <http://code.activestate.com/recipes/81253/>, based on the nicodemus version. Many thanks nicodemus!

class kivy.weakmethod.WeakMethod(method)

Bases: `builtins.object`

Implementation of a **weakref** for functions and bound methods.

is_dead()

Returns True if the referenced callable was a bound method and the instance no longer exists.
Otherwise, return False.

31.28 Weak Proxy

In order to allow garbage collection, the weak proxy provides **weak references** to objects. It effectively enhances the **weakref.proxy** by adding comparison support.

class kivy.weakproxy.WeakProxy(obj, destructor=None)

Bases: `builtins.object`

Replacement for `weakref.proxy` to support comparisons

CORE ABSTRACTION

This module defines the abstraction layers for our core providers and their implementations. For further information, please refer to [Architectural Overview](#) and the [Core Providers and Input Providers](#) section of the documentation.

In most cases, you shouldn't directly use a library that's already covered by the core abstraction. Always try to use our providers first. In case we are missing a feature or method, please let us know by opening a new Bug report instead of relying on your library.

Warning: These are **not** widgets! These are just abstractions of the respective functionality. For example, you cannot add a core image to your window. You have to use the image **widget** class instead. If you're really looking for widgets, please refer to [kivy.uix](#) instead.

exception kivy.core.CoreCriticalException
Bases: `Exception`

32.1 Audio

Load an audio sound and play it with:

```
from kivy.core.audio import SoundLoader

sound = SoundLoader.load('mytest.wav')
if sound:
    print("Sound found at %s" % sound.source)
    print("Sound is %.3f seconds" % sound.length)
    sound.play()
```

You should not use the Sound class directly. The class returned by [SoundLoader.load\(\)](#) will be the best sound provider for that particular file type, so it might return different Sound classes depending the file type.

32.1.1 Event dispatching and state changes

Audio is often processed in parallel to your code. This means you often need to enter the Kivy [eventloop](#) in order to allow events and state changes to be dispatched correctly.

You seldom need to worry about this as Kivy apps typically always require this event loop for the GUI to remain responsive, but it is good to keep this in mind when debugging or running in a [REPL](#) (Read-eval-print loop).

Changed in version 1.10.0: The pygst and gi providers have been removed.

Changed in version 1.8.0: There are now 2 distinct Gstreamer implementations: one using Gi/Gst working for both Python 2+3 with Gstreamer 1.0, and one using PyGST working only for Python 2 + Gstreamer 0.10.

Note: The core audio library does not support recording audio. If you require this functionality, please refer to the [audiostream](#) extension.

class kivy.core.audio.Sound

Bases: [kivy.event.EventDispatcher](#)

Represents a sound to play. This class is abstract, and cannot be used directly.

Use SoundLoader to load a sound.

Events

on_play: None Fired when the sound is played.

on_stop: None Fired when the sound is stopped.

filename

Deprecated since version 1.3.0: Use [source](#) instead.

get_pos()

Returns the current position of the audio file. Returns 0 if not playing.

New in version 1.4.1.

property length

Get length of the sound (in seconds).

load()

Load the file into memory.

loop

Set to True if the sound should automatically loop when it finishes.

New in version 1.8.0.

loop is a [BooleanProperty](#) and defaults to False.

pitch

Pitch of a sound. 2 is an octave higher, .5 one below. This is only implemented for SDL2 audio provider yet.

New in version 1.10.0.

pitch is a [NumericProperty](#) and defaults to 1.

play()

Play the file.

seek(*position*)

Go to the <*position*> (in seconds).

Note: Most sound providers cannot seek when the audio is stopped. Play then seek.

source

Filename / source of your audio file.

New in version 1.3.0.

`source` is a *StringProperty* that defaults to None and is read-only. Use the `SoundLoader.load()` for loading audio.

state

State of the sound, one of 'stop' or 'play'.

New in version 1.3.0.

`state` is a read-only *OptionProperty*.

status

Deprecated since version 1.3.0: Use `state` instead.

stop()

Stop playback.

unload()

Unload the file from memory.

volume

Volume, in the range 0-1. 1 means full volume, 0 means mute.

New in version 1.3.0.

`volume` is a *NumericProperty* and defaults to 1.

class kivy.core.audio.SoundLoader

Bases: `builtins.object`

Load a sound, using the best loader for the given file type.

static load(filename)

Load a sound, and return a Sound() instance.

static register(classobj)

Register a new class to load the sound.

32.2 Camera

Core class for acquiring the camera and converting its input into a *Texture*.

Changed in version 1.10.0: The pygst and videocapture providers have been removed.

Changed in version 1.8.0: There is now 2 distinct Gstreamer implementation: one using Gi/Gst working for both Python 2+3 with Gstreamer 1.0, and one using PyGST working only for Python 2 + Gstreamer 0.10.

class kivy.core.camera.CameraBase(kwargs)**

Bases: `kivy.event.EventDispatcher`

Abstract Camera Widget class.

Concrete camera classes must implement initialization and frame capturing to a buffer that can be uploaded to the gpu.

Parameters

index: int Source index of the camera.

size: tuple (int, int) Size at which the image is drawn. If no size is specified, it defaults to the resolution of the camera image.

resolution: tuple (int, int) Resolution to try to request from the camera. Used in the gstreamer pipeline by forcing the appsink caps to this resolution. If the camera doesn't support the resolution, a negotiation error might be thrown.

Events

on_load Fired when the camera is loaded and the texture has become available.

on_texture Fired each time the camera texture is updated.

property index

Source index of the camera

init_camera()

Initialise the camera (internal)

property resolution

Resolution of camera capture (width, height)

start()

Start the camera acquire

stop()

Release the camera

property texture

Return the camera texture with the latest capture

32.3 Clipboard

Core class for accessing the Clipboard. If we are not able to access the system clipboard, a fake one will be used.

Usage example:

```
#:import Clipboard kivy.core.clipboard.Clipboard

Button:
    on_release:
        self.text = Clipboard.paste()
        Clipboard.copy('Data')
```

32.4 OpenGL

Select and use the best OpenGL library available. Depending on your system, the core provider can select an OpenGL ES or a 'classic' desktop OpenGL library.

32.5 Image

Core classes for loading images and converting them to a *Texture*. The raw image data can be kept in memory for further access.

Changed in version 1.11.0: Add support for argb and abgr image data

32.5.1 In-memory image loading

New in version 1.9.0: Official support for in-memory loading. Not all the providers support it, but currently SDL2, pygame, pil and imageio work.

To load an image with a filename, you would usually do:

```
from kivy.core.image import Image as CoreImage
im = CoreImage("image.png")
```

You can also load the image data directly from a memory block. Instead of passing the filename, you'll need to pass the data as a BytesIO object together with an "ext" parameter. Both are mandatory:

```
import io
from kivy.core.image import Image as CoreImage
data = io.BytesIO(open("image.png", "rb").read())
im = CoreImage(data, ext="png")
```

By default, the image will not be cached as our internal cache requires a filename. If you want caching, add a filename that represents your file (it will be used only for caching):

```
import io
from kivy.core.image import Image as CoreImage
data = io.BytesIO(open("image.png", "rb").read())
im = CoreImage(data, ext="png", filename="image.png")
```

32.5.2 Saving an image

A CoreImage can be saved to a file:

```
from kivy.core.image import Image as CoreImage
image = CoreImage(...)
image.save("/tmp/test.png")
```

Or you can get the bytes (new in 1.11.0):

```
import io from kivy.core.image import Image as CoreImage data = io.BytesIO() image = CoreImage(...) image.save(data, fmt="png") png_bytes = data.read()

class kivy.core.image.Image(arg, **kwargs)
    Bases: kivy.event.EventDispatcher
```

Load an image and store the size and texture.

Changed in version 1.0.7: *mipmap* attribute has been added. The *texture_mipmap* and *texture_rectangle* have been deleted.

Changed in version 1.0.8: An Image widget can change its texture. A new event 'on_texture' has been introduced. New methods for handling sequenced animation have been added.

Parameters

arg: can be a string (str), Texture, BytesIO or Image object A string path to the image file or data URI to be loaded; or a Texture object, which will be wrapped in an Image object; or a BytesIO object containing raw image data; or an already existing image object, in which case, a real copy of the given image object will be returned.

keep_data: bool, defaults to False Keep the image data when the texture is created.

mipmap: bool, defaults to False Create mipmap for the texture.

anim_delay: float, defaults to .25 Delay in seconds between each animation frame.
Lower values means faster animation.

ext: str, only with BytesIO arg File extension to use in determining how to load raw image data.

filename: str, only with BytesIO arg Filename to use in the image cache for raw image data.

property anim_available

Return True if this Image instance has animation available.

New in version 1.0.8.

property anim_delay

Delay between each animation frame. A lower value means faster animation.

New in version 1.0.8.

property anim_index

Return the index number of the image currently in the texture.

New in version 1.0.8.

anim_reset(allow_anim)

Reset an animation if available.

New in version 1.0.8.

Parameters

allow_anim: bool Indicate whether the animation should restart playing or not.

Usage:

```
# start/reset animation
image.anim_reset(True)

# or stop the animation
image.anim_reset(False)
```

You can change the animation speed whilst it is playing:

```
# Set to 20 FPS
image.anim_delay = 1 / 20.
```

property filename

Get/set the filename of image

property height

Image height

property image

Get/set the data image object

static load(filename, **kwargs)

Load an image

Parameters

filename: str Filename of the image.

keep_data: bool, defaults to False Keep the image data when the texture is created.

load_memory(data, ext, filename='__inline__')

(internal) Method to load an image from raw data.

property nocache

Indicate whether the texture will not be stored in the cache or not.

New in version 1.6.0.

on_texture(*args)

This event is fired when the texture reference or content has changed. It is normally used for sequenced images.

New in version 1.0.8.

read_pixel(x, y)

For a given local x/y position, return the pixel color at that position.

Warning: This function can only be used with images loaded with the keep_data=True keyword. For example:

```
m = Image.load('image.png', keep_data=True)
color = m.read_pixel(150, 150)
```

Parameters

x: int Local x coordinate of the pixel in question.

y: int Local y coordinate of the pixel in question.

remove_from_cache()

Remove the Image from cache. This facilitates re-loading of images from disk in case the image content has changed.

New in version 1.3.0.

Usage:

```
im = CoreImage('1.jpg')
# -- do something --
im.remove_from_cache()
im = CoreImage('1.jpg')
# this time image will be re-loaded from disk
```

save(filename, flipped=False, fmt=None)

Save image texture to file.

The filename should have the '.png' extension because the texture data read from the GPU is in the RGBA format. '.jpg' might work but has not been heavily tested so some providers might break when using it. Any other extensions are not officially supported.

The flipped parameter flips the saved image vertically, and defaults to False.

Example:

```
# Save an core image object
from kivy.core.image import Image
img = Image('hello.png')
img.save('hello2.png')

# Save a texture
texture = Texture.create(...)
img = Image(texture)
img.save('hello3.png')
```

New in version 1.7.0.

Changed in version 1.8.0: Parameter *flipped* added to flip the image before saving, default to False.

Changed in version 1.11.0: Parameter *fmt* added to force the output format of the file. File-name can now be a BytesIO object.

property size

Image size (width, height)

property texture

Texture of the image

property width

Image width

class kivy.core.image.ImageData(*width, height, fmt, data, source=None, flip_vertical=True, source_image=None, rowlength=0*)

Bases: `builtins.object`

Container for images and mipmap images. The container will always have at least the mipmap level 0.

add_mipmap(*level, width, height, data, rowlength*)

Add a image for a specific mipmap level.

New in version 1.0.7.

property data

Image data. (If the image is mipmapped, it will use the level 0)

flip_vertical

Indicate if the texture will need to be vertically flipped

fmt

Decoded image format, one of a available texture format

get_mipmap(*level*)

Get the mipmap image at a specific level if it exists

New in version 1.0.7.

property height

Image height in pixels. (If the image is mipmapped, it will use the level 0)

iterate_mipmaps()

Iterate over all mipmap images available.

New in version 1.0.7.

mipmaps

Data for each mipmap.

property rowlength

Image rowlength. (If the image is mipmapped, it will use the level 0)

New in version 1.9.0.

property size

Image (width, height) in pixels. (If the image is mipmapped, it will use the level 0)

source

Image source, if available

property width

Image width in pixels. (If the image is mipmapped, it will use the level 0)

32.6 Spelling

Provides abstracted access to a range of spellchecking backends as well as word suggestions. The API is inspired by enchant but other backends can be added that implement the same API.

Spelling currently requires *python-enchant* for all platforms except OSX, where a native implementation exists.

```
>>> from kivy.core.spelling import Spelling
>>> s = Spelling()
>>> s.list_languages()
['en', 'en_CA', 'en_GB', 'en_US']
>>> s.select_language('en_US')
>>> s.suggest('he-lo')
[u'hole', u'help', u'helot', u'hello', u'halo', u'hero', u'hell', u'held',
 u'helm', u'he-lo']
```

exception kivy.core.spelling.NoLanguageSelectedError

Bases: `Exception`

Exception to be raised when a language-using method is called but no language was selected prior to the call.

exception kivy.core.spelling.NoSuchLangError

Bases: `Exception`

Exception to be raised when a specific language could not be found.

class kivy.core.spelling.SpellingBase(*language=None*)

Bases: `builtins.object`

Base class for all spelling providers. Supports some abstract methods for checking words and getting suggestions.

check(*word*)

If *word* is a valid word in *self._language* (the currently active language), returns True. If the word shouldn't be checked, returns None (e.g. for ''). If it is not a valid word in *self._language*, return False.

Parameters

word: str The word to check.

list_languages()

Return a list of all supported languages. E.g. ['en', 'en_GB', 'en_US', 'de', ...]

select_language(*language*)

From the set of registered languages, select the first language for *language*.

Parameters

language: str Language identifier. Needs to be one of the options returned by `list_languages()`. Sets the language used for spell checking and word suggestions.

suggest(*fragment*)

For a given *fragment* (i.e. part of a word or a word by itself), provide corrections (*fragment* may be misspelled) or completions as a list of strings.

Parameters

fragment: str The word fragment to get suggestions/corrections for. E.g. ‘foo’ might become ‘of’, ‘food’ or ‘foot’.

32.7 Text

An abstraction of text creation. Depending of the selected backend, the accuracy of text rendering may vary.

Changed in version 1.10.1: `LabelBase.find_base_direction()` added.

Changed in version 1.5.0: `LabelBase.line_height` added.

Changed in version 1.0.7: The `LabelBase` does not generate any texture if the text has a width ≤ 1 .

This is the backend layer for rendering text with different text providers, you should only be using this directly if your needs aren’t fulfilled by the `Label`.

Usage example:

```
from kivy.core.text import Label as CoreLabel

...
my_label = CoreLabel()
my_label.text = 'hello'
# the label is usually not drawn until needed, so force it to draw.
my_label.refresh()
# Now access the texture of the label and use it wherever and
# however you may please.
hello_texture = my_label.texture
```

32.7.1 Font Context Manager

A font context is a namespace where multiple fonts are loaded; if a font is missing a glyph needed to render text, it can fall back to a different font in the same context. The font context manager can be used to query and manipulate the state of font contexts when using the Pango text provider (no other provider currently implements it).

New in version 1.11.0.

Warning: This feature requires the Pango text provider.

Font contexts can be created automatically by `kivy.uix.label.Label` or `kivy.uix.textinput.TextInput`; if a non-existent context is used in one of these classes, it will be created automatically, or if a font file is specified without a context (this creates an isolated context, without support for fallback).

Usage example:

```
from kivy.uix.label import Label
from kivy.core.text import FontContextManager as FCM

# Create a font context containing system fonts + one custom TTF
FCM.create('system://myapp')
family = FCM.add_font('/path/to/file.ttf')

# These are now interchangeable ways to refer to the custom font:
lbl1 = Label(font_context='system://myapp', family_name=family)
lbl2 = Label(font_context='system://myapp', font_name='/path/to/file.ttf')

# You could also refer to a system font by family, since this is a
# system:// font context
lbl3 = Label(font_context='system://myapp', family_name='Arial')
```

class kivy.core.text.LabelBase(*text*='', *font_size*=12, *font_name*=None, *bold*=False, *italic*=False, *underline*=False, *strikethrough*=False, *font_family*=None, *halign*='left', *valign*='bottom', *shorten*=False, *text_size*=None, *mipmap*=False, *color*=None, *line_height*=1.0, *strip*=False, *strip_reflow*=True, *shorten_from*='center', *split_str*=' ', *unicode_errors*='replace', *font_hinting*='normal', *font_kerning*=True, *font_blended*=True, *outline_width*=None, *outline_color*=None, *font_context*=None, *font_features*=None, *base_direction*=None, *text_language*=None, **kwargs)

Bases: `builtins.object`

Core text label. This is the abstract class used by different backends to render text.

Warning: The core text label can't be changed at runtime. You must recreate one.

Parameters

***font_size*: int, defaults to 12** Font size of the text

***font_context*: str, defaults to None** Context for the specified font (see [kivy.uix.label.Label](#) for details). *None* will autocreate an isolated context named after the resolved font file.

***font_name*: str, defaults to DEFAULT_FONT** Font name of the text

***font_family*: str, defaults to None** Font family name to request for drawing, this can only be used with *font_context*.

***bold*: bool, defaults to False** Activate "bold" text style

***italic*: bool, defaults to False** Activate "italic" text style

***text_size*: tuple, defaults to (None, None)** Add constraint to render the text (inside a bounding box). If no size is given, the label size will be set to the text size.

***padding*: float, defaults to None** If it's a float, it will set padding_x and padding_y

***padding_x*: float, defaults to 0.0** Left/right padding

***padding_y*: float, defaults to 0.0** Top/bottom padding

***halign*: str, defaults to "left"** Horizontal text alignment inside the bounding box

***valign*: str, defaults to “bottom”** Vertical text alignment inside the bounding box

***shorten*: bool, defaults to False** Indicate whether the label should attempt to shorten its textual contents as much as possible if a *size* is given. Setting this to True without an appropriately set size will lead to unexpected results.

***shorten_from*: str, defaults to center** The side from which we should shorten the text from, can be left, right, or center. E.g. if left, the ellipsis will appear towards the left side and it will display as much text starting from the right as possible.

***split_str*: string, defaults to ‘’ (space)** The string to use to split the words by when shortening. If empty, we can split after every character filling up the line as much as possible.

***max_lines*: int, defaults to 0 (unlimited)** If set, this indicate how maximum line are allowed to render the text. Works only if a limitation on *text_size* is set.

***mipmap*: bool, defaults to False** Create a mipmap for the texture

***strip*: bool, defaults to False** Whether each row of text has its leading and trailing spaces stripped. If *halign* is *justify* it is implicitly True.

***strip_reflow*: bool, defaults to True** Whether text that has been reflowed into a second line should be stripped, even if *strip* is False. This is only in effect when *size_hint_x* is not None, because otherwise lines are never split.

***unicode_errors*: str, defaults to ‘replace’** How to handle unicode decode errors. Can be ‘strict’, ‘replace’ or ‘ignore’.

***outline_width*: int, defaults to None** Width in pixels for the outline.

***outline_color*: tuple, defaults to (0, 0, 0)** Color of the outline.

***font_features*: str, defaults to None** OpenType font features in CSS format (Pango only)

***base_direction*: str, defaults to None (auto)** Text direction, one of *None*, ‘ltr’, ‘rtl’, ‘weak_ltr’, or ‘weak rtl’ (Pango only)

***text_language*: str, defaults to None (user locale)** RFC-3066 format language tag as a string (Pango only)

Changed in version 1.10.1: *font_context*, *font_family*, *font_features*, *base_direction* and *text_language* were added.

Changed in version 1.10.0: *outline_width* and *outline_color* were added.

Changed in version 1.9.0: *strip*, *strip_reflow*, *shorten_from*, *split_str*, and *unicode_errors* were added.

Changed in version 1.9.0: *padding_x* and *padding_y* has been fixed to work as expected. In the past, the text was padded by the negative of their values.

Changed in version 1.8.0: *max_lines* parameters has been added.

Changed in version 1.0.8: *size* have been deprecated and replaced with *text_size*.

Changed in version 1.0.7: The *valign* is now respected. This wasn’t the case previously so you might have an issue in your application if you have not considered this.

property content_height

Return the content height; i.e. the height of the text without any padding.

property content_size

Return the content size (width, height)

property content_width

Return the content width; i.e. the width of the text without any padding.

static find_base_direction(*text*)

Searches a string the first character that has a strong direction, according to the Unicode bidirectional algorithm. Returns *None* if the base direction cannot be determined, or one of '*ltr*' or '*rtl*'.

Note: This feature requires the Pango text provider.

property fontid

Return a unique id for all font parameters

get_cached_extents()

Returns a cached version of the *get_extents()* function.

```
>>> func = self._get_cached_extents()
>>> func
<built-in method size of pygame.font.Font object at 0x01E45650>
>>> func('a line')
(36, 18)
```

Warning: This method returns a size measuring function that is valid for the font settings used at the time *get_cached_extents()* was called. Any change in the font settings will render the returned function incorrect. You should only use this if you know what you're doing.

New in version 1.9.0.

get_extents(*text*)

Return a tuple (width, height) indicating the size of the specified text

static get_system_fonts_dir()

Return the directories used by the system for fonts.

property label

Get/Set the text

refresh()

Force re-rendering of the text

static register(*name, fn_regular, fn_italic=None, fn_bold=None, fn_bolditalic=None*)

Register an alias for a Font.

New in version 1.1.0.

If you're using a ttf directly, you might not be able to use the bold/italic properties of the ttf version. If the font is delivered in multiple files (one regular, one italic and one bold), then you need to register these files and use the alias instead.

All the *fn_regular/fn_italic/fn_bold* parameters are resolved with *kivy.resources.resource_find()*. If *fn_italic/fn_bold* are None, *fn_regular* will be used instead.

render(*real=False*)

Return a tuple (width, height) to create the image with the user constraints. (width, height) includes the padding.

shorten(*text, margin=2*)

Shortens the text to fit into a single line by the width specified by *text_size* [0]. If *text_size* [0] is None, it returns text unchanged.

split_str and *shorten_from* determines how the text is shortened.

Params `text` str, the text to be shortened. `margin` int, the amount of space to leave between the margins and the text. This is in addition to `padding_x`.

Returns the text shortened to fit into a single line.

property text

Get/Set the text

property text_size

Get/set the (width, height) of the ‘‘constrained rendering box

property usersize

(deprecated) Use `text_size` instead.

32.7.2 Text layout

An internal module for laying out text according to options and constraints. This is not part of the API and may change at any time.

class kivy.core.text.text_layout.LayoutLine

Bases: `builtins.object`

Formally describes a line of text. A line of text is composed of many `LayoutWord` instances, each with its own text, size and options.

A `LayoutLine` instance does not always imply that the words contained in the line ended with a newline. That is only the case if `is_last_line` is True. For example a single real line of text can be split across multiple `LayoutLine` instances if the whole line doesn’t fit in the constrained width.

Parameters

`x: int` the location in a texture from where the left side of this line is began drawn.

`y: int` the location in a texture from where the bottom of this line is drawn.

`w: int` the width of the line. This is the sum of the individual widths of its `LayoutWord` instances. Does not include any padding.

`h: int` the height of the line. This is the maximum of the individual heights of its `LayoutWord` instances multiplied by the `line_height` of these instance. So this is larger then the word height.

`is_last_line: bool` whether this line was the last line in a paragraph. When True, it implies that the line was followed by a newline. Newlines should not be included in the text of words, but is implicit by setting this to True.

`line_wrap: bool` whether this line is continued from a previous line which didn’t fit into a constrained width and was therefore split across multiple `LayoutLine` instances. `line_wrap` can be True or False independently of `is_last_line`.

`words: python list` a list that contains only `LayoutWord` instances describing the text of the line.

h

`h: 'int'`

is_last_line

`is_last_line: 'int'`

line_wrap

`line_wrap: 'int'`

w

`w: 'int'`

```
words
    words: list

x
    x: 'int'

y
    y: 'int'

class kivy.core.text.text_layout.LayoutWord
Bases: builtins.object
```

Formally describes a word contained in a line. The name word simply means a chunk of text and can be used to describe any text.

A word has some width, height and is rendered according to options saved in [options](#). See [LayoutLine](#) for its usage.

Parameters

options: dict the label options dictionary for this word.
lw: int the width of the text in pixels.
lh: int the height of the text in pixels.
text: string the text of the word.

lh
lh: 'int'

lw
lw: 'int'

options
options: dict

text
text: object

```
kivy.core.text.text_layout.layout_text(text, list lines, tuple size, tuple text_size, dict options,
                                         get_extents, int append_down, int complete)
```

Lays out text into a series of [LayoutWord](#) and [LayoutLine](#) instances according to the options specified.

The function is designed to be called many times, each time new text is appended to the last line (or first line if appending upwards), unless a newline is present in the text. Each text appended is described by its own options which can change between successive calls. If the text is constrained, we stop as soon as the constraint is reached.

Parameters

text: string or bytes the text to be broken down into lines. If lines is not empty, the text is added to the last line (or first line if *append_down* is False) until a newline is reached which creates a new line in *lines*. See [LayoutLine](#).

lines: list a list of [LayoutLine](#) instances, each describing a line of the text. Calls to [layout_text\(\)](#) append or create new [LayoutLine](#) instances in *lines*.

size: 2-tuple of ints the size of the laid out text so far. Upon first call it should probably be (0, 0), afterwards it should be the (w, h) returned by this function in a previous call. When size reaches the constraining size, *text_size*, we stop adding lines and return True for the clipped parameter. size includes the x and y padding.

text_size: 2-tuple of ints or None. the size constraint on the laid out text. If either element is None, the text is not constrained in that dimension. For example, (None, 200) will constrain the height, including padding to 200, while the width is unconstrained. The first line, and the first character of a line is always returned, even if it exceeds the constraint. The value be changed between different calls.

options: dict the label options of this *text*. The options are saved with each word allowing different words to have different options from successive calls.

Note, *options* must include a *space_width* key with a value indicating the width of a space for that set of options.

get_extents: callable a function called with a string, which returns a tuple containing the width, height of the string.

append_down: bool Whether successive calls to the function appends lines before or after the existing lines. If True, they are appended to the last line and below it. If False, it's appended at the first line and above. For example, if False, everything after the last newline in *text* is appended to the first line in lines. Everything before the last newline is inserted at the start of lines in same order as text; that is we do not invert the line order.

This allows laying out from top to bottom until the constrained is reached, or from bottom to top until the constrained is reached.

complete: bool whether this text complete lines. It use is that normally is strip in *options* is True, all leading and trailing spaces are removed from each line except from the last line (or first line if *append_down* is False) which only removes leading spaces. That's because further text can still be appended to the last line so we cannot strip them. If *complete* is True, it indicates no further text is coming and all lines will be stripped.

The function can also be called with *text* set to the empty string and *complete* set to True in order for the last (first) line to be stripped.

Returns 3-tuple, (w, h, clipped). w and h is the width and height of the text in lines so far and includes padding. This can be larger than *text_size*, e.g. if not even a single fitted, the first line would still be returned. *clipped* is True if not all the text has been added to lines because w, h reached the constrained size.

Following is a simple example with no padding and no stripping:

```
>>> from kivy.core.text import Label
>>> from kivy.core.text.text_layout import layout_text

>>> l = Label()
>>> lines = []
>>> # layout text with width constraint by 50, but no height constraint
>>> w, h, clipped = layout_text('heres some text\nnah, another line',
... lines, (0, 0), (50, None), l.options, l.get_cached_extents(), True,
... False)
>>> w, h, clipped
(46, 90, False)
# now add text from bottom up, and constrain width only be 100
>>> w, h, clipped = layout_text('\nyay, more text\n', lines, (w, h),
... (100, None), l.options, l.get_cached_extents(), False, True)
>>> w, h, clipped
(77, 120, 0)
```

(continues on next page)

```
>>> for line in lines:
...     print('line w: {}, line h: {}'.format(line.w, line.h))
...     for word in line.words:
...         print('w: {}, h: {}, text: {}'.format(word.lw, word.lh,
...                                              [word.text]))
line w: 0, line h: 15
line w: 77, line h: 15
w: 77, h: 15, text: ['yay, more text']
line w: 31, line h: 15
w: 31, h: 15, text: ['heres']
line w: 34, line h: 15
w: 34, h: 15, text: [' some']
line w: 24, line h: 15
w: 24, h: 15, text: [' text']
line w: 17, line h: 15
w: 17, h: 15, text: ['ah,']
line w: 46, line h: 15
w: 46, h: 15, text: [' another']
line w: 23, line h: 15
w: 23, h: 15, text: [' line']
```

32.7.3 Text Markup

New in version 1.1.0.

Changed in version 1.10.1: Added `font_context`, `font_features` and `text_language` (Pango only)

We provide a simple text-markup for inline text styling. The syntax look the same as the [BBCode](#).

A tag is defined as `[tag]`, and should have a corresponding `[/tag]` closing tag. For example:

```
[b]Hello [color=ff0000]world[/color][/b]
```

The following tags are available:

[b] [/b] Activate bold text

[i] [/i] Activate italic text

[u] [/u] Underlined text

[s] [/s] Strikethrough text

[font=<str>] [/font] Change the font (note: this refers to a TTF file or registered alias)

[font_context=<str>] [/font_context] Change context for the font, use string value “none” for isolated context.

[font_family=<str>] [/font_family] Font family to request for drawing. This is only valid when using a font context, and takes precedence over `[font]`. See [kivy.uix.label.Label](#) for details.

[font_features=<str>] [/font_features] OpenType font features, in CSS format, this is passed straight through to Pango. The effects of requesting a feature depends on loaded fonts, library versions, etc. Pango only, requires v1.38 or later.

[size=<size>] [/size] Change the font size. `<size>` should be an integer, optionally with a unit (i.e. 16sp)

[color=#<color>] [/color] Change the text color

[ref=<str>] [/ref] Add an interactive zone. The reference + all the word box inside the reference will be available in `MarkupLabel.refs`

[anchor=<str>] Put an anchor in the text. You can get the position of your anchor within the text with `MarkupLabel.anchors`

[sub] [/sub] Display the text at a subscript position relative to the text before it.

[sup] [/sup] Display the text at a superscript position relative to the text before it.

[text_language=<str>] [/text_language] Language of the text, this is an RFC-3066 format language tag (as string), for example “en_US”, “zh_CN”, “fr” or “ja”. This can impact font selection, metrics and rendering. For example, the same bytes of text can look different for *ur* and *ar* languages, though both use Arabic script. Use the string ‘*none*’ to revert to locale detection. Pango only.

If you need to escape the markup from the current text, use `kivy.utils.escape_markup()`.

class kivy.core.text.markup.MarkupLabel(*args, **kwargs)
Bases: `kivy.core.text.LabelBase`

Markup text label.

See module documentation for more information.

property anchors

Get the position of all the [anchor=...]:

```
{ 'anchorA': (x, y), 'anchorB': (x, y), ... }
```

property markup

Return the text with all the markup split:

```
>>> MarkupLabel('[b]Hello world[/b]').markup
>>> ('[b]', 'Hello world', '[/b]')
```

property refs

Get the bounding box of all the [ref=...]:

```
{ 'refA': ((x1, y1, x2, y2), (x1, y1, x2, y2)), ... }
```

render(real=False)

Return a tuple (width, height) to create the image with the user constraints. (width, height) includes the padding.

shorten_post(lines, w, h, margin=2)

Shortens the text to a single line according to the label options.

This function operates on a text that has already been laid out because for markup, parts of text can have different size and options.

If `text_size` [0] is None, the lines are returned unchanged. Otherwise, the lines are converted to a single line fitting within the constrained width, `text_size` [0].

Params `lines`: list of `LayoutLine` instances describing the text. `w`: int, the width of the text in lines, including padding. `h`: int, the height of the text in lines, including padding. `margin` int, the additional space left on the sides. This is in addition to `padding_x`.

Returns 3-tuple of (xw, h, lines), where w, and h is similar to the input and contains the resulting width / height of the text, including padding. `lines`, is a list containing a single `LayoutLine`, which contains the words for the line.

32.8 Video

Core class for reading video files and managing the video *Texture*.

Changed in version 1.10.0: The pyglet, pygst and gi providers have been removed.

Changed in version 1.8.0: There are now 2 distinct Gstreamer implementations: one using Gi/Gst working for both Python 2+3 with Gstreamer 1.0, and one using PyGST working only for Python 2 + Gstreamer 0.10.

Note: Recording is not supported.

class `kivy.core.video.VideoBase(**kwargs)`
Bases: `kivy.event.EventDispatcher`

VideoBase, a class used to implement a video reader.

Parameters

`filename: str` Filename of the video. Can be a file or an URI.

`eos: str, defaults to 'pause'` Action to take when EOS is hit. Can be one of 'pause', 'stop' or 'loop'.

Changed in version 1.4.0: added 'pause'

`async: bool, defaults to True` Load the video asynchronously (may be not supported by all providers).

`autoplay: bool, defaults to False` Auto play the video on init.

Events

`on_eos` Fired when EOS is hit.

`on_load` Fired when the video is loaded and the texture is available.

`on_frame` Fired when a new frame is written to the texture.

property duration

Get the video duration (in seconds)

property filename

Get/set the filename/uri of the current video

load()

Load the video from the current filename

pause()

Pause the video

New in version 1.4.0.

play()

Play the video

property position

Get/set the position in the video (in seconds)

seek(percent, precise=True)

Move to position as percentage (strictly, a proportion from 0 - 1) of the duration

property state

Get the video playing status

```

stop()
    Stop the video playing

property texture
    Get the video texture

unload()
    Unload the actual video

property volume
    Get/set the volume in the video (1.0 = 100%)

```

32.9 Window

Core class for creating the default Kivy window. Kivy supports only one window per application: please don't try to create more than one.

```
class kivy.core.window.Keyboard(**kwargs)
Bases: kivy.event.EventDispatcher
```

Keyboard interface that is returned by [*WindowBase.request_keyboard\(\)*](#). When you request a keyboard, you'll get an instance of this class. Whatever the keyboard input is (system or virtual keyboard), you'll receive events through this instance.

Events

```

on_key_down: keycode, text, modifiers Fired when a new key is pressed down
on_key_up: keycode Fired when a key is released (up)

```

Here is an example of how to request a Keyboard in accordance with the current configuration:

```

import kivy
kivy.require('1.0.8')

from kivy.core.window import Window
from kivy.uix.widget import Widget

class MyKeyboardListener(Widget):

    def __init__(self, **kwargs):
        super(MyKeyboardListener, self).__init__(**kwargs)
        self._keyboard = Window.request_keyboard(
            self._keyboard_closed, self, 'text')
        if self._keyboard.widget:
            # If it exists, this widget is a VKeyboard object which
            # you can use
            # to change the keyboard layout.
            pass
        self._keyboard.bind(on_key_down=self._on_keyboard_down)

    def _keyboard_closed(self):
        print('My keyboard have been closed!')
        self._keyboard.unbind(on_key_down=self._on_keyboard_down)
        self._keyboard = None

    def _on_keyboard_down(self, keyboard, keycode, text, modifiers):

```

(continues on next page)

```

print('The key', keycode, 'have been pressed')
print(' - text is %r' % text)
print(' - modifiers are %r' % modifiers)

# Keycode is composed of an integer + a string
# If we hit escape, release the keyboard
if keycode[1] == 'escape':
    keyboard.release()

# Return True to accept the key. Otherwise, it will be used by
# the system.
return True

if __name__ == '__main__':
    from kivy.base import runTouchApp
    runTouchApp(MyKeyboardListener())

```

callback

Callback that will be called when the keyboard is released

keycode_to_string(value)

Convert a keycode number to a string according to the `Keyboard.keycodes`. If the value is not found in the keycodes, it will return “”.

release()

Call this method to release the current keyboard. This will ensure that the keyboard is no longer attached to your callback.

string_to_keycode(value)

Convert a string to a keycode number according to the `Keyboard.keycodes`. If the value is not found in the keycodes, it will return -1.

target

Target that have requested the keyboard

widget

VKeyboard widget, if allowed by the configuration

window

Window which the keyboard is attached too

class kivy.core.window.WindowBase(kwargs)**

Bases: `kivy.event.EventDispatcher`

WindowBase is an abstract window widget for any window implementation.

Parameters

borderless: str, one of ('0', '1') Set the window border state. Check the [config](#) documentation for a more detailed explanation on the values.

custom_titlebar: str, one of ('0', '1') Set to '1' to uses a custom titlebar

fullscreen: str, one of ('0', '1', 'auto', 'fake') Make the window fullscreen. Check the [config](#) documentation for a more detailed explanation on the values.

width: int Width of the window.

height: int Height of the window.

`minimum_width: int` Minimum width of the window (only works for sdl2 window provider).

`minimum_height: int` Minimum height of the window (only works for sdl2 window provider).

`allow_screensaver: bool` Allow the device to show a screen saver, or to go to sleep on mobile devices. Defaults to True. Only works for sdl2 window provider.

Events

`on_motion: etype, motionevent` Fired when a new *MotionEvent* is dispatched

`on_touch_down:` Fired when a new touch event is initiated.

`on_touch_move:` Fired when an existing touch event changes location.

`on_touch_up:` Fired when an existing touch event is terminated.

`on_draw:` Fired when the `Window` is being drawn.

`on_flip:` Fired when the `Window` GL surface is being flipped.

`on_rotate: rotation` Fired when the `Window` is being rotated.

`on_close:` Fired when the `Window` is closed.

`on_request_close:` Fired when the event loop wants to close the window, or if the escape key is pressed and `exit_on_escape` is `True`. If a function bound to this event returns `True`, the window will not be closed. If the the event is triggered because of the keyboard escape key, the keyword argument `source` is dispatched along with a value of `keyboard` to the bound functions.

New in version 1.9.0.

`on_cursor_enter:` Fired when the cursor enters the window.

New in version 1.9.1.

`on_cursor_leave:` Fired when the cursor leaves the window.

New in version 1.9.1.

`on_minimize:` Fired when the window is minimized.

New in version 1.10.0.

`on_maximize:` Fired when the window is maximized.

New in version 1.10.0.

`on_restore:` Fired when the window is restored.

New in version 1.10.0.

`on_hide:` Fired when the window is hidden.

New in version 1.10.0.

`on_show:` Fired when when the window is shown.

New in version 1.10.0.

`on_keyboard: key, scancode, codepoint, modifier` Fired when the keyboard is used for input.

Changed in version 1.3.0: The `unicode` parameter has been deprecated in favor of `codepoint`, and will be removed completely in future versions.

on_key_down: **key, scancode, codepoint, modifier** Fired when a key pressed.

Changed in version 1.3.0: The *unicode* parameter has been deprecated in favor of *codepoint*, and will be removed completely in future versions.

on_key_up: **key, scancode, codepoint** Fired when a key is released.

Changed in version 1.3.0: The *unicode* parameter has been deprecated in favor of *codepoint*, and will be removed completely in future versions.

on_drop_begin: **x, y, *args** Fired when text(s) or file(s) drop on the application is about to begin.

New in version 2.1.0.

on_drop_file: **filename (bytes), x, y, *args** Fired when a file is dropped on the application.

New in version 1.2.0.

Changed in version 2.1.0: Renamed from *on_dropfile* to *on_drop_file*.

on_drop_text: **text (bytes), x, y, *args** Fired when a text is dropped on the application.

New in version 2.1.0.

on_drop_end: **x, y, *args** Fired when text(s) or file(s) drop on the application has ended.

New in version 2.1.0.

on_memorywarning: Fired when the platform have memory issue (iOS / Android mostly) You can listen to this one, and clean whatever you can.

New in version 1.9.0.

on_textedit(self, text): Fired when inputting with IME. The string inputting with IME is set as the parameter of this event.

New in version 1.10.1.

`add_widget(widget, canvas=None)`

Add a widget to a window

`allow_screensaver`

Whether the screen saver is enabled, or on mobile devices whether the device is allowed to go to sleep while the app is open.

New in version 1.10.0.

allow_screensaver is a *BooleanProperty* and defaults to True.

`borderless`

When set to True, this property removes the window border/decoration. Check the *config* documentation for a more detailed explanation on the values.

New in version 1.9.0.

borderless is a *BooleanProperty* and defaults to False.

`center`

Center of the rotated window.

New in version 1.0.9.

center is an *AliasProperty*.

children

List of the children of this window.

children is a *ListProperty* instance and defaults to an empty list.

Use *add_widget()* and *remove_widget()* to manipulate the list of children. Don't manipulate the list directly unless you know what you are doing.

clear()

Clear the window with the background color

clearcolor

Color used to clear the window.

```
from kivy.core.window import Window

# red background color
Window.clearcolor = (1, 0, 0, 1)

# don't clear background at all
Window.clearcolor = None
```

Changed in version 1.7.2: The clearcolor default value is now: (0, 0, 0, 1).

New in version 1.0.9.

clearcolor is an *ColorProperty* and defaults to (0, 0, 0, 1).

Changed in version 2.1.0: Changed from *AliasProperty* to *ColorProperty*.

close()

Close the window

create_window(*largs)

Will create the main window and configure it.

Warning: This method is called automatically at runtime. If you call it, it will recreate a RenderContext and Canvas. This means you'll have a new graphics tree, and the old one will be unusable.

This method exist to permit the creation of a new OpenGL context AFTER closing the first one. (Like using runTouchApp() and stopTouchApp()).

This method has only been tested in a unittest environment and is not suitable for Applications.

Again, don't use this method unless you know exactly what you are doing!

custom_titlebar

When set to True, allows the user to set a widget as a titlebar. Check the *config* documentation for a more detailed explanation on the values.

New in version 2.1.0.

see *set_custom_titlebar()* for detailed usage *custom_titlebar* is a *BooleanProperty* and defaults to False.

dpi

Return the DPI of the screen as computed by the window. If the implementation doesn't support DPI lookup, it's 96.

Warning: This value is not cross-platform. Use `kivy.metrics.Metrics.dpi` instead.

event_managers = None

Holds a *list* of registered event managers.

Don't change the property directly but use `register_event_manager()` and `unregister_event_manager()` to register and unregister an event manager.

Event manager is an instance of `EventManagerBase`.

New in version 2.1.0.

Warning: This is an experimental property and it remains so while this warning is present.

event_managers_dict = None

Holds a *dict* of `type_id` to *list* of event managers.

Don't change the property directly but use `register_event_manager()` and `unregister_event_manager()` to register and unregister an event manager.

Event manager is an instance of `EventManagerBase`.

New in version 2.1.0.

Warning: This is an experimental property and it remains so while this warning is present.

flip()

Flip between buffers

focus

Check whether or not the window currently has focus.

New in version 1.9.1.

`focus` is a read-only `AliasProperty` and defaults to True.

fullscreen

This property sets the fullscreen mode of the window. Available options are: True, False, 'auto' and 'fake'. Check the `config` documentation for more detailed explanations on these values.

`fullscreen` is an `OptionProperty` and defaults to False.

New in version 1.2.0.

Note: The 'fake' option has been deprecated, use the `borderless` property instead.

get_gl_backend_name()

Returns the gl backend that will or is used with this window.

gl_backends_allowed = []

A list of Kivy gl backend names, which if not empty, will be the exclusive list of gl backends that can be used with this window.

gl_backends_ignored = []

A list of Kivy gl backend names that may not be used with this window.

grab_mouse()

Grab mouse - so won't leave window

New in version 1.10.0.

Note: This feature requires the SDL2 window provider.

height

Rotated window height.

height is a read-only *AliasProperty*.

hide()

Hides the window. This method should be used on desktop platforms only.

New in version 1.9.0.

Note: This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

icon

A path to the window icon.

New in version 1.1.2.

icon is a *StringProperty*.

keyboard_anim_args = {'d': 0.5, 't': 'in_out_quart'}

The attributes for animating softkeyboard/IME. *t* = *transition*, *d* = *duration*. This value will have no effect on desktops.

New in version 1.10.0.

keyboard_anim_args is a dict and defaults to {'t': 'in_out_quart', 'd': .5}.

keyboard_height

Returns the height of the softkeyboard/IME on mobile platforms. Will return 0 if not on mobile platform or if IME is not active.

Note: This property returns 0 with SDL2 on Android, but setting Window.softinput_mode does work.

New in version 1.9.0.

keyboard_height is a read-only *AliasProperty* and defaults to 0.

keyboard_padding

The padding to have between the softkeyboard/IME & target or bottom of window. Will have no effect on desktops.

New in version 1.10.0.

keyboard_padding is a *NumericProperty* and defaults to 0.

left

Left position of the window.

Note: It's an SDL2 property with [0, 0] in the top-left corner.

Changed in version 1.10.0: `left` is now an [AliasProperty](#)

New in version 1.9.1.

`left` is an [AliasProperty](#) and defaults to the position set in [Config](#).

mainloop()

Called by the EventLoop every frame after it idles.

managed_textinput = False

True if this Window class uses `on_textinput` to insert text, internal.

maximize()

Maximizes the window. This method should be used on desktop platforms only.

New in version 1.9.0.

Note: This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

minimize()

Minimizes the window. This method should be used on desktop platforms only.

New in version 1.9.0.

Note: This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

minimum_height

The minimum height to restrict the window to.

New in version 1.9.1.

`minimum_height` is a [NumericProperty](#) and defaults to 0.

minimum_width

The minimum width to restrict the window to.

New in version 1.9.1.

`minimum_width` is a [NumericProperty](#) and defaults to 0.

modifiers

List of keyboard modifiers currently active.

New in version 1.0.9.

`modifiers` is an [AliasProperty](#).

mouse_pos

2d position of the mouse cursor within the window.

Position is relative to the left/bottom point of the window.

Note: Cursor position will be scaled by the pixel density if the high density mode is supported by the window provider.

New in version 1.2.0.

`mouse_pos` is an [ObjectProperty](#) and defaults to (0, 0).

on_close(*args)

Event called when the window is closed.

on_cursor_enter(*args)

Event called when the cursor enters the window.

New in version 1.9.1.

Note: This feature requires the SDL2 window provider.

on_cursor_leave(*args)

Event called when the cursor leaves the window.

New in version 1.9.1.

Note: This feature requires the SDL2 window provider.

on_drop_begin(x, y, *args)

Event called when a text or a file drop on the application is about to begin. It will be followed-up by a single or a multiple *on_drop_text* or *on_drop_file* events ending with an *on_drop_end* event.

Arguments *x* and *y* are the mouse cursor position at the time of the drop and you should only rely on them if the drop originated from the mouse.

Parameters

x: int Cursor x position, relative to the window *left*, at the time of the drop.

y: int Cursor y position, relative to the window *top*, at the time of the drop.

**args: tuple* Additional arguments.

Note: This event works with sdl2 window provider.

New in version 2.1.0.

on_drop_end(x, y, *args)

Event called when a text or a file drop on the application has ended.

Arguments *x* and *y* are the mouse cursor position at the time of the drop and you should only rely on them if the drop originated from the mouse.

Parameters

x: int Cursor x position, relative to the window *left*, at the time of the drop.

y: int Cursor y position, relative to the window *top*, at the time of the drop.

**args: tuple* Additional arguments.

Note: This event works with sdl2 window provider.

New in version 2.1.0.

on_drop_file(filename, x, y, *args)

Event called when a file is dropped on the application.

Arguments *x* and *y* are the mouse cursor position at the time of the drop and you should only rely on them if the drop originated from the mouse.

Parameters

filename: bytes Absolute path to a dropped file.
x: int Cursor x position, relative to the window *left*, at the time of the drop.
y: int Cursor y position, relative to the window *top*, at the time of the drop.
**args: tuple* Additional arguments.

Warning: This event currently works with sdl2 window provider, on pygame window provider and OS X with a patched version of pygame. This event is left in place for further evolution (ios, android etc.)

Note: On Windows it is possible to drop a file on the window title bar or on its edges and for that case *mouse_pos* won't be updated as the mouse cursor is not within the window.

Note: This event doesn't work for apps with elevated permissions, because the OS API calls are filtered. Check issue [#4999](#) for pointers to workarounds.

New in version 1.2.0.

Changed in version 2.1.0: Renamed from *on_dropfile* to *on_drop_file*.

on_drop_text(*text, x, y, *args*)

Event called when a text is dropped on the application.

Arguments *x* and *y* are the mouse cursor position at the time of the drop and you should only rely on them if the drop originated from the mouse.

Parameters

text: bytes Text which is dropped.
x: int Cursor x position, relative to the window *left*, at the time of the drop.
y: int Cursor y position, relative to the window *top*, at the time of the drop.
**args: tuple* Additional arguments.

Note: This event works with sdl2 window provider on x11 window.

Note: On Windows it is possible to drop a text on the window title bar or on its edges and for that case *mouse_pos* won't be updated as the mouse cursor is not within the window.

New in version 2.1.0.

on_flip()

Flip between buffers (event)

on_hide(args*)**

Event called when the window is hidden.

New in version 1.10.0.

Note: This feature requires the SDL2 window provider.

on_joy_axis(*stickid, axisid, value*)

Event called when a joystick has a stick or other axis moved.

New in version 1.9.0.

on_joy_ball(*stickid, ballid, xvalue, yvalue*)

Event called when a joystick has a ball moved.

New in version 1.9.0.

on_joy_button_down(*stickid, buttonid*)

Event called when a joystick has a button pressed.

New in version 1.9.0.

on_joy_button_up(*stickid, buttonid*)

Event called when a joystick has a button released.

New in version 1.9.0.

on_joy_hat(*stickid, hatid, value*)

Event called when a joystick has a hat/dpad moved.

New in version 1.9.0.

on_key_down(*key, scancode=None, codepoint=None, modifier=None, **kwargs*)

Event called when a key is down (same arguments as on_keyboard)

on_key_up(*key, scancode=None, codepoint=None, modifier=None, **kwargs*)

Event called when a key is released (same arguments as on_keyboard).

on_keyboard(*key, scancode=None, codepoint=None, modifier=None, **kwargs*)

Event called when keyboard is used.

Warning: Some providers may omit *scancode*, *codepoint* and/or *modifier*.

on_maximize(**largs*)

Event called when the window is maximized.

New in version 1.10.0.

Note: This feature requires the SDL2 window provider.

on_memorywarning()

Event called when the platform have memory issue. Your goal is to clear the cache in your app as much as you can, release unused widgets, do garbage collection etc.

Currently, this event is fired only from the SDL2 provider, for iOS and Android.

New in version 1.9.0.

on_minimize(**largs*)

Event called when the window is minimized.

New in version 1.10.0.

Note: This feature requires the SDL2 window provider.

on_motion(etype, me)

Event called when a motion event is received.

Parameters

etype: str One of “begin”, “update” or “end”.

me: **MotionEvent** The motion event currently dispatched.

Changed in version 2.1.0: Event managers get to handle the touch event first and if none of them accepts the event (by returning *True*) then window will dispatch *me* through “on_touch_down”, “on_touch_move”, “on_touch_up” events depending on the *etype*. All non-touch events will go only through managers.

on_mouse_down(x, y, button, modifiers)

Event called when the mouse is used (pressed/released).

on_mouse_move(x, y, modifiers)

Event called when the mouse is moved with buttons pressed.

on_mouse_up(x, y, button, modifiers)

Event called when the mouse is moved with buttons pressed.

on_request_close(*largs, **kwargs)

Event called before we close the window. If a bound function returns *True*, the window will not be closed. If the the event is triggered because of the keyboard escape key, the keyword argument *source* is dispatched along with a value of *keyboard* to the bound functions.

Warning: When the bound function returns True the window will not be closed, so use with care because the user would not be able to close the program, even if the red X is clicked.

on_resize(width, height)

Event called when the window is resized.

on_restore(*largs)

Event called when the window is restored.

New in version 1.10.0.

Note: This feature requires the SDL2 window provider.

on_rotate(rotation)

Event called when the screen has been rotated.

on_show(*largs)

Event called when the window is shown.

New in version 1.10.0.

Note: This feature requires the SDL2 window provider.

on_textedit(text)

Event called when inputting with IME. The string inputting with IME is set as the parameter of this event.

New in version 1.10.1.

on_textinput(*text*)

Event called when text: i.e. alpha numeric non control keys or set of keys is entered. As it is not guaranteed whether we get one character or multiple ones, this event supports handling multiple characters.

New in version 1.9.0.

on_touch_down(*touch*)

Event called when a touch down event is initiated.

Changed in version 1.9.0: The touch *pos* is now transformed to window coordinates before this method is called. Before, the touch *pos* coordinate would be $(0, 0)$ when this method was called.

on_touch_move(*touch*)

Event called when a touch event moves (changes location).

Changed in version 1.9.0: The touch *pos* is now transformed to window coordinates before this method is called. Before, the touch *pos* coordinate would be $(0, 0)$ when this method was called.

on_touch_up(*touch*)

Event called when a touch event is released (terminated).

Changed in version 1.9.0: The touch *pos* is now transformed to window coordinates before this method is called. Before, the touch *pos* coordinate would be $(0, 0)$ when this method was called.

parent

Parent of this window.

parent is a *ObjectProperty* instance and defaults to None. When created, the parent is set to the window itself. You must take care of it if you are doing a recursive check.

raise_window()

Raise the window. This method should be used on desktop platforms only.

New in version 1.9.1.

Note: This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

register_event_manager(*manager*)

Register and start an event manager to handle events declared in *type_ids* attribute.

New in version 2.1.0.

Warning: This is an experimental method and it remains so until this warning is present as it can be changed or removed in the next versions of Kivy.

release_all_keyboards()

New in version 1.0.8.

This will ensure that no virtual keyboard / system keyboard is requested. All instances will be closed.

release_keyboard(*target=None*)

New in version 1.0.4.

Internal method for the widget to release the real-keyboard. Check *request_keyboard()* to understand how it works.

remove_widget(widget)

Remove a widget from a window

request_keyboard(callback, target, input_type='text', keyboardSuggestions=True)

New in version 1.0.4.

Internal widget method to request the keyboard. This method is rarely required by the end-user as it is handled automatically by the [TextInput](#). We expose it in case you want to handle the keyboard manually for unique input scenarios.

A widget can request the keyboard, indicating a callback to call when the keyboard is released (or taken by another widget).

Parameters

callback: func Callback that will be called when the keyboard is closed. This can be because somebody else requested the keyboard or the user closed it.

target: Widget Attach the keyboard to the specified *target*. This should be the widget that requested the keyboard. Ensure you have a different target attached to each keyboard if you're working in a multi user mode.

New in version 1.0.8.

input_type: string Choose the type of soft keyboard to request. Can be one of 'null', 'text', 'number', 'url', 'mail', 'datetime', 'tel', 'address'.

Note: *input_type* is currently only honored on Android.

New in version 1.8.0.

Changed in version 2.1.0: Added *null* to soft keyboard types.

keyboardSuggestions: bool If True provides auto suggestions on top of keyboard. This will only work if *input_type* is set to *text*, *url*, *mail* or *address*.

New in version 2.1.0.

Return An instance of [Keyboard](#) containing the callback, target, and if the configuration allows it, a [VKeyboard](#) instance attached as a *.widget* property.

Note: The behavior of this function is heavily influenced by the current *keyboard_mode*. Please see the Config's [configuration tokens](#) section for more information.

restore()

Restores the size and position of a maximized or minimized window. This method should be used on desktop platforms only.

New in version 1.9.0.

Note: This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

rotation

Get/set the window content rotation. Can be one of 0, 90, 180, 270 degrees.

New in version 1.0.9.

rotation is an [AliasProperty](#).

screenshot(*name*=‘screenshot{:04d}.png’)

Save the actual displayed image to a file.

set_custom_titlebar(*widget*)

Sets a Widget as a titlebar

widget The widget you want to set as the titlebar

New in version 2.1.0.

This function returns *True* on successfully setting the custom titlebar, else false

How to use this feature

1. first set Window.custom_titlebar to **True**
2. then call Window.set_custom_titlebar **with** the widget/layout you
want to set **as** titlebar **as** the argument # noqa: E501

If you want a child of the widget to receive touch events, in that child define a property *draggable* and set it to False

If you set the property *draggable* on a layout, all the child in the layout will receive touch events

If you want to override default behaviour, add function *in_drag_area(x,y)* to the widget

The function is call with two args x,y which are mouse.x, and mouse.y the function should return

True if that point should be used to drag the window

False if you want to receive the touch event at the point

Note: If you use *in_drag_area()* property *draggable* will not be checked

Note: This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

Warning: *custom_titlebar* must be set to True for the widget to be successfully set as a titlebar

set_icon(*filename*)

Set the icon of the window.

New in version 1.0.5.

set_system_cursor(*cursor_name*)

Set type of a mouse cursor in the Window.

It can be one of ‘arrow’, ‘ibeam’, ‘wait’, ‘crosshair’, ‘wait_arrow’, ‘size_nwse’, ‘size_nesw’, ‘size_we’, ‘size_ns’, ‘size_all’, ‘no’, or ‘hand’.

On some platforms there might not be a specific cursor supported and such an option falls back to one of the substitutable alternatives:

	Windows	MacOS	Linux X11	Linux Wayland
arrow	arrow	arrow	arrow	arrow
ibeam	ibeam	ibeam	ibeam	ibeam
wait	wait	arrow	wait	wait
crosshair	crosshair	crosshair	crosshair	hand
wait_arrow	arrow	arrow	wait	wait
size_nwse	size_nwse	size_all	size_all	hand
size_nesw	size_nesw	size_all	size_all	hand
size_we	size_we	size_we	size_we	hand
size_ns	size_ns	size_ns	size_ns	hand
size_all	size_all	size_all	size_all	hand
no	no	no	no	ibeam
hand	hand	hand	hand	hand

New in version 1.10.1.

Note: This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

set_title(*title*)

Set the window title.

New in version 1.0.5.

set_vkeyboard_class(*cls*)

New in version 1.0.8.

Set the VKeyboard class to use. If set to *None*, it will use the [kivy.uix.vkeyboard.VKeyboard](#).

shape_color_key

Color key of the shaped window - sets which color will be hidden from the window [shape_image](#) (only works for sdl2 window provider).

New in version 1.10.1.

shape_color_key is a [ColorProperty](#) instance and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from [ListProperty](#) to [ColorProperty](#).

shape_cutoff

The window [shape_image](#) cutoff property (only works for sdl2 window provider).

New in version 1.10.1.

shape_cutoff is a [BooleanProperty](#) and defaults to True.

shape_image

An image for the window shape (only works for sdl2 window provider).

Warning: The image size has to be the same like the window's size!

New in version 1.10.1.

shape_image is a [StringProperty](#) and defaults to 'data/images/defaultshape.png'. This value is taken from [Config](#).

shape_mode

Window mode for shaping (only works for sdl2 window provider).

- can be RGB only
 - *default* - does nothing special
 - *colorkey* - hides a color of the *shape_color_key*
- has to contain alpha channel
 - *binalpha* - hides an alpha channel of the *shape_image*
 - *reversebinalpha* - shows only the alpha of the *shape_image*

Note: Before actually setting the mode make sure the Window has the same size like the *shape_image*, preferably via Config before the Window is actually created.

If the *shape_image* isn't set, the default one will be used and the mode might not take the desired visual effect.

New in version 1.10.1.

shape_mode is an *AliasProperty*.

shaped

Read only property to check if the window is shapable or not (only works for sdl2 window provider).

New in version 1.10.1.

shaped is an *AliasProperty*.

show()

Shows the window. This method should be used on desktop platforms only.

New in version 1.9.0.

Note: This feature requires the SDL2 window provider and is currently only supported on desktop platforms.

show_cursor

Set whether or not the cursor is shown on the window.

New in version 1.9.1.

show_cursor is a *BooleanProperty* and defaults to True.

size

Get the rotated size of the window. If *rotation* is set, then the size will change to reflect the rotation.

New in version 1.0.9.

size is an *AliasProperty*.

softinput_mode

This specifies the behavior of window contents on display of the soft keyboard on mobile platforms. It can be one of "", 'pan', 'scale', 'resize' or 'below_target'. Their effects are listed below.

Value	Effect
''	The main window is left as is, allowing you to use the <code>keyboard_height</code> to manage the window contents manually.
'pan'	The main window pans, moving the bottom part of the window to be always on top of the keyboard.
'resize'	The window is resized and the contents scaled to fit the remaining space.
'be-low_target'	The window pans so that the current target TextInput widget requesting the keyboard is presented just above the soft keyboard.

`softinput_mode` is an *OptionProperty* and defaults to ''.

Note: The `resize` option does not currently work with SDL2 on Android.

New in version 1.9.0.

Changed in version 1.9.1: The 'below_target' option was added.

system_size

Real size of the window ignoring rotation. If the density is not 1, the `system_size` is the `size` divided by density.

New in version 1.0.9.

`system_size` is an *AliasProperty*.

to_normalized_pos(x, y)

Transforms absolute coordinates to normalized (0-1) coordinates using `system_size`.

New in version 2.1.0.

toggleFullscreen()

Toggle between fullscreen and windowed mode.

Deprecated since version 1.9.0: Use `fullscreen` instead.

top

Top position of the window.

Note: It's an SDL2 property with [0, 0] in the top-left corner.

Changed in version 1.10.0: `top` is now an *AliasProperty*

New in version 1.9.1.

`top` is an *AliasProperty* and defaults to the position set in `Config`.

transform_motion_event_2d(me, widget=None)

Transforms the motion event `me` to this window size and then if `widget` is passed transforms `me` to `widget`'s local coordinates.

Raises `AttributeError`: If `widget`'s ancestor is None.

Note: Unless it's a specific case, call `push()` before and `pop()` after this method's call to preserve previous values of `me`'s attributes.

New in version 2.1.0.

ungrab_mouse()

Ungrab mouse

New in version 1.10.0.

Note: This feature requires the SDL2 window provider.

unregister_event_manager(*manager*)

Unregister and stop an event manager previously registered with [*register_event_manager\(\)*](#).

New in version 2.1.0.

Warning: This is an experimental method and it remains so until this warning is present as it can be changed or removed in the next versions of Kivy.

width

Rotated window width.

width is a read-only [*AliasProperty*](#).

KIVY MODULE FOR BINARY DEPENDENCIES.

Binary dependencies such as gstreamer is installed as a namespace module of kivy.deps. These modules are responsible for making sure that the binaries are available to kivy.

EFFECTS

New in version 1.7.0.

Everything starts with the *KineticEffect*, the base class for computing velocity out of a movement.

This base class is used to implement the *ScrollEffect*, a base class used for our *ScrollView* widget effect. We have multiple implementations:

- *ScrollEffect*: base class used for implementing an effect. It only calculates the scrolling and the overscroll.
- *DampedScrollEffect*: uses the overscroll information to allow the user to drag more than expected. Once the user stops the drag, the position is returned to one of the bounds.
- *OpacityScrollEffect*: uses the overscroll information to reduce the opacity of the scrollview widget. When the user stops the drag, the opacity is set back to 1.

34.1 Damped scroll effect

New in version 1.7.0.

This damped scroll effect will use the *overscroll* to calculate the scroll value, and slows going back to the upper or lower limit.

```
class kivy.effects.dampedscroll.DampedScrollEffect(**kwargs)
Bases: kivy.effects.scroll.ScrollEffect
```

DampedScrollEffect class. See the module documentation for more information.

edge_damping

Edge damping.

edge_damping is a *NumericProperty* and defaults to 0.25

min_overscroll

An overscroll less than this amount will be normalized to 0.

New in version 1.8.0.

min_overscroll is a *NumericProperty* and defaults to .5.

round_value

If True, when the motion stops, *value* is rounded to the nearest integer.

New in version 1.8.0.

round_value is a *BooleanProperty* and defaults to True.

spring_constant

Spring constant.

spring_constant is a *NumericProperty* and defaults to 2.0

update_velocity(dt)

(internal) Update the velocity according to the frametime and friction.

34.2 Kinetic effect

New in version 1.7.0.

The *KineticEffect* is the base class that is used to compute the velocity out of a movement. When the movement is finished, the effect will compute the position of the movement according to the velocity, and reduce the velocity with a friction. The movement stop until the velocity is 0.

Conceptually, the usage could be:

```
>>> effect = KineticEffect()
>>> effect.start(10)
>>> effect.update(15)
>>> effect.update(30)
>>> effect.stop(48)
```

Over the time, you will start a movement of a value, update it, and stop the movement. At this time, you'll get the movement value into *KineticEffect.value*. On the example i've typed manually, the computed velocity will be:

```
>>> effect.velocity
3.1619100231163046
```

After multiple clock interaction, the velocity will decrease according to *KineticEffect.friction*. The computed value will be stored in *KineticEffect.value*. The output of this *value* could be:

```
46.30038145219605
54.58302451968686
61.9229016256196
# ...
```

class kivy.effects.kinetic.KineticEffect(kwargs)**

Bases: *kivy.event.EventDispatcher*

Kinetic effect class. See module documentation for more information.

cancel()

Cancel a movement. This can be used in case *stop()* cannot be called. It will reset *is_manual* to False, and compute the movement if the velocity is > 0.

friction

Friction to apply on the velocity

friction is a *NumericProperty* and defaults to 0.05.

is_manual

Indicate if a movement is in progress (True) or not (False).

is_manual is a *BooleanProperty* and defaults to False.

max_history

Save up to *max_history* movement value into the history. This is used for correctly calculating the velocity according to the movement.

max_history is a *NumericProperty* and defaults to 5.

min_distance

The minimal distance for a movement to have nonzero velocity.

New in version 1.8.0.

min_distance is *NumericProperty* and defaults to 0.1.

min_velocity

Velocity below this quantity is normalized to 0. In other words, any motion whose velocity falls below this number is stopped.

New in version 1.8.0.

min_velocity is a *NumericProperty* and defaults to 0.5.

start(val, t=None)

Start the movement.

Parameters

val: float or int Value of the movement

t: float, defaults to None Time when the movement happen. If no time is set, it will use `time.time()`

std_dt

`std_dt` correction update_velocity if dt is not constant

New in version 2.0.0.

std_dt is a *NumericProperty* and defaults to 0.017.

stop(val, t=None)

Stop the movement.

See [start\(\)](#) for the arguments.

update(val, t=None)

Update the movement.

See [start\(\)](#) for the arguments.

update_velocity(dt)

(internal) Update the velocity according to the frametime and friction.

value

Value (during the movement and computed) of the effect.

value is a *NumericProperty* and defaults to 0.

velocity

Velocity of the movement.

velocity is a *NumericProperty* and defaults to 0.

34.3 Opacity scroll effect

Based on the `DampedScrollEffect`, this one will also decrease the opacity of the target widget during the overscroll.

```
class kivy.effects.opacityscroll.OpacityScrollEffect(**kwargs)
Bases: kivy.effects.dampedscroll.DampedScrollEffect
```

OpacityScrollEffect class. Uses the overscroll information to reduce the opacity of the scrollview widget. When the user stops the drag, the opacity is set back to 1.

34.4 Scroll effect

New in version 1.7.0.

Based on the `kinetic` effect, the `ScrollEffect` will limit the movement to bounds determined by its `min` and `max` properties. If the movement exceeds these bounds, it will calculate the amount of `overscroll` and try to return to the value of one of the bounds.

This is very useful for implementing a scrolling list. We actually use this class as a base effect for our `ScrollView` widget.

```
class kivy.effects.scroll.ScrollEffect(**kwargs)
Bases: kivy.effects.kinetic.KineticEffect
```

ScrollEffect class. See the module documentation for more information.

displacement

Cumulative distance of the movement during the interaction. This is used to determine if the movement is a drag (more than `drag_threshold`) or not.

`displacement` is a `NumericProperty` and defaults to 0.

drag_threshold

Minimum distance to travel before the movement is considered as a drag.

`drag_threshold` is a `NumericProperty` and defaults to 20sp.

max

Maximum boundary to use for scrolling.

`max` is a `NumericProperty` and defaults to 0.

min

Minimum boundary to use for scrolling.

`min` is a `NumericProperty` and defaults to 0.

overscroll

Computed value when the user over-scrolls i.e. goes out of the bounds.

`overscroll` is a `NumericProperty` and defaults to 0.

reset(pos)

(internal) Reset the value and the velocity to the `pos`. Mostly used when the bounds are checked.

scroll

Computed value for scrolling. This value is different from `kivy.effects.kinetic.KineticEffect.value` in that it will return to one of the min/max bounds.

`scroll` is a `NumericProperty` and defaults to 0.

start(val, t=None)

Start the movement.

Parameters

val: float or int Value of the movement

t: float, defaults to None Time when the movement happen. If no time is set, it will use time.time()

stop(val, t=None)

Stop the movement.

See [start\(\)](#) for the arguments.

target_widget

Widget to attach to this effect. Even if this class doesn't make changes to the *target_widget* by default, subclasses can use it to change the graphics or apply custom transformations.

target_widget is a *ObjectProperty* and defaults to None.

update(val, t=None)

Update the movement.

See [start\(\)](#) for the arguments.

EVENT MANAGER

The `EventManagerBase` is the abstract class intended for specific implementation of dispatching motion events (instances of `MotionEvent`) to widgets through `on_motion()` method of the `Widget` class.

Warning: This feature is experimental and it remains so while this warning is present.

Manager is a layer between the window and its widgets. `WindowBase` will forward all the events it receives in `on_motion()` method to the all managers who declared to receive types of those events. Event will continue to go through the managers list even if one of them accept it (by returning `True`).

35.1 When to use an event manager

Use a manager when you want to:

- Dispatch touch, hover, keyboard, joystick or any other events to the widgets through `on_motion()` method.
- Dispatch filtered motion events by any criteria, like by a `device` or a `profile`.
- Combine several motion events (touch, hover etc.) into one new event and dispatch it to the widgets.
- Dispatch one-time generic events, like app pause/resume.
- Write an event simulator, like a touch simulator which draws a circle on window's canvas for every simulated touch.

35.2 Defining and registering an event manager

1. Inherit `EventManagerBase` and set which events this manager should receive by declaring event types in `EventManagerBase.type_ids` attribute.
2. Implement `EventManagerBase.dispatch()` which will be called by window to pass event type (one of "begin", "update", "end") and an event.
3. Implement `EventManagerBase.start()` and `EventManagerBase.stop()` to allocate and release additional resources if needed.
4. Register a manager instance to window using method `register_event_manager()`. This can be done by overriding methods `build()` or `on_start()`.

All registered managers are kept in the `event_managers` list. To unregister a manager call `unregister_event_manager()` which itself can be called in `on_stop()` method.

35.3 Dispatching events to the widgets

Once registered, window will start the manager and forward all events of types declared in `EventManagerBase.type_ids` to the manager's `EventManagerBase.dispatch()` method. It's up to manager to decide how to dispatch them, either by going through `EventManagerBase.window.children` list and dispatching `on_motion` event or by using some different logic. It's also up to manager to dispatch grabbed events if grab feature is supported by the event (see `grab()` and `ungrab()` methods).

Manager can assign a different dispatch mode to decide how event should be dispatched throughout the widget tree by changing the value of the `dispatch_mode` attribute. Before changing the mode manager should store/restore the current one, either by using a local variable or by using event's `push()` / `pop()` methods.

Currently there are three dispatch modes (behaviors) recognized by the `on_motion` method in `Widget` class:

1. Default dispatch (requires `MODE_DEFAULT_DISPATCH`) - event will go through widget's `children` list, starting with the first widget in the list until event gets accepted or last widget registered for that event is reached. Mode `MODE_DEFAULT_DISPATCH` is assigned by default in `MotionEvent` class.
2. Filtered dispatch (requires `MODE_FILTERED_DISPATCH`) - event will go only through registered child widgets.
3. No dispatch to children (requires `MODE_DONT_DISPATCH`) - event will not be dispatched to child widgets.

Note that window does not have a `motion_filter` property and therefore does not have a list of filtered widgets from its `children` list.

`class kivy.eventmanager.EventManagerBase`
Bases: `builtins.object`

Abstract class with methods `start()`, `stop()` and `dispatch()` for specific class to implement.

Example of the manager receiving touch and hover events:

```
class TouchHoverManager(EventManagerBase):  
  
    type_ids = ('touch', 'hover')  
  
    def start(self):  
        # Create additional resources, bind callbacks to self.window  
  
    def dispatch(self, etype, me):  
        if me.type_id == 'touch':  
            # Handle touch event  
        elif me.type_id == 'hover':  
            # Handle hover event  
  
    def stop(self):  
        # Release resources
```

`dispatch(etype, me)`
Dispatch event `me` to the widgets in the `window`.

Parameters

etype: str One of “begin”, “update” or “end”

me: MotionEvent The Motion Event currently dispatched.

Returns *bool* True to stop event dispatching

New in version 2.1.0.

start()

Start the manager, bind callbacks to the objects and create additional resources. Attribute *window* is assigned when this method is called.

New in version 2.1.0.

stop()

Stop the manager, unbind from any objects and release any allocated resources.

New in version 2.1.0.

type_ids = None

Override this attribute to declare the type ids of the events which manager wants to receive. This attribute will be used by *WindowBase* to know which events to pass to the *dispatch()* method.

New in version 2.1.0.

window = None

Holds the instance of the *WindowBase*.

New in version 2.1.0.

kivy.eventmanager.MODE_DEFAULT_DISPATCH = 'default'

Assign this mode to make event dispatch through widget’s *children* list, starting with the first widget in the list until event gets accepted or last widget registered for that event is reached. Widgets after the last registered widget are ignored.

New in version 2.1.0.

kivy.eventmanager.MODE_DONT_DISPATCH = 'none'

Assign this mode to prevent event from dispatching to child widgets.

New in version 2.1.0.

kivy.eventmanager.MODE_FILTERED_DISPATCH = 'filtered'

Assign this mode to make event dispatch only to child widgets which were previously registered to receive events of the same *type_id* and not to all child widgets.

New in version 2.1.0.

GARDEN

New in version 1.7.0.

Changed in version 1.11.1.

Garden is a project to centralize addons for Kivy maintained by users. You can find more information at [Kivy Garden](#). All the garden packages are centralized on the [kivy-garden Github](#) repository.

Warning: The garden flower widgets are contributed by regular users such as yourself. The kivy developers do not take any responsibility for the code hosted in the garden organization repositories - we do not actively monitor the flower repos. Please use at your own risk.

36.1 Update to garden structure

Starting with the kivy 1.11.0 release, kivy has [shifted](#) from using the garden legacy tool that installs flowers with *garden install flower* where the flower does not have a proper python package structure to flowers that can be installed with pip and uploaded to pypi. Kivy supports the legacy garden flowers side by side with the newer packages so the garden tool and legacy flowers will be able to be used indefinitely. But we will only provide support for the newer packages format in the future.

For garden package maintainers - for a guide how to migrate your garden package from the legacy structure *garden.flower* to the newer *flower* structure used with the pip, see [this guide](#).

We hope most garden packages will be converted to the newer format to help with installation.

36.2 General Usage Guidelines

To use a kivy garden flower, first check if the flower is in the legacy format. If the flower name is in the format of *garden.flower*, such as [garden.graph](#) it is a legacy flower. If it is just *flower* such as [graph](#) it is in the present format. If it is in the legacy format see [Legacy garden tool instructions](#) for how to install and use it. Otherwise, continue with the guide below.

Garden flowers can now be installed with the *pip* tool like a normal python package. Given a flower that you want to install, lets use [graph](#) as an example. You can install master directly from github with:

```
python -m pip install https://github.com/kivy-garden/graph/archive/master.  
zip
```

Look under the repository's releases tab if you'd like to install a specific release or a pre-compiled wheel, if the flower has any. Then use the url with *pip*.

Or you can automatically install it using garden's pypi server with:

```
python -m pip install kivy_garden.graph --extra-index-url https://kivy-garden.github.io/simple/
```

To permanently add our garden server to your pip configuration so that you don't have to specify it with *--extra-index-url*, add:

```
[global]
timeout = 60
index-url = https://kivy-garden.github.io/simple/
```

to your `pip.conf`.

If the flower maintainer has uploaded the flower to [pypi](#), you can just install it with `pip install kivy_garden.flower`.

36.3 Legacy garden tool instructions

Garden is now distributed as a separate Python module, `kivy-garden`. You can install it with pip:

```
pip install kivy-garden
```

The garden module does not initially include any packages. You can download them with the garden tool installed by the pip package:

```
# Installing a garden package
garden install graph

# Upgrade a garden package
garden install --upgrade graph

# Uninstall a garden package
garden uninstall graph

# List all the garden packages installed
garden list

# Search new packages
garden search

# Search all the packages that contain "graph"
garden search graph

# Show the help
garden --help
```

All the garden packages are installed by default in `~/.kivy/garden`.

Note: In previous versions of Kivy, garden was a tool at `kivy/tools/garden`. This no longer exists, but the `kivy-garden` module provides exactly the same functionality.

36.3.1 Packaging

If you want to include garden packages in your application, you can add `-app` to the `install` command. This will create a `libs/garden` directory in your current directory which will be used by `kivy.garden`.

For example:

```
cd myapp  
garden install --app graph
```

```
kivy.garden.garden_system_dir = 'garden'  
    system path where garden modules can be installed
```


GRAPHICS

This package assembles many low level functions used for drawing. The whole graphics package is compatible with OpenGL ES 2.0 and has many rendering optimizations.

37.1 The basics

For drawing on a screen, you will need :

1. a *Canvas* object.
2. *Instruction* objects.

Each *Widget* in Kivy already has a *Canvas* by default. When you create a widget, you can create all the instructions needed for drawing. If *self* is your current widget, you can do:

```
from kivy.graphics import *
with self.canvas:
    # Add a red color
    Color(1., 0, 0)

    # Add a rectangle
    Rectangle(pos=(10, 10), size=(500, 500))
```

The instructions *Color* and *Rectangle* are automatically added to the canvas object and will be used when the window is drawn.

Note: Kivy drawing instructions are not automatically relative to the position or size of the widget. You, therefore, need to consider these factors when drawing. In order to make your drawing instructions relative to the widget, the instructions need either to be declared in the *KvLang* or bound to pos and size changes. Please see *Adding a Background to a Layout* for more detail.

37.2 GL Reloading mechanism

New in version 1.2.0.

During the lifetime of the application, the OpenGL context might be lost. This happens:

- when the window is resized on OS X or the Windows platform and you're using pygame as a window provider. This is due to SDL 1.2. In the SDL 1.2 design, it needs to recreate a GL context everytime the window is resized. This was fixed in SDL 1.3 but pygame is not yet available on it by default.
- when Android releases the app resources: when your application goes to the background, Android might reclaim your opengl context to give the resource to another app. When the user switches back to your application, a newly created gl context is given to your app.

Starting from 1.2.0, we have introduced a mechanism for reloading all the graphics resources using the GPU: Canvas, FBO, Shader, Texture, VBO, and VertexBatch:

- VBO and VertexBatch are constructed by our graphics instructions. We have all the data needed to reconstruct when reloading.
- Shader: same as VBO, we store the source and values used in the shader so we are able to recreate the vertex/fragment/program.
- Texture: if the texture has a source (an image file or atlas), the image is reloaded from the source and reuploaded to the GPU.

You should cover these cases yourself:

- Textures without a source: if you manually created a texture and manually blit data / a buffer to it, you must handle the reloading yourself. Check the [Texture](#) to learn how to manage that case. (The text rendering already generates the texture and handles the reloading. You don't need to reload text yourself.)
- FBO: if you added / removed / drew things multiple times on the FBO, we can't reload it. We don't keep a history of the instructions put on it. As for textures without a source, check the [Framebuffer](#) to learn how to manage that case.

```
class kivy.graphics.ApplyContextMatrix(**kwargs)
Bases: kivy.graphics.instructions.ContextInstruction
target_stack by the matrix at the top of the 'source_stack'
```

New in version 1.6.0.

source_stack

Name of the matrix stack to use as a source. Can be 'modelview_mat', 'projection_mat' or 'frag_modelview_mat'.

New in version 1.6.0.

target_stack

Name of the matrix stack to use as a target. Can be 'modelview_mat', 'projection_mat' or 'frag_modelview_mat'.

New in version 1.6.0.

```
class kivy.graphics.Bezier(**kwargs)
Bases: kivy.graphics.instructions.VertexInstruction
```

New in version 1.0.8.

Parameters

points: list List of points in the format (x1, y1, x2, y2...)

segments: int, defaults to 180 Define how many segments are needed for drawing the curve. The drawing will be smoother if you have many segments.

loop: bool, defaults to False Set the bezier curve to join the last point to the first.

dash_length: int Length of a segment (if dashed), defaults to 1.

dash_offset: int Distance between the end of a segment and the start of the next one, defaults to 0. Changing this makes it dashed.

dash_length

Property for getting/setting the length of the dashes in the curve.

dash_offset

Property for getting/setting the offset between the dashes in the curve.

points

Property for getting/settings the points of the triangle.

Warning: This will always reconstruct the whole graphic from the new points list. It can be very CPU intensive.

segments

Property for getting/setting the number of segments of the curve.

class kivy.graphics.BindTexture(kwargs)**

Bases: *kivy.graphics.instructions.ContextInstruction*

The BindTexture Instruction will bind a texture and enable GL_TEXTURE_2D for subsequent drawing.

Parameters

texture: Texture Specifies the texture to bind to the given index.

source

Set/get the source (filename) to load for the texture.

class kivy.graphics.BorderImage(kwargs)**

Bases: *kivy.graphics.vertex_instructions.Rectangle*

concept of a CSS3 border-image.

Parameters

border: list Border information in the format (bottom, right, top, left). Each value is in pixels.

auto_scale: string New in version 1.9.1.

Changed in version 1.9.2: This used to be a bool and has been changed to be a string state.

Can be one of ‘off’, ‘both’, ‘x_only’, ‘y_only’, ‘y_full_x_lower’, ‘x_full_y_lower’, ‘both_lower’.

Autoscale controls the behavior of the 9-slice.

By default the border values are preserved exactly, meaning that if the total size of the object is smaller than the border values you will have some ‘rendering errors’ where your texture appears inside out. This also makes it impossible to achieve a rounded button that scales larger than the size of its source texture. The various options for auto_scale will let you achieve some mixes of the 2 types of rendering.

'off': is the default and behaves as BorderImage did when auto_scale was False before.

'both': Scales both x and y dimension borders according to the size of the BorderImage, this disables the BorderImage making it render the same as a regular Image.

'x_only': The Y dimension functions as the default, and the X scales to the size of the BorderImage's width.

'y_only': The X dimension functions as the default, and the Y scales to the size of the BorderImage's height.

'y_full_x_lower': Y scales as in 'y_only', Y scales if the size of the scaled version would be smaller than the provided border only.

'x_full_y_lower': X scales as in 'x_only', Y scales if the size of the scaled version would be smaller than the provided border only.

'both_lower': This is what auto_scale did when it was True in 1.9.1 Both X and Y dimensions will be scaled if the BorderImage is smaller than the source.

If the BorderImage's size is less than the sum of its borders, horizontally or vertically, and this property is set to True, the borders will be rescaled to accommodate for the smaller size.

auto_scale

Property for setting if the corners are automatically scaled when the BorderImage is too small.

border

Property for getting/setting the border of the class.

display_border

Property for getting/setting the border display size.

class kivy.graphics.Callback(*callback=None, **kwargs*)
Bases: *kivy.graphics.instructions.Instruction*

A Callback is an instruction that will be called when the drawing operation is performed. When adding instructions to a canvas, you can do this:

```
with self.canvas:  
    Color(1, 1, 1)  
    Rectangle(pos=self.pos, size=self.size)  
    Callback(self.my_callback)
```

The definition of the callback must be:

```
def my_callback(self, instr):  
    print('I have been called!')
```

Warning: Note that if you perform many and/or costly calls to callbacks, you might potentially slow down the rendering performance significantly.

The updating of your canvas does not occur until something new happens. From your callback, you can ask for an update:

```
with self.canvas:
    self.cb = Callback(self.my_callback)
# then later in the code
self.cb.ask_update()
```

If you use the `Callback` class to call rendering methods of another toolkit, you will have issues with the OpenGL context. The OpenGL state may have been manipulated by the other toolkit, and as soon as program flow returns to Kivy, it will just break. You can have glitches, crashes, black holes might occur, etc. To avoid that, you can activate the `reset_context` option. It will reset the OpenGL context state to make Kivy's rendering correct after the call to your callback.

Warning: The `reset_context` is not a full OpenGL reset. If you have issues regarding that, please contact us.

`ask_update()`

Inform the parent canvas that we'd like it to update on the next frame. This is useful when you need to trigger a redraw due to some value having changed for example.

New in version 1.0.4.

`callback`

Property for getting/setting func.

`reset_context`

Set this to True if you want to reset the OpenGL context for Kivy after the callback has been called.

`class kivy.graphics.Canvas(**kwargs)`

Bases: `kivy.graphics.instructions.CanvasBase`

instructions that you want to be used for drawing.

Note: The Canvas supports Python's `with` statement and its enter & exit semantics.

Usage of a canvas without the `with` statement:

```
self.canvas.add(Color(1., 1., 0))
self.canvas.add(Rectangle(size=(50, 50)))
```

Usage of a canvas with Python's `with` statement:

```
with self.canvas:
    Color(1., 1., 0)
    Rectangle(size=(50, 50))
```

`add(Instruction c)`

`after`

Property for getting the 'after' group.

`ask_update()`

Inform the canvas that we'd like it to update on the next frame. This is useful when you need to trigger a redraw due to some value having changed for example.

`before`

Property for getting the 'before' group.

clear()
Clears every *Instruction* in the canvas, leaving it clean.

draw()
Apply the instruction to our window.

has_after
Property to see if the *after* group has already been created.

New in version 1.7.0.

has_before
Property to see if the *before* group has already been created.

New in version 1.7.0.

opacity
Property to get/set the opacity value of the canvas.

New in version 1.4.1.

The opacity attribute controls the opacity of the canvas and its children. Be careful, it's a cumulative attribute: the value is multiplied to the current global opacity and the result is applied to the current context color.

For example: if your parent has an opacity of 0.5 and a child has an opacity of 0.2, the real opacity of the child will be $0.5 * 0.2 = 0.1$.

Then, the opacity is applied on the shader as:

```
frag_color = color * vec4(1.0, 1.0, 1.0, opacity);
```

remove(*Instruction c*)

class kivy.graphics.CanvasBase
Bases: *kivy.graphics.instructions.InstructionGroup*
CanvasBase provides the context manager methods for the *Canvas*.

class kivy.graphics.ChangeState(kwargs)**
Bases: *kivy.graphics.instructions.ContextInstruction*
current render context.
New in version 1.6.0.

class kivy.graphics.ClearBuffers(*args, **kwargs)
Bases: *kivy.graphics.instructions.Instruction*
New in version 1.3.0.

Clear the buffers specified by the instructions buffer mask property. By default, only the coloc buffer is cleared.

clear_color
If True, the color buffer will be cleared.

clear_depth
If True, the depth buffer will be cleared.

clear_stencil
If True, the stencil buffer will be cleared.

class kivy.graphics.ClearColor(r, g, b, a, **kwargs)
Bases: *kivy.graphics.instructions.Instruction*
New in version 1.3.0.

Sets the clear color used to clear buffers with the glClear function or [ClearBuffers](#) graphics instructions.

a

Alpha component, between 0 and 1.

b

Blue component, between 0 and 1.

g

Green component, between 0 and 1.

r

Red component, between 0 and 1.

rgb

RGB color, a list of 3 values in 0-1 range where alpha will be 1.

rgba

RGBA color used for the clear color, a list of 4 values in the 0-1 range.

```
class kivy.graphics.Color(*args, **kwargs)
Bases: kivy.graphics.instructions.ContextInstruction
```

drawn after it.

This represents a color between 0 and 1, but is applied as a *multiplier* to the texture of any vertex instructions following it in a canvas. If no texture is set, the vertex instruction takes the precise color of the Color instruction.

For instance, if a Rectangle has a texture with uniform color `(0.5, 0.5, 0.5, 1.0)` and the preceding Color has `rgba=(1, 0.5, 2, 1)`, the actual visible color will be `(0.5, 0.25, 1.0, 1.0)` since the Color instruction is applied as a multiplier to every rgba component. In this case, a Color component outside the 0-1 range gives a visible result as the intensity of the blue component is doubled.

To declare a Color in Python, you can do:

```
from kivy.graphics import Color

# create red v
c = Color(1, 0, 0)
# create blue color
c = Color(0, 1, 0)
# create blue color with 50% alpha
c = Color(0, 1, 0, .5)

# using hsv mode
c = Color(0, 1, 1, mode='hsv')
# using hsv mode + alpha
c = Color(0, 1, 1, .2, mode='hsv')
```

You can also set color components that are available as properties by passing them as keyword arguments:

```
c = Color(b=0.5) # sets the blue component only
```

In kv lang you can set the color properties directly:

```
<Rule>:
    canvas:
```

(continues on next page)

```

# red color
Color:
    rgb: 1, 0, 0
# blue color
Color:
    rgb: 0, 1, 0
# blue color with 50% alpha
Color:
    rgba: 0, 1, 0, .5

# using hsv mode
Color:
    hsv: 0, 1, 1
# using hsv mode + alpha
Color:
    hsv: 0, 1, 1
    a: .5

```

a

Alpha component, between 0 and 1.

b

Blue component, between 0 and 1.

g

Green component, between 0 and 1.

h

Hue component, between 0 and 1.

hsv

HSV color, list of 3 values in 0-1 range, alpha will be 1.

r

Red component, between 0 and 1.

rgb

RGB color, list of 3 values in 0-1 range. The alpha will be 1.

rgba

RGBA color, list of 4 values in 0-1 range.

s

Saturation component, between 0 and 1.

v

Value component, between 0 and 1.

class kivy.graphics.ContextInstruction(kwargs)**
 Bases: *kivy.graphics.instructions.Instruction*

that don't have a direct visual representation, but instead modify the current Canvas' state, e.g. texture binding, setting color parameters, matrix manipulation and so on.

class kivy.graphics.Ellipse(*args, **kwargs)
 Bases: *kivy.graphics.vertex_instructions.Rectangle*

Changed in version 1.0.7: Added angle_start and angle_end.

Parameters

segments: int, defaults to 180 Define how many segments are needed for drawing the ellipse. The drawing will be smoother if you have many segments.

angle_start: int, defaults to 0 Specifies the starting angle, in degrees, of the disk portion.

angle_end: int, defaults to 360 Specifies the ending angle, in degrees, of the disk portion.

angle_end

End angle of the ellipse in degrees, defaults to 360.

angle_start

Start angle of the ellipse in degrees, defaults to 0.

segments

Property for getting/setting the number of segments of the ellipse.

class kivy.graphics.Fbo(*args, **kwargs)

Bases: *kivy.graphics.instructions.RenderContext*

“with” statement.

Parameters

clear_color: tuple, defaults to (0, 0, 0, 0) Define the default color for clearing the framebuffer

size: tuple, defaults to (1024, 1024) Default size of the framebuffer

push_viewport: bool, defaults to True If True, the OpenGL viewport will be set to the framebuffer size, and will be automatically restored when the framebuffer released.

with_depthbuffer: bool, defaults to False If True, the framebuffer will be allocated with a Z buffer.

with_stencilbuffer: bool, defaults to False New in version 1.9.0.

If True, the framebuffer will be allocated with a stencil buffer.

texture: Texture, defaults to None If None, a default texture will be created.

Note: Using both of `with_stencilbuffer` and `with_depthbuffer` is not supported in kivy 1.9.0

add_reload_observer(callback)

Add a callback to be called after the whole graphics context has been reloaded. This is where you can reupload your custom data in GPU.

New in version 1.2.0.

Parameters

callback: func(context) -> return None The first parameter will be the context itself

bind()

Bind the FBO to the current opengl context. *Bind* mean that you enable the Framebuffer, and all the drawing operations will act inside the Framebuffer, until `release()` is called.

The bind/release operations are automatically called when you add graphics objects into it. If you want to manipulate a Framebuffer yourself, you can use it like this:

```

self.fbo = FBO()
self.fbo.bind()
# do any drawing command
self.fbo.release()

# then, your fbo texture is available at
print(self.fbo.texture)

```

clear_buffer()

Clear the framebuffer with the [clear_color](#).

You need to bind the framebuffer yourself before calling this method:

```

fbo.bind()
fbo.clear_buffer()
fbo.release()

```

clear_color

Clear color in (red, green, blue, alpha) format.

get_pixel_color(int wx, int wy)

Get the color of the pixel with specified window coordinates wx, wy. It returns result in RGBA format.

New in version 1.8.0.

pixels

Get the pixels texture, in RGBA format only, unsigned byte. The origin of the image is at bottom left.

New in version 1.7.0.

release()

Release the Framebuffer (unbind).

remove_reload_observer(callback)

Remove a callback from the observer list, previously added by [add_reload_observer\(\)](#).

New in version 1.2.0.

size

Size of the framebuffer, in (width, height) format.

If you change the size, the framebuffer content will be lost.

texture

Return the framebuffer texture

exception kivy.graphics.GraphicException

Bases: [Exception](#)

Exception raised when a graphics error is fired.

class kivy.graphics.Instruction(kwargs)**

Bases: [kivy.event.ObjectWithUid](#)

usage only, don't use it directly.

flag_data_update()

flag_update(int do_parent=1)

group

group: unicode

proxy_ref

Return a proxy reference to the Instruction i.e. without creating a reference of the widget.
See [weakref.proxy](#) for more information.

New in version 1.7.2.

class `kivy.graphics.InstructionGroup(**kwargs)`
Bases: [kivy.graphics.instructions.Instruction](#)

of graphics instructions. It can be used directly as follows:

```
blue = InstructionGroup() blue.add(Color(0, 0, 1, 0.2)) blue.add(Rectangle(pos=self.pos, size=(100, 100)))
```

```
green = InstructionGroup() green.add(Color(0, 1, 0, 0.4)) green.add(Rectangle(pos=(100, 100), size=(100, 100)))
```

Here, self should be a Widget or subclass [self.canvas.add(group) for group in [blue, green]]

add(*Instruction c*)

Add a new [Instruction](#) to our list.

children

children: list

clear()

Remove all the [Instructions](#).

get_group(*unicode groupname*)

Return an iterable for all the [Instructions](#) with a specific group name.

indexof(*Instruction c*)

insert(*int index, Instruction c*)

Insert a new [Instruction](#) into our list at index.

length()

remove(*Instruction c*)

Remove an existing [Instruction](#) from our list.

remove_group(*unicode groupname*)

Remove all [Instructions](#) with a specific group name.

class `kivy.graphics.Line(**kwargs)`


Bases: [kivy.graphics.instructions.VertexInstruction](#)

Drawing a line can be done easily:

```
with self.canvas:  
    Line(points=[100, 100, 200, 100, 100, 200], width=10)
```

The line has 3 internal drawing modes that you should be aware of for optimal results:

1. If the *width* is 1.0, then the standard GL_LINE drawing from OpenGL will be used. *dash_length*, *dash_offset*, and *dashes* will work, while properties for cap and joint have no meaning here.
2. If the *width* is greater than 1.0, then a custom drawing method, based on triangulation, will be used. *dash_length*, *dash_offset*, and *dashes* do not work in this mode. Additionally, if the current color has an alpha less than 1.0, a stencil will be used internally to draw the line.



Parameters

points: list List of points in the format (x1, y1, x2, y2...)

dash_length: int Length of a segment (if dashed), defaults to 1.

dash_offset: int Offset between the end of a segment and the beginning of the next one, defaults to 0. Changing this makes it dashed.

dashes: list of ints List of [ON length, offset, ON length, offset, ...]. E.g. [2, 4, 1, 6, 8, 2] would create a line with the first dash length 2 then an offset of 4 then a dash length of 1 then an offset of 6 and so on. Defaults to []. Changing this makes it dashed and overrides *dash_length* and *dash_offset*.

width: float Width of the line, defaults to 1.0.

cap: str, defaults to 'round' See [cap](#) for more information.

joint: str, defaults to 'round' See [joint](#) for more information.

cap_precision: int, defaults to 10 See [cap_precision](#) for more information

joint_precision: int, defaults to 10 See [joint_precision](#) for more information
See [cap_precision](#) for more information.

joint_precision: int, defaults to 10 See [joint_precision](#) for more information.

close: bool, defaults to False If True, the line will be closed.

circle: list If set, the *points* will be set to build a circle. See [circle](#) for more information.

ellipse: list If set, the *points* will be set to build an ellipse. See [ellipse](#) for more information.

rectangle: list If set, the *points* will be set to build a rectangle. See [rectangle](#) for more information.

bezier: list If set, the *points* will be set to build a bezier line. See [bezier](#) for more information.

bezier_precision: int, defaults to 180 Precision of the Bezier drawing.

Changed in version 1.0.8: *dash_offset* and *dash_length* have been added.

Changed in version 1.4.1: *width*, *cap*, *joint*, *cap_precision*, *joint_precision*, *close*, *ellipse*, *rectangle* have been added.

Changed in version 1.4.1: *bezier*, *bezier_precision* have been added.

Changed in version 1.11.0: *dashes* have been added

bezier

Use this property to build a bezier line, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of 2n elements, n being the number of points.

Usage:

```
Line(bezier=(x1, y1, x2, y2, x3, y3))
```

New in version 1.4.2.

Note: Bezier lines calculations are inexpensive for a low number of points, but complexity is quadratic, so lines with a lot of points can be very expensive to build, use with care!

bezier_precision

Number of iteration for drawing the bezier between 2 segments, defaults to 180. The *bezier_precision* must be at least 1.

New in version 1.4.2.

cap

Determine the cap of the line, defaults to ‘round’. Can be one of ‘none’, ‘square’ or ‘round’

New in version 1.4.1.

cap_precision

Number of iteration for drawing the “round” cap, defaults to 10. The *cap_precision* must be at least 1.

New in version 1.4.1.

circle

Use this property to build a circle, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (center_x, center_y, radius, angle_start, angle_end, segments):

- *center_x* and *center_y* represent the center of the circle
- *radius* represent the radius of the circle

- (optional) angle_start and angle_end are in degree. The default value is 0 and 360.
- (optional) segments is the precision of the ellipse. The default value is calculated from the range between angle.

Note that it's up to you to *close* the circle or not.

For example, for building a simple ellipse, in python:

```
# simple circle
Line(circle=(150, 150, 50))

# only from 90 to 180 degrees
Line(circle=(150, 150, 50, 90, 180))

# only from 90 to 180 degrees, with few segments
Line(circle=(150, 150, 50, 90, 180, 20))
```

New in version 1.4.1.

close

If True, the line will be closed.

New in version 1.4.1.

dash_length

Property for getting/setting the length of the dashes in the curve

New in version 1.0.8.

dash_offset

Property for getting/setting the offset between the dashes in the curve

New in version 1.0.8.

dashes

Property for getting/setting dashes.

List of [ON length, offset, ON length, offset, ...]. E.g. [2,4,1,6,8,2] would create a line with the first dash length 2 then an offset of 4 then a dash length of 1 then an offset of 6 and so on.

New in version 1.11.0.

ellipse

Use this property to build an ellipse, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (x, y, width, height, angle_start, angle_end, segments):

- x and y represent the bottom left of the ellipse
- width and height represent the size of the ellipse
- (optional) angle_start and angle_end are in degree. The default value is 0 and 360.
- (optional) segments is the precision of the ellipse. The default value is calculated from the range between angle.

Note that it's up to you to *close* the ellipse or not.

For example, for building a simple ellipse, in python:

```
# simple ellipse
Line(ellipse=(0, 0, 150, 150))
```

(continues on next page)

```
# only from 90 to 180 degrees
Line(ellipse=(0, 0, 150, 150, 90, 180))

# only from 90 to 180 degrees, with few segments
Line(ellipse=(0, 0, 150, 150, 90, 180, 20))
```

New in version 1.4.1.

joint

Determine the join of the line, defaults to ‘round’. Can be one of ‘none’, ‘round’, ‘bevel’, ‘miter’.

New in version 1.4.1.

joint_precision

Number of iteration for drawing the “round” joint, defaults to 10. The joint_precision must be at least 1.

New in version 1.4.1.

points

Property for getting/settings points of the line

Warning: This will always reconstruct the whole graphics from the new points list. It can be very CPU expensive.

rectangle

Use this property to build a rectangle, without calculating the **points**. You can only set this property, not get it.

The argument must be a tuple of (x, y, width, height):

- x and y represent the bottom-left position of the rectangle
- width and height represent the size

The line is automatically closed.

Usage:

```
Line(rectangle=(0, 0, 200, 200))
```

New in version 1.4.1.

rounded_rectangle

Use this property to build a rectangle, without calculating the **points**. You can only set this property, not get it.

The argument must be a tuple of one of the following forms:

- (x, y, width, height, corner_radius)
- (x, y, width, height, corner_radius, resolution)
- (x, y, width, height, corner_radius1, corner_radius2, corner_radius3, corner_radius4)
- (x, y, width, height, corner_radius1, corner_radius2, corner_radius3, corner_radius4, resolution)
- x and y represent the bottom-left position of the rectangle

- width and height represent the size
- corner_radius is the number of pixels between two borders and the center of the circle arc joining them
- resolution is the number of line segment that will be used to draw the circle arc at each corner (defaults to 30)

The line is automatically closed.

Usage:

```
Line(rounded_rectangle=(0, 0, 200, 200, 10, 20, 30, 40, 100))
```

New in version 1.9.0.

width

Determine the width of the line, defaults to 1.0.

New in version 1.4.1.

class kivy.graphics.LoadIdentity(**kwargs)

Bases: *kivy.graphics.instructions.ContextInstruction*

the instructions stack property (default='modelview_mat')

New in version 1.6.0.

stack

Name of the matrix stack to use. Can be 'modelview_mat', 'projection_mat' or 'frag_modelview_mat'.

class kivy.graphics.MatrixInstruction(*args, **kwargs)

Bases: *kivy.graphics.instructions.ContextInstruction*

matrix

Matrix property. Matrix from the transformation module. Setting the matrix using this property when a change is made is important because it will notify the context about the update.

stack

Name of the matrix stack to use. Can be 'modelview_mat', 'projection_mat' or 'frag_modelview_mat'.

New in version 1.6.0.

class kivy.graphics.Mesh(**kwargs)

Bases: *kivy.graphics.instructions.VertexInstruction*

In OpenGL ES 2.0 and in our graphics implementation, you cannot have more than 65535 indices.

A list of vertices is described as:

```
vertices = [x1, y1, u1, v1, x2, y2, u2, v2, ...]
           |   |   |   |
           +---+---+---+---+
```

If you want to draw a triangle, add 3 vertices. You can then make an indices list as follows:

```
indices = [0, 1, 2]
```

New in version 1.1.0.

Parameters

vertices: iterable List of vertices in the format (x1, y1, u1, v1, x2, y2, u2, v2...).

indices: iterable List of indices in the format (i1, i2, i3...).

mode: str Mode of the vbo. Check [mode](#) for more information. Defaults to ‘points’.

fmt: list The format for vertices, by default, each vertex is described by 2D coordinates (x, y) and 2D texture coordinate (u, v). Each element of the list should be a tuple or list, of the form

(variable_name, size, type)

which will allow mapping vertex data to the glsl instructions.

[('v_pos', 2, 'float'), ('v_tc', 2, 'float')]

will allow using

attribute vec2 v_pos; attribute vec2 v_tc;

in glsl’s vertex shader.

Changed in version 1.8.1: Before, *vertices* and *indices* would always be converted to a list, now, they are only converted to a list if they do not implement the buffer interface. So e.g. numpy arrays, python arrays etc. are used in place, without creating any additional copies. However, the buffers cannot be readonly (even though they are not changed, due to a cython limitation) and must be contiguous in memory.

Note: When passing a memoryview or a instance that implements the buffer interface, *vertices* should be a buffer of floats ('f' code in python array) and *indices* should be a buffer of unsigned short ('H' code in python array). Arrays in other formats will still have to be converted internally, negating any potential gain.

indices

Vertex indices used to specify the order when drawing the mesh.

mode

VBO Mode used for drawing vertices/indices. Can be one of ‘points’, ‘line_strip’, ‘line_loop’, ‘lines’, ‘triangles’, ‘triangle_strip’ or ‘triangle_fan’.

vertices

List of x, y, u, v coordinates used to construct the Mesh. Right now, the Mesh instruction doesn’t allow you to change the format of the vertices, which means it’s only x, y + one texture coordinate.

class kivy.graphics.Point(**kwargs)
Bases: [kivy.graphics.instructions.VertexInstruction](#)

width/height of 2 times the [pointsize](#).

Parameters

points: list List of points in the format (x1, y1, x2, y2...), where each pair of coordinates specifies the center of a new point.

pointsize: float, defaults to 1. The size of the point, measured from the center to the edge. A value of 1.0 therefore means the real size will be 2.0 x 2.0.

Warning: Starting from version 1.0.7, vertex instruction have a limit of 65535 vertices (indices of vertex to be accurate). 2 entries in the list (x, y) will be converted to 4 vertices. So the limit inside Point() class is $2^{15}-2$.

add_point(float x, float y)

Add a point to the current [points](#) list.

If you intend to add multiple points, prefer to use this method instead of reassigning a new `points` list. Assigning a new `points` list will recalculate and reupload the whole buffer into the GPU. If you use `add_point`, it will only upload the changes.

points

Property for getting/settings the center points in the points list. Each pair of coordinates specifies the center of a new point.

pointsize

Property for getting/setting point size. The size is measured from the center to the edge, so a value of 1.0 means the real size will be 2.0 x 2.0.

```
class kivy.graphics.PopMatrix(*args, **kwargs)
    Bases: kivy.graphics.instructions.ContextInstruction
```

stack

Name of the matrix stack to use. Can be 'modelview_mat', 'projection_mat' or 'frag_modelview_mat'.

New in version 1.6.0.

```
class kivy.graphics.PopState(*args, **kwargs)
    Bases: kivy.graphics.instructions.ContextInstruction
```

state stack.

New in version 1.6.0.

```
class kivy.graphics.PushMatrix(*args, **kwargs)
    Bases: kivy.graphics.instructions.ContextInstruction
```

stack

Name of the matrix stack to use. Can be 'modelview_mat', 'projection_mat' or 'frag_modelview_mat'.

New in version 1.6.0.

```
class kivy.graphics.PushState(*args, **kwargs)
    Bases: kivy.graphics.instructions.ContextInstruction
```

state stack.

New in version 1.6.0.

```
class kivy.graphics.Quad(**kwargs)
    Bases: kivy.graphics.instructions.VertexInstruction
```

Parameters

`points: list` List of point in the format (x1, y1, x2, y2, x3, y3, x4, y4).

points

Property for getting/settings points of the quad.

```
class kivy.graphics.Rectangle(**kwargs)
    Bases: kivy.graphics.instructions.VertexInstruction
```

Parameters

`pos: list` Position of the rectangle, in the format (x, y).

`size: list` Size of the rectangle, in the format (width, height).

pos

Property for getting/settings the position of the rectangle.

size

Property for getting/settings the size of the rectangle.

```
class kivy.graphics.RenderContext(*args, **kwargs)
Bases: kivy.graphics.instructions.Canvas
```

- The vertex shader
- The fragment shader
- The default texture
- The state stack (color, texture, matrix...)

shader

Return the shader attached to the render context.

use_parent_frag_modelview

If True, the parent fragment modelview matrix will be used.

New in version 1.10.1: `rc = RenderContext(use_parent_frag_modelview=True)`

use_parent_modelview

If True, the parent modelview matrix will be used.

New in version 1.7.0.

Before:

```
rc['modelview_mat'] = Window.render_context['modelview_mat']
```

Now:

```
rc = RenderContext(use_parent_modelview=True)
```

use_parent_projection

If True, the parent projection matrix will be used.

New in version 1.7.0.

Before:

```
rc['projection_mat'] = Window.render_context['projection_mat']
```

Now:

```
rc = RenderContext(use_parent_projection=True)
```

```
class kivy.graphics.Rotate(*args, **kwargs)
```

Bases: *kivy.graphics.context_instructions.Transform*

on the modelview matrix. You can set the properties of the instructions afterwards with e.g.

```
rot.angle = 90
rot.axis = (0, 0, 1)
```

angle

Property for getting/setting the angle of the rotation.

axis

Property for getting/setting the axis of the rotation.

The format of the axis is (x, y, z).

origin

Origin of the rotation.

New in version 1.7.0.

The format of the origin can be either (x, y) or (x, y, z).

set(*float angle, float ax, float ay, float az*)
Set the angle and axis of rotation.

```
>>> rotationobject.set(90, 0, 0, 1)
```

Deprecated since version 1.7.0: The set() method doesn't use the new *origin* property.

class kivy.graphics.Scale(*args, **kwargs)
Bases: kivy.graphics.context_instructions.Transform

Create using one or three arguments:

```
Scale(s)      # scale all three axes the same  
Scale(x, y, z)  # scale the axes independently
```

Deprecated since version 1.6.0: Deprecated single scale property in favor of x, y, z, xyz axis independent scaled factors.

origin

Origin of the scale.

New in version 1.9.0.

The format of the origin can be either (x, y) or (x, y, z).

scale

Property for getting/setting the scale.

Deprecated since version 1.6.0: Deprecated in favor of per axis scale properties x,y,z, xyz, etc.

x

Property for getting/setting the scale on the X axis.

Changed in version 1.6.0.

xyz

3 tuple scale vector in 3D in x, y, and z axis.

Changed in version 1.6.0.

y

Property for getting/setting the scale on the Y axis.

Changed in version 1.6.0.

z

Property for getting/setting the scale on Z axis.

Changed in version 1.6.0.

class kivy.graphics.SmoothLine(**kwargs)
Bases: *kivy.graphics.vertex_instructions.Line*

results. It has few drawbacks:

- drawing a line with alpha will probably not have the intended result if the line crosses itself.
- *cap*, *joint* and *dash* properties are not supported.
- it uses a custom texture with a premultiplied alpha.
- lines under 1px in width are not supported: they will look the same.

Warning: This is an unfinished work, experimental, and subject to crashes.

New in version 1.9.0.

overdraw_width

Determine the overdraw width of the line, defaults to 1.2.

premultiplied_texture()

class kivy.graphics.StencilPop

Bases: *kivy.graphics.instructions.Instruction*

Pop the stencil stack. See the module documentation for more information.

class kivy.graphics.StencilPush

Bases: *kivy.graphics.instructions.Instruction*

Push the stencil stack. See the module documentation for more information.

class kivy.graphics.StencilUnUse

Bases: *kivy.graphics.instructions.Instruction*

Use current stencil buffer to unset the mask.

class kivy.graphics.StencilUse(kwargs)**

Bases: *kivy.graphics.instructions.Instruction*

more information.

func_op

Determine the stencil operation to use for glStencilFunc(). Can be one of ‘never’, ‘less’, ‘equal’, ‘lequal’, ‘greater’, ‘notequal’, ‘gequal’ or ‘always’.

By default, the operator is set to ‘equal’.

New in version 1.5.0.

class kivy.graphics.Translate(*args, **kwargs)

Bases: *kivy.graphics.context_instructions.Transform*

Construct by either:

```
Translate(x, y)      # translate in just the two axes
Translate(x, y, z)    # translate in all three axes
```

x

Property for getting/setting the translation on the X axis.

xy

2 tuple with translation vector in 2D for x and y axis.

xyz

3 tuple translation vector in 3D in x, y, and z axis.

y

Property for getting/setting the translation on the Y axis.

z

Property for getting/setting the translation on the Z axis.

class kivy.graphics.Triangle(kwargs)**

Bases: *kivy.graphics.instructions.VertexInstruction*

Parameters

points: list List of points in the format (x1, y1, x2, y2, x3, y3).

points

Property for getting/settings points of the triangle.

class kivy.graphics.UpdateNormalMatrix

Bases: *kivy.graphics.instructions.ContextInstruction*

Update the normal matrix ‘normal_mat’ based on the current modelview matrix. This will compute ‘normal_mat’ uniform as: *inverse(transpose(mat3(mvm)))*

New in version 1.6.0.

class kivy.graphics.VertexInstruction(**kwargs)

Bases: *kivy.graphics.instructions.Instruction*

that have a direct visual representation on the canvas, such as Rectangles, Triangles, Lines, Ellipse and so on.

source

This property represents the filename to load the texture from. If you want to use an image as source, do it like this:

```
with self.canvas:  
    Rectangle(source='mylogo.png', pos=self.pos, size=self.size)
```

Here's the equivalent in Kivy language:

```
<MyWidget>:  
    canvas:  
        Rectangle:  
            source: 'mylogo.png'  
            pos: self.pos  
            size: self.size
```

Note: The filename will be searched for using the *kivy.resources.resource_find()* function.

tex_coords

This property represents the texture coordinates used for drawing the vertex instruction. The value must be a list of 8 values.

A texture coordinate has a position (u, v), and a size (w, h). The size can be negative, and would represent the ‘flipped’ texture. By default, the tex_coords are:

```
[u, v, u + w, v, u + w, v + h, u, v + h]
```

You can pass your own texture coordinates if you want to achieve fancy effects.

Warning: The default values just mentioned can be negative. Depending on the image and label providers, the coordinates are flipped vertically because of the order in which the image is internally stored. Instead of flipping the image data, we are just flipping the texture coordinates to be faster.

texture

Property that represents the texture used for drawing this Instruction. You can set a new texture like this:

```

from kivy.core.image import Image

texture = Image('logo.png').texture
with self.canvas:
    Rectangle(texture=texture, pos=self.pos, size=self.size)

```

Usually, you will use the `source` attribute instead of the texture.

```
kivy.graphics.gl_init_resources()
```

37.3 Canvas

The `Canvas` is the root object used for drawing by a `Widget`. Check the class documentation for more information about the usage of Canvas.

```

class kivy.graphics.instructions.Callback(callback=None, **kwargs)
Bases: kivy.graphics.instructions.Instruction

```

A `Callback` is an instruction that will be called when the drawing operation is performed. When adding instructions to a canvas, you can do this:

```

with self.canvas:
    Color(1, 1, 1)
    Rectangle(pos=self.pos, size=self.size)
    Callback(self.my_callback)

```

The definition of the callback must be:

```

def my_callback(self, instr):
    print('I have been called!')

```

Warning: Note that if you perform many and/or costly calls to callbacks, you might potentially slow down the rendering performance significantly.

The updating of your canvas does not occur until something new happens. From your callback, you can ask for an update:

```

with self.canvas:
    self.cb = Callback(self.my_callback)
# then later in the code
self.cb.ask_update()

```

If you use the `Callback` class to call rendering methods of another toolkit, you will have issues with the OpenGL context. The OpenGL state may have been manipulated by the other toolkit, and as soon as program flow returns to Kivy, it will just break. You can have glitches, crashes, black holes might occur, etc. To avoid that, you can activate the `reset_context` option. It will reset the OpenGL context state to make Kivy's rendering correct after the call to your callback.

Warning: The `reset_context` is not a full OpenGL reset. If you have issues regarding that, please contact us.

ask_update()

Inform the parent canvas that we'd like it to update on the next frame. This is useful when you need to trigger a redraw due to some value having changed for example.

New in version 1.0.4.

callback

Property for getting/setting func.

reset_context

Set this to True if you want to reset the OpenGL context for Kivy after the callback has been called.

class kivy.graphics.instructions.Canvas(kwargs)**

Bases: *kivy.graphics.instructions.CanvasBase*

instructions that you want to be used for drawing.

Note: The Canvas supports Python's `with` statement and its enter & exit semantics.

Usage of a canvas without the `with` statement:

```
self.canvas.add(Color(1., 1., 0))
self.canvas.add(Rectangle(size=(50, 50)))
```

Usage of a canvas with Python's `with` statement:

```
with self.canvas:
    Color(1., 1., 0)
    Rectangle(size=(50, 50))
```

add(*Instruction c*)**after**

Property for getting the 'after' group.

ask_update()

Inform the canvas that we'd like it to update on the next frame. This is useful when you need to trigger a redraw due to some value having changed for example.

before

Property for getting the 'before' group.

clear()

Clears every *Instruction* in the canvas, leaving it clean.

draw()

Apply the instruction to our window.

has_after

Property to see if the `after` group has already been created.

New in version 1.7.0.

has_before

Property to see if the `before` group has already been created.

New in version 1.7.0.

opacity

Property to get/set the opacity value of the canvas.

New in version 1.4.1.

The opacity attribute controls the opacity of the canvas and its children. Be careful, it's a cumulative attribute: the value is multiplied to the current global opacity and the result is applied to the current context color.

For example: if your parent has an opacity of 0.5 and a child has an opacity of 0.2, the real opacity of the child will be $0.5 * 0.2 = 0.1$.

Then, the opacity is applied on the shader as:

```
frag_color = color * vec4(1.0, 1.0, 1.0, opacity);
```

```
remove(Instruction c)

class kivy.graphics.instructions.CanvasBase
    Bases: kivy.graphics.instructions.InstructionGroup
    CanvasBase provides the context manager methods for the Canvas.

class kivy.graphics.instructions.ContextInstruction(**kwargs)
    Bases: kivy.graphics.instructions.Instruction
    that don't have a direct visual representation, but instead modify the current Canvas' state, e.g. texture binding, setting color parameters, matrix manipulation and so on.

class kivy.graphics.instructions.Instruction(**kwargs)
    Bases: kivy.event.ObjectWithUid
    usage only, don't use it directly.

flag_data_update()
flag_update(int do_parent=1)

group
    group: unicode

proxy_ref
    Return a proxy reference to the Instruction i.e. without creating a reference of the widget.
    See weakref.proxy for more information.

    New in version 1.7.2.

class kivy.graphics.instructions.InstructionGroup(**kwargs)
    Bases: kivy.graphics.instructions.Instruction
    of graphics instructions. It can be used directly as follows:

    blue = InstructionGroup() blue.add(Color(0, 0, 1, 0.2)) blue.add(Rectangle(pos=self.pos, size=(100, 100)))

    green = InstructionGroup() green.add(Color(0, 1, 0, 0.4)) green.add(Rectangle(pos=(100, 100), size=(100, 100)))

    # Here, self should be a Widget or subclass [self.canvas.add(group) for group in [blue, green]]

add(Instruction c)
    Add a new Instruction to our list.

children
    children: list

clear()
    Remove all the Instructions.

get_group(unicode groupname)
    Return an iterable for all the Instructions with a specific group name.

indexof(Instruction c)
```

```
insert(int index, Instruction c)
    Insert a new Instruction into our list at index.

length()

remove(Instruction c)
    Remove an existing Instruction from our list.

remove_group(unicode groupname)
    Remove all Instructions with a specific group name.

class kivy.graphics.instructions.RenderContext(*args, **kwargs)
Bases: kivy.graphics.instructions.Canvas
```

- The vertex shader
- The fragment shader
- The default texture
- The state stack (color, texture, matrix...)

shader

Return the shader attached to the render context.

use_parent_frag_modelview

If True, the parent fragment modelview matrix will be used.

New in version 1.10.1: rc = RenderContext(use_parent_frag_modelview=True)

use_parent_modelview

If True, the parent modelview matrix will be used.

New in version 1.7.0.

Before:

```
rc['modelview_mat'] = Window.render_context['modelview_mat']
```

Now:

```
rc = RenderContext(use_parent_modelview=True)
```

use_parent_projection

If True, the parent projection matrix will be used.

New in version 1.7.0.

Before:

```
rc['projection_mat'] = Window.render_context['projection_mat']
```

Now:

```
rc = RenderContext(use_parent_projection=True)
```

```
class kivy.graphics.instructions.VertexInstruction(**kwargs)
Bases: kivy.graphics.instructions.Instruction
```

that have a direct visual representation on the canvas, such as Rectangles, Triangles, Lines, Ellipse and so on.

source

This property represents the filename to load the texture from. If you want to use an image as source, do it like this:

```
with self.canvas:  
    Rectangle(source='mylogo.png', pos=self.pos, size=self.size)
```

Here's the equivalent in Kivy language:

```
<MyWidget>:  
    canvas:  
        Rectangle:  
            source: 'mylogo.png'  
            pos: self.pos  
            size: self.size
```

Note: The filename will be searched for using the `kivy.resources.resource_find()` function.

tex_coords

This property represents the texture coordinates used for drawing the vertex instruction. The value must be a list of 8 values.

A texture coordinate has a position (u, v), and a size (w, h). The size can be negative, and would represent the 'flipped' texture. By default, the tex_coords are:

```
[u, v, u + w, v, u + w, v + h, u, v + h]
```

You can pass your own texture coordinates if you want to achieve fancy effects.

Warning: The default values just mentioned can be negative. Depending on the image and label providers, the coordinates are flipped vertically because of the order in which the image is internally stored. Instead of flipping the image data, we are just flipping the texture coordinates to be faster.

texture

Property that represents the texture used for drawing this Instruction. You can set a new texture like this:

```
from kivy.core.image import Image  
  
texture = Image('logo.png').texture  
with self.canvas:  
    Rectangle(texture=texture, pos=self.pos, size=self.size)
```

Usually, you will use the `source` attribute instead of the texture.

37.4 CGL: standard C interface for OpenGL

Kivy uses OpenGL and therefore requires a backend that provides it. The backend used is controlled through the `USE_OPENGL_MOCK` and `USE SDL2` compile-time variables and through the `KIVY_GL_BACKEND` runtime environmental variable.

Currently, OpenGL is used through direct linking (`gl/glew`), `sdl2`, or by mocking it. Setting `USE_OPENGL_MOCK` disables `gl/glew`. Similarly, setting `USE SDL2` to `0` will disable `sdl2`. Mocking is always available.

At runtime the following backends are available and can be set using `KIVY_GL_BACKEND`:

- `gl` – Available on unix (the default backend). Unavailable when `USE_OPENGL_MOCK=0`. Requires `gl` be installed.
- `glew` – Available on Windows (the default backend). Unavailable when `USE_OPENGL_MOCK=0`. Requires `glew` be installed.
- `sdl2` – Available on Windows/unix (the default when `gl/glew` is disabled). Unavailable when `USE SDL2=0`. Requires `kivy_deps.sdl2` be installed.
- `angle_sdl2` – Available on Windows with Python 3.5+. Unavailable when `USE SDL2=0`. Requires `kivy_deps.sdl2` and `kivy_deps.angle` be installed.
- `mock` – Always available. Doesn't actually do anything.

Additionally, the following environmental runtime variables control the graphics system:

- `KIVY_GL_DEBUG` – Logs all `gl` calls when 1.
- `KIVY_GRAPHICS` – Forces OpenGL ES2 when it is `gles`. OpenGL ES2 is always used on the android, ios, rpi, and mali OSs.

```
kivy.graphics.cgl.cgl_get_backend_name(allowed=[], ignored=[])
kivy.graphics.cgl.cgl_get_initialized_backend_name()
kivy.graphics.cgl.cgl_init(allowed=[], ignored=[])

```

37.5 Context instructions

The context instructions represent non graphics elements such as:

- Matrix manipulations (`PushMatrix`, `PopMatrix`, `Rotate`, `Translate`, `Scale`, `MatrixInstruction`)
- Color manipulations (`Color`)
- Texture bindings (`BindTexture`)

Changed in version 1.0.8: The `LineWidth` instruction has been removed. It wasn't working before and we actually have no working implementation. We need to do more experimentation to get it right. Check the bug [#207](#) for more information.

```
class kivy.graphics.context_instructions.BindTexture(**kwargs)
    Bases: kivy.graphics.instructions.ContextInstruction

```

The `BindTexture` Instruction will bind a texture and enable `GL_TEXTURE_2D` for subsequent drawing.

Parameters

`texture: Texture` Specifies the texture to bind to the given index.

source

Set/get the source (filename) to load for the texture.

```
class kivy.graphics.context_instructions.Color(*args, **kwargs)
Bases: kivy.graphics.instructions.ContextInstruction
```

drawn after it.

This represents a color between 0 and 1, but is applied as a *multiplier* to the texture of any vertex instructions following it in a canvas. If no texture is set, the vertex instruction takes the precise color of the Color instruction.

For instance, if a Rectangle has a texture with uniform color (0.5, 0.5, 0.5, 1.0) and the preceding Color has `rgba=(1, 0.5, 2, 1)`, the actual visible color will be (0.5, 0.25, 1.0, 1.0) since the Color instruction is applied as a multiplier to every rgba component. In this case, a Color component outside the 0-1 range gives a visible result as the intensity of the blue component is doubled.

To declare a Color in Python, you can do:

```
from kivy.graphics import Color

# create red v
c = Color(1, 0, 0)
# create blue color
c = Color(0, 1, 0)
# create blue color with 50% alpha
c = Color(0, 1, 0, .5)

# using hsv mode
c = Color(0, 1, 1, mode='hsv')
# using hsv mode + alpha
c = Color(0, 1, 1, .2, mode='hsv')
```

You can also set color components that are available as properties by passing them as keyword arguments:

```
c = Color(b=0.5) # sets the blue component only
```

In kv lang you can set the color properties directly:

```
<Rule>:
    canvas:
        # red color
        Color:
            rgb: 1, 0, 0
        # blue color
        Color:
            rgb: 0, 1, 0
        # blue color with 50% alpha
        Color:
            rgba: 0, 1, 0, .5

        # using hsv mode
        Color:
            hsv: 0, 1, 1
        # using hsv mode + alpha
        Color:
            hsv: 0, 1, 1
            a: .5
```

a
Alpha component, between 0 and 1.

b
Blue component, between 0 and 1.

g
Green component, between 0 and 1.

h
Hue component, between 0 and 1.

hsv
HSV color, list of 3 values in 0-1 range, alpha will be 1.

r
Red component, between 0 and 1.

rgb
RGB color, list of 3 values in 0-1 range. The alpha will be 1.

rgba
RGBA color, list of 4 values in 0-1 range.

s
Saturation component, between 0 and 1.

v
Value component, between 0 and 1.

class kivy.graphics.context_instructions.MatrixInstruction(*args, **kwargs)
Bases: *kivy.graphics.instructions.ContextInstruction*

matrix
Matrix property. Matrix from the transformation module. Setting the matrix using this property when a change is made is important because it will notify the context about the update.

stack
Name of the matrix stack to use. Can be ‘modelview_mat’, ‘projection_mat’ or ‘frag_modelview_mat’.
New in version 1.6.0.

class kivy.graphics.context_instructions.PopMatrix(*args, **kwargs)
Bases: *kivy.graphics.instructions.ContextInstruction*

stack
Name of the matrix stack to use. Can be ‘modelview_mat’, ‘projection_mat’ or ‘frag_modelview_mat’.
New in version 1.6.0.

class kivy.graphics.context_instructions.PushMatrix(*args, **kwargs)
Bases: *kivy.graphics.instructions.ContextInstruction*

stack
Name of the matrix stack to use. Can be ‘modelview_mat’, ‘projection_mat’ or ‘frag_modelview_mat’.
New in version 1.6.0.

class kivy.graphics.context_instructions.Rotate(*args, **kwargs)
Bases: *kivy.graphics.context_instructions.Transform*
on the modelview matrix. You can set the properties of the instructions afterwards with e.g.

```
rot.angle = 90
rot.axis = (0, 0, 1)
```

angle

Property for getting/setting the angle of the rotation.

axis

Property for getting/setting the axis of the rotation.

The format of the axis is (x, y, z).

origin

Origin of the rotation.

New in version 1.7.0.

The format of the origin can be either (x, y) or (x, y, z).

set(*float angle, float ax, float ay, float az*)

Set the angle and axis of rotation.

```
>>> rotationobject.set(90, 0, 0, 1)
```

Deprecated since version 1.7.0: The set() method doesn't use the new *origin* property.

class kivy.graphics.context_instructions.Scale(*args, **kwargs)

Bases: kivy.graphics.context_instructions.Transform

Create using one or three arguments:

```
Scale(s)      # scale all three axes the same
Scale(x, y, z) # scale the axes independently
```

Deprecated since version 1.6.0: Deprecated single scale property in favor of x, y, z, xyz axis independent scaled factors.

origin

Origin of the scale.

New in version 1.9.0.

The format of the origin can be either (x, y) or (x, y, z).

scale

Property for getting/setting the scale.

Deprecated since version 1.6.0: Deprecated in favor of per axis scale properties x,y,z, xyz, etc.

x

Property for getting/setting the scale on the X axis.

Changed in version 1.6.0.

xyz

3 tuple scale vector in 3D in x, y, and z axis.

Changed in version 1.6.0.

y

Property for getting/setting the scale on the Y axis.

Changed in version 1.6.0.

z

Property for getting/setting the scale on Z axis.

Changed in version 1.6.0.

```
class kivy.graphics.context_instructions.Translate(*args, **kwargs)
Bases: kivy.graphics.context_instructions.Transform
```

Construct by either:

<code>Translate(x, y)</code>	<i># translate in just the two axes</i>
<code>Translate(x, y, z)</code>	<i># translate in all three axes</i>

x

Property for getting/setting the translation on the X axis.

xy

2 tuple with translation vector in 2D for x and y axis.

xyz

3 tuple translation vector in 3D in x, y, and z axis.

y

Property for getting/setting the translation on the Y axis.

z

Property for getting/setting the translation on the Z axis.

```
kivy.graphics.context_instructions.gl_init_resources()
```

37.6 Context management

New in version 1.2.0.

This class manages a registry of all created graphics instructions. It has the ability to flush and delete them.

You can read more about Kivy graphics contexts in the [Graphics](#) module documentation. These are based on [OpenGL graphics contexts](#).

```
class kivy.graphics.context.Context
```

Bases: `builtins.object`

observer callbacks. See [`add_reload_observer\(\)`](#) and [`remove_reload_observer\(\)`](#) for more information.

`add_reload_observer(callback, before=False)`

(internal) Add a callback to be called after the whole graphics context has been reloaded.
This is where you can reupload your custom data into the GPU.

Parameters

`callback: func(context) -> return None` The first parameter will be the context itself

`before: boolean, defaults to False` If True, the callback will be executed before all the reloading processes. Use it if you want to clear your cache for example.

Changed in version 1.4.0: `before` parameter added.

`flag_update_canvas()`

`flush() → void`

`gl_dealloc(*largs)`

`reload()`

```

remove_reload_observer(callback, before=False)
    (internal) Remove a callback from the observer list previously added by
    add_reload_observer().
trigger_gl_dealloc()

```

37.7 Framebuffer

The Fbo is like an offscreen window. You can activate the fbo for rendering into a texture and use your fbo as a texture for other drawing.

The Fbo acts as a [kivy.graphics.instructions.Canvas](#).

Here is an example of using an fbo for some colored rectangles:

```

from kivy.graphics import Fbo, Color, Rectangle

class FboTest(Widget):
    def __init__(self, **kwargs):
        super(FboTest, self).__init__(**kwargs)

        # first step is to create the fbo and use the fbo texture on other
        # rectangle

        with self.canvas:
            # create the fbo
            self.fbo = Fbo(size=(256, 256))

            # show our fbo on the widget in different size
            Color(1, 1, 1)
            Rectangle(size=(32, 32), texture=self.fbo.texture)
            Rectangle(pos=(32, 0), size=(64, 64), texture=self.fbo.texture)
            Rectangle(pos=(96, 0), size=(128, 128), texture=self.fbo.
→texture)

            # in the second step, you can draw whatever you want on the fbo
            with self.fbo:
                Color(1, 0, 0, .8)
                Rectangle(size=(256, 64))
                Color(0, 1, 0, .8)
                Rectangle(size=(64, 256))

```

If you change anything in the `self.fbo` object, it will be automatically updated. The canvas where the fbo is put will be automatically updated as well.

37.7.1 Reloading the FBO content

New in version 1.2.0.

If the OpenGL context is lost, then the FBO is lost too. You need to reupload data on it yourself. Use the `Fbo.add_reload_observer()` to add a reloading function that will be automatically called when needed:

```
def __init__(self, **kwargs):
    super(...).__init__(**kwargs)
    self.fbo = Fbo(size=(512, 512))
    self.fbo.add_reload_observer(self.populate_fbo)

    # and load the data now.
    self.populate_fbo(self.fbo)

def populate_fbo(self, fbo):
    with fbo:
        # .. put your Color / Rectangle / ... here
```

This way, you could use the same method for initialization and for reloading. But it's up to you.

`class kivy.graphics.fbo.Fbo(*args, **kwargs)`
Bases: `kivy.graphics.instructions.RenderContext`
“with” statement.

Parameters

`clear_color: tuple, defaults to (0, 0, 0, 0)` Define the default color for clearing the framebuffer

`size: tuple, defaults to (1024, 1024)` Default size of the framebuffer

`push_viewport: bool, defaults to True` If True, the OpenGL viewport will be set to the framebuffer size, and will be automatically restored when the framebuffer released.

`with_depthbuffer: bool, defaults to False` If True, the framebuffer will be allocated with a Z buffer.

`with_stencilbuffer: bool, defaults to False` New in version 1.9.0.

If True, the framebuffer will be allocated with a stencil buffer.

`texture: Texture, defaults to None` If None, a default texture will be created.

Note: Using both of `with_stencilbuffer` and `with_depthbuffer` is not supported in kivy 1.9.0

`add_reload_observer(callback)`

Add a callback to be called after the whole graphics context has been reloaded. This is where you can reupload your custom data in GPU.

New in version 1.2.0.

Parameters

`callback: func(context) -> return None` The first parameter will be the context itself

bind()

Bind the FBO to the current opengl context. *Bind* mean that you enable the Framebuffer, and all the drawing operations will act inside the Framebuffer, until *release()* is called.

The bind/release operations are automatically called when you add graphics objects into it. If you want to manipulate a Framebuffer yourself, you can use it like this:

```
self.fbo = FBO()
self.fbo.bind()
# do any drawing command
self.fbo.release()

# then, your fbo texture is available at
print(self.fbo.texture)
```

clear_buffer()

Clear the framebuffer with the *clear_color*.

You need to bind the framebuffer yourself before calling this method:

```
fbo.bind()
fbo.clear_buffer()
fbo.release()
```

clear_color

Clear color in (red, green, blue, alpha) format.

get_pixel_color(*int wx, int wy*)

Get the color of the pixel with specified window coordinates *wx, wy*. It returns result in RGBA format.

New in version 1.8.0.

pixels

Get the pixels texture, in RGBA format only, unsigned byte. The origin of the image is at bottom left.

New in version 1.7.0.

release()

Release the Framebuffer (unbind).

remove_reload_observer(*callback*)

Remove a callback from the observer list, previously added by *add_reload_observer()*.

New in version 1.2.0.

size

Size of the framebuffer, in (width, height) format.

If you change the size, the framebuffer content will be lost.

texture

Return the framebuffer texture

37.8 GL instructions

New in version 1.3.0.

37.8.1 Clearing an FBO

To clear an FBO, you can use `ClearColor` and `ClearBuffers` instructions like this example:

```
self.fbo = Fbo(size=self.size)
with self.fbo:
    ClearColor(0, 0, 0, 0)
    ClearBuffers()
```

```
class kivy.graphics.gl_instructions.ClearBuffers(*args, **kwargs)
Bases: kivy.graphics.instructions.Instruction
```

New in version 1.3.0.

Clear the buffers specified by the instructions buffer mask property. By default, only the coloc buffer is cleared.

`clear_color`

If True, the color buffer will be cleared.

`clear_depth`

If True, the depth buffer will be cleared.

`clear_stencil`

If True, the stencil buffer will be cleared.

```
class kivy.graphics.gl_instructions.ClearColor(r, g, b, a, **kwargs)
Bases: kivy.graphics.instructions.Instruction
```

New in version 1.3.0.

Sets the clear color used to clear buffers with the glClear function or `ClearBuffers` graphics instructions.

`a`

Alpha component, between 0 and 1.

`b`

Blue component, between 0 and 1.

`g`

Green component, between 0 and 1.

`r`

Red component, between 0 and 1.

`rgb`

RGB color, a list of 3 values in 0-1 range where alpha will be 1.

`rgba`

RGBA color used for the clear color, a list of 4 values in the 0-1 range.

37.9 Graphics compiler

Before rendering an *InstructionGroup*, we compile the group in order to reduce the number of instructions executed at rendering time.

37.9.1 Reducing the context instructions

Imagine that you have a scheme like this:

```
Color(1, 1, 1)
Rectangle(source='button.png', pos=(0, 0), size=(20, 20))
Color(1, 1, 1)
Rectangle(source='button.png', pos=(10, 10), size=(20, 20))
Color(1, 1, 1)
Rectangle(source='button.png', pos=(10, 20), size=(20, 20))
```

The real instructions seen by the graphics canvas would be:

```
Color: change 'color' context to 1, 1, 1
BindTexture: change 'texture0' to `button.png texture`
Rectangle: push vertices (x1, y1...) to vbo & draw
Color: change 'color' context to 1, 1, 1
BindTexture: change 'texture0' to `button.png texture`
Rectangle: push vertices (x1, y1...) to vbo & draw
Color: change 'color' context to 1, 1, 1
BindTexture: change 'texture0' to `button.png texture`
Rectangle: push vertices (x1, y1...) to vbo & draw
```

Only the first *Color* and *BindTexture* are useful and really change the context. We can reduce them to:

```
Color: change 'color' context to 1, 1, 1
BindTexture: change 'texture0' to `button.png texture`
Rectangle: push vertices (x1, y1...) to vbo & draw
Rectangle: push vertices (x1, y1...) to vbo & draw
Rectangle: push vertices (x1, y1...) to vbo & draw
```

This is what the compiler does in the first place, by flagging all the unused instruction with `GI_IGNORE` flag. As soon as a Color content changes, the whole *InstructionGroup* will be recompiled and a previously unused Color might be used for the next compilation.

Note to any Kivy contributor / internal developer:

- All context instructions are checked to see if they change anything in the cache.
- We must ensure that a context instruction is needed for our current Canvas.
- We must ensure that we don't depend of any other canvas.
- We must reset our cache if one of our children is another instruction group because we don't know whether it might do weird things or not.

37.10 OpenGL

This module is a Python wrapper for OpenGL commands.

Warning: Not every OpenGL command has been wrapped and because we are using the C binding for higher performance, and you should rather stick to the Kivy Graphics API. By using OpenGL commands directly, you might change the OpenGL context and introduce inconsistency between the Kivy state and the OpenGL state.

`kivy.graphics.opengl.glActiveTexture(GLenum texture)`

See: [glActiveTexture\(\)](#) on Kronos website

`kivy.graphics.opengl.glAttachShader(GLuint program, GLuint shader)`

See: [glAttachShader\(\)](#) on Kronos website

`kivy.graphics.opengl glBindAttribLocation(GLuint program, GLuint index, bytes name)`

See: [glBindAttribLocation\(\)](#) on Kronos website

`kivy.graphics.opengl glBindBuffer(GLenum target, GLuint buffer)`

See: [glBindBuffer\(\)](#) on Kronos website

`kivy.graphics.opengl glBindFramebuffer(GLenum target, GLuint framebuffer)`

See: [glBindFramebuffer\(\)](#) on Kronos website

`kivy.graphics.opengl glBindRenderbuffer(GLenum target, GLuint renderbuffer)`

See: [glBindRenderbuffer\(\)](#) on Kronos website

`kivy.graphics.opengl glBindTexture(GLenum target, GLuint texture)`

See: [glBindTexture\(\)](#) on Kronos website

`kivy.graphics.opengl glBindColor(GLclampf red, GLclampf green, GLclampf blue, GLclampf alpha)`

See: [glBlendColor\(\)](#) on Kronos website

`kivy.graphics.opengl glBindEquation(GLenum mode)`

See: [glBlendEquation\(\)](#) on Kronos website

`kivy.graphics.opengl glBindEquationSeparate(GLenum modeRGB, GLenum modeAlpha)`

See: [glBlendEquationSeparate\(\)](#) on Kronos website

`kivy.graphics.opengl glBindFunc(GLenum sfactor, GLenum dfactor)`

See: [glBlendFunc\(\)](#) on Kronos website

`kivy.graphics.opengl glBindFuncSeparate(GLenum srcRGB, GLenum dstRGB, GLenum srcAlpha, GLenum dstAlpha)`

See: [glBlendFuncSeparate\(\)](#) on Kronos website

`kivy.graphics.opengl glBindBufferData(GLenum target, GLsizeiptr size, bytes data, GLenum usage)`

See: [glBufferData\(\)](#) on Kronos website

`kivy.graphics.opengl glBindBufferSubData(GLenum target, GLintptr offset, GLsizeiptr size, bytes data)`

See: [glBufferSubData\(\)](#) on Kronos website

`kivy.graphics.opengl glBindFramebufferStatus(GLenum target)`

See: [glCheckFramebufferStatus\(\)](#) on Kronos website

`kivy.graphics.opengl glBindClear(GLbitfield mask)`

See: [glClear\(\)](#) on Kronos website

`kivy.graphics.opengl.glClearColor(GLclampf red, GLclampf green, GLclampf blue, GLclampf alpha)`
See: [glClearColor\(\)](#) on Kronos website

`kivy.graphics.opengl.glClearStencil(GLint s)`
See: [glClearStencil\(\)](#) on Kronos website

`kivy.graphics.opengl.glColorMask(GLboolean red, GLboolean green, GLboolean blue, GLboolean alpha)`
See: [glColorMask\(\)](#) on Kronos website

`kivy.graphics.opengl.glCompileShader(GLuint shader)`
See: [glCompileShader\(\)](#) on Kronos website

`kivy.graphics.opengl.glCompressedTexImage2D(GLenum target, GLint level, GLenum internalformat, GLsizei width, GLsizei height, GLint border, GLsizei imageSize, bytes data)`
See: [glCompressedTexImage2D\(\)](#) on Kronos website

`kivy.graphics.opengl.glCompressedTexSubImage2D(GLenum target, GLint level, GLint xoffset, GLint yoffset, GLsizei width, GLsizei height, GLenum format, GLsizei imageSize, bytes data)`
See: [glCompressedTexSubImage2D\(\)](#) on Kronos website

`kivy.graphics.opengl.glCopyTexImage2D(GLenum target, GLint level, GLenum internalformat, GLint x, GLint y, GLsizei width, GLsizei height, GLint border)`
See: [glCopyTexImage2D\(\)](#) on Kronos website

`kivy.graphics.opengl.glCopyTexSubImage2D(GLenum target, GLint level, GLint xoffset, GLint yoffset, GLint x, GLint y, GLsizei width, GLsizei height)`
See: [glCopyTexSubImage2D\(\)](#) on Kronos website

`kivy.graphics.opengl.glCreateProgram()`
See: [glCreateProgram\(\)](#) on Kronos website

`kivy.graphics.opengl.glCreateShader(GLenum type)`
See: [glCreateShader\(\)](#) on Kronos website

`kivy.graphics.opengl.glCullFace(GLenum mode)`
See: [glCullFace\(\)](#) on Kronos website

`kivy.graphics.opengl.glDeleteBuffers(GLsizei n, bytes buffers)`
See: [glDeleteBuffers\(\)](#) on Kronos website

`kivy.graphics.opengl.glDeleteFramebuffers(GLsizei n, bytes framebuffers)`
See: [glDeleteFramebuffers\(\)](#) on Kronos website

`kivy.graphics.opengl.glDeleteProgram(GLuint program)`
See: [glDeleteProgram\(\)](#) on Kronos website

`kivy.graphics.opengl.glDeleteRenderbuffers(GLsizei n, bytes renderbuffers)`
See: [glDeleteRenderbuffers\(\)](#) on Kronos website

`kivy.graphics.opengl.glDeleteShader(GLuint shader)`
See: [glDeleteShader\(\)](#) on Kronos website

`kivy.graphics.opengl.glDeleteTextures(GLsizei n, bytes textures)`
See: [glDeleteTextures\(\)](#) on Kronos website

`kivy.graphics.opengl.glDepthFunc(GLenum func)`
See: [glDepthFunc\(\)](#) on Kronos website

`kivy.graphics.opengl.glDepthMask(GLboolean flag)`
See: [glDepthMask\(\)](#) on Kronos website

`kivy.graphics.opengl.glDetachShader(GLuint program, GLuint shader)`
See: [glDetachShader\(\)](#) on Kronos website

`kivy.graphics.opengl.glDisable(GLenum cap)`
See: [glDisable\(\)](#) on Kronos website

`kivy.graphics.opengl.glDisableVertexAttribArray(GLuint index)`
See: [glDisableVertexAttribArray\(\)](#) on Kronos website

`kivy.graphics.opengl.glDrawArrays(GLenum mode, GLint first, GLsizei count)`
See: [glDrawArrays\(\)](#) on Kronos website

`kivy.graphics.opengl.glDrawElements(GLenum mode, GLsizei count, GLenum type, indices)`
See: [glDrawElements\(\)](#) on Kronos website

`kivy.graphics.opengl glEnable(GLenum cap)`
See: [glEnable\(\)](#) on Kronos website

`kivy.graphics.opengl glEnableVertexAttribArray(GLuint index)`
See: [glEnableVertexAttribArray\(\)](#) on Kronos website

`kivy.graphics.opengl.glFinish()`
See: [glFinish\(\)](#) on Kronos website

`kivy.graphics.opengl.glFlush()`
See: [glFlush\(\)](#) on Kronos website

`kivy.graphics.opengl.glFramebufferRenderbuffer(GLenum target, GLenum attachment, GLenum renderbuffertarget, GLuint renderbuffer)`
See: [glFramebufferRenderbuffer\(\)](#) on Kronos website

`kivy.graphics.opengl.glFramebufferTexture2D(GLenum target, GLenum attachment, GLenum textarget, GLuint texture, GLint level)`
See: [glFramebufferTexture2D\(\)](#) on Kronos website

`kivy.graphics.opengl.glFrontFace(GLenum mode)`
See: [glFrontFace\(\)](#) on Kronos website

`kivy.graphics.opengl.glGenBuffers(GLsizei n)`
See: [glGenBuffers\(\)](#) on Kronos website
Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGenFramebuffers(GLsizei n)`
See: [glGenFramebuffers\(\)](#) on Kronos website
Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGenRenderbuffers(GLsizei n)`
See: [glGenRenderbuffers\(\)](#) on Kronos website
Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGenTextures(GLsizei n)`
See: [glGenTextures\(\)](#) on Kronos website
Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGenerateMipmap(GLenum target)`
See: [glGenerateMipmap\(\)](#) on Kronos website

`kivy.graphics.opengl.glGetActiveAttrib(GLuint program, GLuint index)`

See: [glGetActiveAttrib\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetActiveUniform(GLuint program, GLuint index)`

See: [glGetActiveUniform\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetAttachedShaders(GLuint program, GLsizei maxcount)`

See: [glGetAttachedShaders\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetAttribLocation(GLuint program, bytes name)`

See: [glGetAttribLocation\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetBooleanv(GLenum pname)`

See: [glGetBooleanv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetBufferParameteriv(GLenum target, GLenum pname)`

See: [glGetBufferParameteriv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetError()`

See: [glGetError\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetFloatv(GLenum pname)`

See: [glGetFloatv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetFramebufferAttachmentParameteriv(GLenum target, GLenum attachment, GLenum pname)`

See: [glGetFramebufferAttachmentParameteriv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetIntegerv(GLenum pname)`

See: [glGetIntegerv\(\) on Kronos website](#)

Unlike the C specification, the value(s) will be the result of the call

`kivy.graphics.opengl.glGetProgramInfoLog(GLuint program, GLsizei bufsize)`

See: [glGetProgramInfoLog\(\) on Kronos website](#)

Unlike the C specification, the source code will be returned as a string.

`kivy.graphics.opengl.glGetProgramiv(GLuint program, GLenum pname)`

See: [glGetProgramiv\(\) on Kronos website](#)

Unlike the C specification, the value(s) will be the result of the call

`kivy.graphics.opengl.glGetRenderbufferParameteriv(GLenum target, GLenum pname)`

See: [glGetRenderbufferParameteriv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetShaderInfoLog(GLuint shader, GLsizei bufsize)`

See: [glGetShaderInfoLog\(\) on Kronos website](#)

Unlike the C specification, the source code will be returned as a string.

`kivy.graphics.opengl.glGetShaderPrecisionFormat(GLenum shadertype, GLenum preciontype)`

See: [glGetShaderPrecisionFormat\(\) on Kronos website](#)

Warning: Not implemented yet.

`kivy.graphics.opengl.glGetShaderSource(GLuint shader)`

See: [glGetShaderSource\(\) on Kronos website](#)

Unlike the C specification, the source code will be returned as a string.

`kivy.graphics.opengl.glGetShaderiv(GLuint shader, GLenum pname)`

See: [glGetShaderiv\(\) on Kronos website](#)

Unlike the C specification, the value will be the result of call.

`kivy.graphics.opengl.glGetString(GLenum name)`

See: [glGetString\(\) on Kronos website](#)

Unlike the C specification, the value will be returned as a string.

`kivy.graphics.opengl.glGetTexParameterfv(GLenum target, GLenum pname)`

See: [glGetTexParameterfv\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetTexParameteriv(GLenum target, GLenum pname)`

See: [glGetTexParameteriv\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetUniformLocation(GLuint program, bytes name)`

See: [glGetUniformLocation\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetUniformfv(GLuint program, GLint location)`

See: [glGetUniformfv\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetUniformiv(GLuint program, GLint location)`

See: [glGetUniformiv\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetVertexAttribPointerv(GLuint index, GLenum pname)`

See: [glGetVertexAttribPointerv\(\) on Kronos website](#)

Warning: Not implemented yet.

`kivy.graphics.opengl.glGetVertexAttribfv(GLuint index, GLenum pname)`

See: [glGetVertexAttribfv\(\) on Kronos website](#)

`kivy.graphics.opengl.glGetVertexAttribiv(GLuint index, GLenum pname)`

See: [glGetVertexAttribiv\(\) on Kronos website](#)

`kivy.graphics.opengl.glHint(GLenum target, GLenum mode)`

See: [glHint\(\) on Kronos website](#)

`kivy.graphics.opengl.gliIsBuffer(GLuint buffer)`

See: [gliIsBuffer\(\) on Kronos website](#)

`kivy.graphics.opengl.gliEnabled(GLenum cap)`

See: [gliEnabled\(\) on Kronos website](#)

`kivy.graphics.opengl.glIsFramebuffer(GLuint framebuffer)`

See: [glIsFramebuffer\(\)](#) on Kronos website

`kivy.graphics.opengl.glIsProgram(GLuint program)`

See: [glIsProgram\(\)](#) on Kronos website

`kivy.graphics.opengl.glIsRenderbuffer(GLuint renderbuffer)`

See: [glIsRenderbuffer\(\)](#) on Kronos website

`kivy.graphics.opengl.glIsShader(GLuint shader)`

See: [glIsShader\(\)](#) on Kronos website

`kivy.graphics.opengl.glIsTexture(GLuint texture)`

See: [glIsTexture\(\)](#) on Kronos website

`kivy.graphics.opengl.gLineWidth(GLfloat width)`

See: [gLineWidth\(\)](#) on Kronos website

`kivy.graphics.opengl.gLLinkProgram(GLuint program)`

See: [gLLinkProgram\(\)](#) on Kronos website

`kivy.graphics.opengl.glPixelStorei(GLenum pname, GLint param)`

See: [glPixelStorei\(\)](#) on Kronos website

`kivy.graphics.opengl.glPolygonOffset(GLfloat factor, GLfloat units)`

See: [glPolygonOffset\(\)](#) on Kronos website

`kivy.graphics.opengl.glReadPixels(GLint x, GLint y, GLsizei width, GLsizei height, GLenum format, GLenum type)`

See: [glReadPixels\(\)](#) on Kronos website

We support only GL_RGB/GL_RGBA as a format and GL_UNSIGNED_BYTE as a type.

`kivy.graphics.opengl.glReleaseShaderCompiler()`

See: [glReleaseShaderCompiler\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glRenderbufferStorage(GLenum target, GLenum internalformat, GLsizei width, GLsizei height)`

See: [glRenderbufferStorage\(\)](#) on Kronos website

`kivy.graphics.opengl.glSampleCoverage(GLclampf value, GLboolean invert)`

See: [glSampleCoverage\(\)](#) on Kronos website

`kivy.graphics.opengl.glScissor(GLint x, GLint y, GLsizei width, GLsizei height)`

See: [glScissor\(\)](#) on Kronos website

`kivy.graphics.opengl.glShaderBinary()`

See: [glShaderBinary\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glShaderSource(GLuint shader, bytes source)`

See: [glShaderSource\(\)](#) on Kronos website

`kivy.graphics.opengl.glStencilFunc(GLenum func, GLint ref, GLuint mask)`

See: [glStencilFunc\(\)](#) on Kronos website

`kivy.graphics.opengl.glStencilFuncSeparate(GLenum face, GLenum func, GLint ref, GLuint mask)`

See: [glStencilFuncSeparate\(\)](#) on Kronos website

`kivy.graphics.opengl.glStencilMask(GLuint mask)`

See: [glStencilMask\(\)](#) on Kronos website

`kivy.graphics.opengl.glStencilMaskSeparate(GLenum face, GLuint mask)`

See: [glStencilMaskSeparate\(\)](#) on Kronos website

`kivy.graphics.opengl.glStencilOp(GLenum fail, GLenum zfail, GLenum zpass)`

See: [glStencilOp\(\)](#) on Kronos website

`kivy.graphics.opengl.glStencilOpSeparate(GLenum face, GLenum fail, GLenum zfail, GLenum zpass)`

See: [glStencilOpSeparate\(\)](#) on Kronos website

`kivy.graphics.opengl.glTexImage2D(GLenum target, GLint level, GLint internalformat, GLsizei width, GLsizei height, GLint border, GLenum format, GLenum type, bytes pixels)`

See: [glTexImage2D\(\)](#) on Kronos website

`kivy.graphics.opengl.glTexParameterf(GLenum target, GLenum pname, GLfloat param)`

See: [glTexParameterf\(\)](#) on Kronos website

`kivy.graphics.opengl.glTexParameterfv(GLenum target, GLenum pname)`

See: [glTexParameterfv\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glTexParameterI(GLenum target, GLenum pname, GLint param)`

See: [glTexParameterI\(\)](#) on Kronos website

`kivy.graphics.opengl.glTexParameteriv(GLenum target, GLenum pname)`

See: [glTexParameteriv\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glTexSubImage2D(GLenum target, GLint level, GLint xoffset, GLint yoffset, GLsizei width, GLsizei height, GLenum format, GLenum type, bytes pixels)`

See: [glTexSubImage2D\(\)](#) on Kronos website

`kivy.graphics.opengl.glUniform1f(GLint location, GLfloat x)`

See: [glUniform1f\(\)](#) on Kronos website

`kivy.graphics.opengl.glUniform1fv(GLint location, GLsizei count)`

See: [glUniform1fv\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniform1i(GLint location, GLint x)`

See: [glUniform1i\(\)](#) on Kronos website

`kivy.graphics.opengl.glUniform1iv(GLint location, GLsizei count)`

See: [glUniform1iv\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniform2f(GLint location, GLfloat x, GLfloat y)`

See: [glUniform2f\(\) on Kronos website](#)

`kivy.graphics.opengl.glUniform2fv(GLint location, GLsizei count)`

See: [glUniform2fv\(\) on Kronos website](#)

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniform2i(GLint location, GLint x, GLint y)`

See: [glUniform2i\(\) on Kronos website](#)

`kivy.graphics.opengl.glUniform2iv(GLint location, GLsizei count)`

See: [glUniform2iv\(\) on Kronos website](#)

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniform3f(GLint location, GLfloat x, GLfloat y, GLfloat z)`

See: [glUniform3f\(\) on Kronos website](#)

`kivy.graphics.opengl.glUniform3fv(GLint location, GLsizei count)`

See: [glUniform3fv\(\) on Kronos website](#)

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniform3i(GLint location, GLint x, GLint y, GLint z)`

See: [glUniform3i\(\) on Kronos website](#)

`kivy.graphics.opengl.glUniform3iv(GLint location, GLsizei count)`

See: [glUniform3iv\(\) on Kronos website](#)

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniform4f(GLint location, GLfloat x, GLfloat y, GLfloat z, GLfloat w)`

See: [glUniform4f\(\) on Kronos website](#)

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniform4fv(GLint location, GLsizei count)`

See: [glUniform4fv\(\) on Kronos website](#)

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniform4i(GLint location, GLint x, GLint y, GLint z, GLint w)`

See: [glUniform4i\(\) on Kronos website](#)

`kivy.graphics.opengl.glUniform4iv(GLint location, GLsizei count)`

See: [glUniform4iv\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniformMatrix2fv(GLint location, GLsizei count)`

See: [glUniformMatrix2fv\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniformMatrix3fv(GLint location, GLsizei count)`

See: [glUniformMatrix3fv\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glUniformMatrix4fv(GLint location, GLsizei count, GLboolean transpose, bytes value)`

See: [glUniformMatrix4fv\(\)](#) on Kronos website

`kivy.graphics.opengl.glUseProgram(GLuint program)`

See: [glUseProgram\(\)](#) on Kronos website

`kivy.graphics.opengl.glValidateProgram(GLuint program)`

See: [glValidateProgram\(\)](#) on Kronos website

`kivy.graphics.opengl.glVertexAttrib1f(GLuint indx, GLfloat x)`

See: [glVertexAttrib1f\(\)](#) on Kronos website

`kivy.graphics.opengl.glVertexAttrib1fv(GLuint indx, list values)`

See: [glVertexAttrib1fv\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glVertexAttrib2f(GLuint indx, GLfloat x, GLfloat y)`

See: [glVertexAttrib2f\(\)](#) on Kronos website

`kivy.graphics.opengl.glVertexAttrib2fv(GLuint indx, list values)`

See: [glVertexAttrib2fv\(\)](#) on Kronos website

Warning: Not implemented yet.

`kivy.graphics.opengl.glVertexAttrib3f(GLuint indx, GLfloat x, GLfloat y, GLfloat z)`

See: [glVertexAttrib3f\(\)](#) on Kronos website

`kivy.graphics.opengl.glVertexAttrib3fv(GLuint indx, list values)`

See: [glVertexAttrib3fv\(\)](#) on Kronos website

Warning: Not implemented yet.

```
kivy.graphics.opengl.glVertexAttrib4f(GLuint idx, GLfloat x, GLfloat y, GLfloat z, GLfloat w)
```

See: [glVertexAttrib4f\(\) on Kronos website](#)

```
kivy.graphics.opengl.glVertexAttrib4fv(GLuint idx, list values)
```

See: [glVertexAttrib4fv\(\) on Kronos website](#)

Warning: Not implemented yet.

```
kivy.graphics.opengl.glVertexAttribPointer(GLuint index, GLint size, GLenum type, GLboolean normalized, GLsizei stride, data)
```

See: [glVertexAttribPointer\(\) on Kronos website](#)

```
kivy.graphics.opengl.glViewport(GLint x, GLint y, GLsizei width, GLsizei height)
```

See: [glViewport\(\) on Kronos website](#)

```
kivy.graphics.opengl.gl_init_symbols(allowed=[], ignored=[])
```

37.11 OpenGL utilities

New in version 1.0.7.

```
kivy.graphics.opengl_utils.gl_get_extensions() → list
```

Return a list of OpenGL extensions available. All the names in the list have the *GL_* stripped at the start (if it exists) and are in lowercase.

```
>>> print(gl_get_extensions())
['arb_blend_func_extended', 'arb_color_buffer_float', 'arb_compatibility',
 'arb_copy_buffer'... ]
```

```
kivy.graphics.opengl_utils.gl_get_texture_formats() → tuple
```

Return a list of texture formats recognized by kivy. The texture list is informative but might not been supported by your hardware. If you want a list of supported textures, you must filter that list as follows:

```
supported_fmts = [gl_has_texture_format(x) for x in gl_get_texture_formats()]
```

```
kivy.graphics.opengl_utils.gl_get_version() → tuple
```

Return the (major, minor) OpenGL version, parsed from the *GL_VERSION*.

New in version 1.2.0.

```
kivy.graphics.opengl_utils.gl_get_version_major() → int
```

Return the major component of the OpenGL version.

New in version 1.2.0.

```
kivy.graphics.opengl_utils.gl_get_version_minor() → int
```

Return the minor component of the OpenGL version.

New in version 1.2.0.

```
kivy.graphics.opengl_utils.gl_has_capability(int cap) → int
```

Return the status of a OpenGL Capability. This is a wrapper that auto-discovers all the capabilities that Kivy might need. The current capabilities tested are:

- GLCAP_BGRA: Test the support of BGRA texture format

- GLCAP_NPOT: Test the support of Non Power of Two texture
- GLCAP_S3TC: Test the support of S3TC texture (DXT1, DXT3, DXT5)
- GLCAP_DXT1: Test the support of DXT texture (subset of S3TC)
- GLCAP_ETC1: Test the support of ETC1 texture

`kivy.graphics.opengl_utils.gl_has_extension(name) → int`

Check if an OpenGL extension is available. If the name starts with `GL_`, it will be stripped for the test and converted to lowercase.

```
>>> gl_has_extension('NV_get_tex_image')
False
>>> gl_has_extension('OES_texture_npot')
True
```

`kivy.graphics.opengl_utils.gl_has_texture_conversion(fmt) → int`

Return 1 if the texture can be converted to a native format.

`kivy.graphics.opengl_utils.gl_has_texture_format(fmt) → int`

Return whether a texture format is supported by your system, natively or by conversion. For example, if your card doesn't support 'bgra', we are able to convert to 'rgba' but only in software mode.

`kivy.graphics.opengl_utils.gl_has_texture_native_format(fmt) → int`

Return 1 if the texture format is handled natively.

```
>>> gl_has_texture_format('azdmok')
0
>>> gl_has_texture_format('rgba')
1
>>> gl_has_texture_format('s3tc_dxt1')
[INFO    ] [GL           ] S3TC texture support is available
[INFO    ] [GL           ] DXT1 texture support is available
1
```

`kivy.graphics.opengl_utils.gl_register_get_size(int constid, int size)`

Register an association between an OpenGL Const used in `glGet*` to a number of elements.

By example, the `GPU_MEMORY_INFO_DEDICATED_VIDMEM_NVX` is a special pname that will return the integer 1 (nvidia only).

```
>>> GPU_MEMORY_INFO_DEDICATED_VIDMEM_NVX = 0x9047
>>> gl_register_get_size(GPU_MEMORY_INFO_DEDICATED_VIDMEM_NVX, 1)
>>> glGetIntegerv(GPU_MEMORY_INFO_DEDICATED_VIDMEM_NVX)[0]
524288
```

37.12 Scissor Instructions

New in version 1.9.1.

Scissor instructions clip your drawing area into a rectangular region.

- `ScissorPush`: Begins clipping, sets the bounds of the clip space
- `ScissorPop`: Ends clipping

The area provided to clip is in screenspace pixels and must be provided as integer values not floats.

The following code will draw a circle on top of our widget while clipping the circle so it does not expand beyond the widget borders.

```
with self.canvas.after:  
    #If our widget is inside another widget that modified the coordinates  
    #spacing (such as ScrollView) we will want to convert to Window coords  
    x,y = self.to_window(*self.pos)  
    width, height = self.size  
    #We must convert from the possible float values provided by kivy  
    #widgets to an integer screenspace, in python3 round returns an int so  
    #the int cast will be unnecessary.  
    ScissorPush(x=int(round(x)), y=int(round(y)),  
                width=int(round(width)), height=int(round(height)))  
    Color(rgba=(1., 0., 0., .5))  
    Ellipse(size=(width*2., height*2.),  
            pos=self.center)  
    ScissorPop()
```

class kivy.graphics.scissor_instructions.Rect(*int x, int y, int width, int height*)

Bases: builtins.object

Rect class used internally by ScissorStack and ScissorPush to determine correct clipping area.

intersect(*Rect other*)

class kivy.graphics.scissor_instructions.ScissorPop

Bases: kivy.graphics.instructions.Instruction

Pop the scissor stack. Call after ScissorPush, once you have completed the drawing you wish to be clipped.

class kivy.graphics.scissor_instructions.ScissorPush(**kwargs)

Bases: kivy.graphics.instructions.Instruction

to control the area and position of the scissoring region. Defaults to 0, 0, 100, 100

Scissor works by clipping all drawing outside of a rectangle starting at int x, int y position and having sides of int width by int height in Window space coordinates

class kivy.graphics.scissor_instructions.ScissorStack

Bases: builtins.object

Class used internally to keep track of the current state of glScissors regions. Do not instantiate, prefer to inspect the module's scissor_stack.

pop()

push(*element*)

37.13 Shader

The **Shader** class handles the compilation of the vertex and fragment shader as well as the creation of the program in OpenGL.

Todo: Include more complete documentation about the shader.

37.13.1 Header inclusion

New in version 1.0.7.

When you are creating a Shader, Kivy will always include default parameters. If you don't want to rewrite this each time you want to customize / write a new shader, you can add the "\$HEADER\$" token and it will be replaced by the corresponding shader header.

Here is the header for the fragment Shader:

```
#ifdef GL_ES
    precision highp float;
#endif

/* Outputs from the vertex shader */
varying vec4 frag_color;
varying vec2 tex_coord0;

/* uniform texture samplers */
uniform sampler2D texture0;

uniform mat4 frag_modelview_mat;
```

And the header for vertex Shader:

```
#ifdef GL_ES
    precision highp float;
#endif

/* Outputs to the fragment shader */
varying vec4 frag_color;
varying vec2 tex_coord0;

/* vertex attributes */
attribute vec2      vPosition;
attribute vec2      vTexCoords0;

/* uniform variables */
uniform mat4      modelview_mat;
uniform mat4      projection_mat;
uniform vec4      color;
uniform float      opacity;
```

37.13.2 Single file glsl shader programs

New in version 1.6.0.

To simplify shader management, the vertex and fragment shaders can be loaded automatically from a single glsl source file (plain text). The file should contain sections identified by a line starting with '--vertex' and '--fragment' respectively (case insensitive), e.g.

```
// anything before a meaningful section such as this comment are ignored

---VERTEX SHADER--- // vertex shader starts here
void main(){
    ...
}
```

(continues on next page)

```

}

---FRAGMENT SHADER--- // fragment shader starts here
void main(){
    ...
}

```

The source property of the Shader should be set to the filename of a glsl shader file (of the above format), e.g. *phong.glsl*

class kivy.graphics.shader.**Shader**(*unicode vs=None, unicode fs=None, unicode source=None*)
Bases: builtins.object

Parameters

vs: string, defaults to None Source code for vertex shader

fs: string, defaults to None Source code for fragment shader

fs

Fragment shader source code.

If you set a new fragment shader code source, it will be automatically compiled and will replace the current fragment shader.

source

glsl source code.

source should be the filename of a glsl shader that contains both the vertex and fragment shader sourcecode, each designated by a section header consisting of one line starting with either “-VERTEX” or “-FRAGMENT” (case insensitive).

New in version 1.6.0.

success

Indicate whether the shader loaded successfully and is ready for usage or not.

vs

Vertex shader source code.

If you set a new vertex shader code source, it will be automatically compiled and will replace the current vertex shader.

37.14 Stencil instructions

New in version 1.0.4.

Changed in version 1.3.0: The stencil operation has been updated to resolve some issues that appeared when nested. You **must** now have a `StencilUnUse` and repeat the same operation as you did after `StencilPush`.

Stencil instructions permit you to draw and use the current drawing as a mask. They don’t give as much control as pure OpenGL, but you can still do fancy things!

The stencil buffer can be controlled using these 3 instructions:

- **StencilPush**: push a new stencil layer. Any drawing that happens after this will be used as a mask.
- **StencilUse** : now draw the next instructions and use the stencil for masking them.
- **StencilUnUse** : stop using the stencil i.e. remove the mask and draw normally.

- **StencilPop**: pop the current stencil layer.

You should always respect this scheme:

StencilPush

```
# PHASE 1: put any drawing instructions to use as a mask here.
```

StencilUse

```
# PHASE 2: all the drawing here will be automatically clipped by the
# mask created in PHASE 1.
```

StencilUnUse

```
# PHASE 3: put the same drawing instruction here as you did in PHASE 1
```

StencilPop

```
# PHASE 4: the stencil is now removed from the stack and unloaded.
```

37.14.1 Limitations

- Drawing in PHASE 1 and PHASE 3 must not collide or you will get unexpected results
- The stencil is activated as soon as you perform a StencilPush
- The stencil is deactivated as soon as you've correctly popped all the stencil layers
- You must not play with stencils yourself between a StencilPush / StencilPop
- You can push another stencil after a StencilUse / before the StencilPop
- You can push up to 128 layers of stencils (8 for kivy < 1.3.0)

37.14.2 Example of stencil usage

Here is an example, in kv style:

StencilPush

```
# create a rectangular mask with a pos of (100, 100) and a (100, 100) size.
```

Rectangle:

```
    pos: 100, 100
    size: 100, 100
```

StencilUse

```
# we want to show a big green rectangle, however, the previous stencil
# mask will crop us :)
```

Color:

```
    rgb: 0, 1, 0
```

Rectangle:

```
    size: 900, 900
```

StencilUnUse

(continues on next page)

```
# you must redraw the stencil mask to remove it
Rectangle:
    pos: 100, 100
    size: 100, 100
```

StencilPop

class `kivy.graphics.stencil_instructions.StencilPop`
 Bases: `kivy.graphics.instructions.Instruction`

Pop the stencil stack. See the module documentation for more information.

class `kivy.graphics.stencil_instructions.StencilPush`
 Bases: `kivy.graphics.instructions.Instruction`

Push the stencil stack. See the module documentation for more information.

class `kivy.graphics.stencil_instructions.StencilUnUse`
 Bases: `kivy.graphics.instructions.Instruction`

Use current stencil buffer to unset the mask.

class `kivy.graphics.stencil_instructions.StencilUse(**kwargs)`
 Bases: `kivy.graphics.instructions.Instruction`

more information.

func_op

Determine the stencil operation to use for glStencilFunc(). Can be one of ‘never’, ‘less’, ‘equal’, ‘lequal’, ‘greater’, ‘notequal’, ‘gequal’ or ‘always’.

By default, the operator is set to ‘equal’.

New in version 1.5.0.

37.15 SVG

New in version 1.9.0.

Warning: This is highly experimental and subject to change. Don’t use it in production.

Load an SVG as a graphics instruction:

```
from kivy.graphics.svg import Svg
with widget.canvas:
    svg = Svg("image.svg")
```

There is no widget that can display Svg directly, you have to make your own for now. Check the `examples/svg` for more information.

class `kivy.graphics.svg.Svg(source=None, anchor_x=0, anchor_y=0, bezier_points=64, circle_points=64, color=None)`
 Bases: `kivy.graphics.instructions.RenderContext`

anchor_x

Horizontal anchor position for scaling and rotations. Defaults to 0. The symbolic values ‘left’, ‘center’ and ‘right’ are also accepted.

anchor_y

Vertical anchor position for scaling and rotations. Defaults to 0. The symbolic values 'bottom', 'center' and 'top' are also accepted.

color

The default color

Used for SvgElements that specify "currentColor"

Changed in version 1.10.3: The color is gettable and settable

New in version 1.9.1.

current_color

current_color: object

gradients

gradients: object

height

height: 'double'

set_tree(*tree*)

sets the tree used to render the Svg and triggers reloading.

Parameters **tree** (*xml.etree.cElementTree*) – the tree parsed from the SVG source

New in version 2.0.0.

source

Filename / source to load.

The parsing and rendering is done as soon as you set the source.

Changed in version 2.0.0: The property name is now *source* instead of *filename*


Changed in version 1.10.3: You can get the used filename


width

width: 'double'

37.16 Tesselator

New in version 1.9.0.





Warning: This is experimental and subject to change as long as this warning notice is present. Only TYPE_POLYGONS is currently supported.

Tesselator is a library for tessellating polygons, based on [libtess2](#). It renders concave filled polygons by first tessellating them into convex polygons. It also supports holes.

37.16.1 Usage

First, you need to create a `Tesselator` object and add contours. The first one is the external contour of your shape and all of the following ones should be holes:

```
from kivy.graphics.tesselator import Tesselator

tess = Tesselator()
tess.add_contour([0, 0, 200, 0, 200, 200, 0, 200])
tess.add_contour([50, 50, 150, 50, 150, 150, 50, 150])
```

Second, call the `Tesselator.tesselate()` method to compute the points. It is possible that the tesselator won't work. In that case, it can return False:

```
if not tess.tesselate():
    print("Tesselator didn't work :(")
    return
```

After the tessellation, you have multiple ways to iterate over the result. The best approach is using `Tesselator.meshes` to get a format directly usable for a `Mesh`:

```
for vertices, indices in tess.meshes:
    self.canvas.add(Mesh(
        vertices=vertices,
        indices=indices,
        mode="triangle_fan"
    ))
```

Or, you can get the “raw” result, with just polygons and x/y coordinates with `Tesselator.vertices()`:

```
for vertices in tess.vertices:
    print("got polygon", vertices)
```

```
class kivy.graphics.tesselator.Tesselator
Bases: builtins.object
```

Tesselator class. See module for more information about the usage.

add_contour(*points*)

Add a contour to the tesselator. It can be:

- a list of $[x, y, x2, y2, \dots]$ coordinates
- a float array: $array("f", [x, y, x2, y2, \dots])$
- any buffer with floats in it.

element_count

Returns the number of convex polygon.

meshes

Iterate through the result of the **tessellate()** to give a result that can be easily pushed into Kivy's Mesh object.

It's a list of: $[[vertices, indices], [vertices, indices], \dots]$. The vertices in the format $[x, y, u, v, x2, y2, u2, v2]$.

Careful, u/v coordinates are the same as x/y. You are responsible to change them for texture mapping if you need to.

You can create Mesh objects like that:

```
tess = Tesselator()
# add contours here
tess.tessellate()
for vertices, indices in self.meshes:
    self.canvas.add(Mesh(
        vertices=vertices,
        indices=indices,
        mode="triangle_fan"))
```

tessellate(*int winding_rule=WINDING_ODD, int element_type=TYPE_POLYGONS, int polysize=65535*) → int

Compute all the contours added with **add_contour()**, and generate polygons.

Parameters

winding_rule: enum The winding rule classifies a region as inside if its winding number belongs to the chosen category. Can be one of WINDING_ODD, WINDING_NONZERO, WINDING_POSITIVE, WINDING_NEGATIVE, WINDING_ABS_GEQ_TWO. Defaults to WINDING_ODD.

element_type: enum The result type, you can generate the polygons with TYPE_POLYGONS, or the contours with TYPE_BOUNDARY_CONTOURS. Defaults to TYPE_POLYGONS.

Returns 1 if the tessellation happened, 0 otherwise.

Return type int

vertex_count

Returns the number of vertex generated.

This is the raw result, however, because the Tesselator format the result for you with **meshes** or **vertices** per polygon, you'll have more vertices in the result

vertices

Iterate through the result of the `tessellate()` in order to give only a list of $[x, y, x2, y2, \dots]$ polygons.

37.17 Texture

Changed in version 1.6.0: Added support for palettes texture on OES: 'palette4_rgb8', 'palette4_rgba8', 'palette4_r5_g6_b5', 'palette4_rgba4', 'palette4_rgb5_a1', 'palette8_rgb8', 'palette8_rgba8', 'palette8_r5_g6_b5', 'palette8_rgba4' and 'palette8_rgb5_a1'.

`Texture` is a class that handles OpenGL textures. Depending on the hardware, some OpenGL capabilities might not be available (BGRA support, NPOT support, etc.)

You cannot instantiate this class yourself. You must use the function `Texture.create()` to create a new texture:

```
texture = Texture.create(size=(640, 480))
```

When you create a texture, you should be aware of the default color and buffer format:

- the color/pixel format (`Texture.colorfmt`) that can be one of 'rgb', 'rgba', 'luminance', 'luminance_alpha', 'bgr' or 'bgra'. The default value is 'rgb'
- the buffer format determines how a color component is stored into memory. This can be one of 'ubyte', 'ushort', 'uint', 'byte', 'short', 'int' or 'float'. The default value and the most commonly used is 'ubyte'.

So, if you want to create an RGBA texture:

```
texture = Texture.create(size=(640, 480), colorfmt='rgba')
```

You can use your texture in almost all vertex instructions with the `kivy.graphics.VertexInstruction.texture` parameter. If you want to use your texture in kv lang, you can save it in an `ObjectProperty` inside your widget.

Warning: Using Texture before OpenGL has been initialized will lead to a crash. If you need to create textures before the application has started, import Window first: `from kivy.core.window import Window`

37.17.1 Blitting custom data

You can create your own data and blit it to the texture using `Texture.blit_buffer()`.

For example, to blit immutable bytes data:

```
# create a 64x64 texture, defaults to rgba / ubyte
texture = Texture.create(size=(64, 64))

# create 64x64 rgb tab, and fill with values from 0 to 255
# we'll have a gradient from black to white
size = 64 * 64 * 3
buf = [int(x * 255 / size) for x in range(size)]

# then, convert the array to a ubyte string
buf = bytes(buf)
```

(continues on next page)

```
# then blit the buffer
texture.blit_buffer(buf, colorfmt='rgb', bufferfmt='ubyte')

# that's all ! you can use it in your graphics now :)
# if self is a widget, you can do this
with self.canvas:
    Rectangle(texture=texture, pos=self.pos, size=(64, 64))
```

Since 1.9.0, you can blit data stored in a instance that implements the python buffer interface, or a memoryview thereof, such as numpy arrays, python `array.array`, a `bytarray`, or a cython array. This is beneficial if you expect to blit similar data, with perhaps a few changes in the data.

When using a bytes representation of the data, for every change you have to regenerate the bytes instance, from perhaps a list, which is very inefficient. When using a buffer object, you can simply edit parts of the original data. Similarly, unless starting with a bytes object, converting to bytes requires a full copy, however, when using a buffer instance, no memory is copied, except to upload it to the GPU.

Continuing with the example above:

```
from array import array

size = 64 * 64 * 3
buf = [int(x * 255 / size) for x in range(size)]
# initialize the array with the buffer values
arr = array('B', buf)
# now blit the array
texture.blit_buffer(arr, colorfmt='rgb', bufferfmt='ubyte')

# now change some elements in the original array
arr[24] = arr[50] = 99
# blit again the buffer
texture.blit_buffer(arr, colorfmt='rgb', bufferfmt='ubyte')
```

37.17.2 BGR/BGRA support

The first time you try to create a BGR or BGRA texture, we check whether your hardware supports BGR / BGRA textures by checking the extension ‘GL_EXT_bgra’.

If the extension is not found, the conversion to RGB / RGBA will be done in software.

37.17.3 NPOT texture

Changed in version 1.0.7: If your hardware supports NPOT, no POT is created.

As the OpenGL documentation says, a texture must be power-of-two sized. That means your width and height can be one of 64, 32, 256... but not 3, 68, 42. NPOT means non-power-of-two. OpenGL ES 2 supports NPOT textures natively but with some drawbacks. Another type of NPOT texture is called a rectangle texture. POT, NPOT and textures all have their own pro/cons.

Features	POT	NPOT	Rectangle
OpenGL Target	GL_TEXTURE_2D	GL_TEXTURE_2D	GL_TEXTURE_RECTANGLE_(NV ARB EXT)
Texture coords	0-1 range	0-1 range	width-height range
Mipmapping	Supported	Partially	No
Wrap mode	Supported	Supported	No

If you create a NPOT texture, we first check whether your hardware supports it by checking the extensions GL_ARB_texture_non_power_of_two or OES_texture_npot. If none of these are available, we create the nearest POT texture that can contain your NPOT texture. The `Texture.create()` will return a `TextureRegion` instead.

37.17.4 Texture atlas

A texture atlas is a single texture that contains many images. If you want to separate the original texture into many single ones, you don't need to. You can get a region of the original texture. That will return the original texture with custom texture coordinates:

```
# for example, load a 128x128 image that contain 4 64x64 images
from kivy.core.image import Image
texture = Image('mycombinedimage.png').texture

bottomleft = texture.get_region(0, 0, 64, 64)
bottomright = texture.get_region(0, 64, 64, 64)
topleft = texture.get_region(0, 64, 64, 64)
topright = texture.get_region(64, 64, 64, 64)
```

37.17.5 Mipmapping

New in version 1.0.7.

Mipmapping is an OpenGL technique for enhancing the rendering of large textures to small surfaces. Without mipmapping, you might see pixelation when you render to small surfaces. The idea is to precalculate the subtexture and apply some image filter as a linear filter. Then, when you render a small surface, instead of using the biggest texture, it will use a lower filtered texture. The result can look better this way.

To make that happen, you need to specify `mipmap=True` when you create a texture. Some widgets already give you the ability to create mipmapped textures, such as the `Label` and `Image`.

From the OpenGL Wiki : "So a 64x16 2D texture can have 5 mip-maps: 32x8, 16x4, 8x2, 4x1, 2x1, and 1x1". Check <http://www.opengl.org/wiki/Texture> for more information.

Note: As the table in previous section said, if your texture is NPOT, we create the nearest POT texture and generate a mipmap from it. This might change in the future.

37.17.6 Reloading the Texture

New in version 1.2.0.

If the OpenGL context is lost, the Texture must be reloaded. Textures that have a source are automatically reloaded but generated textures must be reloaded by the user.

Use the `Texture.add_reload_observer()` to add a reloading function that will be automatically called when needed:

```
def __init__(self, **kwargs):
    super(...).__init__(**kwargs)
    self.texture = Texture.create(size=(512, 512), colorfmt='RGB',
        bufferfmt='ubyte')
    self.texture.add_reload_observer(self.populate_texture)

    # and load the data now.
    self.cbuffer = '\x00\xf0\xff' * 512 * 512
    self.populate_texture(self.texture)

def populate_texture(self, texture):
    texture.blit_buffer(self.cbuffer)
```

This way, you can use the same method for initialization and reloading.

Note: For all text rendering with our core text renderer, the texture is generated but we already bind a method to redo the text rendering and reupload the text to the texture. You don't have to do anything.

```
class kivy.graphics.texture.Texture(width, height, target, texid=0, colorfmt='rgb',
    bufferfmt='ubyte', mipmap=False, source=None,
    callback=None, icolorfmt='rgb')
```

Bases: `builtins.object`

textures or complex textures based on `ImageData`.

add_reload_observer(callback)

Add a callback to be called after the whole graphics context has been reloaded. This is where you can reupload your custom data into the GPU.

New in version 1.2.0.

Parameters

`callback: func(context) -> return None` The first parameter will be the context itself.

ask_update(callback)

Indicate that the content of the texture should be updated and the callback function needs to be called when the texture will be used.

bind()

Bind the texture to the current opengl state.

blit_buffer(pbuffer, size=None, colorfmt=None, pos=None, bufferfmt=None, mipmap_level=0, mipmap_generation=True, int rowlength=0)

Blit a buffer into the texture.

Note: Unless the canvas will be updated due to other changes, `ask_update()` should be

called in order to update the texture.

Parameters

***pbuffer*: bytes, or a class that implements the buffer interface (including memoryview).**

A buffer containing the image data. It can be either a bytes object or a instance of a class that implements the python buffer interface, e.g. `array.array`, `bytearray`, numpy arrays etc. If it's not a bytes object, the underlying buffer must be contiguous, have only one dimension and must not be readonly, even though the data is not modified, due to a cython limitation. See module description for usage details.

***size*: tuple, defaults to texture size** Size of the image (width, height)

***colorfmt*: str, defaults to 'rgb'** Image format, can be one of 'rgb', 'rgba', 'bgr', 'bgra', 'luminance' or 'luminance_alpha'.

***pos*: tuple, defaults to (0, 0)** Position to blit in the texture.

***bufferfmt*: str, defaults to 'ubyte'** Type of the data buffer, can be one of 'ubyte', 'ushort', 'uint', 'byte', 'short', 'int' or 'float'.

***mipmap_level*: int, defaults to 0** Indicate which mipmap level we are going to update.

***mipmap_generation*: bool, defaults to True** Indicate if we need to regenerate the mipmap from level 0.

Changed in version 1.0.7: added `mipmap_level` and `mipmap_generation`

Changed in version 1.9.0: `pbuffer` can now be any class instance that implements the python buffer interface and / or memoryviews thereof.

`blit_data(im, pos=None)`

Replace a whole texture with image data.

`bufferfmt`

Return the buffer format used in this texture (readonly).

New in version 1.2.0.

`colorfmt`

Return the color format used in this texture (readonly).

New in version 1.0.7.

`static create(size=None, colorfmt=None, bufferfmt=None, mipmap=False, callback=None, icolorfmt=None)`

`texture_create(size=None, colorfmt=None, bufferfmt=None, mipmap=False, callback=None, icolorfmt=None)` Create a texture based on size.

Parameters

***size*: tuple, defaults to (128, 128)** Size of the texture.

***colorfmt*: str, defaults to 'rgba'** Color format of the texture. Can be 'rgba' or 'rgb', 'luminance' or 'luminance_alpha'. On desktop, additional values are available: 'red', 'rg'.

***icolorfmt*: str, defaults to the value of `colorfmt`** Internal format storage of the texture. Can be 'rgba' or 'rgb', 'luminance' or 'luminance_alpha'. On desktop, additional values are available: 'r8', 'rg8', 'rgba8'.

bufferfmt: str, defaults to 'ubyte' Internal buffer format of the texture.
Can be 'ubyte', 'ushort', 'uint', 'bute', 'short', 'int' or 'float'.

mipmap: bool, defaults to False If True, it will automatically generate the mipmap texture.

callback: callable(), defaults to False If a function is provided, it will be called when data is needed in the texture.

Changed in version 1.7.0: `callback` has been added

static create_from_data(im, mipmap=False)

`texture_create_from_data(im, mipmap=False)` Create a texture from an `ImageData` class.

flip_horizontal()

Flip tex_coords for horizontal display.

New in version 1.9.0.

flip_vertical()

Flip tex_coords for vertical display.

get_region(x, y, width, height)

Return a part of the texture defined by the rectangular arguments (x, y, width, height). Returns a `TextureRegion` instance.

height

Return the height of the texture (readonly).

id

Return the OpenGL ID of the texture (readonly).

mag_filter

Get/set the mag filter texture. Available values:

- linear
- nearest

Check the opengl documentation for more information about the behavior of these values :
<http://www.khronos.org/opengles/sdk/docs/man/xhtml/glTexParameter.xml>.

min_filter

Get/set the min filter texture. Available values:

- linear
- nearest
- linear_mipmap_linear
- linear_mipmap_nearest
- nearest_mipmap_nearest
- nearest_mipmap_linear

Check the opengl documentation for more information about the behavior of these values :
<http://www.khronos.org/opengles/sdk/docs/man/xhtml/glTexParameter.xml>.

mipmap

Return True if the texture has mipmap enabled (readonly).

pixels

Get the pixels texture, in RGBA format only, unsigned byte. The origin of the image is at bottom left.

New in version 1.7.0.

remove_reload_observer(callback)

Remove a callback from the observer list, previously added by [add_reload_observer\(\)](#).

New in version 1.2.0.

save(filename, flipped=True, fmt=None)

Save the texture content to a file. Check [kivy.core.image.Image.save\(\)](#) for more information.

The flipped parameter flips the saved image vertically, and defaults to True.

New in version 1.7.0.

Changed in version 1.8.0: Parameter *flipped* added, defaults to True. All the OpenGL Texture are read from bottom / left, it need to be flipped before saving. If you don't want to flip the image, set *flipped* to False.

Changed in version 1.11.0: Parameter *fmt* added, to pass the final format to the image provider. Used if filename is a BytesIO

size

Return the (width, height) of the texture (readonly).

target

Return the OpenGL target of the texture (readonly).

tex_coords

Return the list of tex_coords (opengl).

uvpos

Get/set the UV position inside the texture.

uvsize

Get/set the UV size inside the texture.

Warning: The size can be negative if the texture is flipped.

width

Return the width of the texture (readonly).

wrap

Get/set the wrap texture. Available values:

- repeat
- mirrored_repeat
- clamp_to_edge

Check the opengl documentation for more information about the behavior of these values :

<http://www.khronos.org/opengles/sdk/docs/man/xhtml/glTexParameter.xml>.

class kivy.graphics.texture.TextureRegion(int x, int y, int width, int height, Texture origin)

Bases: [kivy.graphics.texture.Texture](#)

texture handling.

ask_update(callback)**bind()****pixels**

37.18 Transformation

This module contains a Matrix class used for our Graphics calculations. We currently support:

- rotation, translation and scaling matrices
- multiplication matrix
- clip matrix (with or without perspective)
- transformation matrix for 3d touch

For more information on transformation matrices, please see the [OpenGL Matrices Tutorial](#).

Changed in version 1.6.0: Added `Matrix.perspective()`, `Matrix.look_at()` and `Matrix.transpose()`.

class kivy.graphics.transformation.Matrix
Bases: `builtins.object`

```
>>> from kivy.graphics.transformation import Matrix
>>> m = Matrix()
>>> print(m)
[[ 1.000000 0.000000 0.000000 0.000000 ]
 [ 0.000000 1.000000 0.000000 0.000000 ]
 [ 0.000000 0.000000 1.000000 0.000000 ]
 [ 0.000000 0.000000 0.000000 1.000000 ]]
```

[0 1 2 3] [4 5 6 7] [8 9 10 11] [12 13 14 15]

get()

Retrieve the value of the current as a flat list.

New in version 1.9.1.

identity() → Matrix

Reset the matrix to the identity matrix (inplace).

inverse() → Matrix

Return the inverse of the matrix as a new Matrix.

look_at(double eyex, double eyey, double eyez, double centerx, double centery, double centerz, double upx, double upy, double upz)

Returns a new lookat Matrix (similar to `gluLookAt`).

Parameters

eyex: float Eyes X co-ordinate

eyey: float Eyes Y co-ordinate

eyez: float Eyes Z co-ordinate

centerx: float The X position of the reference point

centery: float The Y position of the reference point

centerz: float The Z position of the reference point

upx: float The X value up vector.

upy: float The Y value up vector.

upz: float The Z value up vector.

New in version 1.6.0.

multiply(*mb, Matrix ma*) → *Matrix*

Multiply the given matrix with self (from the left) i.e. we premultiply the given matrix by the current matrix and return the result (not inplace):

```
m.multiply(n) -> n * m
```

Parameters

ma: **Matrix** The matrix to multiply by

normal_matrix() → *Matrix*

Computes the normal matrix, which is the inverse transpose of the top left 3x3 modelview matrix used to transform normals into eye/camera space.

New in version 1.6.0.

perspective(*double fovy, double aspect, double zNear, double zFar*) → *Matrix*

Creates a perspective matrix (inplace).

Parameters

fovy: **float** "Field Of View" angle

aspect: **float** Aspect ratio

zNear: **float** Near clipping plane

zFar: **float** Far clippin plane

New in version 1.6.0.

project(*double objx, double objy, double objz, Matrix model, Matrix proj, double vx, double vy, double vw, double vh*)

Project a point from 3d space into a 2d viewport.

Parameters

objx: **float** Points X co-ordinate

objy: **float** Points Y co-ordinate

objz: **float** Points Z co-ordinate

model: **Matrix** The model matrix

proj: **Matrix** The projection matrix

vx: **float** Viewports X co-ordinate

vy: **float** Viewports y co-ordinate

vw: **float** Viewports width

vh: **float** Viewports height

New in version 1.7.0.

rotate(*double angle, double x, double y, double z*) → *Matrix*

Rotate the matrix through the angle around the axis (x, y, z) (inplace).

Parameters

angle: **float** The angle through which to rotate the matrix

x: **float** X position of the point

y: **float** Y position of the point

z: **float** Z position of the point

scale(double x, double y, double z) → *Matrix*

Scale the current matrix by the specified factors over each dimension (inplace).

Parameters

x: float The scale factor along the X axis

y: float The scale factor along the Y axis

z: float The scale factor along the Z axis

set(flat=None, array=None)

Insert custom values into the matrix in a flat list format or 4x4 array format like below:

```
m.set(array=[  
    [1.0, 0.0, 0.0, 0.0],  
    [0.0, 1.0, 0.0, 0.0],  
    [0.0, 0.0, 1.0, 0.0],  
    [0.0, 0.0, 0.0, 1.0]]  
)
```

New in version 1.9.0.

tolist()

Retrieve the value of the current matrix in numpy format. for example m.tolist() will return:

```
[[1.0, 0.0, 0.0, 0.0],  
 [0.0, 1.0, 0.0, 0.0],  
 [0.0, 0.0, 1.0, 0.0],  
 [0.0, 0.0, 0.0, 1.0]]
```

you can use this format to plug the result straight into numpy in this way
numpy.array(m.tolist())

New in version 1.9.0.

transform_point(double x, double y, double z, t=None) → tuple

Transforms the point by the matrix and returns the transformed point as a (x, y, z) tuple.
If the point is a vector v, the returned values is v2 = matrix * v.

If t is provided, it multiplies it with the last column of the matrix and returns the transformed
(x, y, z, t).

translate(double x, double y, double z) → *Matrix*

Translate the matrix.

Parameters

x: float The translation factor along the X axis

y: float The translation factor along the Y axis

z: float The translation factor along the Z axis

transpose() → *Matrix*

Return the transposed matrix as a new Matrix.

New in version 1.6.0.

view_clip(double left, double right, double bottom, double top, double near, double far, int perspective) → *Matrix*

Create a clip matrix (inplace).

Parameters

left: float Co-ordinate

```

right: float Co-ordinate
bottom: float Co-ordinate
top: float Co-ordinate
near: float Co-ordinate
far: float Co-ordinate
perspective: int Co-ordinate

```

Changed in version 1.6.0: Enable support for perspective parameter.

37.19 Vertex Instructions

This module includes all the classes for drawing simple vertex objects.

37.19.1 Updating properties

The list attributes of the graphics instruction classes (e.g. `Triangle.points`, `Mesh.indices` etc.) are not Kivy properties but Python properties. As a consequence, the graphics will only be updated when the list object itself is changed and not when list values are modified.

For example in python:

```

class MyWidget(Button):

    triangle = ObjectProperty(None)
    def __init__(self, **kwargs):
        super(MyWidget, self). __init__(**kwargs)
        with self.canvas:
            self.triangle = Triangle(points=[0,0, 100,100, 200,0])

```

and in kv:

```

<MyWidget>:
    text: 'Update'
    on_press:
        self.triangle.points[3] = 400

```

Although pressing the button will change the triangle coordinates, the graphics will not be updated because the list itself has not changed. Similarly, no updates will occur using any syntax that changes only elements of the list e.g. `self.triangle.points[0:2] = [10,10]` or `self.triangle.points.insert(10)` etc. To force an update after a change, the list variable itself must be changed, which in this case can be achieved with:

```

<MyWidget>:
    text: 'Update'
    on_press:
        self.triangle.points[3] = 400
        self.triangle.points = self.triangle.points

```

```

class kivy.graphics.vertex_instructions.Bezier(**kwargs)
Bases: kivy.graphics.instructions.VertexInstruction

```

New in version 1.0.8.

Parameters

points: list List of points in the format (x1, y1, x2, y2...)

segments: int, defaults to 180 Define how many segments are needed for drawing the curve. The drawing will be smoother if you have many segments.

loop: bool, defaults to False Set the bezier curve to join the last point to the first.

dash_length: int Length of a segment (if dashed), defaults to 1.

dash_offset: int Distance between the end of a segment and the start of the next one, defaults to 0. Changing this makes it dashed.

dash_length

Property for getting/setting the length of the dashes in the curve.

dash_offset

Property for getting/setting the offset between the dashes in the curve.

points

Property for getting/settings the points of the triangle.

Warning: This will always reconstruct the whole graphic from the new points list. It can be very CPU intensive.

segments

Property for getting/setting the number of segments of the curve.

class kivy.graphics.vertex_instructions.BorderImage(kwargs)**

Bases: *kivy.graphics.vertex_instructions.Rectangle*

concept of a CSS3 border-image.

Parameters

border: list Border information in the format (bottom, right, top, left). Each value is in pixels.

auto_scale: string New in version 1.9.1.

Changed in version 1.9.2: This used to be a bool and has been changed to be a string state.

Can be one of 'off', 'both', 'x_only', 'y_only', 'y_full_x_lower', 'x_full_y_lower', 'both_lower'.

Autoscale controls the behavior of the 9-slice.

By default the border values are preserved exactly, meaning that if the total size of the object is smaller than the border values you will have some 'rendering errors' where your texture appears inside out. This also makes it impossible to achieve a rounded button that scales larger than the size of its source texture. The various options for auto_scale will let you achieve some mixes of the 2 types of rendering.

'off': is the default and behaves as BorderImage did when auto_scale was False before.

'both': Scales both x and y dimension borders according to the size of the BorderImage, this disables the BorderImage making it render the same as a regular Image.

'x_only': The Y dimension functions as the default, and the X scales to the size of the BorderImage's width.

'y_only': The X dimension functions as the default, and the Y scales to the size of the BorderImage's height.

'y_full_x_lower': Y scales as in 'y_only', Y scales if the size of the scaled version would be smaller than the provided border only.

'x_full_y_lower': X scales as in 'x_only', Y scales if the size of the scaled version would be smaller than the provided border only.

'both_lower': This is what auto_scale did when it was True in 1.9.1 Both X and Y dimensions will be scaled if the BorderImage is smaller than the source.

If the BorderImage's size is less than the sum of its borders, horizontally or vertically, and this property is set to True, the borders will be rescaled to accommodate for the smaller size.

auto_scale

Property for setting if the corners are automatically scaled when the BorderImage is too small.

border

Property for getting/setting the border of the class.

display_border

Property for getting/setting the border display size.

class kivy.graphics.vertex_instructions.Ellipse(*args, **kwargs)

Bases: *kivy.graphics.vertex_instructions.Rectangle*

Changed in version 1.0.7: Added angle_start and angle_end.

Parameters

segments: int, defaults to 180 Define how many segments are needed for drawing the ellipse. The drawing will be smoother if you have many segments.

angle_start: int, defaults to 0 Specifies the starting angle, in degrees, of the disk portion.

angle_end: int, defaults to 360 Specifies the ending angle, in degrees, of the disk portion.

angle_end

End angle of the ellipse in degrees, defaults to 360.

angle_start

Start angle of the ellipse in degrees, defaults to 0.

segments

Property for getting/setting the number of segments of the ellipse.

exception kivy.graphics.vertex_instructions.GraphicException

Bases: Exception

Exception raised when a graphics error is fired.

class kivy.graphics.vertex_instructions.Line(**kwargs)


Bases: *kivy.graphics.instructions.VertexInstruction*

Drawing a line can be done easily:

```
with self.canvas:  
    Line(points=[100, 100, 200, 100, 100, 200], width=10)
```

The line has 3 internal drawing modes that you should be aware of for optimal results:

- If the `width` is 1.0, then the standard GL_LINE drawing from OpenGL will be used. `dash_length`, `dash_offset`, and `dashes` will work, while properties for cap and joint have no meaning here.
- If the `width` is greater than 1.0, then a custom drawing method, based on triangulation, will be used. `dash_length`, `dash_offset`, and `dashes` do not work in this mode. Additionally, if the current color has an alpha less than 1.0, a stencil will be used internally to draw the line.



Parameters

`points: list` List of points in the format (x1, y1, x2, y2...)

`dash_length: int` Length of a segment (if dashed), defaults to 1.

`dash_offset: int` Offset between the end of a segment and the beginning of the next one, defaults to 0. Changing this makes it dashed.

`dashes: list of ints` List of [ON length, offset, ON length, offset, ...]. E.g. [2, 4, 1, 6, 8, 2] would create a line with the first dash length 2 then an offset of 4 then a dash length of 1 then an offset of 6 and so on. Defaults to []. Changing this makes it dashed and overrides `dash_length` and `dash_offset`.

`width: float` Width of the line, defaults to 1.0.

`cap: str, defaults to 'round'` See `cap` for more information.

joint: str, defaults to 'round' See [joint](#) for more information.

cap_precision: int, defaults to 10 See [cap_precision](#) for more information

joint_precision: int, defaults to 10 See [joint_precision](#) for more information
See [cap_precision](#) for more information.

joint_precision: int, defaults to 10 See [joint_precision](#) for more information.

close: bool, defaults to False If True, the line will be closed.

circle: list If set, the [points](#) will be set to build a circle. See [circle](#) for more information.

ellipse: list If set, the [points](#) will be set to build an ellipse. See [ellipse](#) for more information.

rectangle: list If set, the [points](#) will be set to build a rectangle. See [rectangle](#) for more information.

bezier: list If set, the [points](#) will be set to build a bezier line. See [bezier](#) for more information.

bezier_precision: int, defaults to 180 Precision of the Bezier drawing.

Changed in version 1.0.8: *dash_offset* and *dash_length* have been added.

Changed in version 1.4.1: *width*, *cap*, *joint*, *cap_precision*, *joint_precision*, *close*, *ellipse*, *rectangle* have been added.

Changed in version 1.4.1: *bezier*, *bezier_precision* have been added.

Changed in version 1.11.0: *dashes* have been added

bezier

Use this property to build a bezier line, without calculating the [points](#). You can only set this property, not get it.

The argument must be a tuple of 2n elements, n being the number of points.

Usage:

```
Line(bezier=(x1, y1, x2, y2, x3, y3))
```

New in version 1.4.2.

Note: Bezier lines calculations are inexpensive for a low number of points, but complexity is quadratic, so lines with a lot of points can be very expensive to build, use with care!

bezier_precision

Number of iteration for drawing the bezier between 2 segments, defaults to 180. The *bezier_precision* must be at least 1.

New in version 1.4.2.

cap

Determine the cap of the line, defaults to 'round'. Can be one of 'none', 'square' or 'round'

New in version 1.4.1.

cap_precision

Number of iteration for drawing the "round" cap, defaults to 10. The *cap_precision* must be at least 1.

New in version 1.4.1.

circle

Use this property to build a circle, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (center_x, center_y, radius, angle_start, angle_end, segments):

- center_x and center_y represent the center of the circle
- radius represent the radius of the circle
- (optional) angle_start and angle_end are in degree. The default value is 0 and 360.
- (optional) segments is the precision of the ellipse. The default value is calculated from the range between angle.

Note that it's up to you to *close* the circle or not.

For example, for building a simple ellipse, in python:

```
# simple circle
Line(circle=(150, 150, 50))

# only from 90 to 180 degrees
Line(circle=(150, 150, 50, 90, 180))

# only from 90 to 180 degrees, with few segments
Line(circle=(150, 150, 50, 90, 180, 20))
```

New in version 1.4.1.

close

If True, the line will be closed.

New in version 1.4.1.

dash_length

Property for getting/setting the length of the dashes in the curve

New in version 1.0.8.

dash_offset

Property for getting/setting the offset between the dashes in the curve

New in version 1.0.8.

dashes

Property for getting/setting dashes.

List of [ON length, offset, ON length, offset, ...]. E.g. [2, 4, 1, 6, 8, 2] would create a line with the first dash length 2 then an offset of 4 then a dash length of 1 then an offset of 6 and so on.

New in version 1.11.0.

ellipse

Use this property to build an ellipse, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (x, y, width, height, angle_start, angle_end, segments):

- x and y represent the bottom left of the ellipse
- width and height represent the size of the ellipse
- (optional) angle_start and angle_end are in degree. The default value is 0 and 360.

- (optional) segments is the precision of the ellipse. The default value is calculated from the range between angle.

Note that it's up to you to *close* the ellipse or not.

For example, for building a simple ellipse, in python:

```
# simple ellipse
Line(ellipse=(0, 0, 150, 150))

# only from 90 to 180 degrees
Line(ellipse=(0, 0, 150, 150, 90, 180))

# only from 90 to 180 degrees, with few segments
Line(ellipse=(0, 0, 150, 150, 90, 180, 20))
```

New in version 1.4.1.

joint

Determine the join of the line, defaults to 'round'. Can be one of 'none', 'round', 'bevel', 'miter'.

New in version 1.4.1.

joint_precision

Number of iteration for drawing the "round" joint, defaults to 10. The joint_precision must be at least 1.

New in version 1.4.1.

points

Property for getting/settings points of the line

Warning: This will always reconstruct the whole graphics from the new points list. It can be very CPU expensive.

rectangle

Use this property to build a rectangle, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of (x, y, width, height):

- x and y represent the bottom-left position of the rectangle
- width and height represent the size

The line is automatically closed.

Usage:

```
Line(rectangle=(0, 0, 200, 200))
```

New in version 1.4.1.

rounded_rectangle

Use this property to build a rectangle, without calculating the *points*. You can only set this property, not get it.

The argument must be a tuple of one of the following forms:

- (x, y, width, height, corner_radius)
- (x, y, width, height, corner_radius, resolution)

- (x, y, width, height, corner_radius1, corner_radius2, corner_radius3, corner_radius4)
- (x, y, width, height, corner_radius1, corner_radius2, corner_radius3, corner_radius4, resolution)
 - x and y represent the bottom-left position of the rectangle
 - width and height represent the size
 - corner_radius is the number of pixels between two borders and the center of the circle arc joining them
 - resolution is the number of line segment that will be used to draw the circle arc at each corner (defaults to 30)

The line is automatically closed.

Usage:

```
Line(rounded_rectangle=(0, 0, 200, 200, 10, 20, 30, 40, 100))
```

New in version 1.9.0.

width

Determine the width of the line, defaults to 1.0.

New in version 1.4.1.

```
class kivy.graphics.vertex_instructions.Mesh(**kwargs)
Bases: kivy.graphics.instructions.VertexInstruction
```

In OpenGL ES 2.0 and in our graphics implementation, you cannot have more than 65535 indices.

A list of vertices is described as:

```
vertices = [x1, y1, u1, v1, x2, y2, u2, v2, ...]
           |   |   |   |
           +---+ i1 +---+ i2 +---+
```

If you want to draw a triangle, add 3 vertices. You can then make an indices list as follows:

```
indices = [0, 1, 2]
```

New in version 1.1.0.

Parameters

vertices: iterable List of vertices in the format (x1, y1, u1, v1, x2, y2, u2, v2...).
indices: iterable List of indices in the format (i1, i2, i3...).
mode: str Mode of the vbo. Check *mode* for more information. Defaults to ‘points’.
fmt: list The format for vertices, by default, each vertex is described by 2D coordinates (x, y) and 2D texture coordinate (u, v). Each element of the list should be a tuple or list, of the form

(variable_name, size, type)

which will allow mapping vertex data to the glsl instructions.

[('v_pos', 2, 'float'), ('v_tc', 2, 'float')]

will allow using

attribute vec2 v_pos; attribute vec2 v_tc;

in glsl’s vertex shader.

Changed in version 1.8.1: Before, *vertices* and *indices* would always be converted to a list, now, they are only converted to a list if they do not implement the buffer interface. So e.g. numpy arrays, python arrays etc. are used in place, without creating any additional copies. However, the buffers cannot be readonly (even though they are not changed, due to a cython limitation) and must be contiguous in memory.

Note: When passing a memoryview or a instance that implements the buffer interface, *vertices* should be a buffer of floats ('f' code in python array) and *indices* should be a buffer of unsigned short ('H' code in python array). Arrays in other formats will still have to be converted internally, negating any potential gain.

indices

Vertex indices used to specify the order when drawing the mesh.

mode

VBO Mode used for drawing vertices/indices. Can be one of 'points', 'line_strip', 'line_loop', 'lines', 'triangles', 'triangle_strip' or 'triangle_fan'.

vertices

List of x, y, u, v coordinates used to construct the Mesh. Right now, the Mesh instruction doesn't allow you to change the format of the vertices, which means it's only x, y + one texture coordinate.

```
class kivy.graphics.vertex_instructions.Point(**kwargs)
```

Bases: *kivy.graphics.instructions.VertexInstruction*

width/height of 2 times the *pointsize*.

Parameters

points: list List of points in the format (x1, y1, x2, y2...), where each pair of coordinates specifies the center of a new point.

pointsize: float, defaults to 1. The size of the point, measured from the center to the edge. A value of 1.0 therefore means the real size will be 2.0 x 2.0.

Warning: Starting from version 1.0.7, vertex instruction have a limit of 65535 vertices (indices of vertex to be accurate). 2 entries in the list (x, y) will be converted to 4 vertices. So the limit inside Point() class is $2^{15}-2$.

add_point(float x, float y)

Add a point to the current *points* list.

If you intend to add multiple points, prefer to use this method instead of reassigning a new *points* list. Assigning a new *points* list will recalculate and reupload the whole buffer into the GPU. If you use add_point, it will only upload the changes.

points

Property for getting/settings the center points in the points list. Each pair of coordinates specifies the center of a new point.

pointsize

Property for getting/setting point size. The size is measured from the center to the edge, so a value of 1.0 means the real size will be 2.0 x 2.0.

```
class kivy.graphics.vertex_instructions.Quad(**kwargs)
```

Bases: *kivy.graphics.instructions.VertexInstruction*

Parameters

points: list List of point in the format (x1, y1, x2, y2, x3, y3, x4, y4).

points

Property for getting/settings points of the quad.

class `kivy.graphics.vertex_instructions.Rectangle(**kwargs)`
Bases: `kivy.graphics.instructions.VertexInstruction`

Parameters

pos: list Position of the rectangle, in the format (x, y).

size: list Size of the rectangle, in the format (width, height).

pos

Property for getting/settings the position of the rectangle.

size

Property for getting/settings the size of the rectangle.

class `kivy.graphics.vertex_instructions.RoundedRectangle(**kwargs)`
Bases: `kivy.graphics.vertex_instructions.Rectangle`

New in version 1.9.1.

Parameters

segments: int, defaults to 10 Define how many segments are needed for drawing the rounded corner. The drawing will be smoother if you have many segments.

radius: list, defaults to [(10.0, 10.0), (10.0, 10.0), (10.0, 10.0), (10.0, 10.0)] Specifies the radii used for the rounded corners clockwise: top-left, top-right, bottom-right, bottom-left. Elements of the list can be numbers or tuples of two numbers to specify different x,y dimensions. One value will define all corner radii to be of this value. Four values will define each corner radius separately. Higher numbers of values will be truncated to four. The first value will be used for all corners if there are fewer than four values.

radius

Corner radii of the rounded rectangle, defaults to [10,].

segments

Property for getting/setting the number of segments for each corner.

class `kivy.graphics.vertex_instructions.SmoothLine(**kwargs)`
Bases: `kivy.graphics.vertex_instructions.Line`

results. It has few drawbacks:

- drawing a line with alpha will probably not have the intended result if the line crosses itself.
- `cap`, `joint` and `dash` properties are not supported.
- it uses a custom texture with a premultiplied alpha.
- lines under 1px in width are not supported: they will look the same.

Warning: This is an unfinished work, experimental, and subject to crashes.

New in version 1.9.0.

overdraw_width

Determine the overdraw width of the line, defaults to 1.2.

premultiplied_texture()

```
class kivy.graphics.vertex_instructions.Triangle(**kwargs)
Bases: kivy.graphics.instructions.VertexInstruction
```

Parameters

points: list List of points in the format (x1, y1, x2, y2, x3, y3).

points

Property for getting/settings points of the triangle.

INPUT MANAGEMENT

Our input system is wide and simple at the same time. We are currently able to natively support :

- Windows multitouch events (pencil and finger)
- OS X touchpads
- Linux multitouch events (kernel and mtdev)
- Linux wacom drivers (pencil and finger)
- TUOI

All the input management is configurable in the Kivy [config](#). You can easily use many multitouch devices in one Kivy application.

When the events have been read from the devices, they are dispatched through a post processing module before being sent to your application. We also have several default modules for :

- Double tap detection
- Decreasing jittering
- Decreasing the inaccuracy of touch on “bad” DIY hardware
- Ignoring regions

class `kivy.input.MotionEvent(device, id, args, is_touch=False, type_id=None)`
Bases: `kivy.input.motionevent.MotionEvent`

Abstract class that represents an input event.

Parameters

`id: str` unique ID of the MotionEvent

`args: list` list of parameters, passed to the depack() function

`apply_transform_2d(transform)`

Apply a transformation on x, y, z, px, py, pz, ox, oy, oz, dx, dy, dz.

`button`

Currently pressed button.

`copy_to(to)`

Copy some attribute to another motion event object.

`depack(args)`

Depack `args` into attributes of the class

`device`

Device used for creating this event.

dispatch_done()

Notify that dispatch to the listeners is done.

Called by the `EventLoopBase.post_dispatch_input()`.

New in version 2.1.0.

dispatch_mode

(Experimental) Used by a event manager or a widget to assign the dispatching mode. Defaults to `MODE_DEFAULT_DISPATCH`. See [eventmanager](#) for available modes.

New in version 2.1.0.

distance(*other_touch*)

Return the distance between the two events.

double_tap_time

If the touch is a `is_double_tap`, this is the time between the previous tap and the current touch.

property dpos

Return delta between last position and current position, in the screen coordinate system (`self.dx`, `self.dy`).

dsx

Delta between `self.sx` and `self.psx`, in 0-1 range.

dsy

Delta between `self.sy` and `self.psy`, in 0-1 range.

dsz

Delta between `self.sz` and `self.psz`, in 0-1 range.

dx

Delta between `self.x` and `self.px`, in window range.

dy

Delta between `self.y` and `self.py`, in window range.

dz

Delta between `self.z` and `self.pz`, in window range.

grab(*class_instance*, *exclusive=False*)

Grab this motion event.

If this event is a touch you can grab it if you want to receive subsequent `on_touch_move()` and `on_touch_up()` events, even if the touch is not dispatched by the parent:

```
def on_touch_down(self, touch):
    touch.grab(self)

def on_touch_move(self, touch):
    if touch.grab_current is self:
        # I received my grabbed touch
    else:
        # it's a normal touch

def on_touch_up(self, touch):
    if touch.grab_current is self:
        # I receive my grabbed touch, I must ungrab it!
        touch.ungrab(self)
    else:
```

(continues on next page)

```
# it's a normal touch
pass
```

Changed in version 2.1.0: Allowed grab for non-touch events.

grab_current

Used to determine which widget the event is being dispatched to. Check the [grab\(\)](#) function for more information.

id

Id of the event, not unique. This is generally the Id set by the input provider, like ID in TUIO. If you have multiple TUIO sources, then same id can be used. Prefer to use [uid](#) attribute instead.

is_double_tap

Indicate if the touch event is a double tap or not.

property is_mouse_scrolling

Returns True if the touch event is a mousewheel scrolling

New in version 1.6.0.

is_touch

True if the MotionEvent is a touch.

is_triple_tap

Indicate if the touch event is a triple tap or not.

New in version 1.7.0.

move(args)

Move to another position.

property opos

Return the initial position of the motion event in the screen coordinate system (self.ox, self.oy).

osx

Origin X position, in 0-1 range.

osy

Origin Y position, in 0-1 range.

osz

Origin Z position, in 0-1 range.

ox

Origin X position, in window range.

oy

Origin Y position, in window range.

oz

Origin Z position, in window range.

pop()

Pop attributes values from the stack.

pos

Position (X, Y), in window range.

property ppos

Return the previous position of the motion event in the screen coordinate system (self.px, self.py).

profile

Profiles currently used in the event.

psx

Previous X position, in 0-1 range.

psy

Previous Y position, in 0-1 range.

psz

Previous Z position, in 0-1 range.

push(attrs=None)

Push attribute values in *attrs* onto the stack.

push_attrs_stack

Attributes to push by default, when we use **push()** : x, y, z, dx, dy, dz, ox, oy, oz, px, py, pz.

px

Previous X position, in window range.

py

Previous Y position, in window range.

pz

Previous Z position, in window range.

scale_for_screen(w, h, p=None, rotation=0, smode='None', kheight=0)

Scale position for the screen.

Changed in version 2.1.0: Max value for *x*, *y* and *z* is changed respectively to *w* - 1, *h* - 1 and *p* - 1.

shape

Shape of the touch event, subclass of **Shape**. By default, the property is set to None.

property spos

Return the position in the 0-1 coordinate system (self.sx, self.sy).

sx

X position, in 0-1 range.

sy

Y position, in 0-1 range.

sync_with_dispatch

If set to *True* (default) keeps first previous position (X, Y, Z in 0-1 range) and ignore all other until **MotionEvent.dispatch_done()** is called from the *EventLoop*.

This attribute is needed because event provider can make many calls to **MotionEvent.move()**, but for all those calls event is dispatched to the listeners only once. Assigning *False* will keep latest previous position. See **MotionEvent.move()**.

New in version 2.1.0.

sz

Z position, in 0-1 range.

time_end

Time of the end event (last event usage).

time_start

Initial time of the event creation.

time_update

Time of the last update.

to_absolute_pos(*nx*, *ny*, *x_max*, *y_max*, *rotation*)

Transforms normalized (0-1) coordinates *nx* and *ny* to absolute coordinates using *x_max*, *y_max* and *rotation*.

Raises *ValueError*: If *rotation* is not one of: 0, 90, 180 or 270

New in version 2.1.0.

triple_tap_time

If the touch is a *is_triple_tap*, this is the time between the first tap and the current touch.

New in version 1.7.0.

type_id

(Experimental) String to identify event type.

New in version 2.1.0.

ud

User data dictionary. Use this dictionary to save your own data on the event.

uid

Uniq ID of the event. You can safely use this property, it will be never the same across all existing events.

ungrab(*class_instance*)

Ungrab a previously grabbed motion event.

x

X position, in window range.

y

Y position, in window range.

z

Z position, in window range.

class kivy.input.MotionEventFactory

Bases: `builtins.object`

MotionEvent factory is a class that registers all availables input factories. If you create a new input factory, you need to register it here:

```
MotionEventFactory.register('myproviderid', MyInputProvider)
```

static get(*name*)

Get a provider class from the provider id

static list()

Get a list of all available providers

static register(*name*, *classname*)

Register a input provider in the database

class kivy.input.MotionEventProvider(*device*, *args*)

Bases: `builtins.object`

Base class for a provider.

start()

Start the provider. This method is automatically called when the application is started and if the configuration uses the current provider.

stop()

Stop the provider.

update(*dispatch_fn*)

Update the provider and dispatch all the new touch events through the *dispatch_fn* argument.

38.1 Input Postprocessing

38.1.1 Calibration

New in version 1.9.0.

Recalibrate input device to a specific range / offset.

Let's say you have 3 1080p displays, the 2 firsts are multitouch. By default, both will have mixed touch, the range will conflict with each others: the 0-1 range will go to 0-5760 px (remember, $3 * 1920 = 5760$.)

To fix it, you need to manually reference them. For example:

```
[input]
left = mtdev,/dev/input/event17
middle = mtdev,/dev/input/event15
# the right screen is just a display.
```

Then, you can use the calibration postproc module:

```
[postproc:calibration]
left = xratio=0.3333
middle = xratio=0.3333,xoffset=0.3333
```

Now, the touches from the left screen will be within 0-0.3333 range, and the touches from the middle screen will be within 0.3333-0.6666 range.

You can also match calibration rules to devices based on their provider type. This is useful when probesysfs is used to match devices. For example:

```
[input]
mtdev_(name)s = probesysfs,provider=mtdev
```

Then to apply calibration to any mtdev device, you can assign rules to the provider name enclosed by parentheses:

```
[postproc:calibration]
(mtdev) = xratio=0.3333,xoffset=0.3333
```

Calibrating devices like this means the device's path doesn't need to be configured ahead of time. Note that with this method, all mtdev inputs will have the same calibration applied to them. For this reason, matching by provider will typically be useful when expecting only one input device.

class kivy.input.postproc.calibration.InputPostprocCalibration
Bases: `builtins.object`

Recalibrate the inputs.

The configuration must go within a section named *postproc:calibration*. Within the section, you must have a line like:

```
devicename = param=value,param=value
```

If you wish to match by provider, you must have a line like:

```
(provider) = param=value,param=value
```

Parameters

xratio: float Value to multiply X
yratio: float Value to multiply Y
xoffset: float Value to add to X
yoffset: float Value to add to Y
auto: str If set, then the touch is transformed from screen-relative to window-relative. The value is used as an indication of screen size, e.g for fullHD:

auto=1920x1080

If present, this setting overrides all the others. This assumes the input device exactly covers the display area, if they are different, the computations will be wrong.

Changed in version 1.11.0: Added *auto* parameter

38.1.2 Dejitter

Prevent blob jittering.

A problem that is often faced (esp. in optical MT setups) is that of jitterish BLOBs caused by bad camera characteristics. With this module you can get rid of that jitter. You just define a threshold *jitter_distance* in your config, and all touch movements that move the touch by less than the jitter distance are considered ‘bad’ movements caused by jitter and will be discarded.

class kivy.input.postproc.dejitter.InputPostprocDejitter
Bases: `builtins.object`

Get rid of jitterish BLOBs. Example:

```
[postproc]
jitter_distance = 0.004
jitter_ignore_devices = mouse,mactouch
```

Configuration

jitter_distance: float A float in range 0-1.
jitter_ignore_devices: string A comma-separated list of device identifiers that should not be processed by dejitter (because they’re very precise already).

38.1.3 Double Tap

Search touch for a double tap

class kivy.input.postproc.doubletap.InputPostprocDoubleTap
Bases: `builtins.object`

`InputPostProcDoubleTap` is a post-processor to check if a touch is a double tap or not. Double tap can be configured in the Kivy config file:

```
[postproc]
double_tap_time = 250
double_tap_distance = 20
```

Distance parameter is in the range 0-1000 and time is in milliseconds.

find_double_tap(ref)

Find a double tap touch within self.touches. The touch must be not a previous double tap and the distance must be within the specified threshold. Additionally, the touch profiles must be the same kind of touch.

38.1.4 Ignore list

Ignore touch on some areas of the screen

```
class kivy.input.postproc.ignorelist.InputPostprocIgnoreList
Bases: builtins.object
```

InputPostprocIgnoreList is a post-processor which removes touches in the Ignore list. The Ignore list can be configured in the Kivy config file:

```
[postproc]
# Format: [(xmin, ymin, xmax, ymax), ...]
ignore = [(0.1, 0.1, 0.15, 0.15)]
```

The Ignore list coordinates are in the range 0-1, not in screen pixels.

38.1.5 Retain Touch

Reuse touch to counter lost finger behavior

```
class kivy.input.postproc.retaintouch.InputPostprocRetainTouch
Bases: builtins.object
```

InputPostprocRetainTouch is a post-processor to delay the ‘up’ event of a touch, to reuse it under certain conditions. This module is designed to prevent lost finger touches on some hardware/setups.

Retain touch can be configured in the Kivy config file:

```
[postproc]
    retain_time = 100
    retain_distance = 50
```

The distance parameter is in the range 0-1000 and time is in milliseconds.

38.1.6 Triple Tap

New in version 1.7.0.

Search touch for a triple tap

```
class kivy.input.postproc.tripletap.InputPostprocTripleTap
Bases: builtins.object
```

InputPostProcTripleTap is a post-processor to check if a touch is a triple tap or not. Triple tap can be configured in the Kivy config file:

```
[postproc]
triple_tap_time = 250
triple_tap_distance = 20
```

The distance parameter is in the range 0-1000 and time is in milliseconds.

find_triple_tap(ref)

Find a triple tap touch within *self.touches*. The touch must be not be a previous triple tap and the distance must be within the bounds specified. Additionally, the touch profile must be the same kind of touch.

38.2 Providers

38.2.1 Android Joystick Input Provider

This module is based on the PyGame JoyStick Input Provider. For more information, please refer to <http://www.pygame.org/docs/ref/joystick.html>

```
class kivy.input.providers.androidjoystick.AndroidMotionEventProvider(device,
args)
```

Bases: *kivy.input.provider.MotionEventProvider*

start()

Start the provider. This method is automatically called when the application is started and if the configuration uses the current provider.

stop()

Stop the provider.

update(dispatch_fn)

Update the provider and dispatch all the new touch events though the *dispatch_fn* argument.

38.2.2 Auto Create Input Provider Config Entry for Available MT Hardware (linux only).

Thanks to Marc Tardif for the probing code, taken from scan-for-mt-device.

The device discovery is done by this provider. However, the reading of input can be performed by other providers like: hidinput, mtdev and linuxwacom. mtdev is used prior to other providers. For more information about mtdev, check [mtdev](#).

Here is an example of auto creation:

```
[input]
# using mtdev
device_(name)s = probesysfs,provider=mtdev
# using hidinput
device_(name)s = probesysfs,provider=hidinput
# using mtdev with a match on name
device_(name)s = probesysfs,provider=mtdev,match=acer

# using hidinput with custom parameters to hidinput (all on one line)
%(name)s = probesysfs,
    provider=hidinput,param=min_pressure=1,param=max_pressure=99
```

(continues on next page)

(continued from previous page)

```
# you can also match your wacom touchscreen
touch = probesysfs,match=E3 Finger,provider=linuxwacom,
    select_all=1,param=mode=touch
# and your wacom pen
pen = probesysfs,match=E3 Pen,provider=linuxwacom,
    select_all=1,param=mode=pen
```

By default, ProbeSysfs module will enumerate hardware from the /sys/class/input device, and configure hardware with ABS_MT_POSITION_X capability. But for example, the wacom screen doesn't support this capability. You can prevent this behavior by putting select_all=1 in your config line. Add use_mouse=1 to also include touchscreen hardware that offers core pointer functionality.

38.2.3 Common definitions for a Windows provider

This file provides common definitions for constants used by WM_Touch / WM_Pen.

38.2.4 Leap Motion - finger only

```
class kivy.input.providers.leapfinger.LeapFingerEvent(*args, **kwargs)
Bases: kivy.input.motionevent.MotionEvent

depack(args)
    Depack args into attributes of the class

class kivy.input.providers.leapfinger.LeapFingerEventProvider(device, args)
Bases: kivy.input.provider.MotionEventProvider

start()
    Start the provider. This method is automatically called when the application is started and if
    the configuration uses the current provider.

update(dispatch_fn)
    Update the provider and dispatch all the new touch events though the dispatch_fn argument.
```

38.2.5 Mouse provider implementation

On linux systems, the mouse provider can be annoying when used with another multitouch provider (hidinput or mtdev). The Mouse can conflict with them: a single touch can generate one event from the mouse provider and another from the multitouch provider.

To avoid this behavior, you can activate the "disable_on_activity" token in the mouse configuration. Then, if any touches are created by another provider, the mouse event will be discarded. Add this to your configuration:

```
[input]
mouse = mouse,disable_on_activity
```

Using multitouch interaction with the mouse

New in version 1.3.0.

By default, the middle and right mouse buttons, as well as a combination of ctrl + left mouse button are used for multitouch emulation. If you want to use them for other purposes, you can disable this behavior by activating the “`disable_multitouch`” token:

```
[input]
mouse = mouse,disable_multitouch
```

Changed in version 1.9.0.

You can now selectively control whether a click initiated as described above will emulate multi-touch. If the touch has been initiated in the above manner (e.g. right mouse button), a `multitouch_sim` value will be added to the touch’s profile, and a `multitouch_sim` property will be added to the touch. By default, `multitouch_sim` is `True` and multitouch will be emulated for that touch. If, however, `multitouch_on_demand` is added to the config:

```
[input]
mouse = mouse,multitouch_on_demand
```

then `multitouch_sim` defaults to `False`. In that case, if `multitouch_sim` is set to `True` before the mouse is released (e.g. in `on_touch_down/move`), the touch will simulate a multi-touch event. For example:

```
if 'multitouch_sim' in touch.profile:
    touch.multitouch_sim = True
```

Changed in version 2.1.0.

Provider dispatches hover events by listening to properties/events in `Window`. Dispatching can be disabled by setting `MouseMotionEventProvider.disable_hover` to `True` or by adding `disable_hover` in the config:

```
[input]
mouse = mouse,disable_hover
```

It’s also possible to enable/disable hover events at runtime with `MouseMotionEventProvider.disable_hover` property.

Following is a list of the supported values for the `profile` property list.

Profile value	Description
<code>button</code>	Mouse button (one of <code>left</code> , <code>right</code> , <code>middle</code> , <code>scrollup</code> or <code>scrolldown</code>). Accessed via the ‘button’ property.
<code>pos</code>	2D position. Also reflected in the <code>x</code> , <code>y</code> and <code>pos</code> properties.
<code>multi-touch_sim</code>	Specifies whether multitouch is simulated or not. Accessed via the ‘ <code>multitouch_sim</code> ’ property.

```
class kivy.input.providers.mouse.MouseMotionEventProvider(device, args)
Bases: kivy.input.provider.MotionEventProvider

property disable_hover
    Disables dispatching of hover events if set to True.

    Hover events are enabled by default (disable_hover is False). See module documentation if
    you want to enable/disable hover events through config file.

New in version 2.1.0.
```

```

start()
    Start the mouse provider

stop()
    Stop the mouse provider

update(dispatch_fn)
    Update the mouse provider (pop event from the queue)

```

38.2.6 Native support for HID input from the linux kernel

Support starts from 2.6.32-ubuntu, or 2.6.34.

To configure HIDInput, add this to your configuration:

```

[input]
# devicename = hidinput,/dev/input/eventXX
# example with Stantum MTP4.3" screen
stantum = hidinput,/dev/input/event2

```

Note: You must have read access to the input event.

You can use a custom range for the X, Y and pressure values. For some drivers, the range reported is invalid. To fix that, you can add these options to the argument line:

- invert_x : 1 to invert X axis
- invert_y : 1 to invert Y axis
- min_position_x : X relative minimum
- max_position_x : X relative maximum
- min_position_y : Y relative minimum
- max_position_y : Y relative maximum
- min_abs_x : X absolute minimum
- min_abs_y : Y absolute minimum
- max_abs_x : X absolute maximum
- max_abs_y : Y absolute maximum
- min_pressure : pressure minimum
- max_pressure : pressure maximum
- rotation : rotate the input coordinate (0, 90, 180, 270)

For example, on the Asus T101M, the touchscreen reports a range from 0-4095 for the X and Y values, but the real values are in a range from 0-32768. To correct this, you can add the following to the configuration:

```

[input]
t101m = hidinput,/dev/input/event7,max_position_x=32768,max_position_
→y=32768

```

New in version 1.9.1: *rotation* configuration token added.

```

class kivy.input.providers.hidinput.HIDMotionEvent(*args, **kwargs)
    Bases: kivy.input.motionevent.MotionEvent

```

depack(args)

Depack *args* into attributes of the class

38.2.7 Native support for Multitouch devices on Linux, using libmtdev.

The Mtdev project is a part of the Ubuntu Maverick multitouch architecture. You can read more on <http://wiki.ubuntu.com/Multitouch>

To configure MTDev, it's preferable to use probesysfs providers. Check *probesysfs* for more information.

Otherwise, add this to your configuration:

```
[input]
# devicename = hidinput,/dev/input/eventXX
acert230h = mtdev,/dev/input/event2
```

Note: You must have read access to the input event.

You can use a custom range for the X, Y and pressure values. On some drivers, the range reported is invalid. To fix that, you can add these options to the argument line:

- invert_x : 1 to invert X axis
- invert_y : 1 to invert Y axis
- min_position_x : X minimum
- max_position_x : X maximum
- min_position_y : Y minimum
- max_position_y : Y maximum
- min_pressure : pressure minimum
- max_pressure : pressure maximum
- min_touch_major : width shape minimum
- max_touch_major : width shape maximum
- min_touch_minor : height shape minimum
- max_touch_minor : height shape maximum
- rotation : 0,90,180 or 270 to rotate

An inverted display configuration will look like this:

```
[input]
# example for inverting touch events
display = mtdev,/dev/input/event0,invert_x=1,invert_y=1
```

```
class kivy.input.providers.mtdev.MTDMotionEvent(*args, **kwargs)
Bases: kivy.input.motionevent.MotionEvent
```

depack(args)

Depack *args* into attributes of the class

38.2.8 Native support of MultitouchSupport framework for MacBook (MaxOSX platform)

```
class kivy.input.providers.mactouch.MacMotionEventProvider(*largs, **kwargs)
Bases: kivy.input.provider.MotionEventProvider

start()
    Start the provider. This method is automatically called when the application is started and if
    the configuration uses the current provider.

stop()
    Stop the provider.

update(dispatch_fn)
    Update the provider and dispatch all the new touch events though the dispatch_fn argument.
```

38.2.9 Native support of Wacom tablet from linuxwacom driver

To configure LinuxWacom, add this to your configuration:

```
[input]
pen = linuxwacom,/dev/input/event2,mode=pen
finger = linuxwacom,/dev/input/event3,mode=touch
```

Note: You must have read access to the input event.

You can use a custom range for the X, Y and pressure values. On some drivers, the range reported is invalid. To fix that, you can add these options to the argument line:

- invert_x : 1 to invert X axis
- invert_y : 1 to invert Y axis
- min_position_x : X minimum
- max_position_x : X maximum
- min_position_y : Y minimum
- max_position_y : Y maximum
- min_pressure : pressure minimum
- max_pressure : pressure maximum

```
class kivy.input.providers.linuxwacom.LinuxWacomMotionEvent(*args, **kwargs)
Bases: kivy.input.motionevent.MotionEvent

depack(args)
    Depack args into attributes of the class
```

38.2.10 TUO Input Provider

TUO is the de facto standard network protocol for the transmission of touch and fiducial information between a server and a client. To learn more about TUO (which is itself based on the OSC protocol), please refer to <http://tuio.org> – The specification should be of special interest.

Configure a TUO provider in the config.ini

The TUO provider can be configured in the configuration file in the [input] section:

```
[input]
# name = tuio,<ip>:<port>
multitouchtable = tuio,192.168.0.1:3333
```

Configure a TUO provider in the App

You must add the provider before your application is run, like this:

```
from kivy.app import App
from kivy.config import Config

class TestApp(App):
    def build(self):
        Config.set('input', 'multitouchscreen1', 'tuio,0.0.0.0:3333')
        # You can also add a second TUO listener
        # Config.set('input', 'source2', 'tuio,0.0.0.0:3334')
        # Then do the usual things
        #
    return
```

class kivy.input.providers.tuio.Tuio2dCurMotionEvent(*args, **kwargs)
Bases: kivy.input.providers.tuio.TuioMotionEvent

A 2dCur TUO touch.

depack(args)

Depack args into attributes of the class

class kivy.input.providers.tuio.Tuio2dObjMotionEvent(*args, **kwargs)
Bases: kivy.input.providers.tuio.TuioMotionEvent

A 2dObj TUO object.

depack(args)

Depack args into attributes of the class

class kivy.input.providers.tuio.TuioMotionEventProvider(device, args)
Bases: [kivy.input.provider.MotionEventProvider](#)

The TUO provider listens to a socket and handles some of the incoming OSC messages:

- /tuio/2Dcur
- /tuio/2Dobj

You can easily extend the provider to handle new TUO paths like so:

```

# Create a class to handle the new TUIO type/path
# Replace NEWPATH with the pathname you want to handle
class TuioNEWPATHMotionEvent(MotionEvent):

    def depack(self, args):
        # In this method, implement 'unpacking' for the received
        # arguments. You basically translate from TUIO args to Kivy
        # MotionEvent variables. If all you receive are x and y
        # values, you can do it like this:
        if len(args) == 2:
            self.sx, self.sy = args
            self.profile = ('pos', )
            self.sy = 1 - self.sy
        super().depack(args)

    # Register it with the TUIO MotionEvent provider.
    # You obviously need to replace the PATH placeholders appropriately.
    TuioMotionEventProvider.register('/tuio/PATH', TuioNEWPATHMotionEvent)

```

Note: The class name is of no technical importance. Your class will be associated with the path that you pass to the `register()` function. To keep things simple, you should name your class after the path that it handles, though.

```

static create(oscpath, **kwargs)
    Create a touch event from a TUIO path

static register(oscpath, classname)
    Register a new path to handle in TUIO provider

start()
    Start the TUIO provider

stop()
    Stop the TUIO provider

static unregister(oscpath, classname)
    Unregister a path to stop handling it in the TUIO provider

update(dispatch_fn)
    Update the TUIO provider (pop events from the queue)

```

38.3 Input recorder

New in version 1.1.0.

Warning: This part of Kivy is still experimental and this API is subject to change in a future version.

This is a class that can record and replay some input events. This can be used for test cases, screen savers etc.

Once activated, the recorder will listen for any input event and save its properties in a file with the delta time. Later, you can play the input file: it will generate fake touch events with the saved properties and dispatch it to the event loop.

By default, only the position is saved ('pos' profile and 'sx', 'sy', attributes). Change it only if you understand how input handling works.

38.3.1 Recording events

The best way is to use the “recorder” module. Check the [Modules](#) documentation to see how to activate a module.

Once activated, you can press F8 to start the recording. By default, events will be written to `<current-path>/recorder.kvi`. When you want to stop recording, press F8 again.

You can replay the file by pressing F7.

Check the [Recorder module](#) module for more information.

38.3.2 Manual play

You can manually open a recorder file, and play it by doing:

```
from kivy.input.recorder import Recorder  
  
rec = Recorder(filename='myrecorder.kvi')  
rec.play = True
```

If you want to loop over that file, you can do:

```
from kivy.input.recorder import Recorder  
  
def recorder_loop(instance, value):  
    if value is False:  
        instance.play = True  
  
rec = Recorder(filename='myrecorder.kvi')  
rec.bind(play=recorder_loop)  
rec.play = True
```

38.3.3 Recording more attributes

You can extend the attributes to save on one condition: attributes values must be simple values, not instances of complex classes.

Let's say you want to save the angle and pressure of the touch, if available:

```
from kivy.input.recorder import Recorder  
  
rec = Recorder(filename='myrecorder.kvi',  
    record_attrs=['is_touch', 'sx', 'sy', 'angle', 'pressure'],  
    record_profile_mask=['pos', 'angle', 'pressure'])  
rec.record = True
```

Or with modules variables:

```
$ python main.py -m recorder,attrs=is_touch:sx:sy:angle:pressure,  
    ↴ profile_mask=pos:angle:pressure
```

38.3.4 Known limitations

- Unable to save attributes with instances of complex classes.
- Values that represent time will not be adjusted.
- Can replay only complete records. If a begin/update/end event is missing, this could lead to ghost touches.
- Stopping the replay before the end can lead to ghost touches.

class `kivy.input.recorder.Recorder(**kwargs)`
Bases: `kivy.event.EventDispatcher`

Recorder class. Please check module documentation for more information.

Events

`on_stop`: Fired when the playing stops.

Changed in version 1.10.0: Event `on_stop` added.

counter

Number of events recorded in the last session.

`counter` is a `NumericProperty` and defaults to 0, read-only.

filename

Filename to save the output of the recorder.

`filename` is a `StringProperty` and defaults to ‘recorder.kvi’.

play

Boolean to start/stop the replay of the current file (if it exists).

`play` is a `BooleanProperty` and defaults to False.

record

Boolean to start/stop the recording of input events.

`record` is a `BooleanProperty` and defaults to False.

record_attrs

Attributes to record from the motion event.

`record_attrs` is a `ListProperty` and defaults to ['is_touch', 'sx', 'sy'].

record_profile_mask

Profile to save in the fake motion event when replayed.

`record_profile_mask` is a `ListProperty` and defaults to ['pos'].

window

Window instance to attach the recorder. If None, it will use the default instance.

`window` is a `ObjectProperty` and defaults to None.

38.4 Motion Event

The `MotionEvent` is the base class used for events provided by pointing devices (touch and non-touch). This class defines all the properties and methods needed to handle 2D and 3D movements but has many more capabilities.

Usually you would never need to create the `MotionEvent` yourself as this is the role of the `providers`.

38.4.1 Flow of the motion events

1. The `MotionEvent`'s are gathered from input providers by `EventLoopBase`.
2. Post processing is performed by registered processors `postproc`.
3. `EventLoopBase` dispatches all motion events using `on_motion` event to all registered listeners including the `WindowBase`.
4. Once received in `on_motion()` events (touch or non-touch) are all registered managers. If a touch event is not handled by at least one manager, then it is dispatched through `on_touch_down()`, `on_touch_move()` and `on_touch_up()`.
5. Widgets receive events in `on_motion()` method (if passed by a manager) or on `on_touch_xxx` methods.

38.4.2 Motion events and event managers

A motion event is a touch event if its `MotionEvent.is_touch` is set to `True`. Beside `is_touch` attribute, `MotionEvent.type_id` can be used to check for event's general type. Currently two types are dispatched by input providers: "touch" and "hover".

Event managers can be used to dispatch any motion event throughout the widget tree and a manager uses `type_id` to specify which event types it want to receive. See `eventmanager` to learn how to define and register an event manager.

A manager can also assign a new `type_id` to `MotionEvent.type_id` before dispatching it to the widgets. This useful when dispatching a specific event:

```
class MouseTouchManager(EventManagerBase):  
  
    type_ids = ('touch',)  
  
    def dispatch(self, etype, me):  
        accepted = False  
        if me.device == 'mouse':  
            me.push() # Save current type_id and other values  
            me.type_id = 'mouse_touch'  
            self.window.transform_motion_event_2d(me)  
            # Dispatch mouse touch event to widgets which registered  
            # to receive 'mouse_touch'  
            for widget in self.window.children[:]:  
                if widget.dispatch('on_motion', etype, me):  
                    accepted = True  
                    break  
            me.pop() # Restore  
        return accepted
```

38.4.3 Listening to a motion event

If you want to receive all motion events, touch or not, you can bind the MotionEvent from the Window to your own callback:

```
def on_motion(self, etype, me):
    # will receive all motion events.
    pass

Window.bind(on_motion=on_motion)
```

You can also listen to changes of the mouse position by watching `mouse_pos`.

38.4.4 Profiles

The `MotionEvent` stores device specific information in various properties listed in the `profile`. For example, you can receive a MotionEvent that has an angle, a fiducial ID, or even a shape. You can check the `profile` attribute to see what is currently supported by the MotionEvent provider.

This is a short list of the profile values supported by default. Please check the `MotionEvent.profile` property to see what profile values are available.

Profile value	Description
angle	2D angle. Accessed via the <code>a</code> property.
button	Mouse button ('left', 'right', 'middle', 'scrollup' or 'scrolldown'). Accessed via the <code>button</code> property.
markerid	Marker or Fiducial ID. Accessed via the <code>fid</code> property.
pos	2D position. Accessed via the <code>x</code> , <code>y</code> or <code>pos</code> properties.
pos3d	3D position. Accessed via the <code>x</code> , <code>y</code> or <code>z</code> properties.
pressure	Pressure of the contact. Accessed via the <code>pressure</code> property.
shape	Contact shape. Accessed via the <code>shape</code> property .

If you want to know whether the current `MotionEvent` has an angle:

```
def on_touch_move(self, touch):
    if 'angle' in touch.profile:
        print('The touch angle is', touch.a)
```

If you want to select only the fiducials:

```
def on_touch_move(self, touch):
    if 'markerid' not in touch.profile:
        return
```

class `kivy.input.motionevent.MotionEvent`(`device, id, args, is_touch=False, type_id=None`)
Bases: `kivy.input.motionevent.MotionEvent`

Abstract class that represents an input event.

Parameters

`id: str` unique ID of the MotionEvent

`args: list` list of parameters, passed to the `depack()` function

`apply_transform_2d(transform)`

Apply a transformation on x, y, z, px, py, pz, ox, oy, oz, dx, dy, dz.

button

Currently pressed button.

copy_to(*to*)

Copy some attribute to another motion event object.

depack(*args*)

D unpack *args* into attributes of the class

device

Device used for creating this event.

dispatch_done()

Notify that dispatch to the listeners is done.

Called by the `EventLoopBase.post_dispatch_input()`.

New in version 2.1.0.

dispatch_mode

(Experimental) Used by a event manager or a widget to assign the dispatching mode. Defaults to `MODE_DEFAULT_DISPATCH`. See `eventmanager` for available modes.

New in version 2.1.0.

distance(*other_touch*)

Return the distance between the two events.

double_tap_time

If the touch is a `is_double_tap`, this is the time between the previous tap and the current touch.

property dpos

Return delta between last position and current position, in the screen coordinate system (`self.dx`, `self.dy`).

dsx

Delta between `self.sx` and `self.psx`, in 0-1 range.

dsy

Delta between `self.sy` and `self.psy`, in 0-1 range.

dsz

Delta between `self.sz` and `self.psz`, in 0-1 range.

dx

Delta between `self.x` and `self.px`, in window range.

dy

Delta between `self.y` and `self.py`, in window range.

dz

Delta between `self.z` and `self.pz`, in window range.

grab(*class_instance*, *exclusive=False*)

Grab this motion event.

If this event is a touch you can grab it if you want to receive subsequent `on_touch_move()` and `on_touch_up()` events, even if the touch is not dispatched by the parent:

```
def on_touch_down(self, touch):
    touch.grab(self)

def on_touch_move(self, touch):
    if touch.grab_current is self:
```

(continues on next page)

```

# I received my grabbed touch
else:
    # it's a normal touch

def on_touch_up(self, touch):
    if touch.grab_current is self:
        # I receive my grabbed touch, I must ungrab it!
        touch.ungrab(self)
    else:
        # it's a normal touch
        pass

```

Changed in version 2.1.0: Allowed grab for non-touch events.

grab_current

Used to determine which widget the event is being dispatched to. Check the [grab\(\)](#) function for more information.

id

Id of the event, not unique. This is generally the Id set by the input provider, like ID in TUO. If you have multiple TUO sources, then same id can be used. Prefer to use [uid](#) attribute instead.

is_double_tap

Indicate if the touch event is a double tap or not.

property is_mouse_scrolling

Returns True if the touch event is a mousewheel scrolling

New in version 1.6.0.

is_touch

True if the MotionEvent is a touch.

is_triple_tap

Indicate if the touch event is a triple tap or not.

New in version 1.7.0.

move(args)

Move to another position.

property opos

Return the initial position of the motion event in the screen coordinate system (self.ox, self.oy).

osx

Origin X position, in 0-1 range.

osy

Origin Y position, in 0-1 range.

osz

Origin Z position, in 0-1 range.

ox

Origin X position, in window range.

oy

Origin Y position, in window range.

oz

Origin Z position, in window range.

pop()

Pop attributes values from the stack.

pos

Position (X, Y), in window range.

property ppos

Return the previous position of the motion event in the screen coordinate system (self.px, self.py).

profile

Profiles currently used in the event.

psx

Previous X position, in 0-1 range.

psy

Previous Y position, in 0-1 range.

psz

Previous Z position, in 0-1 range.

push(attrs=None)

Push attribute values in *attrs* onto the stack.

push_attrs_stack

Attributes to push by default, when we use **push()** : x, y, z, dx, dy, dz, ox, oy, oz, px, py, pz.

px

Previous X position, in window range.

py

Previous Y position, in window range.

pz

Previous Z position, in window range.

scale_for_screen(w, h, p=None, rotation=0, smode='None', kheight=0)

Scale position for the screen.

Changed in version 2.1.0: Max value for *x*, *y* and *z* is changed respectively to *w* - 1, *h* - 1 and *p* - 1.

shape

Shape of the touch event, subclass of **Shape**. By default, the property is set to None.

property spos

Return the position in the 0-1 coordinate system (self.sx, self.sy).

sx

X position, in 0-1 range.

sy

Y position, in 0-1 range.

sync_with_dispatch

If set to *True* (default) keeps first previous position (X, Y, Z in 0-1 range) and ignore all other until **MotionEvent.dispatch_done()** is called from the *EventLoop*.

This attribute is needed because event provider can make many calls to **MotionEvent.move()**, but for all those calls event is dispatched to the listeners only once. Assigning *False* will keep latest previous position. See **MotionEvent.move()**.

New in version 2.1.0.

sz

Z position, in 0-1 range.

time_end

Time of the end event (last event usage).

time_start

Initial time of the event creation.

time_update

Time of the last update.

to_absolute_pos(*nx*, *ny*, *x_max*, *y_max*, *rotation*)

Transforms normalized (0-1) coordinates *nx* and *ny* to absolute coordinates using *x_max*, *y_max* and *rotation*.

Raises *ValueError*: If *rotation* is not one of: 0, 90, 180 or 270

New in version 2.1.0.

triple_tap_time

If the touch is a *is_triple_tap*, this is the time between the first tap and the current touch.

New in version 1.7.0.

type_id

(Experimental) String to identify event type.

New in version 2.1.0.

ud

User data dictionary. Use this dictionary to save your own data on the event.

uid

Uniq ID of the event. You can safely use this property, it will be never the same across all existing events.

ungrab(*class_instance*)

Ungrab a previously grabbed motion event.

x

X position, in window range.

y

Y position, in window range.

z

Z position, in window range.

38.5 Motion Event Factory

Factory of *MotionEvent* providers.

class kivy.input.factory.**MotionEventFactory**
Bases: `builtins.object`

MotionEvent factory is a class that registers all availables input factories. If you create a new input factory, you need to register it here:

```
MotionEventFactory.register('myproviderid', MyInputProvider)
```

```
static get(name)
    Get a provider class from the provider id

static list()
    Get a list of all available providers

static register(name, classname)
    Register a input provider in the database
```

38.6 Motion Event Provider

Abstract class for the implementation of a *MotionEvent* provider. The implementation must support the *start()*, *stop()* and *update()* methods.

```
class kivy.input.provider.MotionEventProvider(device, args)
    Bases: builtins.object

    Base class for a provider.

start()
    Start the provider. This method is automatically called when the application is started and if
    the configuration uses the current provider.

stop()
    Stop the provider.

update(dispatch_fn)
    Update the provider and dispatch all the new touch events though the dispatch_fn argument.
```

38.7 Motion Event Shape

Represent the shape of the *MotionEvent*

```
class kivy.input.shape.Shape
    Bases: builtins.object

    Abstract class for all implementations of a shape

class kivy.input.shape.ShapeRect
    Bases: kivy.input.shape.Shape

    Class for the representation of a rectangle.

height
    Height of the rect

width
    Width of the rect
```


KIVY LANGUAGE

The Kivy language is a language dedicated to describing user interface and interactions. You could compare this language to Qt's QML (<http://qt.nokia.com>), but we included new concepts such as rule definitions (which are somewhat akin to what you may know from CSS), templating and so on.

Changed in version 1.7.0: The Builder doesn't execute canvas expressions in realtime anymore. It will pack all the expressions that need to be executed first and execute them after dispatching input, just before drawing the frame. If you want to force the execution of canvas drawing, just call *Builder.sync*.

An experimental profiling tool for the kv lang is also included. You can activate it by setting the environment variable *KIVY_PROFILE_LANG=1*. It will then generate an html file named *builder_stats.html*.

39.1 Overview

The language consists of several constructs that you can use:

Rules A rule is similar to a CSS rule. A rule applies to specific widgets (or classes thereof) in your widget tree and modifies them in a certain way. You can use rules to specify interactive behaviour or use them to add graphical representations of the widgets they apply to. You can target a specific class of widgets (similar to the CSS concept of a *class*) by using the `cls` attribute (e.g. `cls=MyTestWidget`).

A Root Widget You can use the language to create your entire user interface. A kv file must contain only one root widget at most.

Dynamic Classes (*introduced in version 1.7.0*) Dynamic classes let you create new widgets and rules on-the-fly, without any Python declaration.

Templates (deprecated) (*introduced in version 1.0.5, deprecated from version 1.7.0*) Templates were used to populate parts of an application, such as styling the content of a list (e.g. icon on the left, text on the right). They are now deprecated by dynamic classes.

39.2 Syntax of a kv File

A Kivy language file must have `.kv` as filename extension.

The content of the file should always start with the Kivy header, where *version* must be replaced with the Kivy language version you're using. For now, use 1.0:

```
#:kivy `1.0`  
  
# content here
```

The *content* can contain rule definitions, a root widget, dynamic class definitions and templates:

```
# Syntax of a rule definition. Note that several Rules can share the same
# definition (as in CSS). Note the braces: they are part of the definition.
<Rule1,Rule2>:
    # .. definitions ..

<Rule3>:
    # .. definitions ..

# Syntax for creating a root widget
RootClassName:
    # .. definitions ..

# Syntax for creating a dynamic class
<NewWidget@BaseClass>:
    # .. definitions ..

# Syntax for create a template
[TemplateName@BaseClass1,BaseClass2]:
    # .. definitions ..
```

Regardless of whether it's a rule, root widget, dynamic class or template you're defining, the definition should look like this:

```
# With the braces it's a rule. Without them, it's a root widget.
<ClassName>:
    prop1: value1
    prop2: value2

    canvas:
        CanvasInstruction1:
            canvasprop1: value1
        CanvasInstruction2:
            canvasprop2: value2

    AnotherClass:
        prop3: value1
```

Here *prop1* and *prop2* are the properties of *ClassName* and *prop3* is the property of *AnotherClass*. If the widget doesn't have a property with the given name, an *ObjectProperty* will be automatically created and added to the widget.

AnotherClass will be created and added as a child of the *ClassName* instance.

- The indentation is important and must be consistent. The spacing must be a multiple of the number of spaces used on the first indented line. Spaces are encouraged: mixing tabs and spaces is not recommended.
- The value of a property must be given on a single line (for now at least).
- Keep class names capitalized to avoid syntax errors.
- The *canvas* property is special: you can put graphics instructions in it to create a graphical representation of the current class.

Here is a simple example of a kv file that contains a root widget:

```
#:kivy 1.0

Button:
    text: 'Hello world'
```

Changed in version 1.7.0: The indentation is not limited to 4 spaces anymore. The spacing must be a multiple of the number of spaces used on the first indented line.

Both the `load_file()` and the `load_string()` methods return the root widget defined in your kv file/string. They will also add any class and template definitions to the `Factory` for later usage.

39.3 Value Expressions, on_property Expressions, ids, and Reserved Keywords

When you specify a property's value, the value is evaluated as a Python expression. This expression can be static or dynamic, which means that the value can use the values of other properties using reserved keywords.

self The keyword self references the “current widget instance”:

```
Button:
    text: 'My state is %s' % self.state
```

root This keyword is available only in rule definitions and represents the root widget of the rule (the first instance of the rule):

```
<MyWidget>:
    custom: 'Hello world'
    Button:
        text: root.custom
```

app This keyword always refers to your app instance. It's equivalent to a call to `kivy.app.App.get_running_app()` in Python.

```
Label:
    text: app.name
```

args This keyword is available in on_<action> callbacks. It refers to the arguments passed to the callback.

```
TextInput:
    on_focus: self.insert_text("Focus" if args[1] else "No_
        focus")
```

Changed in version 2.1.0: f-strings are now parsed in value expressions, allowing to bind to the properties that they contain.

39.3.1 ids

Class definitions may contain ids which can be used as a keywords::

```
<MyWidget>:  
    Button:  
        id: btn1  
    Button:  
        text: 'The state of the other button is %s' % btn1.state
```

Please note that the *id* will not be available in the widget instance: it is used exclusively for external references. *id* is a weakref to the widget, and not the widget itself. The widget itself can be accessed with `<id>.__self__` (`btn1.__self__` in this case).

When the kv file is processed, weakrefs to all the widgets tagged with ids are added to the root widget's *ids* dictionary. In other words, following on from the example above, the buttons state could also be accessed as follows:

```
widget = MyWidget()  
state = widget.ids["btn1"].state  
  
# Or, as an alternative syntax,  
state = widget.ids.btn1.state
```

Note that the outermost widget applies the kv rules to all its inner widgets before any other rules are applied. This means if an inner widget contains ids, these ids may not be available during the inner widget's `__init__` function.

39.3.2 Valid expressions

There are two places that accept python statements in a kv file: after a property, which assigns to the property the result of the expression (such as the text of a button as shown above) and after a `on_property`, which executes the statement when the property is updated (such as `on_state`).

In the former case, the `expression` can only span a single line, cannot be extended to multiple lines using newline escaping, and must return a value. An example of a valid expression is `text: self.state` and `('up' if self.state == 'normal' else 'down')`.

In the latter case, multiple single line statements are valid, including those that escape their newline, as long as they don't add an indentation level.

Examples of valid statements are:

```
on_press: if self.state == 'normal': print('normal')  
on_state:  
    if self.state == 'normal': print('normal')  
    else: print('down')  
    if self.state == 'normal': \  
        print('multiline normal')  
    for i in range(10): print(i)  
    print([1,2,3,4,  
          5,6,7])
```

An example of a invalid statement:

```
on_state:  
    if self.state == 'normal':  
        print('normal')
```

39.4 Relation Between Values and Properties

When you use the Kivy language, you might notice that we do some work behind the scenes to automatically make things work properly. You should know that *Properties* implement the **Observer Design Pattern**. That means that you can bind your own function to be called when the value of a property changes (i.e. you passively *observe* the property for potential changes).

The Kivy language detects properties in your *value* expression and will create callbacks to automatically update the property via your expression when changes occur.

Here's a simple example that demonstrates this behaviour:

```
Button:  
    text: str(self.state)
```

In this example, the parser detects that *self.state* is a dynamic value (a property). The *state* property of the button can change at any moment (when the user touches it). We now want this button to display its own state as text, even as the state changes. To do this, we use the *state* property of the Button and use it in the value expression for the button's *text* property, which controls what text is displayed on the button (We also convert the state to a string representation). Now, whenever the button state changes, the *text* property will be updated automatically.

Remember: The value is a python expression! That means that you can do something more interesting like:

```
Button:  
    text: 'Plop world' if self.state == 'normal' else 'Release me!'
```

The Button text changes with the state of the button. By default, the button text will be 'Plop world', but when the button is being pressed, the text will change to 'Release me!'.

More precisely, the kivy language parser detects all substrings of the form *X.a.b* where *X* is *self* or *root* or *app* or a known id, and *a* and *b* are properties: it then adds the appropriate dependencies to cause the constraint to be reevaluated whenever something changes. For example, this works exactly as expected:

```
<IndexedExample>:  
    beta: self.a.b[self.c.d]
```

However, due to limitations in the parser which hopefully may be lifted in the future, the following doesn't work:

```
<BadExample>:  
    beta: self.a.b[self.c.d].e.f
```

indeed the *.f* part is not recognized because it doesn't follow the expected pattern, and so, does not result in an appropriate dependency being setup. Instead, an intermediate property should be introduced to allow the following constraint:

```
<GoodExample>:  
    alpha: self.a.b[self.c.d]  
    beta: self.alpha.e.f
```

In addition, properties in python f-strings are also not yet supported:

```
<FStringExample>:  
    text: f"I want to use {self.a} in property"
```

Instead, the `format()` method should be used:

```
<FormatStringExample>:  
    text: "I want to use {} in property".format(self.a)
```

39.5 Graphical Instructions

The graphical instructions are a special part of the Kivy language. They are handled by the 'canvas' property definition:

```
Widget:  
    canvas:  
        Color:  
            rgb: (1, 1, 1)  
        Rectangle:  
            size: self.size  
            pos: self.pos
```

All the classes added inside the `canvas` property must be derived from the *Instruction* class. You cannot put any `Widget` class inside the `canvas` property (as that would not make sense because a widget is not a graphics instruction).

If you want to do theming, you'll have the same question as in CSS: which rules have been executed first? In our case, the rules are executed in processing order (i.e. top-down).

If you want to change how Buttons are rendered, you can create your own kv file and add something like this:

```
<Button>:  
    canvas:  
        Color:  
            rgb: (1, 0, 0)  
        Rectangle:  
            pos: self.pos  
            size: self.size  
        Rectangle:  
            pos: self.pos  
            size: self.texture_size  
            texture: self.texture
```

This will result in buttons having a red background with the label in the bottom left, in addition to all the preceding rules. You can clear all the previous instructions by using the `Clear` command:

```
<Button>:  
    canvas:  
        Clear  
        Color:  
            rgb: (1, 0, 0)  
        Rectangle:  
            pos: self.pos
```

(continues on next page)

```

    size: self.size
Rectangle:
    pos: self.pos
    size: self.texture_size
    texture: self.texture

```

Then, only your rules that follow the *Clear* command will be taken into consideration.

39.6 Dynamic classes

Dynamic classes allow you to create new widgets on-the-fly, without any python declaration in the first place. The syntax of the dynamic classes is similar to the Rules, but you need to specify the base classes you want to subclass.

The syntax looks like:

```

# Simple inheritance
<NewWidget@Button>:
    # kv code here ...

# Multiple inheritance
<NewWidget@ButtonBehavior+Label>:
    # kv code here ...

```

The @ character is used to separate your class name from the classes you want to subclass. The Python equivalent would have been:

```

# Simple inheritance
class NewWidget(Button):
    pass

# Multiple inheritance
class NewWidget(ButtonBehavior, Label):
    pass

```

Any new properties, usually added in python code, should be declared first. If the property doesn't exist in the dynamic class, it will be automatically created as an *ObjectProperty* (pre 1.8.0) or as an appropriate typed property (from version 1.8.0).

Changed in version 1.8.0: If the property value is an expression that can be evaluated right away (no external binding), then the value will be used as default value of the property, and the type of the value will be used for the specialization of the Property class. In other terms: if you declare *hello: "world"*, a new *StringProperty* will be instantiated, with the default value "world". Lists, tuples, dictionaries and strings are supported.

Let's illustrate the usage of these dynamic classes with an implementation of a basic Image button. We could derive our classes from the Button and just add a property for the image filename:

```

<ImageButton@Button>:
    source: None

    Image:
        source: root.source
        pos: root.pos

```

(continues on next page)

```

        size: root.size

# let's use the new classes in another rule:
<MainUI>:
    BoxLayout:
        ImageButton:
            source: 'hello.png'
            on_press: root.do_something()
        ImageButton:
            source: 'world.png'
            on_press: root.do_something_else()

```

In Python, you can create an instance of the dynamic class as follows:

```

from kivy.factory import Factory
button_inst = Factory.ImageButton()

```

Note: Using dynamic classes, a child class can be declared before its parent. This however, leads to the unintuitive situation where the parent properties/methods override those of the child. Be careful if you choose to do this.

39.7 Templates

Changed in version 1.7.0: Template usage is now deprecated. Please use Dynamic classes instead.

39.7.1 Syntax of templates

Using a template in Kivy requires 2 things :

1. a context to pass for the context (will be ctx inside template).
2. a kv definition of the template.

Syntax of a template:

```

# With only one base class
[ClassName@BaseClass]:
    # .. definitions ..

# With more than one base class
[ClassName@BaseClass1,BaseClass2]:
    # .. definitions ..

```

For example, for a list, you'll need to create a entry with a image on the left, and a label on the right. You can create a template for making that definition easier to use. So, we'll create a template that uses 2 entries in the context: an image filename and a title:

```

[IconItem@BoxLayout]:
    Image:
        source: ctx.image
    Label:
        text: ctx.title

```

Then in Python, you can instantiate the template using:

```
from kivy.lang import Builder

# create a template with hello world + an image
# the context values should be passed as kwargs to the Builder.template
# function
icon1 = Builder.template('IconItem', title='Hello world',
    image='myimage.png')

# create a second template with other information
ctx = {'title': 'Another hello world',
    'image': 'myimage2.png'}
icon2 = Builder.template('IconItem', **ctx)
# and use icon1 and icon2 as other widget.
```

39.7.2 Template example

Most of time, when you are creating a screen in the kv lang, you use a lot of redefinitions. In our example, we'll create a Toolbar, based on a BoxLayout, and put in a few *Image* widgets that will react to the *on_touch_down* event.

```
<MyToolbar>:
    BoxLayout:
        Image:
            source: 'data/text.png'
            size: self.texture_size
            size_hint: None, None
            on_touch_down: self.collide_point(*args[1].pos) and root.
                ↪create_text()

        Image:
            source: 'data/image.png'
            size: self.texture_size
            size_hint: None, None
            on_touch_down: self.collide_point(*args[1].pos) and root.
                ↪create_image()

        Image:
            source: 'data/video.png'
            size: self.texture_size
            size_hint: None, None
            on_touch_down: self.collide_point(*args[1].pos) and root.
                ↪create_video()
```

We can see that the size and size_hint attribute are exactly the same. More than that, the callback in on_touch_down and the image are changing. These can be the variable part of the template that we can put into a context. Let's try to create a template for the Image:

```
[ToolbarButton@Image]:
    # This is the same as before
    size: self.texture_size
    size_hint: None, None
```

(continues on next page)

```
# Now, we are using the ctx for the variable part of the template
source: 'data/%s.png' % ctx.image
on_touch_down: self.collide_point(*args[1].pos) and ctx.callback()
```

The template can be used directly in the MyToolbar rule:

```
<MyToolbar>:
    BoxLayout:
        ToolbarButton:
            image: 'text'
            callback: root.create_text
        ToolbarButton:
            image: 'image'
            callback: root.create_image
        ToolbarButton:
            image: 'video'
            callback: root.create_video
```

That's all :)

39.7.3 Template limitations

When you are creating a context:

1. you cannot use references other than “root”:

```
<MyRule>:
    Widget:
        id: mywidget
        value: 'bleh'
    Template:
        ctxkey: mywidget.value # << fail, this references the
        ↪id
        # mywidget
```

2. not all of the dynamic parts will be understood:

```
<MyRule>
    Template:
        ctxkey: 'value 1' if root.prop1 else 'value2' # <<
        ↪even if
        # root.prop1 is a property, if it changes value, ctxkey
        # will not be updated
```

Template definitions also replace any similarly named definitions in their entirety and thus do not support inheritance.

39.8 Redefining a widget's style

Sometimes we would like to inherit from a widget in order to use its Python properties without also using its .kv defined style. For example, we would like to inherit from a Label, but we would also like to define our own canvas instructions instead of automatically using the canvas instructions inherited from the Label. We can achieve this by prepending a dash (-) before the class name in the .kv style definition.

In myapp.py:

```
class MyWidget(Label):
    pass
```

and in my.kv:

```
<-MyWidget>:
    canvas:
        Color:
            rgb: 1, 1, 1
        Rectangle:
            size: (32, 32)
```

MyWidget will now have a Color and Rectangle instruction in its canvas without any of the instructions inherited from the Label.

39.9 Redefining a widget's property style

Similar to *redefining style*, sometimes we would like to inherit from a widget, keep all its KV defined styles, except for the style applied to a specific property. For example, we would like to inherit from a **Button**, but we would also like to set our own *state_image*, rather than relying on the *background_normal* and *background_down* values. We can achieve this by prepending a dash (-) before the *state_image* property name in the .kv style definition.

In myapp.py:

```
class MyWidget(Button):
    new_background = StringProperty('my_background.png')
```

and in my.kv:

```
<MyWidget>:
    -state_image: self.new_background
```

MyWidget will now have a *state_image* background set only by *new_background*, and not by any previous styles that may have set *state_image*.

Note: Although the previous rules are cleared, they are still applied during widget construction and are only removed when the new rule with the dash is reached. This means that initially, previous rules could be used to set the property.

39.10 Order of kwargs and KV rule application

Properties can be initialized in KV as well as in python. For example, in KV:

```
<MyRule@Widget>:  
    text: 'Hello'  
    ramp: 45.  
    order: self.x + 10
```

Then *MyRule()* would initialize all three kivy properties to the given KV values. Separately in python, if the properties already exist as kivy properties one can do for example *MyRule(line='Bye', side=55)*.

However, what will be the final values of the properties when *MyRule(text='Bye', order=55)* is executed? The quick rule is that python initialization is stronger than KV initialization only for constant rules.

Specifically, the *kwargs* provided to the python initializer are always applied first. So in the above example, *text* is set to '*Bye*' and *order* is set to 55. Then, all the KV rules are applied, except those constant rules that overwrite a python initializer provided value.

That is, the KV rules that do not creates bindings such as *text: 'Hello'* and *ramp: 45.*, if a value for that property has been provided in python, then that rule will not be applied.

So in the *MyRule(text='Bye', order=55)* example, *text* will be '*Bye*', *ramp* will be 45., and *order*, which creates a binding, will first be set to 55, but then when KV rules are applied will end up being whatever *self.x + 10* is.

Changed in version 1.9.1: Before, KV rules always overwrote the python values, now, python values are not overwritten by constant rules.

39.11 Lang Directives

You can use directives to add declarative commands, such as imports or constant definitions, to the lang files. Directives are added as comments in the following format:

```
#:<directivename> <options>
```

39.11.1 import <package>

New in version 1.0.5.

Syntax:

```
#:import <alias> <package>
```

You can import a package by writing:

```
#:import os os  
  
<Rule>:  
    Button:  
        text: os.getcwd()
```

Or more complex:

```
#:import ut kivy.utils

<Rule>:
    canvas:
        Color:
            rgba: ut.get_random_color()
```

New in version 1.0.7.

You can directly import classes from a module:

```
#: import Animation kivy.animation.Animation
<Rule>:
    on_prop: Animation(x=.5).start(self)
```

39.11.2 set <key> <expr>

New in version 1.0.6.

Syntax:

```
#:set <key> <expr>
```

Set a key that will be available anywhere in the kv. For example:

```
#:set my_color (.4, .3, .4)
#:set my_color_hl (.5, .4, .5)

<Rule>:
    state: 'normal'
    canvas:
        Color:
            rgb: my_color if self.state == 'normal' else my_color_hl
```

39.11.3 include <file>

New in version 1.9.0.

Syntax:

```
#:include [force] <file>
```

Includes an external kivy file. This allows you to split complex widgets into their own files. If the include is forced, the file will first be unloaded and then reloaded again. For example:

```
# Test.kv
#:include mycomponent.kv
#:include force mybutton.kv

<Rule>:
    state: 'normal'
    MyButton:
    MyComponent:
```

```
# mycomponent.kv
#:include mybutton.kv

<MyComponent>:
    MyButton:
```

```
# mybutton.kv

<MyButton>:
    canvas:
        Color:
            rgb: (1.0, 0.0, 0.0)
        Rectangle:
            pos: self.pos
            size: (self.size[0]/4, self.size[1]/4)
```

```
class kivy.lang.BuilderBase
Bases: builtins.object
```

The Builder is responsible for creating a [Parser](#) for parsing a kv file, merging the results into its internal rules, templates, etc.

By default, `Builder` is a global Kivy instance used in widgets that you can use to load other kv files in addition to the default ones.

apply(*widget*, *ignored_consts*={}, *rule_children*=None, *dispatch_kv_post*=False)

Search all the rules that match the widget and apply them.

Parameters

widget: [Widget](#) The widget whose class rules should be applied to this widget.

ignored_consts: [set](#) A set or list type whose elements are property names for which constant KV rules (i.e. those that don't create bindings) of that widget will not be applied. This allows e.g. skipping constant rules that overwrite a value initialized in python.

rule_children: [list](#) If not `None`, it should be a list that will be populated with all the widgets created by the kv rules being applied.

Changed in version 1.11.0.

dispatch_kv_post: [bool](#) Normally the class `Widget` dispatches the `on_kv_post` event to widgets created during kv rule application. But if the rules are manually applied by calling [apply\(\)](#), that may not happen, so if this is `True`, we will dispatch the `on_kv_post` event where needed after applying the rules to *widget* (we won't dispatch it for *widget* itself).

Defaults to False.

Changed in version 1.11.0.

apply_rules(*widget*, *rule_name*, *ignored_consts*={}, *rule_children*=None, *dispatch_kv_post*=False)

Search all the rules that match the name *rule_name* and apply them to *widget*.

New in version 1.10.0.

Parameters

widget: [Widget](#) The widget to whom the matching rules should be applied to.

ignored_consts: [set](#) A set or list type whose elements are property names for which constant KV rules (i.e. those that don't create bindings) of that widget

will not be applied. This allows e.g. skipping constant rules that overwrite a value initialized in python.

rule_children: list If not `None`, it should be a list that will be populated with all the widgets created by the kv rules being applied.

Changed in version 1.11.0.

dispatch_kv_post: bool Normally the class `Widget` dispatches the `on_kv_post` event to widgets created during kv rule application. But if the rules are manually applied by calling `apply()`, that may not happen, so if this is `True`, we will dispatch the `on_kv_post` event where needed after applying the rules to `widget` (we won't dispatch it for `widget` itself).

Defaults to `False`.

Changed in version 1.11.0.

classmethod create_from(builder)

Creates a instance of the class, and initializes to the state of `builder`.

Parameters `builder` – The builder to initialize from.

Returns A new instance of this class.

load_file(filename, encoding='utf8', **kwargs)

Insert a file into the language builder and return the root widget (if defined) of the kv file.

Parameters

rulesonly: bool, defaults to False If True, the Builder will raise an exception if you have a root widget inside the definition.

encoding: File character encoding. Defaults to utf-8,

load_string(string, **kwargs)

Insert a string into the Language Builder and return the root widget (if defined) of the kv string.

Parameters

rulesonly: bool, defaults to False If True, the Builder will raise an exception if you have a root widget inside the definition.

filename: str, defaults to None If specified, the filename used to index the kv rules.

The filename parameter can be used to unload kv strings in the same way as you unload kv files. This can be achieved using pseudo file names e.g.:

```
Build.load_string("""  
    <MyRule>:  
        Label:  
            text="Hello"  
    """), filename="myrule.kv")
```

can be unloaded via:

```
Build.unload_file("myrule.kv")
```

match(widget)

Return a list of `ParserRule` objects matching the widget.

match_rule_name(rule_name)

Return a list of `ParserRule` objects matching the widget.

sync()

Execute all the waiting operations, such as the execution of all the expressions related to the canvas.

New in version 1.7.0.

template(*args, **ctx)

Create a specialized template using a specific context.

New in version 1.0.5.

With templates, you can construct custom widgets from a kv lang definition by giving them a context. Check [Template usage](#).

unbind_property(widget, name)

Unbind the handlers created by all the rules of the widget that set the name.

This effectively clears all the rules of widget that take the form:

```
name: rule
```

For example:

```
>>> w = Builder.load_string('''
... Widget:
...     height: self.width / 2. if self.disabled else self.width
...     x: self.y + 50
...
...
>>> w.size
[100, 100]
>>> w.pos
[50, 0]
>>> w.width = 500
>>> w.size
[500, 500]
>>> Builder.unbind_property(w, 'height')
>>> w.width = 222
>>> w.size
[222, 500]
>>> w.y = 500
>>> w.pos
[550, 500]
```

New in version 1.9.1.

unbind_widget(uid)

Unbind all the handlers created by the KV rules of the widget. The `kivy.uix.widget.Widget.uid` is passed here instead of the widget itself, because Builder is using it in the widget destructor.

This effectively clears all the KV rules associated with this widget. For example:

```
>>> w = Builder.load_string('''
... Widget:
...     height: self.width / 2. if self.disabled else self.width
...     x: self.y + 50
...
...
>>> w.size
[100, 100]
```

(continues on next page)

```
>>> w.pos
[50, 0]
>>> w.width = 500
>>> w.size
[500, 500]
>>> Builder.unbind_widget(w.uid)
>>> w.width = 222
>>> w.y = 500
>>> w.size
[222, 500]
>>> w.pos
[50, 500]
```

New in version 1.7.2.

unload_file(filename)

Unload all rules associated with a previously imported file.

New in version 1.0.8.

Warning: This will not remove rules or templates already applied/used on current widgets. It will only effect the next widgets creation or template invocation.

exception kivy.lang.BuilderException(context, line, message, cause=None)

Bases: *kivy.lang.parser.ParserException*

Exception raised when the Builder failed to apply a rule on a widget.

class kivy.lang.Observable

Bases: *kivy.event.ObjectWithUid*

Observable is a stub class defining the methods required for binding. *EventDispatcher* is (the) one example of a class that implements the binding interface. See *EventDispatcher* for details.

New in version 1.9.0.

bind(kwargs)**

fbind(name, func, *largs, **kwargs)

See *EventDispatcher.fbind()*.

Note: To keep backward compatibility with derived classes which may have inherited from *Observable* before, the *fbind()* method was added. The default implementation of *fbind()* is to create a partial function that it passes to bind while saving the uid and largs/kwargs. However, *funbind()* (and *unbind_uid()*) are fairly inefficient since we have to first lookup this partial function using the largs/kwargs or uid and then call *unbind()* on the returned function. It is recommended to overwrite these methods in derived classes to bind directly for better performance.

Similarly to *EventDispatcher.fbind()*, this method returns 0 on failure and a positive unique uid on success. This uid can be used with *unbind_uid()*.

funbind(name, func, *largs, **kwargs)

See *fbind()* and *EventDispatcher.funbind()*.

unbind(kwargs)**

```

unbind_uid(name, uid)
    See fbind\(\) and EventDispatcher.unbind_uid().

class kivy.lang.Parser(**kwargs)
Bases: builtins.object

Create a Parser object to parse a Kivy language file or Kivy content.

parse(content)
    Parse the contents of a Parser file and return a list of root objects.

parse_level(level, lines, spaces=0)
    Parse the current level (level * spaces) indentation.

strip_comments(lines)
    Remove all comments from all lines in-place. Comments need to be on a single line and not
    at the end of a line. i.e. a comment line's first non-whitespace character must be a #.

exception kivy.lang.ParserException(context, line, message, cause=None)
Bases: Exception

Exception raised when something wrong happened in a kv file.

```

39.12 Builder

Class used for the registering and application of rules for specific widgets.

```

kivy.lang.builder.Builder: kivy.lang.builder.BuilderBase =
<kivy.lang.builder.BuilderBase object>
    Main instance of a BuilderBase.

class kivy.lang.builder.BuilderBase
Bases: builtins.object

The Builder is responsible for creating a Parser for parsing a kv file, merging the results into its
internal rules, templates, etc.

By default, Builder is a global Kivy instance used in widgets that you can use to load other kv
files in addition to the default ones.

apply(widget, ignored_consts={}, rule_children=None, dispatch_kv_post=False)
    Search all the rules that match the widget and apply them.

```

Parameters

`widget: Widget` The widget whose class rules should be applied to this widget.

`ignored_consts: set` A set or list type whose elements are property names for
which constant KV rules (i.e. those that don't create bindings) of that widget
will not be applied. This allows e.g. skipping constant rules that overwrite a
value initialized in python.

`rule_children: list` If not `None`, it should be a list that will be populated with all
the widgets created by the kv rules being applied.

Changed in version 1.11.0.

`dispatch_kv_post: bool` Normally the class `Widget` dispatches the `on_kv_post`
event to widgets created during kv rule application. But if the rules are man-
ually applied by calling [apply\(\)](#), that may not happen, so if this is `True`, we
will dispatch the `on_kv_post` event where needed after applying the rules to
`widget` (we won't dispatch it for `widget` itself).

Defaults to False.

Changed in version 1.11.0.

`apply_rules(widget, rule_name, ignored_consts={}, rule_children=None, dispatch_kv_post=False)`

Search all the rules that match the name `rule_name` and apply them to `widget`.

New in version 1.10.0.

Parameters

`widget: Widget` The widget to whom the matching rules should be applied to.

`ignored_consts: set` A set or list type whose elements are property names for which constant KV rules (i.e. those that don't create bindings) of that widget will not be applied. This allows e.g. skipping constant rules that overwrite a value initialized in python.

`rule_children: list` If not `None`, it should be a list that will be populated with all the widgets created by the kv rules being applied.

Changed in version 1.11.0.

`dispatch_kv_post: bool` Normally the class `Widget` dispatches the `on_kv_post` event to widgets created during kv rule application. But if the rules are manually applied by calling `apply()`, that may not happen, so if this is `True`, we will dispatch the `on_kv_post` event where needed after applying the rules to `widget` (we won't dispatch it for `widget` itself).

Defaults to `False`.

Changed in version 1.11.0.

`classmethod create_from(builder)`

Creates a instance of the class, and initializes to the state of `builder`.

Parameters `builder` – The builder to initialize from.

Returns A new instance of this class.

`load_file(filename, encoding='utf8', **kwargs)`

Insert a file into the language builder and return the root widget (if defined) of the kv file.

Parameters

`rulesonly: bool, defaults to False` If True, the Builder will raise an exception if you have a root widget inside the definition.

`encoding: File character encoding. Defaults to utf-8,`

`load_string(string, **kwargs)`

Insert a string into the Language Builder and return the root widget (if defined) of the kv string.

Parameters

`rulesonly: bool, defaults to False` If True, the Builder will raise an exception if you have a root widget inside the definition.

`filename: str, defaults to None` If specified, the filename used to index the kv rules.

The filename parameter can be used to unload kv strings in the same way as you unload kv files. This can be achieved using pseudo file names e.g.:

```
Build.load_string("""
    <MyRule>:
        Label:
```

(continues on next page)

```
        text="Hello"
    "", filename="myrule.kv")
```

can be unloaded via:

```
Build.unload_file("myrule.kv")
```

match(widget)

Return a list of `ParserRule` objects matching the widget.

match_rule_name(rule_name)

Return a list of `ParserRule` objects matching the widget.

sync()

Execute all the waiting operations, such as the execution of all the expressions related to the canvas.

New in version 1.7.0.

template(*args, **ctx)

Create a specialized template using a specific context.

New in version 1.0.5.

With templates, you can construct custom widgets from a kv lang definition by giving them a context. Check [Template usage](#).

unbind_property(widget, name)

Unbind the handlers created by all the rules of the widget that set the name.

This effectively clears all the rules of widget that take the form:

```
name: rule
```

For example:

```
>>> w = Builder.load_string('''
... Widget:
...     height: self.width / 2. if self.disabled else self.width
...     x: self.y + 50
...
...
>>> w.size
[100, 100]
>>> w.pos
[50, 0]
>>> w.width = 500
>>> w.size
[500, 500]
>>> Builder.unbind_property(w, 'height')
>>> w.width = 222
>>> w.size
[222, 500]
>>> w.y = 500
>>> w.pos
[550, 500]
```

New in version 1.9.1.

unbind_widget(*uid*)

Unbind all the handlers created by the KV rules of the widget. The `kivy.uix.widget.Widget.uid` is passed here instead of the widget itself, because Builder is using it in the widget destructor.

This effectively clears all the KV rules associated with this widget. For example:

```
>>> w = Builder.load_string('''
... Widget:
...     height: self.width / 2. if self.disabled else self.width
...     x: self.y + 50
...
...
>>> w.size
[100, 100]
>>> w.pos
[50, 0]
>>> w.width = 500
>>> w.size
[500, 500]
>>> Builder.unbind_widget(w.uid)
>>> w.width = 222
>>> w.y = 500
>>> w.size
[222, 500]
>>> w.pos
[50, 500]
```

New in version 1.7.2.

unload_file(*filename*)

Unload all rules associated with a previously imported file.

New in version 1.0.8.

Warning: This will not remove rules or templates already applied/used on current widgets. It will only effect the next widgets creation or template invocation.

exception kivy.lang.builder.BuilderException(*context, line, message, cause=None*)

Bases: `kivy.lang.parser.ParserException`

Exception raised when the Builder failed to apply a rule on a widget.

class kivy.lang.builder.Observable

Bases: `kivy.event.ObjectWithUid`

`Observable` is a stub class defining the methods required for binding. `EventDispatcher` is (the) one example of a class that implements the binding interface. See `EventDispatcher` for details.

New in version 1.9.0.

bind(kwargs)**

fbind(*name, func, *largs, **kwargs*)

See `EventDispatcher.fbind()`.

Note: To keep backward compatibility with derived classes which may have inherited from `Observable` before, the `fbind()` method was added. The default implementa-

tion of `fbind()` is to create a partial function that it passes to bind while saving the uid and largs/kwargs. However, `funbind()` (and `unbind_uid()`) are fairly inefficient since we have to first lookup this partial function using the largs/kwargs or uid and then call `unbind()` on the returned function. It is recommended to overwrite these methods in derived classes to bind directly for better performance.

Similarly to `EventDispatcher.fbind()`, this method returns 0 on failure and a positive unique uid on success. This uid can be used with `unbind_uid()`.

funbind(*name, func, *largs, **kwargs*)

See `fbind()` and `EventDispatcher.funbind()`.

unbind(***kwargs*)

unbind_uid(*name, uid*)

See `fbind()` and `EventDispatcher.unbind_uid()`.

39.13 Parser

Class used for the parsing of .kv files into rules.

class `kivy.lang.parser.Parser(**kwargs)`

Bases: `builtins.object`

Create a Parser object to parse a Kivy language file or Kivy content.

parse(*content*)

Parse the contents of a Parser file and return a list of root objects.

parse_level(*level, lines, spaces=0*)

Parse the current level (level * spaces) indentation.

strip_comments(*lines*)

Remove all comments from all lines in-place. Comments need to be on a single line and not at the end of a line. i.e. a comment line's first non-whitespace character must be a #.

exception `kivy.lang.parser.ParserException(context, line, message, cause=None)`

Bases: `Exception`

Exception raised when something wrong happened in a kv file.

EXTERNAL LIBRARIES

Kivy comes with other python/C libraries:

- **ddsf** - used for parsing and saving DDS files.
- **osc** - a modified/optimized version of PyOSC for using the Open Sound Control protocol.
- **mtdev** - provides support for the Kernel multi-touch transformation library.

Warning: Even though Kivy comes with these external libraries, we do not provide any support for them and they might change in the future. Don't rely on them in your code.

40.1 GstPlayer

New in version 1.8.0.

GstPlayer is a media player implemented specifically for Kivy with Gstreamer 1.0. It doesn't use Gi at all and is focused on what we want: the ability to read video and stream the image in a callback, or read an audio file. Don't use it directly but use our Core providers instead.

This player is automatically compiled if you have `pkg-config --libs --cflags gstreamer-1.0` working.

Warning: This is an external library and Kivy does not provide any support for it. It might change in the future and we advise you don't rely on it in your code.

40.2 DDS File library

This library can be used to parse and save DDS (*DirectDraw Surface* <https://en.wikipedia.org/wiki/DirectDraw_Surface>) files.

The initial version was written by:

Alexey Borzenkov (snaury@gmail.com)

All the initial work credits go to him! Thank you :)

This version uses structs instead of ctypes.

40.2.1 DDS Format

```
[DDS ][SurfaceDesc][Data]

[SurfaceDesc]:: (everything is uint32)
    Size
    Flags
    Height
    Width
    PitchOrLinearSize
    Depth
    MipmapCount
    Reserved1 * 11
    [PixelFormat]::
        Size
        Flags
        FourCC
        RGBBitCount
        RBitMask
        GBitMask
        BBitMask
        ABitMask
    [Caps]::
        Caps1
        Caps2
        Reserved1 * 2
    Reserved2
```

Warning: This is an external library and Kivy does not provide any support for it. It might change in the future and we advise you don't rely on it in your code.

```
exception kivy.lib.ddsfile.DDSEException
    Bases: Exception

class kivy.lib.ddsfile.QueryDict
    Bases: builtins.dict
```

40.3 Python mtdev

The mtdev module provides Python bindings to the [Kernel multi-touch transformation library](#), also known as mtdev (MIT license).

The mtdev library transforms all variants of kernel MT events to the slotted type B protocol. The events put into mtdev may be from any MT device, specifically type A without contact tracking, type A with contact tracking, or type B with contact tracking. See the kernel documentation for further details.

Warning: This is an external library and Kivy does not provide any support for it. It might change in the future and we advise you don't rely on it in your code.

```
class kivy.lib.mtdev.input_absinfo
    Bases: _ctypes.Structure
```

```
class kivy.lib.mtdev.input_event
    Bases: _ctypes.Structure

class kivy.lib.mtdev.mtdev
    Bases: _ctypes.Structure

class kivy.lib.mtdev.mtdev_caps
    Bases: _ctypes.Structure

class kivy.lib.mtdev.timeval
    Bases: _ctypes.Structure
```


MODULES

Modules are classes that can be loaded when a Kivy application is starting. The loading of modules is managed by the config file. Currently, we include:

- *touchring*: Draw a circle around each touch.
- *monitor*: Add a red topbar that indicates the FPS and a small graph indicating input activity.
- *keybinding*: Bind some keys to actions, such as a screenshot.
- *recorder*: Record and playback a sequence of events.
- *screen*: Emulate the characteristics (dpi/density/ resolution) of different screens.
- *inspector*: Examines your widget hierarchy and widget properties.
- *webdebugger*: Realtime examination of your app internals via a web browser.
- *joycursor*: Navigate in your app with a joystick.
- *showborder*: Show widget's border.

Modules are automatically loaded from the Kivy path and User path:

- *PATH_TO_KIVY/kivy/modules*
- *HOME/.kivy/mods*

41.1 Activating a module

There are various ways in which you can activate a kivy module.

41.1.1 Activate a module in the config

To activate a module this way, you can edit your configuration file (in your *HOME/.kivy/config.ini*):

```
[modules]
# uncomment to activate
touchring =
# monitor =
# keybinding =
```

Only the name of the module followed by “=” is sufficient to activate the module.

41.1.2 Activate a module in Python

Before starting your application, preferably at the start of your import, you can do something like this:

```
import kivy
kivy.require('1.0.8')

# Activate the touchring module
from kivy.config import Config
Config.set('modules', 'touchring', '')
```

41.1.3 Activate a module via the commandline

When starting your application from the commandline, you can add a `-m <modulename>` to the arguments. For example:

```
python main.py -m webdebugger
```

Note: Some modules, such as the screen, may require additional parameters. They will, however, print these parameters to the console when launched without them.

41.2 Create your own module

Create a file in your `HOME/.kivy/mods`, and create 2 functions:

```
def start(win, ctx):
    pass

def stop(win, ctx):
    pass
```

`start`/`stop` are functions that will be called for every window opened in Kivy. When you are starting a module, you can use these to store and manage the module state. Use the `ctx` variable as a dictionary. This context is unique for each instance/`start()` call of the module, and will be passed to `stop()` too.

41.3 Console

New in version 1.9.1.

Reboot of the old inspector, designed to be modular and keep concerns separated. It also has an addons architecture that allow you to add a button, panel, or more in the Console itself.

Warning: This module works, but might fail in some cases. Please contribute!

41.3.1 Usage

For normal module usage, please see the [modules](#) documentation:

```
python main.py -m console
```

41.3.2 Mouse navigation

When the “Select” button is activated, you can:

- tap once on a widget to select it without leaving inspect mode
- double tap on a widget to select and leave inspect mode (then you can manipulate the widget again)

41.3.3 Keyboard navigation

- “Ctrl + e”: toggle console
- “Escape”: cancel widget lookup, then hide inspector view
- “Up”: select the parent widget
- “Down”: select the first child of the currently selected widget
- “Left”: select the previous sibling
- “Right”: select the next sibling

41.3.4 Additional information

Some properties can be edited live. However, due to the delayed usage of some properties, it might crash if you don’t handle the required cases.

41.3.5 Addons

Addons must be added to `Console.addons` before the first Clock tick of the application, or before `create_console` is called. You currently cannot add addons on the fly. Addons are quite cheap until the Console is activated. Panels are even cheaper as nothing is done until the user selects them.

We provide multiple addons activated by default:

- `ConsoleAddonFps`: display the FPS at the top-right
- `ConsoleAddonSelect`: activate the selection mode
- `ConsoleAddonBreadcrumb`: display the hierarchy of the current widget at the bottom
- `ConsoleAddonWidgetTree`: panel to display the widget tree of the application
- `ConsoleAddonWidgetPanel`: panel to display the properties of the selected widget

If you need to add custom widgets in the Console, please use either `ConsoleButton`, `ConsoleToggleButton` or `ConsoleLabel`.

An addon must inherit from the `ConsoleAddon` class.

For example, here is a simple addon for displaying the FPS at the top/right of the Console:

```

from kivy.modules.console import Console, ConsoleAddon

class ConsoleAddonFps(ConsoleAddon):
    def __init__(self):
        self.lbl = ConsoleLabel(text="0 Fps")
        self.console.add_toolbar_widget(self.lbl, right=True)

    def activate(self):
        self.event = Clock.schedule_interval(self.update_fps, 1 / 2.)

    def deactivated(self):
        self.event.cancel()

    def update_fps(self, *args):
        fps = Clock.get_fps()
        self.lbl.text = "{} Fps".format(int(fps))

Console.register_addon(ConsoleAddonFps)

```

You can create addons that add panels. Panel activation/deactivation is not tied to the addon activation/deactivation, but in some cases, you can use the same callback for deactivating the addon and the panel. Here is a simple “About” panel addon:

```

from kivy.modules.console import Console, ConsoleAddon, ConsoleLabel

class ConsoleAddonAbout(ConsoleAddon):
    def __init__(self):
        self.console.add_panel("About", self.panel_activate,
                              self.panel_deactivate)

    def panel_activate(self):
        self.console.bind(widget=self.update_content)
        self.update_content()

    def panel_deactivate(self):
        self.console.unbind(widget=self.update_content)

    def deactivate(self):
        self.panel_deactivate()

    def update_content(self, *args):
        widget = self.console.widget
        if not widget:
            return
        text = "Selected widget is: {!r}".format(widget)
        lbl = ConsoleLabel(text=text)
        self.console.set_content(lbl)

Console.register_addon(ConsoleAddonAbout)

```

class kivy.modules.console.Console(kwargs)**
Bases: *kivy.uix.relativelayout.RelativeLayout*

Console interface

This widget is created by `create_console()`, when the module is loaded. During that time, you

can add addons on the console to extend the functionalities, or add your own application stats / debugging module.

activated

True if the Console is activated (showed)

add_panel(name, cb_activate, cb_deactivate, cb_refresh=None)

Add a new panel in the Console.

- *cb_activate* is a callable that will be called when the panel is activated by the user.
- *cb_deactivate* is a callable that will be called when the panel is deactivated or when the console will hide.
- *cb_refresh* is an optional callable that is called if the user click again on the button for display the panel

When activated, it's up to the panel to display a content in the Console by using `set_content()`.

add_toolbar_widget(widget, right=False)

Add a widget in the top left toolbar of the Console. Use *right=True* if you wanna add the widget at the right instead.

```
addons = [<class 'kivy.modules.console.ConsoleAddonSelect'>, <class 'kivy.modules.console.ConsoleAddonFps'>, <class 'kivy.modules.console.ConsoleAddonWidgetPanel'>, <class 'kivy.modules.console.ConsoleAddonWidgetTree'>, <class 'kivy.modules.console.ConsoleAddonBreadcrumb'>]
```

Array of addons that will be created at Console creation

highlight_at(x, y)

Select a widget from a x/y window coordinate. This is mostly used internally when Select mode is activated

inspect_enabled

Indicate if the inspector inspection is enabled. If yes, the next touch down will select a the widget under the touch

mode

Display mode of the Console, either docked at the bottom, or as a floating window.

on_touch_down(touch)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.
See `relativelayout` for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See `on_touch_down()` for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See `on_touch_down()` for more information.

pick(widget, x, y)

Pick a widget at x/y, given a root *widget*

```

remove_toolbar_widget(widget)
    Remove a widget from the toolbar

set_content(content)
    Replace the Console content with a new one.

widget
    Current widget being selected

class kivy.modules.console.ConsoleAddon(console)
    Bases: builtins.object
    Base class for implementing addons

activate()
    Method called when the addon is activated by the console (when the console is displayed)

console = None
    Console instance

deactivate()
    Method called when the addon is deactivated by the console (when the console is hidden)

init()
    Method called when the addon is instantiated by the Console

class kivy.modules.console.ConsoleButton(**kwargs)
    Bases: kivy.uix.button.Button
    Button specialized for the Console

class kivy.modules.console.ConsoleLabel(**kwargs)
    Bases: kivy.uix.label.Label
    LabelButton specialized for the Console

class kivy.modules.console.ConsoleToggleButton(**kwargs)
    Bases: kivy.uix.togglebutton.ToggleButton
    ToggleButton specialized for the Console

kivy.modules.console.start(win, ctx)
    Create an Console instance attached to the ctx and bound to the Window's on_keyboard() event
    for capturing the keyboard shortcut.

```

Parameters

`win`: A `Window` The application Window to bind to.
`ctx`: A `Widget` or subclass The Widget to be inspected.

kivy.modules.console.stop(win, ctx)
Stop and unload any active Inspectors for the given `ctx`.

41.4 Inspector

New in version 1.0.9.

Warning: This module is highly experimental, use it with care.

The Inspector is a tool for finding a widget in the widget tree by clicking or tapping on it. Some keyboard shortcuts are activated:

- “Ctrl + e”: activate / deactivate the inspector view
- “Escape”: cancel widget lookup first, then hide the inspector view

Available inspector interactions:

- tap once on a widget to select it without leaving inspect mode
- double tap on a widget to select and leave inspect mode (then you can manipulate the widget again)

Some properties can be edited live. However, due to the delayed usage of some properties, it might crash if you don't handle all the cases.

41.4.1 Usage

For normal module usage, please see the [modules](#) documentation.

The Inspector, however, can also be imported and used just like a normal python module. This has the added advantage of being able to activate and deactivate the module programmatically:

```
from kivy.core.window import Window
from kivy.app import App
from kivy.uix.button import Button
from kivy.modules import inspector

class Demo(App):
    def build(self):
        button = Button(text="Test")
        inspector.create_inspector(Window, button)
        return button

Demo().run()
```

To remove the Inspector, you can do the following:

```
inspector.stop(Window, button)
```

`kivy.modules.inspector.create_inspector(win, ctx, *largs)`

Create an Inspector instance attached to the `ctx` and bound to the Window's `on_keyboard()` event for capturing the keyboard shortcut.

Parameters

`win`: A [Window](#) The application Window to bind to.

`ctx`: A [Widget](#) or subclass The Widget to be inspected.

`kivy.modules.inspector.stop(win, ctx)`

Stop and unload any active Inspectors for the given `ctx`.

41.5 JoyCursor

New in version 1.10.0.

The JoyCursor is a tool for navigating with a joystick as if using a mouse or touch. Most of the actions that are possible for a mouse user are available in this module.

For example:

- left click
- right click
- double click (two clicks)
- moving the cursor
- holding the button (+ moving at the same time)
- selecting
- scrolling

There are some properties that can be edited live, such as intensity of the JoyCursor movement and toggling mouse button holding.

41.5.1 Usage

For normal module usage, please see the [modules](#) documentation and these bindings:

Event	Joystick
cursor move	Axis 3, Axis 4
cursor intensity	Button 0, Button 1
left click	Button 2
right click	Button 3
scroll up	Button 4
scroll down	Button 5
hold button	Button 6
joycursor on/off	Button 7

The JoyCursor, like Inspector, can also be imported and used as a normal python module. This has the added advantage of being able to activate and deactivate the module programmatically:

```
from kivy.lang import Builder
from kivy.base import runTouchApp
runTouchApp(Builder.load_string("""
#:import jc kivy.modules.joycursor
BoxLayout:
    Button:
        text: 'Press & activate with Ctrl+E or Button 7'
        on_release: jc.create_joycursor(root.parent, root)
    Button:
        text: 'Disable'
        on_release: jc.stop(root.parent, root)
"""))
```

`kivy.modules.joycursor.create_joycursor(win, ctx, *args)`

Create a JoyCursor instance attached to the `ctx` and bound to the Window's `on_keyboard()` event for capturing the keyboard shortcuts.

Parameters

win: A **Window** The application Window to bind to.

ctx: A **Widget** or subclass The Widget for JoyCursor to attach to.

`kivy.modules.joycursor.stop(win, ctx)`

Stop and unload any active JoyCursors for the given *ctx*.

41.6 Keybinding

This module forces the mapping of some keys to functions:

- F11: Rotate the Window through 0, 90, 180 and 270 degrees
- Shift + F11: Switches between portrait and landscape on desktops
- F12: Take a screenshot

Note: this doesn't work if the application requests the keyboard beforehand.

41.6.1 Usage

For normal module usage, please see the **modules** documentation.

The Keybinding module, however, can also be imported and used just like a normal python module. This has the added advantage of being able to activate and deactivate the module programmatically:

```
from kivy.app import App
from kivy.uix.button import Button
from kivy.modules import keybinding
from kivy.core.window import Window

class Demo(App):

    def build(self):
        button = Button(text="Hello")
        keybinding.start(Window, button)
        return button

Demo().run()
```

To remove the Keybinding, you can do the following:

```
Keybinding.stop(Window, button)
```

41.7 Monitor module

The Monitor module is a toolbar that shows the activity of your current application :

- FPS
- Graph of input events

41.7.1 Usage

For normal module usage, please see the [modules](#) documentation.

41.8 Recorder module

New in version 1.1.0.

Create an instance of [**Recorder**](#), attach to the class, and bind some keys to record / play sequences:

- F6: play the last record in a loop
- F7: read the latest recording
- F8: record input events

41.8.1 Configuration

Parameters

attrs: str, defaults to `record_attrs` value. Attributes to record from the motion event

profile_mask: str, defaults to `record_profile_mask` value. Mask for motion event profile. Used to filter which profile will appear in the fake motion event when replayed.

filename: str, defaults to ‘recorder.kvi’ Name of the file to record / play with

41.8.2 Usage

For normal module usage, please see the [modules](#) documentation.

41.9 Screen

This module changes some environment and configuration variables to match the density / dpi / screensize of a specific device.

To see a list of the available screenid's, just run:

```
python main.py -m screen
```

To simulate a medium-density screen such as the Motorola Droid 2:

```
python main.py -m screen:droid2
```

To simulate a high-density screen such as HTC One X, in portrait:

```
python main.py -m screen:onex,portrait
```

To simulate the iPad 2 screen:

```
python main.py -m screen:ipad
```

If the generated window is too large, you can specify a scale:

```
python main.py -m screen:note2,portrait,scale=.75
```

Note that to display your contents correctly on a scaled window you must consistently use units 'dp' and 'sp' throughout your app. See `metrics` for more details.

41.10 Touchring

Shows rings around every touch on the surface / screen. You can use this module to check that you don't have any calibration issues with touches.

41.10.1 Configuration

Parameters

`image: str, defaults to '<kivy>/data/images/ring.png'` Filename of the image to use.

`scale: float, defaults to 1.` Scale of the image.

`alpha: float, defaults to 1.` Opacity of the image.

41.10.2 Example

In your configuration (`~/.kivy/config.ini`), you can add something like this:

```
[modules]
touchring = image=mypointer.png,scale=.3,alpha=.7
```

41.11 Web Debugger

New in version 1.2.0.

Warning: This module is highly experimental, use it with care.

This module will start a webserver and run in the background. You can see how your application evolves during runtime, examine the internal cache etc.

Run with:

```
python main.py -m webdebugger
```

Then open your webbrowser on <http://localhost:5000/>

NETWORK SUPPORT

Kivy currently supports basic, asynchronous network requests. Please refer to [kivy.network.urlrequest.UrlRequest](#).

42.1 URLRequest

New in version 1.0.8.

You can use the [URLRequest](#) to make asynchronous requests on the web and get the result when the request is completed. The spirit is the same as the XHR object in Javascript.

The content is also decoded if the Content-Type is application/json and the result automatically passed through json.loads.

The syntax to create a request:

```
from kivy.network.urlrequest import URLRequest
req = URLRequest(url, on_success, on_redirect, on_failure, on_error,
                 on_progress, req_body, req_headers, chunk_size,
                 timeout, method, decode, debug, file_path, ca_file,
                 verify)
```

Only the first argument is mandatory: the rest are optional. By default, a “GET” request will be sent. If the [URLRequest.req_body](#) is not None, a “POST” request will be sent. It’s up to you to adjust [URLRequest.req_headers](#) to suit your requirements and the response to the request will be accessible as the parameter called “result” on the callback function of the on_success event.

Example of fetching JSON:

```
def got_json(req, result):
    for key, value in req.resp_headers.items():
        print('{}: {}'.format(key, value))

req = URLRequest('https://httpbin.org/headers', got_json)
```

Example of Posting data (adapted from httplib example):

```
import urllib

def bug_posted(req, result):
    print('Our bug is posted!')
    print(result)
```

(continues on next page)

(continued from previous page)

```
params = urllib.urlencode({'@number': 12524, '@type': 'issue',
                           '@action': 'show'})
headers = {'Content-type': 'application/x-www-form-urlencoded',
            'Accept': 'text/plain'}
req = UrlRequest('bugs.python.org', on_success=bug_posted, req_body=params,
                  req_headers=headers)
```

If you want a synchronous request, you can call the `wait()` method.

```
class kivy.network.urlrequest.UrlRequest(url, on_success=None, on_redirect=None,
                                            on_failure=None, on_error=None,
                                            on_progress=None, req_body=None,
                                            req_headers=None, chunk_size=8192,
                                            timeout=None, method=None, decode=True,
                                            debug=False, file_path=None, ca_file=None,
                                            verify=True, proxy_host=None, proxy_port=None,
                                            proxy_headers=None, user_agent=None,
                                            on_cancel=None, cookies=None)
```

Bases: `threading.Thread`

A `UrlRequest`. See module documentation for usage.

Changed in version 1.5.1: Add `debug` parameter

Changed in version 1.0.10: Add `method` parameter

Changed in version 1.8.0: Parameter `decode` added. Parameter `file_path` added. Parameter `on_redirect` added. Parameter `on_failure` added.

Changed in version 1.9.1: Parameter `ca_file` added. Parameter `verify` added.

Changed in version 1.10.0: Parameters `proxy_host`, `proxy_port` and `proxy_headers` added.

Changed in version 1.11.0: Parameters `on_cancel` added.

Parameters

`url: str` Complete url string to call.

`on_success: callback(request, result)` Callback function to call when the result has been fetched.

`on_redirect: callback(request, result)` Callback function to call if the server returns a Redirect.

`on_failure: callback(request, result)` Callback function to call if the server returns a Client or Server Error.

`on_error: callback(request, error)` Callback function to call if an error occurs.

`on_progress: callback(request, current_size, total_size)` Callback function that will be called to report progression of the download. `total_size` might be -1 if no Content-Length has been reported in the http response. This callback will be called after each `chunk_size` is read.

`on_cancel: callback(request)` Callback function to call if user requested to cancel the download operation via the `.cancel()` method.

`req_body: str, defaults to None` Data to sent in the request. If it's not None, a POST will be done instead of a GET.

`req_headers: dict, defaults to None` Custom headers to add to the request.

chunk_size: int, defaults to 8192 Size of each chunk to read, used only when `on_progress` callback has been set. If you decrease it too much, a lot of `on_progress` callbacks will be fired and will slow down your download. If you want to have the maximum download speed, increase the `chunk_size` or don't use `on_progress`.

timeout: int, defaults to None If set, blocking operations will timeout after this many seconds.

method: str, defaults to 'GET' (or 'POST' if body is specified) The HTTP method to use.

decode: bool, defaults to True If False, skip decoding of the response.

debug: bool, defaults to False If True, it will use the `Logger.debug` to print information about url access/progression/errors.

file_path: str, defaults to None If set, the result of the `URLRequest` will be written to this path instead of in memory.

ca_file: str, defaults to None Indicates a SSL CA certificate file path to validate HTTPS certificates against

verify: bool, defaults to True If False, disables SSL CA certificate verification

proxy_host: str, defaults to None If set, the proxy host to use for this connection.

proxy_port: int, defaults to None If set, and `proxy_host` is also set, the port to use for connecting to the proxy server.

proxy_headers: dict, defaults to None If set, and `proxy_host` is also set, the headers to send to the proxy server in the CONNECT request.

cancel()

Cancel the current request. It will be aborted, and the result will not be dispatched. Once cancelled, the callback `on_cancel` will be called.

New in version 1.11.0.

property chunk_size

Return the size of a chunk, used only in "progress" mode (when `on_progress` callback is set.)

decode_result(result, resp)

Decode the result fetched from url according to his Content-Type. Currently supports only application/json.

property error

Return the error of the request. This value is not determined until the request is completed.

get_connection_for_scheme(scheme)

Return the Connection class for a particular scheme. This is an internal function that can be expanded to support custom schemes.

Actual supported schemes: http, https.

property is_finished

Return True if the request has finished, whether it's a success or a failure.

req_body

Request body passed in `__init__`

req_headers

Request headers passed in `__init__`

property resp_headers

If the request has been completed, return a dictionary containing the headers of the response. Otherwise, it will return None.

property resp_status

Return the status code of the response if the request is complete, otherwise return None.

property result

Return the result of the request. This value is not determined until the request is finished.

run()

Method representing the thread's activity.

You may override this method in a subclass. The standard run() method invokes the callable object passed to the object's constructor as the target argument, if any, with sequential and keyword arguments taken from the args and kwargs arguments, respectively.

url

Url of the request

wait(*delay=0.5*)

Wait for the request to finish (until *resp_status* is not None)

Note: This method is intended to be used in the main thread, and the callback will be dispatched from the same thread from which you're calling.

New in version 1.1.0.

STORAGE

New in version 1.7.0.

Warning: This module is still experimental, and the API is subject to change in a future version.

43.1 Usage

The idea behind the Storage module is to be able to load/store any number of key-value pairs via an indexed key. The default model is abstract so you cannot use it directly. We provide some implementations such as:

- `kivy.storage.dictstore.DictStore`: use a python dict as a store
- `kivy.storage.jsonstore.JsonStore`: use a JSON file as a store
- `kivy.storage.redisstore.RedisStore`: use a Redis database with redis-py

43.2 Examples

For example, let's use a JsonStore:

```
from kivy.storage.jsonstore import JsonStore

store = JsonStore('hello.json')

# put some values
store.put('tito', name='Mathieu', org='kivy')
store.put('tshirtman', name='Gabriel', age=27)

# using the same index key erases all previously added key-value pairs
store.put('tito', name='Mathieu', age=30)

# get a value using a index key and key
print('tito is', store.get('tito')['age'])

# or guess the key/entry for a part of the key
for item in store.find(name='Gabriel'):
    print('tshirtmans index key is', item[0])
    print('his key value pairs are', str(item[1]))
```

Because the data is persistent, you can check later to see if the key exists:

```
from kivy.storage.jsonstore import JsonStore

store = JsonStore('hello.json')
if store.exists('tito'):
    print('tito exists:', store.get('tito'))
    store.delete('tito')
```

43.3 Synchronous / Asynchronous API

All the standard methods (`get()`, `put()`, `exists()`, `delete()`, `find()`) have an asynchronous version.

For example, the `get` method has a `callback` parameter. If set, the `callback` will be used to return the result to the user when available: the request will be asynchronous. If the `callback` is None, then the request will be synchronous and the result will be returned directly.

Without callback (Synchronous API):

```
entry = mystore.get('tito')
print('tito =', entry)
```

With callback (Asynchronous API):

```
def my_callback(store, key, result):
    print('the key', key, 'has a value of', result)
mystore.get('plop', callback=my_callback)
```

The callback signature (for almost all methods) is:

```
def callback(store, key, result):
    """
    store: the `Store` instance currently used.
    key: the key sought for.
    result: the result of the lookup for the key.
    """
```

43.4 Synchronous container type

The storage API emulates the container type for the synchronous API:

```
store = JsonStore('hello.json')

# original: store.get('tito')
store['tito']

# original: store.put('tito', name='Mathieu')
store['tito'] = {'name': 'Mathieu'}

# original: store.delete('tito')
del store['tito']
```

(continues on next page)

```
# original: store.count()
len(store)

# original: store.exists('tito')
'tito' in store

# original: for key in store.keys()
for key in store:
    pass
```

class kivy.storage.AbstractStore(kwargs)**Bases: *kivy.event.EventDispatcher*

Abstract class used to implement a Store

async_clear(callback)Asynchronous version of *clear()*.**async_count(callback)**

Asynchronously return the number of entries in the storage.

async_delete(callback, key)Asynchronous version of *delete()*.**Callback arguments***store: AbstractStore instance* Store instance*key: string* Name of the key to search for*result: bool* Indicate True if the storage has been updated, or False if nothing has been done (no changes). None if any error.**async_exists(callback, key)**Asynchronous version of *exists()*.**Callback arguments***store: AbstractStore instance* Store instance*key: string* Name of the key to search for*result: bool* Result of the query, None if any error**async_find(callback, **filters)**Asynchronous version of *find()*.

The callback will be called for each entry in the result.

Callback arguments*store: AbstractStore instance* Store instance*key: string* Name of the key to search for, or None if we reach the end of the results*result: bool* Indicate True if the storage has been updated, or False if nothing has been done (no changes). None if any error.**async_get(callback, key)**Asynchronous version of *get()*.**Callback arguments***store: AbstractStore instance* Store instance

key: string Name of the key to search for

result: dict Result of the query, None if any error

async_keys(callback)

Asynchronously return all the keys in the storage.

async_put(callback, key, **values)

Asynchronous version of **put()**.

Callback arguments

store: AbstractStore instance Store instance

key: string Name of the key to search for

result: bool Indicate True if the storage has been updated, or False if nothing has been done (no changes). None if any error.

clear()

Wipe the whole storage.

count()

Return the number of entries in the storage.

delete(key)

Delete a key from the storage. If the key is not found, a *KeyError* exception will be thrown.

exists(key)

Check if a key exists in the store.

find(filters)**

Return all the entries matching the filters. The entries are returned through a generator as a list of (key, entry) pairs where *entry* is a dict of key-value pairs

```
for key, entry in store.find(name='Mathieu'):
    print('key:', key, ', entry:', entry)
```

Because it's a generator, you cannot directly use it as a list. You can do:

```
# get all the (key, entry) availables
entries = list(store.find(name='Mathieu'))
# get only the entry from (key, entry)
entries = list((x[1] for x in store.find(name='Mathieu')))
```

get(key)

Get the key-value pairs stored at *key*. If the key is not found, a *KeyError* exception will be thrown.

keys()

Return a list of all the keys in the storage.

put(key, **values)

Put new key-value pairs (given in *values*) into the storage. Any existing key-value pairs will be removed.

43.5 Dictionary store

Use a Python dictionary as a store.

```
class kivy.storage.dictstore.DictStore(filename, data=None, **kwargs)
Bases: kivy.storage.AbstractStore
```

Store implementation using a pickled *dict*. See the [kivy.storage](#) module documentation for more information.

43.6 JSON store

A *Storage* module used to save/load key-value pairs from a json file.

```
class kivy.storage.jsonstore.JsonStore(filename, indent=None, sort_keys=False, **kwargs)
Bases: kivy.storage.AbstractStore
```

Store implementation using a json file for storing the key-value pairs. See the [kivy.storage](#) module documentation for more information.

43.7 Redis Store

Store implementation using Redis. You must have redis-py installed.

Usage example:

```
from kivy.storage.redisstore import RedisStore

params = dict(host='localhost', port=6379, db=14)
store = RedisStore(params)
```

All the key-value pairs will be stored with a prefix 'store' by default. You can instantiate the storage with another prefix like this:

```
from kivy.storage.redisstore import RedisStore

params = dict(host='localhost', port=6379, db=14)
store = RedisStore(params, prefix='mystore2')
```

The params dictionary will be passed to the redis.StrictRedis class.

See [redis-py](#).

```
class kivy.storage.redisstore.RedisStore(redis_params, **kwargs)
Bases: kivy.storage.AbstractStore
```

Store implementation using a Redis database. See the [kivy.storage](#) module documentation for more information.

TOOLS

The tools module provides various utility scripts, modules and examples.

44.1 Scripts

Some useful scripts include:

- `kviewer.py`: for viewing kv files with automatic updating
- `benchmark.py`: provides detailed OpenGL hardware information as well as some benchmarks measuring kivy specific performance
- `reports.py`: provides a comprehensive report covering your systems providers, libraries, configuration, environment, input devices and options
- `texturecompress.py`: a command line utility for compressing images into PVRTC or ETC1 formats
- `generate-icons.py`: generates set of icons suitable for the various store and package formats
- `gles_compat/subset_gles.py`: examines compatibility between GLEXT and GLES2 headers for finding compatible subsets

44.2 Modules

Tool modules provide various resources for:

- `packaging`
- `text editor highlighting`

44.3 Other

Other miscellaneous resources include

- `pep8checker`: pep8 checking scripts and git hook
- `theming`: demonstrates an alternative theme for kivy
- `travis`: travis continuous integration

This help document is a work-in-progress and currently under construction.

44.4 Packaging

This module contains [PyInstaller](#) hooks in order to assist in the process of building binary packages. PyInstaller allows you to produce stand-alone, self-contained executables of your Kivy app for Windows, Linux and Mac.

For more information, please see the [PyInstaller website](#)

WIDGETS

Widgets are elements of a graphical user interface that form part of the [User Experience](#). The `kivy.uix` module contains classes for creating and managing Widgets. Please refer to the [Widget class](#) documentation for further information.

Kivy widgets can be categorized as follows:

- **UX widgets:** Classical user interface widgets, ready to be assembled to create more complex widgets.

Label, Button, CheckBox, Image, Slider, Progress Bar, TextInput, Toggle button, Switch, Video

- **Layouts:** A layout widget does no rendering but just acts as a trigger that arranges its children in a specific way. Read more on [Layouts here](#).

Anchor Layout, Box Layout, Float Layout, GridLayout, PageLayout, RelativeLayout, Scatter Layout, Stack Layout

- **Complex UX widgets:** Non-atomic widgets that are the result of combining multiple classic widgets. We call them complex because their assembly and usage are not as generic as the classical widgets.

Bubble, Drop-Down List, FileChooser, Popup, Spinner, RecycleView, TabbedPanel, Video player, VKeyboard,

- **Behaviors widgets:** These widgets do no rendering but act on the graphics instructions or interaction (touch) behavior of their children.

Scatter, Stencil View

- **Screen manager:** Manages screens and transitions when switching from one to another.

Screen Manager

45.1 Behaviors

New in version 1.8.0.

45.1.1 Behavior mixin classes

This module implements behaviors that can be [mixed in](#) with existing base widgets. The idea behind these classes is to encapsulate properties and events associated with certain types of widgets.

Isolating these properties and events in a mixin class allows you to define your own implementation for standard kivy widgets that can act as drop-in replacements. This means you can re-style and re-define widgets as desired without breaking compatibility: as long as they implement the behaviors correctly, they can simply replace the standard widgets.

45.1.2 Adding behaviors

Say you want to add [Button](#) capabilities to an [Image](#), you could do:

```
class IconButton(ButtonBehavior, Image):  
    pass
```

This would give you an [Image](#) with the events and properties inherited from [ButtonBehavior](#). For example, the `on_press` and `on_release` events would be fired when appropriate:

```
class IconButton(ButtonBehavior, Image):  
    def on_press(self):  
        print("on_press")
```

Or in kv:

```
IconButton:  
    on_press: print('on_press')
```

Naturally, you could also bind to any property changes the behavior class offers:

```
def state_changed(*args):  
    print('state changed')  
  
button = IconButton()  
button.bind(state=state_changed)
```

Note: The behavior class must always be `_before_` the widget class. If you don't specify the inheritance in this order, the behavior will not work because the behavior methods are overwritten by the class method listed first.

Similarly, if you combine a behavior class with a class which requires the use of the methods also defined by the behavior class, the resulting class may not function properly. For example, when combining the [ButtonBehavior](#) with a [Slider](#), both of which use the `on_touch_up()` method, the resulting class may not work properly.

Changed in version 1.9.1: The individual behavior classes, previously in one big `behaviors.py` file, has been split into a single file for each class under the [behaviors](#) module. All the behaviors are still imported in the [behaviors](#) module so they are accessible as before (e.g. both `from kivy.uix.behaviors import ButtonBehavior` and `from kivy.uix.behaviors.button import ButtonBehavior` work).

```
class kivy.uix.behaviors.ButtonBehavior(**kwargs)  
Bases: builtins.object
```

This [mixin](#) class provides [Button](#) behavior. Please see the [button behaviors module](#) documentation for more information.

Events

`on_press` Fired when the button is pressed.

`on_release` Fired when the button is released (i.e. the touch/click that pressed the button goes away).

`always_release`

This determines whether or not the widget fires an `on_release` event if the touch_up is outside the widget.

New in version 1.9.0.

Changed in version 1.10.0: The default value is now False.

`always_release` is a `BooleanProperty` and defaults to `False`.

`last_touch`

Contains the last relevant touch received by the Button. This can be used in `on_press` or `on_release` in order to know which touch dispatched the event.

New in version 1.8.0.

`last_touch` is a `ObjectProperty` and defaults to `None`.

`min_state_time`

The minimum period of time which the widget must remain in the ‘down’ state.

New in version 1.9.1.

`min_state_time` is a float and defaults to 0.035. This value is taken from `Config`.

`state`

The state of the button, must be one of ‘normal’ or ‘down’. The state is ‘down’ only when the button is currently touched/clicked, otherwise its ‘normal’.

`state` is an `OptionProperty` and defaults to ‘normal’.

`trigger_action(duration=0.1)`

Trigger whatever action(s) have been bound to the button by calling both the `on_press` and `on_release` callbacks.

This is similar to a quick button press without using any touch events, but note that like most kivy code, this is not guaranteed to be safe to call from external threads. If needed use `Clock` to safely schedule this function and the resulting callbacks to be called from the main thread.

Duration is the length of the press in seconds. Pass 0 if you want the action to happen instantly.

New in version 1.8.0.

`class kivy.uix.behaviors.CodeNavigationBehavior`

Bases: `kivy.event.EventDispatcher`

Code navigation behavior. Modifies the navigation behavior in TextInput to work like an IDE instead of a word processor. Please see the `code navigation behaviors module` documentation for more information.

New in version 1.9.1.

`class kivy.uix.behaviors.CompoundSelectionBehavior(**kwargs)`

Bases: `builtins.object`

The Selection behavior `mixin` implements the logic behind keyboard and touch selection of selectable widgets managed by the derived widget. Please see the `compound selection behaviors module` documentation for more information.

New in version 1.9.0.

clear_selection()

Deselects all the currently selected nodes.

deselect_node(node)

Deselects a possibly selected node.

It is called by the controller when it deselects a node and can also be called from the outside to deselect a node directly. The derived widget should overwrite this method and change the node to its unselected state when this is called

Parameters

node The node to be deselected.

Warning: This method must be called by the derived widget using super if it is overwritten.

get_index_of_node(node, selectable_nodes)

(internal) Returns the index of the *node* within the *selectable_nodes* returned by *get_selectable_nodes()*.

get_selectable_nodes()

(internal) Returns a list of the nodes that can be selected. It can be overwritten by the derived widget to return the correct list.

This list is used to determine which nodes to select with group selection. E.g. the last element in the list will be selected when home is pressed, pagedown will move (or add to, if shift is held) the selection from the current position by negative *page_count* nodes starting from the position of the currently selected node in this list and so on. Still, nodes can be selected even if they are not in this list.

Note: It is safe to dynamically change this list including removing, adding, or re-arranging its elements. Nodes can be selected even if they are not on this list. And selected nodes removed from the list will remain selected until *deselect_node()* is called.

Warning: Layouts display their children in the reverse order. That is, the contents of *children* is displayed from right to left, bottom to top. Therefore, internally, the indices of the elements returned by this function are reversed to make it work by default for most layouts so that the final result is consistent e.g. home, although it will select the last element in this list visually, will select the first element when counting from top to bottom and left to right. If this behavior is not desired, a reversed list should be returned instead.

Defaults to returning *children*.

goto_node(key, last_node, last_node_idx)

(internal) Used by the controller to get the node at the position indicated by key. The key can be keyboard inputs, e.g. pageup, or scroll inputs from the mouse scroll wheel, e.g. scrollup. 'last_node' is the last node selected and is used to find the resulting node. For example, if the key is up, the returned node is one node up from the last node.

It can be overwritten by the derived widget.

Parameters

key str, the string used to find the desired node. It can be any of the keyboard keys, as well as the mouse scrollup, scrolldown, scrollright, and scrollleft

strings. If letters are typed in quick succession, the letters will be combined before it's passed in as key and can be used to find nodes that have an associated string that starts with those letters.

last_node The last node that was selected.

last_node_idx The cached index of the last node selected in the `get_selectable_nodes()` list. If the list hasn't changed it saves having to look up the index of *last_node* in that list.

Returns tuple, the node targeted by key and its index in the `get_selectable_nodes()` list. Returning (*last_node*, *last_node_idx*) indicates a node wasn't found.

keyboard_select

Determines whether the keyboard can be used for selection. If False, keyboard inputs will be ignored.

keyboard_select is a `BooleanProperty` and defaults to True.

multiselect

Determines whether multiple nodes can be selected. If enabled, keyboard shift and ctrl selection, optionally combined with touch, for example, will be able to select multiple widgets in the normally expected manner. This dominates `touch_multiselect` when False.

multiselect is a `BooleanProperty` and defaults to False.

nodes_order_reversed

(Internal) Indicates whether the order of the nodes as displayed top- down is reversed compared to their order in `get_selectable_nodes()` (e.g. how the children property is reversed compared to how it's displayed).

page_count

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when pageup (or pagedown) is pressed.

page_count is a `NumericProperty` and defaults to 10.

right_count

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when the right (or left) arrow on the keyboard is pressed.

right_count is a `NumericProperty` and defaults to 1.

scroll_count

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when the mouse scroll wheel is scrolled.

right_count is a `NumericProperty` and defaults to 0.

select_node(*node*)

Selects a node.

It is called by the controller when it selects a node and can be called from the outside to select a node directly. The derived widget should overwrite this method and change the node state to selected when called.

Parameters

node The node to be selected.

Returns bool, True if the node was selected, False otherwise.

Warning: This method must be called by the derived widget using super if it is overwritten.

select_with_key_down(*keyboard*, *scancode*, *codepoint*, *modifiers*, ***kwargs*)

Processes a key press. This is called when a key press is to be used for selection. Depending on the keyboard keys pressed and the configuration, it could select or deselect nodes or node ranges from the selectable nodes list, [get_selectable_nodes\(\)](#).

The parameters are such that it could be bound directly to the on_key_down event of a keyboard. Therefore, it is safe to be called repeatedly when the key is held down as is done by the keyboard.

Returns bool, True if the keypress was used, False otherwise.

select_with_key_up(*keyboard*, *scancode*, ***kwargs*)

(internal) Processes a key release. This must be called by the derived widget when a key that [select_with_key_down\(\)](#) returned True is released.

The parameters are such that it could be bound directly to the on_key_up event of a keyboard.

Returns bool, True if the key release was used, False otherwise.

select_with_touch(*node*, *touch=None*)

(internal) Processes a touch on the node. This should be called by the derived widget when a node is touched and is to be used for selection. Depending on the keyboard keys pressed and the configuration, it could select or deselect this and other nodes in the selectable nodes list, [get_selectable_nodes\(\)](#).

Parameters

node The node that received the touch. Can be None for a scroll type touch.

touch Optionally, the touch. Defaults to None.

Returns bool, True if the touch was used, False otherwise.

selected_nodes

The list of selected nodes.

Note: Multiple nodes can be selected right after one another e.g. using the keyboard. When listening to [selected_nodes](#), one should be aware of this.

[selected_nodes](#) is a [ListProperty](#) and defaults to the empty list, []. It is read-only and should not be modified.

text_entry_timeout

When typing characters in rapid succession (i.e. the time difference since the last character is less than [text_entry_timeout](#)), the keys get concatenated and the combined text is passed as the key argument of [goto_node\(\)](#).

New in version 1.10.0.

touch_deselect_last

Determines whether the last selected node can be deselected when [multiselect](#) or [touch_multiselect](#) is False.

New in version 1.10.0.

[touch_deselect_last](#) is a [BooleanProperty](#) and defaults to True on mobile, False on desktop platforms.

touch_multiselect

A special touch mode which determines whether touch events, as processed by [select_with_touch\(\)](#), will add the currently touched node to the selection, or if it will clear the selection before adding the node. This allows the selection of multiple nodes by simply touching them.

This is different from [multiselect](#) because when it is True, simply touching an unselected node will select it, even if ctrl is not pressed. If it is False, however, ctrl must be pressed in order to add to the selection when [multiselect](#) is True.

Note: [multiselect](#), when False, will disable [touch_multiselect](#).

[touch_multiselect](#) is a [BooleanProperty](#) and defaults to False.

up_count

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when the up (or down) arrow on the keyboard is pressed.

[up_count](#) is a [NumericProperty](#) and defaults to 1.

class kivy.uix.behaviors.CoverBehavior(**kwargs)

Bases: `builtins.object`

The CoverBehavior [mixin](#) provides rendering a texture covering full widget size keeping aspect ratio of the original texture.

New in version 1.10.0.

cover_pos

Position of the aspect ratio aware texture. Gets calculated in [CoverBehavior.calculate_cover](#).

[cover_pos](#) is a [ListProperty](#) and defaults to [0, 0].

cover_size

Size of the aspect ratio aware texture. Gets calculated in [CoverBehavior.calculate_cover](#).

[cover_size](#) is a [ListProperty](#) and defaults to [0, 0].

reference_size

Reference size used for aspect ratio approximation calculation.

[reference_size](#) is a [ListProperty](#) and defaults to [].

class kivy.uix.behaviors.DragBehavior(**kwargs)

Bases: `builtins.object`

The DragBehavior [mixin](#) provides Drag behavior. When combined with a widget, dragging in the rectangle defined by [drag_rectangle](#) will drag the widget. Please see the [drag behaviors module](#) documentation for more information.

New in version 1.8.0.

drag_distance

Distance to move before dragging the [DragBehavior](#), in pixels. As soon as the distance has been traveled, the [DragBehavior](#) will start to drag, and no touch event will be dispatched to the children. It is advisable that you base this value on the dpi of your target device's screen.

[drag_distance](#) is a [NumericProperty](#) and defaults to the [scroll_distance](#) as defined in the user [Config](#) (20 pixels by default).

drag_rect_height

Height of the axis aligned bounding rectangle where dragging is allowed.

drag_rect_height is a *NumericProperty* and defaults to 100.

drag_rect_width

Width of the axis aligned bounding rectangle where dragging is allowed.

drag_rect_width is a *NumericProperty* and defaults to 100.

drag_rect_x

X position of the axis aligned bounding rectangle where dragging is allowed (in window coordinates).

drag_rect_x is a *NumericProperty* and defaults to 0.

drag_rect_y

Y position of the axis aligned bounding rectangle where dragging is allowed (in window coordinates).

drag_rect_Y is a *NumericProperty* and defaults to 0.

drag_rectangle

Position and size of the axis aligned bounding rectangle where dragging is allowed.

drag_rectangle is a *ReferenceListProperty* of (*drag_rect_x*, *drag_rect_y*, *drag_rect_width*, *drag_rect_height*) properties.

drag_timeout

Timeout allowed to trigger the *drag_distance*, in milliseconds. If the user has not moved *drag_distance* within the timeout, dragging will be disabled, and the touch event will be dispatched to the children.

drag_timeout is a *NumericProperty* and defaults to the *scroll_timeout* as defined in the user *Config* (55 milliseconds by default).

class kivy.uix.behaviors.EmacsBehavior(**kwargs)

Bases: `builtins.object`

A *mixin* that enables Emacs-style keyboard shortcuts for the *TextInput* widget. Please see the *Emacs behaviors module* documentation for more information.

New in version 1.9.1.

delete_word_left()

Delete text left of the cursor to the beginning of word

delete_word_right()

Delete text right of the cursor to the end of the word

key_bindings

String name which determines the type of key bindings to use with the *TextInput*. This allows Emacs key bindings to be enabled/disabled programmatically for widgets that inherit from *EmacsBehavior*. If the value is not 'emacs', Emacs bindings will be disabled. Use 'default' for switching to the default key bindings of *TextInput*.

key_bindings is a *StringProperty* and defaults to 'emacs'.

New in version 1.10.0.

class kivy.uix.behaviors.FocusBehavior(**kwargs)

Bases: `builtins.object`

Provides keyboard focus behavior. When combined with other FocusBehavior widgets it allows one to cycle focus among them by pressing tab. Please see the *focus behavior module documentation* for more information.

New in version 1.9.0.

focus

Whether the instance currently has focus.

Setting it to True will bind to and/or request the keyboard, and input will be forwarded to the instance. Setting it to False will unbind and/or release the keyboard. For a given keyboard, only one widget can have its focus, so focusing one will automatically unfocus the other instance holding its focus.

When using a software keyboard, please refer to the `softinput_mode` property to determine how the keyboard display is handled.

`focus` is a `BooleanProperty` and defaults to False.

focus_next

The `FocusBehavior` instance to acquire focus when tab is pressed and this instance has focus, if not `None` or `StopIteration`.

When tab is pressed, focus cycles through all the `FocusBehavior` widgets that are linked through `focus_next` and are focusable. If `focus_next` is `None`, it instead walks the children lists to find the next focusable widget. Finally, if `focus_next` is the `StopIteration` class, focus won't move forward, but end here.

`focus_next` is an `ObjectProperty` and defaults to `None`.

focus_previous

The `FocusBehavior` instance to acquire focus when shift+tab is pressed on this instance, if not `None` or `StopIteration`.

When shift+tab is pressed, focus cycles through all the `FocusBehavior` widgets that are linked through `focus_previous` and are focusable. If `focus_previous` is `None`, it instead walks the children tree to find the previous focusable widget. Finally, if `focus_previous` is the `StopIteration` class, focus won't move backward, but end here.

`focus_previous` is an `ObjectProperty` and defaults to `None`.

focused

An alias of `focus`.

`focused` is a `BooleanProperty` and defaults to False.

Warning: `focused` is an alias of `focus` and will be removed in 2.0.0.

get_focus_next()

Returns the next focusable widget using either `focus_next` or the `children` similar to the order when tabbing forwards with the `tab` key.

get_focus_previous()

Returns the previous focusable widget using either `focus_previous` or the `children` similar to the order when `tab + shift` key are triggered together.

hide_keyboard()

Convenience function to hide the keyboard in managed mode.

ignored_touch = []

A list of touches that should not be used to defocus. After `on_touch_up`, every touch that is not in `ignored_touch` will defocus all the focused widgets if the config keyboard mode is not multi. Touches on focusable widgets that were used to focus are automatically added here.

Example usage:

```

class Unfocusable(Widget):

    def on_touch_down(self, touch):
        if self.collide_point(*touch.pos):
            FocusBehavior.ignored_touch.append(touch)

```

Notice that you need to access this as a class, not an instance variable.

input_type

The kind of input keyboard to request.

New in version 1.8.0.

Changed in version 2.1.0: Changed default value from *text* to *null*. Added *null* to options.

Warning: As the default value has been changed, you may need to adjust *input_type* in your code.

input_type is an *OptionsProperty* and defaults to ‘null’. Can be one of ‘null’, ‘text’, ‘number’, ‘url’, ‘mail’, ‘datetime’, ‘tel’ or ‘address’.

is_focusable

Whether the instance can become focused. If focused, it’ll lose focus when set to False.

is_focusable is a *BooleanProperty* and defaults to True on a desktop (i.e. *desktop* is True in *config*), False otherwise.

keyboard

The keyboard to bind to (or bound to the widget) when focused.

When None, a keyboard is requested and released whenever the widget comes into and out of focus. If not None, it must be a keyboard, which gets bound and unbound from the widget whenever it’s in or out of focus. It is useful only when more than one keyboard is available, so it is recommended to be set to None when only one keyboard is available.

If more than one keyboard is available, whenever an instance gets focused a new keyboard will be requested if None. Unless the other instances lose focus (e.g. if tab was used), a new keyboard will appear. When this is undesired, the keyboard property can be used. For example, if there are two users with two keyboards, then each keyboard can be assigned to different groups of instances of FocusBehavior, ensuring that within each group, only one FocusBehavior will have focus, and will receive input from the correct keyboard. See *keyboard_mode* in *config* for more information on the keyboard modes.

Keyboard and focus behavior

When using the keyboard, there are some important default behaviors you should keep in mind.

- When Config’s *keyboard_mode* is multi, each new touch is considered a touch by a different user and will set the focus (if clicked on a focusable) with a new keyboard. Already focused elements will not lose their focus (even if an unfocusable widget is touched).
- If the keyboard property is set, that keyboard will be used when the instance gets focused. If widgets with different keyboards are linked through *focus_next* and *focus_previous*, then as they are tabbed through, different keyboards will become active. Therefore, typically it’s undesirable to link instances which are assigned different keyboards.
- When a widget has focus, setting its keyboard to None will remove its keyboard, but the widget will then immediately try to get another keyboard. In order to remove its

keyboard, rather set its *focus* to False.

- When using a software keyboard, typical on mobile and touch devices, the keyboard display behavior is determined by the *softinput_mode* property. You can use this property to ensure the focused widget is not covered or obscured.

keyboard is an *AliasProperty* and defaults to None.

keyboard_mode

Determines how the keyboard visibility should be managed. ‘auto’ will result in the standard behaviour of showing/hiding on focus. ‘managed’ requires setting the keyboard visibility manually, or calling the helper functions *show_keyboard()* and *hide_keyboard()*.

keyboard_mode is an *OptionsProperty* and defaults to ‘auto’. Can be one of ‘auto’ or ‘managed’.

keyboard_on_key_down(*window, keycode, text, modifiers*)

The method bound to the keyboard when the instance has focus.

When the instance becomes focused, this method is bound to the keyboard and will be called for every input press. The parameters are the same as *kivy.core.window.WindowBase.on_key_down()*.

When overwriting the method in the derived widget, super should be called to enable tab cycling. If the derived widget wishes to use tab for its own purposes, it can call super after it has processed the character (if it does not wish to consume the tab).

Similar to other keyboard functions, it should return True if the key was consumed.

keyboard_on_key_up(*window, keycode*)

The method bound to the keyboard when the instance has focus.

When the instance becomes focused, this method is bound to the keyboard and will be called for every input release. The parameters are the same as *kivy.core.window.WindowBase.on_key_up()*.

When overwriting the method in the derived widget, super should be called to enable defocusing on escape. If the derived widget wishes to use escape for its own purposes, it can call super after it has processed the character (if it does not wish to consume the escape).

See *keyboard_on_key_down()*

keyboard_suggestions

If True provides auto suggestions on top of keyboard. This will only work if *input_type* is set to *text*, *url*, *mail* or *address*.

New in version 2.1.0.

keyboard_suggestions is a *BooleanProperty* and defaults to True

show_keyboard()

Convenience function to show the keyboard in managed mode.

unfocus_on_touch

Whether a instance should lose focus when clicked outside the instance.

When a user clicks on a widget that is focus aware and shares the same keyboard as this widget (which in the case of only one keyboard, are all focus aware widgets), then as the other widgets gains focus, this widget loses focus. In addition to that, if this property is *True*, clicking on any widget other than this widget, will remove focus from this widget.

unfocus_on_touch is a *BooleanProperty* and defaults to *False* if the *keyboard_mode* in *Config* is ‘multi’ or ‘systemandmulti’, otherwise it defaults to *True*.

class kivy.uix.behaviors.ToggleButtonBehavior(kwargs)**

Bases: *kivy.uix.behaviors.button.ButtonBehavior*

This `mixin` class provides `togglebutton` behavior. Please see the [togglebutton behaviors module](#) documentation for more information.

New in version 1.8.0.

`allow_no_selection`

This specifies whether the widgets in a group allow no selection i.e. everything to be deselected.

New in version 1.9.0.

`allow_no_selection` is a `BooleanProperty` and defaults to `True`

`static get_widgets(groupname)`

Return a list of the widgets contained in a specific group. If the group doesn't exist, an empty list will be returned.

Note: Always release the result of this method! Holding a reference to any of these widgets can prevent them from being garbage collected. If in doubt, do:

```
l = ToggleButtonBehavior.get_widgets('mygroup')
# do your job
del l
```

Warning: It's possible that some widgets that you have previously deleted are still in the list. The garbage collector might need to release other objects before flushing them.

`group`

Group of the button. If `None`, no group will be used (the button will be independent). If specified, `group` must be a hashable object, like a string. Only one button in a group can be in a 'down' state.

`group` is a `ObjectProperty` and defaults to `None`.

`class kivy.uix.behaviors.TouchRippleBehavior(**kwargs)`

Bases: `builtins.object`

Touch ripple behavior.

Supposed to be used as mixin on widget classes.

Ripple behavior does not trigger automatically, concrete implementation needs to call `ripple_show()` respective `ripple_fade()` manually.

Here we create a Label which renders the touch ripple animation on interaction:

```
class RippleLabel(TouchRippleBehavior, Label):

    def __init__(self, **kwargs):
        super(RippleLabel, self).__init__(**kwargs)

    def on_touch_down(self, touch):
        collide_point = self.collide_point(touch.x, touch.y)
        if collide_point:
            touch.grab(self)
            self.ripple_show(touch)
        return True
```

(continues on next page)

```

    return False

def on_touch_up(self, touch):
    if touch.grab_current is self:
        touch.ungrab(self)
        self.ripple_fade()
    return True
return False

```

ripple_duration_in

Animation duration taken to show the overlay.

ripple_duration_in is a *NumericProperty* and defaults to 0.5.

ripple_duration_out

Animation duration taken to fade the overlay.

ripple_duration_out is a *NumericProperty* and defaults to 0.2.

ripple_fade()

Finish ripple animation on current widget.

ripple_fade_from_alpha

Alpha channel for ripple color the animation starts with.

ripple_fade_from_alpha is a *NumericProperty* and defaults to 0.5.

ripple_fade_to_alpha

Alpha channel for ripple color the animation targets to.

ripple_fade_to_alpha is a *NumericProperty* and defaults to 0.8.

ripple_func_in

Animation callback for showing the overlay.

ripple_func_in is a *StringProperty* and defaults to *in_cubic*.

ripple_func_out

Animation callback for hiding the overlay.

ripple_func_out is a *StringProperty* and defaults to *out_quad*.

ripple_rad_default

Default radius the animation starts from.

ripple_rad_default is a *NumericProperty* and defaults to 10.

ripple_scale

Max scale of the animation overlay calculated from max(width/height) of the decorated widget.

ripple_scale is a *NumericProperty* and defaults to 2.0.

ripple_show(touch)

Begin ripple animation on current widget.

Expects touch event as argument.

```
class kivy.uix.behaviors.TouchRippleButtonBehavior(**kwargs)
Bases: kivy.uix.behaviors.touchripple.TouchRippleBehavior
```

This *mixin* class provides a similar behavior to *ButtonBehavior* but provides touch ripple animation instead of button pressed/released as visual effect.

Events

on_press Fired when the button is pressed.

on_release Fired when the button is released (i.e. the touch/click that pressed the button goes away).

always_release

This determines whether or not the widget fires an *on_release* event if the touch_up is outside the widget.

always_release is a *BooleanProperty* and defaults to *False*.

last_touch

Contains the last relevant touch received by the Button. This can be used in *on_press* or *on_release* in order to know which touch dispatched the event.

last_touch is a *ObjectProperty* and defaults to *None*.

45.1.3 Button Behavior

The *ButtonBehavior* mixin class provides *Button* behavior. You can combine this class with other widgets, such as an *Image*, to provide alternative buttons that preserve Kivy button behavior.

For an overview of behaviors, please refer to the *behaviors* documentation.

Example

The following example adds button behavior to an image to make a checkbox that behaves like a button:

```
from kivy.app import App
from kivy.uix.image import Image
from kivy.uix.behaviors import ButtonBehavior

class MyButton(ButtonBehavior, Image):
    def __init__(self, **kwargs):
        super(MyButton, self).__init__(**kwargs)
        self.source = 'atlas://data/images/defaulttheme/checkbox_off'

    def on_press(self):
        self.source = 'atlas://data/images/defaulttheme/checkbox_on'

    def on_release(self):
        self.source = 'atlas://data/images/defaulttheme/checkbox_off'

class SampleApp(App):
    def build(self):
        return MyButton()

SampleApp().run()
```

See *ButtonBehavior* for details.

```
class kivy.uix.behaviors.button.ButtonBehavior(**kwargs)
Bases: builtins.object
```

This *mixin* class provides *Button* behavior. Please see the *button behaviors module* documentation for more information.

Events

`on_press` Fired when the button is pressed.

`on_release` Fired when the button is released (i.e. the touch/click that pressed the button goes away).

`always_release`

This determines whether or not the widget fires an `on_release` event if the `touch_up` is outside the widget.

New in version 1.9.0.

Changed in version 1.10.0: The default value is now False.

`always_release` is a `BooleanProperty` and defaults to `False`.

`last_touch`

Contains the last relevant touch received by the Button. This can be used in `on_press` or `on_release` in order to know which touch dispatched the event.

New in version 1.8.0.

`last_touch` is a `ObjectProperty` and defaults to `None`.

`min_state_time`

The minimum period of time which the widget must remain in the ‘down’ state.

New in version 1.9.1.

`min_state_time` is a float and defaults to 0.035. This value is taken from `Config`.

`state`

The state of the button, must be one of ‘normal’ or ‘down’. The state is ‘down’ only when the button is currently touched/clicked, otherwise its ‘normal’.

`state` is an `OptionProperty` and defaults to ‘normal’.

`trigger_action(duration=0.1)`

Trigger whatever action(s) have been bound to the button by calling both the `on_press` and `on_release` callbacks.

This is similar to a quick button press without using any touch events, but note that like most kivy code, this is not guaranteed to be safe to call from external threads. If needed use `Clock` to safely schedule this function and the resulting callbacks to be called from the main thread.

Duration is the length of the press in seconds. Pass 0 if you want the action to happen instantly.

New in version 1.8.0.

45.1.4 Code Navigation Behavior

The `CodeNavigationBehavior` modifies navigation behavior in the `TextInput`, making it work like an IDE instead of a word processor.

Using this mixin gives the `TextInput` the ability to recognize whitespace, punctuation and case variations (e.g. CamelCase) when moving over text. It is currently used by the `CodeInput` widget.

class `kivy.uix.behaviors.codenavigation.CodeNavigationBehavior`
Bases: `kivy.event.EventDispatcher`

Code navigation behavior. Modifies the navigation behavior in `TextInput` to work like an IDE instead of a word processor. Please see the `code navigation behaviors module` documentation for more information.

New in version 1.9.1.

45.1.5 Compound Selection Behavior

The `CompoundSelectionBehavior` mixin class implements the logic behind keyboard and touch selection of selectable widgets managed by the derived widget. For example, it can be combined with a `GridLayout` to add selection to the layout.

Compound selection concepts

At its core, it keeps a dynamic list of widgets that can be selected. Then, as the touches and keyboard input are passed in, it selects one or more of the widgets based on these inputs. For example, it uses the mouse scroll and keyboard up/down buttons to scroll through the list of widgets. Multiselection can also be achieved using the keyboard shift and ctrl keys.

Finally, in addition to the up/down type keyboard inputs, compound selection can also accept letters from the keyboard to be used to select nodes with associated strings that start with those letters, similar to how files are selected by a file browser.

Selection mechanics

When the controller needs to select a node, it calls `select_node()` and `deselect_node()`. Therefore, they must be overwritten in order alter node selection. By default, the class doesn't listen for keyboard or touch events, so the derived widget must call `select_with_touch()`, `select_with_key_down()`, and `select_with_key_up()` on events that it wants to pass on for selection purposes.

Example

To add selection to a grid layout which will contain Button widgets. For each button added to the layout, you need to bind the `on_touch_down` of the button to `select_with_touch()` to pass on the touch events:

```
from kivy.uix.behaviors.compoundselection import CompoundSelectionBehavior
from kivy.uix.button import Button
from kivy.uix.gridlayout import GridLayout
from kivy.uix.behaviors import FocusBehavior
from kivy.core.window import Window
from kivy.app import App

class SelectableGrid(FocusBehavior, CompoundSelectionBehavior, GridLayout):

    def keyboard_on_key_down(self, window, keycode, text, modifiers):
        """Based on FocusBehavior that provides automatic keyboard
        access, key presses will be used to select children.
        """
        if super>SelectableGrid, self).keyboard_on_key_down(
            window, keycode, text, modifiers):
            return True
        if self.select_with_key_down(window, keycode, text, modifiers):
            return True
        return False
```

(continues on next page)

```

def keyboard_on_key_up(self, window, keycode):
    """Based on FocusBehavior that provides automatic keyboard
    access, key release will be used to select children.
    """
    if super(SelectableGrid, self).keyboard_on_key_up(window, keycode):
        return True
    if self.select_with_key_up(window, keycode):
        return True
    return False

def add_widget(self, widget, *args, **kwargs):
    """Override the adding of widgets so we can bind and catch their
    *on_touch_down* events. """
    widget.bind(on_touch_down=self.button_touch_down,
                on_touch_up=self.button_touch_up)
    return super(SelectableGrid, self).add_
    ↪widget(widget, *args, **kwargs)

def button_touch_down(self, button, touch):
    """Use collision detection to select buttons when the touch occurs
    within their area. """
    if button.collide_point(*touch.pos):
        self.select_with_touch(button, touch)

def button_touch_up(self, button, touch):
    """Use collision detection to de-select buttons when the touch
    occurs outside their area and *touch_multiselect* is not True. """
    if not (button.collide_point(*touch.pos) or
            self.touch_multiselect):
        self.deselect_node(button)

def select_node(self, node):
    node.background_color = (1, 0, 0, 1)
    return super(SelectableGrid, self).select_node(node)

def deselect_node(self, node):
    node.background_color = (1, 1, 1, 1)
    super(SelectableGrid, self).deselect_node(node)

def on_selected_nodes(self, grid, nodes):
    print("Selected nodes = {0}".format(nodes))

class TestApp(App):
    def build(self):
        grid = SelectableGrid(cols=3, rows=2, touch_multiselect=True,
                              multiselect=True)
        for i in range(0, 6):
            grid.add_widget(Button(text="Button {0}".format(i)))
        return grid

TestApp().run()

```

Warning: This code is still experimental, and its API is subject to change in a future version.

```
class kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior(**kwargs)
Bases: builtins.object
```

The Selection behavior `mixin` implements the logic behind keyboard and touch selection of selectable widgets managed by the derived widget. Please see the [compound selection behaviors module](#) documentation for more information.

New in version 1.9.0.

clear_selection()

Deselects all the currently selected nodes.

deselect_node(node)

Deselects a possibly selected node.

It is called by the controller when it deselects a node and can also be called from the outside to deselect a node directly. The derived widget should overwrite this method and change the node to its unselected state when this is called

Parameters

node The node to be deselected.

Warning: This method must be called by the derived widget using super if it is overwritten.

get_index_of_node(node, selectable_nodes)

(internal) Returns the index of the *node* within the *selectable_nodes* returned by `get_selectable_nodes()`.

get_selectable_nodes()

(internal) Returns a list of the nodes that can be selected. It can be overwritten by the derived widget to return the correct list.

This list is used to determine which nodes to select with group selection. E.g. the last element in the list will be selected when home is pressed, pagedown will move (or add to, if shift is held) the selection from the current position by negative `page_count` nodes starting from the position of the currently selected node in this list and so on. Still, nodes can be selected even if they are not in this list.

Note: It is safe to dynamically change this list including removing, adding, or re-arranging its elements. Nodes can be selected even if they are not on this list. And selected nodes removed from the list will remain selected until `deselect_node()` is called.

Warning: Layouts display their children in the reverse order. That is, the contents of `children` is displayed from right to left, bottom to top. Therefore, internally, the indices of the elements returned by this function are reversed to make it work by default for most layouts so that the final result is consistent e.g. home, although it will select the last element in this list visually, will select the first element when counting from top to bottom and left to right. If this behavior is not desired, a reversed list should be returned instead.

Defaults to returning `children`.

goto_node(*key, last_node, last_node_idx*)

(internal) Used by the controller to get the node at the position indicated by key. The key can be keyboard inputs, e.g. pageup, or scroll inputs from the mouse scroll wheel, e.g. scrollup. 'last_node' is the last node selected and is used to find the resulting node. For example, if the key is up, the returned node is one node up from the last node.

It can be overwritten by the derived widget.

Parameters

key str, the string used to find the desired node. It can be any of the keyboard keys, as well as the mouse scrollup, scrolldown, scrollright, and scrollleft strings. If letters are typed in quick succession, the letters will be combined before it's passed in as key and can be used to find nodes that have an associated string that starts with those letters.

last_node The last node that was selected.

last_node_idx The cached index of the last node selected in the [get_selectable_nodes\(\)](#) list. If the list hasn't changed it saves having to look up the index of *last_node* in that list.

Returns tuple, the node targeted by key and its index in the [get_selectable_nodes\(\)](#) list. Returning (*last_node, last_node_idx*) indicates a node wasn't found.

keyboard_select

Determines whether the keyboard can be used for selection. If False, keyboard inputs will be ignored.

keyboard_select is a [BooleanProperty](#) and defaults to True.

multiselect

Determines whether multiple nodes can be selected. If enabled, keyboard shift and ctrl selection, optionally combined with touch, for example, will be able to select multiple widgets in the normally expected manner. This dominates [touch_multiselect](#) when False.

multiselect is a [BooleanProperty](#) and defaults to False.

nodes_order_reversed

(Internal) Indicates whether the order of the nodes as displayed top- down is reversed compared to their order in [get_selectable_nodes\(\)](#) (e.g. how the children property is reversed compared to how it's displayed).

page_count

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when pageup (or pagedown) is pressed.

page_count is a [NumericProperty](#) and defaults to 10.

right_count

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when the right (or left) arrow on the keyboard is pressed.

right_count is a [NumericProperty](#) and defaults to 1.

scroll_count

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when the mouse scroll wheel is scrolled.

right_count is a [NumericProperty](#) and defaults to 0.

select_node(*node*)

Selects a node.

It is called by the controller when it selects a node and can be called from the outside to select a node directly. The derived widget should overwrite this method and change the node state to selected when called.

Parameters

node The node to be selected.

Returns bool, True if the node was selected, False otherwise.

Warning: This method must be called by the derived widget using super if it is overwritten.

select_with_key_down(*keyboard, scancode, codepoint, modifiers, **kwargs*)

Processes a key press. This is called when a key press is to be used for selection. Depending on the keyboard keys pressed and the configuration, it could select or deselect nodes or node ranges from the selectable nodes list, [get_selectable_nodes\(\)](#).

The parameters are such that it could be bound directly to the on_key_down event of a keyboard. Therefore, it is safe to be called repeatedly when the key is held down as is done by the keyboard.

Returns bool, True if the keypress was used, False otherwise.

select_with_key_up(*keyboard, scancode, **kwargs*)

(internal) Processes a key release. This must be called by the derived widget when a key that [select_with_key_down\(\)](#) returned True is released.

The parameters are such that it could be bound directly to the on_key_up event of a keyboard.

Returns bool, True if the key release was used, False otherwise.

select_with_touch(*node, touch=None*)

(internal) Processes a touch on the node. This should be called by the derived widget when a node is touched and is to be used for selection. Depending on the keyboard keys pressed and the configuration, it could select or deselect this and other nodes in the selectable nodes list, [get_selectable_nodes\(\)](#).

Parameters

node The node that received the touch. Can be None for a scroll type touch.

touch Optionally, the touch. Defaults to None.

Returns bool, True if the touch was used, False otherwise.

selected_nodes

The list of selected nodes.

Note: Multiple nodes can be selected right after one another e.g. using the keyboard. When listening to [selected_nodes](#), one should be aware of this.

[selected_nodes](#) is a [ListProperty](#) and defaults to the empty list, []. It is read-only and should not be modified.

text_entry_timeout

When typing characters in rapid succession (i.e. the time difference since the last character is less than [text_entry_timeout](#)), the keys get concatenated and the combined text is passed as the key argument of [goto_node\(\)](#).

New in version 1.10.0.

touch_deselect_last

Determines whether the last selected node can be deselected when `multiselect` or `touch_multiselect` is False.

New in version 1.10.0.

`touch_deselect_last` is a *BooleanProperty* and defaults to True on mobile, False on desktop platforms.

touch_multiselect

A special touch mode which determines whether touch events, as processed by `select_with_touch()`, will add the currently touched node to the selection, or if it will clear the selection before adding the node. This allows the selection of multiple nodes by simply touching them.

This is different from `multiselect` because when it is True, simply touching an unselected node will select it, even if ctrl is not pressed. If it is False, however, ctrl must be pressed in order to add to the selection when `multiselect` is True.

Note: `multiselect`, when False, will disable `touch_multiselect`.

`touch_multiselect` is a *BooleanProperty* and defaults to False.

up_count

Determines by how much the selected node is moved up or down, relative to the position of the last selected node, when the up (or down) arrow on the keyboard is pressed.

`up_count` is a *NumericProperty* and defaults to 1.

45.1.6 Cover Behavior

The `CoverBehavior` mixin is intended for rendering textures to full widget size keeping the aspect ratio of the original texture.

Use cases are i.e. rendering full size background images or video content in a dynamic layout.

For an overview of behaviors, please refer to the `behaviors` documentation.

Example

The following examples add cover behavior to an image:

In python:

```
from kivy.app import App
from kivy.uix.behaviors import CoverBehavior
from kivy.uix.image import Image

class CoverImage(CoverBehavior, Image):

    def __init__(self, **kwargs):
        super(CoverImage, self).__init__(**kwargs)
        texture = self._coreimage.texture
        self.reference_size = texture.size
        self.texture = texture
```

(continues on next page)

```
class MainApp(App):
    def build(self):
        return CoverImage(source='image.jpg')

MainApp().run()
```

In Kivy Language:

```
CoverImage:
    source: 'image.png'

<CoverImage@CoverBehavior+Image>:
    reference_size: self.texture_size
```

See [CoverBehavior](#) for details.

class kivy.uix.behaviors.cover.CoverBehavior(**kwargs)
Bases: `builtins.object`

The CoverBehavior [mixin](#) provides rendering a texture covering full widget size keeping aspect ratio of the original texture.

New in version 1.10.0.

cover_pos

Position of the aspect ratio aware texture. Gets calculated in `CoverBehavior.calculate_cover`.

`cover_pos` is a [ListProperty](#) and defaults to `[0, 0]`.

cover_size

Size of the aspect ratio aware texture. Gets calculated in `CoverBehavior.calculate_cover`.

`cover_size` is a [ListProperty](#) and defaults to `[0, 0]`.

reference_size

Reference size used for aspect ratio approximation calculation.

`reference_size` is a [ListProperty](#) and defaults to `[]`.

45.1.7 Drag Behavior

The `DragBehavior` mixin class provides Drag behavior. When combined with a widget, dragging in the rectangle defined by the `drag_rectangle` will drag the widget.

Example

The following example creates a draggable label:

```
from kivy.uix.label import Label
from kivy.app import App
from kivy.uix.behaviors import DragBehavior
from kivy.lang import Builder

# You could also put the following in your kv file...
kv = '''
<DragLabel>:
    # Define the properties for the DragLabel
    drag_rectangle: self.x, self.y, self.width, self.height
    drag_timeout: 10000000
    drag_distance: 0

FloatLayout:
    # Define the root widget
    DragLabel:
        size_hint: 0.25, 0.2
        text: 'Drag me'
'''


class DragLabel(DragBehavior, Label):
    pass


class TestApp(App):
    def build(self):
        return Builder.load_string(kv)

TestApp().run()
```

```
class kivy.uix.behaviors.drag.DragBehavior(**kwargs)
Bases: builtins.object
```

The `DragBehavior` mixin provides Drag behavior. When combined with a widget, dragging in the rectangle defined by `drag_rectangle` will drag the widget. Please see the [drag behaviors module](#) documentation for more information.

New in version 1.8.0.

`drag_distance`

Distance to move before dragging the `DragBehavior`, in pixels. As soon as the distance has been traveled, the `DragBehavior` will start to drag, and no touch event will be dispatched to the children. It is advisable that you base this value on the dpi of your target device's screen.

`drag_distance` is a [NumericProperty](#) and defaults to the `scroll_distance` as defined in the user [Config](#) (20 pixels by default).

drag_rect_height

Height of the axis aligned bounding rectangle where dragging is allowed.

drag_rect_height is a *NumericProperty* and defaults to 100.

drag_rect_width

Width of the axis aligned bounding rectangle where dragging is allowed.

drag_rect_width is a *NumericProperty* and defaults to 100.

drag_rect_x

X position of the axis aligned bounding rectangle where dragging is allowed (in window coordinates).

drag_rect_x is a *NumericProperty* and defaults to 0.

drag_rect_y

Y position of the axis aligned bounding rectangle where dragging is allowed (in window coordinates).

drag_rect_Y is a *NumericProperty* and defaults to 0.

drag_rectangle

Position and size of the axis aligned bounding rectangle where dragging is allowed.

drag_rectangle is a *ReferenceListProperty* of (*drag_rect_x*, *drag_rect_y*, *drag_rect_width*, *drag_rect_height*) properties.

drag_timeout

Timeout allowed to trigger the *drag_distance*, in milliseconds. If the user has not moved *drag_distance* within the timeout, dragging will be disabled, and the touch event will be dispatched to the children.

drag_timeout is a *NumericProperty* and defaults to the *scroll_timeout* as defined in the user *Config* (55 milliseconds by default).

45.1.8 Emacs Behavior

The *EmacsBehavior* mixin allows you to add *Emacs* keyboard shortcuts for basic movement and editing to the *TextInput* widget. The shortcuts currently available are listed below:

Emacs shortcuts

Shortcut	Description
Control + a	Move cursor to the beginning of the line
Control + e	Move cursor to the end of the line
Control + f	Move cursor one character to the right
Control + b	Move cursor one character to the left
Alt + f	Move cursor to the end of the word to the right
Alt + b	Move cursor to the start of the word to the left
Alt + Backspace	Delete text left of the cursor to the beginning of word
Alt + d	Delete text right of the cursor to the end of the word
Alt + w	Copy selection
Control + w	Cut selection
Control + y	Paste selection

Warning: If you have the `inspector` module enabled, the shortcut for opening the inspector (Control + e) conflicts with the Emacs shortcut to move to the end of the line (it will still move the cursor to the end of the line, but the inspector will open as well).

```
class kivy.uix.behaviors.emacs.EmacsBehavior(**kwargs)
    Bases: builtins.object
```

A `mixin` that enables Emacs-style keyboard shortcuts for the `TextInput` widget. Please see the [Emacs behaviors module](#) documentation for more information.

New in version 1.9.1.

`delete_word_left()`

Delete text left of the cursor to the beginning of word

`delete_word_right()`

Delete text right of the cursor to the end of the word

`key_bindings`

String name which determines the type of key bindings to use with the `TextInput`. This allows Emacs key bindings to be enabled/disabled programmatically for widgets that inherit from `EmacsBehavior`. If the value is not 'emacs', Emacs bindings will be disabled. Use 'default' for switching to the default key bindings of `TextInput`.

`key_bindings` is a `StringProperty` and defaults to 'emacs'.

New in version 1.10.0.

45.1.9 Focus Behavior

The `FocusBehavior` mixin class provides keyboard focus behavior. When combined with other FocusBehavior widgets it allows one to cycle focus among them by pressing tab. In addition, upon gaining focus, the instance will automatically receive keyboard input.

Focus, very different from selection, is intimately tied with the keyboard; each keyboard can focus on zero or one widgets, and each widget can only have the focus of one keyboard. However, multiple keyboards can focus simultaneously on different widgets. When escape is hit, the widget having the focus of that keyboard will de-focus.

Managing focus

In essence, focus is implemented as a doubly linked list, where each node holds a (weak) reference to the instance before it and after it, as visualized when cycling through the nodes using tab (forward) or shift+tab (backward). If a previous or next widget is not specified, `focus_next` and `focus_previous` defaults to `None`. This means that the `children` list and `parents` are walked to find the next focusable widget, unless `focus_next` or `focus_previous` is set to the `StopIteration` class, in which case focus stops there.

For example, to cycle focus between `Button` elements of a `GridLayout`:

```
class FocusButton(FocusBehavior, Button):
    pass

grid = GridLayout(cols=4)
for i in range(40):
    grid.add_widget(FocusButton(text=str(i)))
```

(continues on next page)

(continued from previous page)

```
# clicking on a widget will activate focus, and tab can now be used
# to cycle through
```

When using a software keyboard, typical on mobile and touch devices, the keyboard display behavior is determined by the `softinput_mode` property. You can use this property to ensure the focused widget is not covered or obscured by the keyboard.

Initializing focus

Widgets needs to be visible before they can receive the focus. This means that setting their `focus` property to True before they are visible will have no effect. To initialize focus, you can use the 'on_parent' event:

```
from kivy.app import App
from kivy.uix.textinput import TextInput

class MyTextInput(TextInput):
    def on_parent(self, widget, parent):
        self.focus = True

class SampleApp(App):
    def build(self):
        return MyTextInput()

SampleApp().run()
```

If you are using a `popup`, you can use the 'on_open' event.

For an overview of behaviors, please refer to the [behaviors](#) documentation.

Warning: This code is still experimental, and its API is subject to change in a future version.

class kivy.uix.behaviors.focus.**FocusBehavior**(**kwargs)
Bases: `builtins.object`

Provides keyboard focus behavior. When combined with other FocusBehavior widgets it allows one to cycle focus among them by pressing tab. Please see the [focus behavior module documentation](#) for more information.

New in version 1.9.0.

focus

Whether the instance currently has focus.

Setting it to True will bind to and/or request the keyboard, and input will be forwarded to the instance. Setting it to False will unbind and/or release the keyboard. For a given keyboard, only one widget can have its focus, so focusing one will automatically unfocus the other instance holding its focus.

When using a software keyboard, please refer to the `softinput_mode` property to determine how the keyboard display is handled.

`focus` is a *BooleanProperty* and defaults to False.

focus_next

The `FocusBehavior` instance to acquire focus when tab is pressed and this instance has focus, if not `None` or `StopIteration`.

When tab is pressed, focus cycles through all the *FocusBehavior* widgets that are linked through *focus_next* and are focusable. If *focus_next* is *None*, it instead walks the children lists to find the next focusable widget. Finally, if *focus_next* is the *StopIteration* class, focus won't move forward, but end here.

focus_next is an *ObjectProperty* and defaults to *None*.

focus_previous

The *FocusBehavior* instance to acquire focus when shift+tab is pressed on this instance, if not *None* or *StopIteration*.

When shift+tab is pressed, focus cycles through all the *FocusBehavior* widgets that are linked through *focus_previous* and are focusable. If *focus_previous* is *None*, it instead walks the children tree to find the previous focusable widget. Finally, if *focus_previous* is the *StopIteration* class, focus won't move backward, but end here.

focus_previous is an *ObjectProperty* and defaults to *None*.

focused

An alias of *focus*.

focused is a *BooleanProperty* and defaults to False.

Warning: *focused* is an alias of *focus* and will be removed in 2.0.0.

get_focus_next()

Returns the next focusable widget using either *focus_next* or the *children* similar to the order when tabbing forwards with the *tab* key.

get_focus_previous()

Returns the previous focusable widget using either *focus_previous* or the *children* similar to the order when *tab + shift* key are triggered together.

hide_keyboard()

Convenience function to hide the keyboard in managed mode.

ignored_touch = []

A list of touches that should not be used to defocus. After *on_touch_up*, every touch that is not in *ignored_touch* will defocus all the focused widgets if the config keyboard mode is not multi. Touches on focusable widgets that were used to focus are automatically added here.

Example usage:

```
class Unfocusable(Widget):

    def on_touch_down(self, touch):
        if self.collide_point(*touch.pos):
            FocusBehavior.ignored_touch.append(touch)
```

Notice that you need to access this as a class, not an instance variable.

input_type

The kind of input keyboard to request.

New in version 1.8.0.

Changed in version 2.1.0: Changed default value from *text* to *null*. Added *null* to options.

Warning: As the default value has been changed, you may need to adjust `input_type` in your code.

`input_type` is an `OptionsProperty` and defaults to ‘null’. Can be one of ‘null’, ‘text’, ‘number’, ‘url’, ‘mail’, ‘datetime’, ‘tel’ or ‘address’.

is_focusable

Whether the instance can become focused. If focused, it’ll lose focus when set to False.

`is_focusable` is a `BooleanProperty` and defaults to True on a desktop (i.e. `desktop` is True in `config`), False otherwise.

keyboard

The keyboard to bind to (or bound to the widget) when focused.

When None, a keyboard is requested and released whenever the widget comes into and out of focus. If not None, it must be a keyboard, which gets bound and unbound from the widget whenever it’s in or out of focus. It is useful only when more than one keyboard is available, so it is recommended to be set to None when only one keyboard is available.

If more than one keyboard is available, whenever an instance gets focused a new keyboard will be requested if None. Unless the other instances lose focus (e.g. if tab was used), a new keyboard will appear. When this is undesired, the keyboard property can be used. For example, if there are two users with two keyboards, then each keyboard can be assigned to different groups of instances of FocusBehavior, ensuring that within each group, only one FocusBehavior will have focus, and will receive input from the correct keyboard. See `keyboard_mode` in `config` for more information on the keyboard modes.

Keyboard and focus behavior

When using the keyboard, there are some important default behaviors you should keep in mind.

- When Config’s `keyboard_mode` is multi, each new touch is considered a touch by a different user and will set the focus (if clicked on a focusable) with a new keyboard. Already focused elements will not lose their focus (even if an unfocusable widget is touched).
- If the keyboard property is set, that keyboard will be used when the instance gets focused. If widgets with different keyboards are linked through `focus_next` and `focus_previous`, then as they are tabbed through, different keyboards will become active. Therefore, typically it’s undesirable to link instances which are assigned different keyboards.
- When a widget has focus, setting its keyboard to None will remove its keyboard, but the widget will then immediately try to get another keyboard. In order to remove its keyboard, rather set its `focus` to False.
- When using a software keyboard, typical on mobile and touch devices, the keyboard display behavior is determined by the `softinput_mode` property. You can use this property to ensure the focused widget is not covered or obscured.

`keyboard` is an `AliasProperty` and defaults to None.

keyboard_mode

Determines how the keyboard visibility should be managed. ‘auto’ will result in the standard behaviour of showing/hiding on focus. ‘managed’ requires setting the keyboard visibility manually, or calling the helper functions `show_keyboard()` and `hide_keyboard()`.

`keyboard_mode` is an `OptionsProperty` and defaults to ‘auto’. Can be one of ‘auto’ or ‘managed’.

keyboard_on_key_down(*window, keycode, text, modifiers*)

The method bound to the keyboard when the instance has focus.

When the instance becomes focused, this method is bound to the keyboard and will be called for every input press. The parameters are the same as [kivy.core.window.WindowBase.on_key_down\(\)](#).

When overwriting the method in the derived widget, super should be called to enable tab cycling. If the derived widget wishes to use tab for its own purposes, it can call super after it has processed the character (if it does not wish to consume the tab).

Similar to other keyboard functions, it should return True if the key was consumed.

keyboard_on_key_up(*window, keycode*)

The method bound to the keyboard when the instance has focus.

When the instance becomes focused, this method is bound to the keyboard and will be called for every input release. The parameters are the same as [kivy.core.window.WindowBase.on_key_up\(\)](#).

When overwriting the method in the derived widget, super should be called to enable defocusing on escape. If the derived widget wishes to use escape for its own purposes, it can call super after it has processed the character (if it does not wish to consume the escape).

See [keyboard_on_key_down\(\)](#)

keyboard_suggestions

If True provides auto suggestions on top of keyboard. This will only work if [input_type](#) is set to *text*, *url*, *mail* or *address*.

New in version 2.1.0.

[keyboard_suggestions](#) is a [BooleanProperty](#) and defaults to True

show_keyboard()

Convenience function to show the keyboard in managed mode.

unfocus_on_touch

Whether a instance should lose focus when clicked outside the instance.

When a user clicks on a widget that is focus aware and shares the same keyboard as this widget (which in the case of only one keyboard, are all focus aware widgets), then as the other widgets gains focus, this widget loses focus. In addition to that, if this property is True, clicking on any widget other than this widget, will remove focus from this widget.

[unfocus_on_touch](#) is a [BooleanProperty](#) and defaults to False if the [keyboard_mode](#) in [Config](#) is 'multi' or 'systemandmulti', otherwise it defaults to True.

45.1.10 Kivy Namespaces

New in version 1.9.1.

Warning: This code is still experimental, and its API is subject to change in a future version.

The [KNSpaceBehavior](#) mixin class provides namespace functionality for Kivy objects. It allows kivy objects to be named and then accessed using namespaces.

[KNSpace](#) instances are the namespaces that store the named objects in Kivy [ObjectProperty](#) instances. In addition, when inheriting from [KNSpaceBehavior](#), if the derived object is named, the name will automatically be added to the associated namespace and will point to a [proxy_ref](#) of the derived object.

Basic examples

By default, there's only a single namespace: the `knspace` namespace. The simplest example is adding a widget to the namespace:

```
from kivy.uix.behaviors.knspace import knspace
widget = Widget()
knspace.my_widget = widget
```

This adds a kivy `ObjectProperty` with `rebind=True` and `allowNone=True` to the `knspace` namespace with a property name `my_widget`. And the property now also points to this widget.

This can be done automatically with:

```
class MyWidget(KNSpaceBehavior, Widget):
    pass

widget = MyWidget(knsname='my_widget')
```

Or in kv:

```
<MyWidget@KNSpaceBehavior+Widget>

MyWidget:
    knsname: 'my_widget'
```

Now, `knspace.my_widget` will point to that widget.

When one creates a second widget with the same name, the namespace will also change to point to the new widget. E.g.:

```
widget = MyWidget(knsname='my_widget')
# knspace.my_widget now points to widget
widget2 = MyWidget(knsname='my_widget')
# knspace.my_widget now points to widget2
```

Setting the namespace

One can also create ones own namespace rather than using the default `knspace` by directly setting `KNSpaceBehavior.knspace`:

```
class MyWidget(KNSpaceBehavior, Widget):
    pass

widget = MyWidget(knsname='my_widget')
my_new_namespace = KNSpace()
widget.knspace = my_new_namespace
```

Initially, `my_widget` is added to the default namespace, but when the widget's namespace is changed to `my_new_namespace`, the reference to `my_widget` is moved to that namespace. We could have also of course first set the namespace to `my_new_namespace` and then have named the widget `my_widget`, thereby avoiding the initial assignment to the default namespace.

Similarly, in kv:

```
<MyWidget@KNSpaceBehavior+Widget>

MyWidget:
  knspace: KNSpace()
  knsname: 'my_widget'
```

Inheriting the namespace

In the previous example, we directly set the namespace we wished to use. In the following example, we inherit it from the parent, so we only have to set it once:

```
<MyWidget@KNSpaceBehavior+Widget>
<MyLabel@KNSpaceBehavior+Label>

<MyComplexWidget@MyWidget:>
  knsname: 'my_complex'
  MyLabel:
    knsname: 'label1'
  MyLabel:
    knsname: 'label2'
```

Then, we do:

```
widget = MyComplexWidget()
new_knspace = KNSpace()
widget.knspace = new_knspace
```

The rule is that if no knspace has been assigned to a widget, it looks for a namespace in its parent and parent's parent and so on until it finds one to use. If none are found, it uses the default *knspace*.

When *MyComplexWidget* is created, it still used the default namespace. However, when we assigned the root widget its new namespace, all its children switched to using that new namespace as well. So *new_knspace* now contains *label1* and *label2* as well as *my_complex*.

If we had first done:

```
widget = MyComplexWidget()
new_knspace = KNSpace()
knspace.label1.knspace = knspace
widget.knspace = new_knspace
```

Then *label1* would remain stored in the default *knspace* since it was directly set, but *label2* and *my_complex* would still be added to the new namespace.

One can customize the attribute used to search the parent tree by changing *KNSpaceBehavior.knspace_key*. If the desired knspace is not reachable through a widget's parent tree, e.g. in a popup that is not a widget's child, *KNSpaceBehavior.knspace_key* can be used to establish a different search order.

Accessing the namespace

As seen in the previous example, if not directly assigned, the namespace is found by searching the parent tree. Consequently, if a namespace was assigned further up the parent tree, all its children and below could access that namespace through their *KNSpaceBehavior.knspace* property.

This allows the creation of multiple widgets with identically given names if each root widget instance is assigned a new namespace. For example:

```
<MyComplexWidget@KNSpaceBehavior+Widget>:  
    Label:  
        text: root.knspace.pretty.text if root.knspace.pretty else ''  
  
<MyPrettyWidget@KNSpaceBehavior+TextInput>:  
    knsname: 'pretty'  
    text: 'Hello'  
  
<MyCompositeWidget@KNSpaceBehavior+BoxLayout>:  
    MyComplexWidget  
    MyPrettyWidget
```

Now, when we do:

```
knspace1, knspace2 = KNSpace(), KNSpace()  
composite1 = MyCompositeWidget()  
composite1.knspace = knspace1  
  
composite2 = MyCompositeWidget()  
composite2.knspace = knspace2  
  
knspace1.pretty = "Here's the ladder, now fix the roof!"  
knspace2.pretty = "Get that raccoon off me!"
```

Because each of the *MyCompositeWidget* instances have a different namespace their children also use different namespaces. Consequently, the pretty and complex widgets of each instance will have different text.

Further, because both the namespace *ObjectProperty* references, and *KNSpaceBehavior.knspace* have *rebind=True*, the text of the *MyComplexWidget* label is rebound to match the text of *MyPrettyWidget* when either the root's namespace changes or when the *root.knspace.pretty* property changes, as expected.

Forking a namespace

Forking a namespace provides the opportunity to create a new namespace from a parent namespace so that the forked namespace will contain everything in the origin namespace, but the origin namespace will not have access to anything added to the forked namespace.

For example:

```
child = knspace.fork()  
grandchild = child.fork()  
  
child.label = Label()  
grandchild.button = Button()
```

Now label is accessible by both child and grandchild, but not by knspace. And button is only accessible by the grandchild but not by the child or by knspace. Finally, doing `grandchild.label = Label()` will leave `grandchild.label` and `child.label` pointing to different labels.

A motivating example is the example from above:

```
<MyComplexWidget@KNSpaceBehavior+Widget>:  
    Label:  
        text: root.knspace.pretty.text if root.knspace.pretty else ''  
  
<MyPrettyWidget@KNSpaceBehavior+TextInput>:  
    knsname: 'pretty'  
    text: 'Hello'  
  
<MyCompositeWidget@KNSpaceBehavior+BoxLayout>:  
    knspace: 'fork'  
    MyComplexWidget  
    MyPrettyWidget
```

Notice the addition of `knspace: 'fork'`. This is identical to doing `knspace: self.knspace.fork()`. However, doing that would lead to infinite recursion as that kv rule would be executed recursively because `self.knspace` will keep on changing. However, allowing `knspace: 'fork'` circumvents that. See [KNSpaceBehavior.knspace](#).

Now, having forked, we just need to do:

```
composite1 = MyCompositeWidget()  
composite2 = MyCompositeWidget()  
  
composite1.knspace.pretty = "Here's the ladder, now fix the roof!"  
composite2.knspace.pretty = "Get that raccoon off me!"
```

Since by forking we automatically created a unique namespace for each `MyCompositeWidget` instance.

class kivy.uix.behaviors.knspace.KNSpace(`parent=None, keep_ref=False, **kwargs`)
Bases: [kivy.event.EventDispatcher](#)

Each `KNSpace` instance is a namespace that stores the named Kivy objects associated with this namespace. Each named object is stored as the value of a Kivy `ObjectProperty` of this instance whose property name is the object's given name. Both `rebind` and `allownone` are set to `True` for the property.

See [KNSpaceBehavior.knspace](#) for details on how a namespace is associated with a named object.

When storing an object in the namespace, the object's `proxy_ref` is stored if the object has such an attribute.

Parameters

`parent: (internal)` A `KNSpace` instance or `None`. If specified, it's a parent namespace, in which case, the current namespace will have in its namespace all its named objects as well as the named objects of its parent and parent's parent etc. See `fork()` for more details.

fork()

Returns a new `KNSpace` instance which will have access to all the named objects in the current namespace but will also have a namespace of its own that is unique to it.

For example:

```
forked_knspace1 = knspace.fork()  
forked_knspace2 = knspace.fork()
```

Now, any names added to *knspace* will be accessible by the *forked_knspace1* and *forked_knspace2* namespaces by the normal means. However, any names added to *forked_knspace1* will not be accessible from *knspace* or *forked_knspace2*. Similar for *forked_knspace2*.

keep_ref = False

Whether a direct reference should be kept to the stored objects. If *True*, we use the direct object, otherwise we use *proxy_ref* when present.

Defaults to *False*.

parent = None

(internal) The parent namespace instance, *KNSpace*, or *None*. See *fork()*.

property(self, name, quiet=False)

Get a property instance from the property name. If *quiet* is *True*, *None* is returned instead of raising an exception when *name* is not a property. Defaults to *False*.

New in version 1.0.9.

Returns A *Property* derived instance corresponding to the name.

Changed in version 1.9.0: *quiet* was added.

class kivy.uix.behaviors.knspace.KNSpaceBehavior(knspace=None, **kwargs)

Bases: *builtins.object*

Inheriting from this class allows naming of the inherited objects, which are then added to the associated namespace *knspace* and accessible through it.

Please see the *knspace behaviors module* documentation for more information.

knsname

The name given to this instance. If named, the name will be added to the associated *knspace* namespace, which will then point to the *proxy_ref* of this instance.

When named, one can access this object by e.g. *self.knspace.name*, where *name* is the given name of this instance. See *knspace* and the module description for more details.

knspace

The namespace instance, *KNSpace*, associated with this widget. The *knspace* namespace stores this widget when naming this widget with *knsname*.

If the namespace has been set with a *KNSpace* instance, e.g. with *self.knspace = KNSpace()*, then that instance is returned (setting with *None* doesn't count). Otherwise, if *knspace_key* is not *None*, we look for a namespace to use in the object that is stored in the property named *knspace_key*, of this instance. I.e. *object = getattr(self, self.knspace_key)*.

If that object has a *knspace* property, then we return its value. Otherwise, we go further up, e.g. with *getattr(object, self.knspace_key)* and look for its *knspace* property.

Finally, if we reach a value of *None*, or *knspace_key* was *None*, the default *knspace* namespace is returned.

If *knspace* is set to the string '*fork*', the current namespace in *knspace* will be forked with *KNSpace.fork()* and the resulting namespace will be assigned to this instance's *knspace*. See the module examples for a motivating example.

Both *rebind* and *allownone* are *True*.

knspace_key

The name of the property of this instance, to use to search upwards for a namespace to use by this instance. Defaults to '*parent*' so that we'll search the parent tree. See *knspace*.

When *None*, we won't search the parent tree for the namespace. *allownone* is *True*.

`kivy.uix.behaviors.knspase.knspase = <kivy.uix.behaviors.knspase.KNSpace object>`

The default *KNSpace* namespace. See *KNSpaceBehavior.knspase* for more details.

45.1.11 ToggleButton Behavior

The *ToggleButtonBehavior* mixin class provides *ToggleButton* behavior. You can combine this class with other widgets, such as an *Image*, to provide alternative togglebuttons that preserve Kivy togglebutton behavior.

For an overview of behaviors, please refer to the *behaviors* documentation.

Example

The following example adds togglebutton behavior to an image to make a checkbox that behaves like a togglebutton:

```
from kivy.app import App
from kivy.uix.image import Image
from kivy.uix.behaviors import ToggleButtonBehavior

class MyButton(ToggleButtonBehavior, Image):
    def __init__(self, **kwargs):
        super(MyButton, self).__init__(**kwargs)
        self.source = 'atlas://data/images/defaulttheme/checkbox_off'

    def on_state(self, widget, value):
        if value == 'down':
            self.source = 'atlas://data/images/defaulttheme/checkbox_on'
        else:
            self.source = 'atlas://data/images/defaulttheme/checkbox_off'

class SampleApp(App):
    def build(self):
        return MyButton()

SampleApp().run()
```

class kivy.uix.behaviors.togglebutton.ToggleButtonBehavior(kwargs)**
Bases: *kivy.uix.behaviors.button.ButtonBehavior*

This *mixin* class provides *togglebutton* behavior. Please see the *togglebutton behaviors module* documentation for more information.

New in version 1.8.0.

allow_no_selection

This specifies whether the widgets in a group allow no selection i.e. everything to be deselected.

New in version 1.9.0.

allow_no_selection is a BooleanProperty and defaults to *True*

static get_widgets(groupname)

Return a list of the widgets contained in a specific group. If the group doesn't exist, an empty list will be returned.

Note: Always release the result of this method! Holding a reference to any of these widgets can prevent them from being garbage collected. If in doubt, do:

```
l = ToggleButtonBehavior.get_widgets('mygroup')
# do your job
del l
```

Warning: It's possible that some widgets that you have previously deleted are still in the list. The garbage collector might need to release other objects before flushing them.

group

Group of the button. If *None*, no group will be used (the button will be independent). If specified, **group** must be a hashable object, like a string. Only one button in a group can be in a 'down' state.

group is a *ObjectProperty* and defaults to *None*.

45.1.12 Touch Ripple

New in version 1.10.1.

Warning: This code is still experimental, and its API is subject to change in a future version.

This module contains **mixin** classes to add a touch ripple visual effect known from *Google Material Design* <https://en.wikipedia.org/wiki/Material_Design>_ to widgets.

For an overview of behaviors, please refer to the **behaviors** documentation.

The class **TouchRippleBehavior** provides rendering the ripple animation.

The class **TouchRippleButtonBehavior** basically provides the same functionality as **ButtonBehavior** but rendering the ripple animation instead of default press/release visualization.

```
class kivy.uix.behaviors.touchripple.TouchRippleBehavior(**kwargs)
    Bases: builtins.object
```

Touch ripple behavior.

Supposed to be used as mixin on widget classes.

Ripple behavior does not trigger automatically, concrete implementation needs to call **ripple_show()** respective **ripple_fade()** manually.

Here we create a Label which renders the touch ripple animation on interaction:

```
class RippleLabel(TouchRippleBehavior, Label):
    def __init__(self, **kwargs):
        super(RippleLabel, self).__init__(**kwargs)
```

(continues on next page)

```

def on_touch_down(self, touch):
    collide_point = self.collide_point(touch.x, touch.y)
    if collide_point:
        touch.grab(self)
        self.ripple_show(touch)
        return True
    return False

def on_touch_up(self, touch):
    if touch.grab_current is self:
        touch.ungrab(self)
        self.ripple_fade()
        return True
    return False

```

ripple_duration_in

Animation duration taken to show the overlay.

ripple_duration_in is a *NumericProperty* and defaults to 0.5.

ripple_duration_out

Animation duration taken to fade the overlay.

ripple_duration_out is a *NumericProperty* and defaults to 0.2.

ripple_fade()

Finish ripple animation on current widget.

ripple_fade_from_alpha

Alpha channel for ripple color the animation starts with.

ripple_fade_from_alpha is a *NumericProperty* and defaults to 0.5.

ripple_fade_to_alpha

Alpha channel for ripple color the animation targets to.

ripple_fade_to_alpha is a *NumericProperty* and defaults to 0.8.

ripple_func_in

Animation callback for showing the overlay.

ripple_func_in is a *StringProperty* and defaults to *in_cubic*.

ripple_func_out

Animation callback for hiding the overlay.

ripple_func_out is a *StringProperty* and defaults to *out_quad*.

ripple_rad_default

Default radius the animation starts from.

ripple_rad_default is a *NumericProperty* and defaults to 10.

ripple_scale

Max scale of the animation overlay calculated from max(width/height) of the decorated widget.

ripple_scale is a *NumericProperty* and defaults to 2.0.

ripple_show(touch)

Begin ripple animation on current widget.

Expects touch event as argument.

```
class kivy.uix.behaviors.touchripple.TouchRippleButtonBehavior(**kwargs)
Bases: kivy.uix.behaviors.touchripple.TouchRippleBehavior
```

This **mixin** class provides a similar behavior to **ButtonBehavior** but provides touch ripple animation instead of button pressed/released as visual effect.

Events

on_press Fired when the button is pressed.

on_release Fired when the button is released (i.e. the touch/click that pressed the button goes away).

always_release

This determines whether or not the widget fires an **on_release** event if the touch_up is outside the widget.

always_release is a **BooleanProperty** and defaults to *False*.

last_touch

Contains the last relevant touch received by the Button. This can be used in **on_press** or **on_release** in order to know which touch dispatched the event.

last_touch is a **ObjectProperty** and defaults to *None*.

45.2 RecycleView

New in version 1.10.0.

The RecycleView provides a flexible model for viewing selected sections of large data sets. It aims to prevent the performance degradation that can occur when generating large numbers of widgets in order to display many data items.

Warning: Because **RecycleView** reuses widgets, any state change to a single widget will stay with that widget as it's reused, even if the **data** assigned to it by the **RecycleView** changes. Unless the complete state is tracked in **data** (see below).

The view is generated by processing the **data**, essentially a list of dicts, and uses these dicts to generate instances of the **viewclass** as required. Its design is based on the MVC (**Model-view-controller**) pattern.

- Model: The model is formed by **data** you pass in via a list of dicts.
- View: The View is split across layout and views and implemented using adapters.
- Controller: The controller determines the logical interaction and is implemented by **RecycleViewBehavior**.

These are abstract classes and cannot be used directly. The default concrete implementations are the **RecycleDataModel** for the model, the **RecycleLayout** for the view, and the **RecycleView** for the controller.

When a RecycleView is instantiated, it automatically creates the views and data classes. However, one must manually create the layout classes and add them to the RecycleView.

A layout manager is automatically created as a **layout_manager** when added as the child of the RecycleView. Similarly when removed. A requirement is that the layout manager must be contained as a child somewhere within the RecycleView's widget tree so the view port can be found.

A minimal example might look something like this:

```
from kivy.app import App
from kivy.lang import Builder
from kivy.uix.recycleview import RecycleView

Builder.load_string('''
<RV>:
    viewclass: 'Label'
    RecycleBoxLayout:
        default_size: None, dp(56)
        default_size_hint: 1, None
        size_hint_y: None
        height: self.minimum_height
        orientation: 'vertical'
''')

class RV(RecycleView):
    def __init__(self, **kwargs):
        super(RV, self).__init__(**kwargs)
        self.data = [{'text': str(x)} for x in range(100)]


class TestApp(App):
    def build(self):
        return RV()

if __name__ == '__main__':
    TestApp().run()
```

In order to support selection in the view, you can add the required behaviours as follows:

```
from kivy.app import App
from kivy.lang import Builder
from kivy.uix.recycleview import RecycleView
from kivy.uix.recycleview.views import RecycleDataViewBehavior
from kivy.uix.label import Label
from kivy.properties import BooleanProperty
from kivy.uix.recycleboxlayout import RecycleBoxLayout
from kivy.uix.behaviors import FocusBehavior
from kivy.uix.recycleview.layout import LayoutSelectionBehavior

Builder.load_string('''
<SelectableLabel>
    # Draw a background to indicate selection
    canvas.before:
        Color:
            rgba: (.0, 0.9, .1, .3) if self.selected else (0, 0, 0, 1)
        Rectangle:
            pos: self.pos
            size: self.size
<RV>:
    viewclass: 'SelectableLabel'
    SelectableRecycleBoxLayout:
```

(continues on next page)

```

default_size: None, dp(56)
default_size_hint: 1, None
size_hint_y: None
height: self.minimum_height
orientation: 'vertical'
multiselect: True
touch_multiselect: True
...)

class SelectableRecycleBoxLayout(FocusBehavior, LayoutSelectionBehavior,
                                 RecycleBoxLayout):
    ''' Adds selection and focus behaviour to the view. '''

class SelectableLabel(RecycleDataViewBehavior, Label):
    ''' Add selection support to the Label '''
    index = None
    selected = BooleanProperty(False)
    selectable = BooleanProperty(True)

    def refresh_view_attrs(self, rv, index, data):
        ''' Catch and handle the view changes '''
        self.index = index
        return super(SelectableLabel, self).refresh_view_attrs(
            rv, index, data)

    def on_touch_down(self, touch):
        ''' Add selection on touch down '''
        if super(SelectableLabel, self).on_touch_down(touch):
            return True
        if self.collide_point(*touch.pos) and self.selectable:
            return self.parent.select_with_touch(self.index, touch)

    def apply_selection(self, rv, index, is_selected):
        ''' Respond to the selection of items in the view. '''
        self.selected = is_selected
        if is_selected:
            print("selection changed to {0}".format(rv.data[index]))
        else:
            print("selection removed for {0}".format(rv.data[index]))

class RV(RecycleView):
    def __init__(self, **kwargs):
        super(RV, self).__init__(**kwargs)
        self.data = [{'text': str(x)} for x in range(100)]


class TestApp(App):
    def build(self):
        return RV()

```

```
if __name__ == '__main__':
    TestApp().run()
```

Please see the *examples/widgets/recycleview/basic_data.py* file for a more complete example.

45.2.1 Viewclass State

Because the viewclass widgets are reused or instantiated as needed by the *RecycleView*, the order and content of the widgets are mutable. So any state change to a single widget will stay with that widget, even when the data assigned to it from the *data* dict changes, unless *data* tracks those changes or they are manually refreshed when re-used.

There are two methods for managing state changes in viewclass widgets:

1. Store state in the *RecycleView.data* Model
2. Generate state changes on-the-fly by catching *data* updates and manually refreshing.

An example:

```
from kivy.app import App
from kivy.lang import Builder
from kivy.uix.boxlayout import BoxLayout
from kivy.uix.recycleview import RecycleView
from kivy.uix.recycleview.views import RecycleDataViewBehavior
from kivy.properties import BooleanProperty, StringProperty

Builder.load_string('''
<StatefulLabel>:
    active: stored_state.active
    CheckBox:
        id: stored_state
        active: root.active
        on_release: root.store_checkbox_state()
    Label:
        text: root.text
    Label:
        id: generate_state
        text: root.generated_state_text

<RV>:
    viewclass: 'StatefulLabel'
    RecycleBoxLayout:
        size_hint_y: None
        height: self.minimum_height
        orientation: 'vertical'
''')

class StatefulLabel(RecycleDataViewBehavior, BoxLayout):
    text = StringProperty()
    generated_state_text = StringProperty()
    active = BooleanProperty()
    index = 0

    ...
```

(continues on next page)

```

To change a viewclass' state as the data assigned to it changes,
overload the refresh_view_attrs function (inherited from
RecycleDataViewBehavior)
...
def refresh_view_attrs(self, rv, index, data):
    self.index = index
    if data['text'] == '0':
        self.generated_state_text = "is zero"
    elif int(data['text']) % 2 == 1:
        self.generated_state_text = "is odd"
    else:
        self.generated_state_text = "is even"
    super(StatefulLabel, self).refresh_view_attrs(rv, index, data)
...

To keep state changes in the viewclass with associated data,
they can be explicitly stored in the RecycleView's data object
...
def store_checkbox_state(self):
    rv = App.get_running_app().rv
    rv.data[self.index]['active'] = self.active

class RV(RecycleView, App):
    def __init__(self, **kwargs):
        super(RV, self).__init__(**kwargs)
        self.data = [{text: str(x), active: False} for x in range(10)]
        App.get_running_app().rv = self

    def build(self):
        return self

if __name__ == '__main__':
    RV().run()

```

TODO:

- Method to clear cached class instances.
- Test when views cannot be found (e.g. viewclass is None).
- Fix selection goto.

Warning: When views are re-used they may not trigger if the data remains the same.

```

class kivy.uix.recycleview.RecycleView(**kwargs)
Bases:   kivy.uix.recycleview.RecycleViewBehavior, kivy.uix.scrollview.
ScrollView

RecycleView is a flexible view for providing a limited window into a large data set.

See the module documentation for more information.

add_widget(widget, *args, **kwargs)
    Add a new widget as a child of this widget.

    Parameters

```

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

data

The data used by the current view adapter. This is a list of dicts whose keys map to the corresponding property names of the [viewclass](#).

data is an [AliasProperty](#) that gets and sets the data used to generate the views.

key_viewclass

key_viewclass is an [AliasProperty](#) that gets and sets the key viewclass for the current layout_manager.

remove_widget(widget, *args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: Widget Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

viewclass

The viewclass used by the current layout_manager.

viewclass is an [AliasProperty](#) that gets and sets the class used to generate the individual items presented in the view.

class kivy.uix.recycleview.RecycleViewBehavior(**kwargs)

Bases: `builtins.object`

RecycleViewBehavior provides a behavioral model upon which the [RecycleView](#) is built. Together, they offer an extensible and flexible way to produce views with limited windows over large data sets.

See the module documentation for more information.

data_model

The Data model responsible for maintaining the data set.

data_model is an [AliasProperty](#) that gets and sets the current data model.

layout_manager

The Layout manager responsible for positioning views within the *RecycleView*.

`layout_manager` is an *AliasProperty* that gets and sets the `layout_manger`.

refresh_from_data(*largs, **kwargs)

This should be called when data changes. Data changes typically indicate that everything should be recomputed since the source data changed.

This method is automatically bound to the `on_data_changed` method of the `RecycleDataModelBehavior` class and therefore responds to and accepts the keyword arguments of that event.

It can be called manually to trigger an update.

refresh_from_layout(*largs, **kwargs)

This should be called when the layout changes or needs to change. It is typically called when a layout parameter has changed and therefore the layout needs to be recomputed.

refresh_from_viewport(*largs)

This should be called when the viewport changes and the displayed data must be updated. Neither the data nor the layout will be recomputed.

view_adapter

The adapter responsible for providing views that represent items in a data set.

`view_adapter` is an *AliasProperty* that gets and sets the current view adapter.

45.2.2 RecycleView Data Model

New in version 1.10.0.

The data model part of the RecycleView model-view-controller pattern.

It defines the models (classes) that store the data associated with a *RecycleViewBehavior*. Each model (class) determines how the data is stored and emits requests to the controller (*RecycleViewBehavior*) when the data is modified.

class kivy.uix.recycleview.datamodel.RecycleDataModel(kwargs)**

Bases: `kivy.uix.recycleview.datamodel.RecycleDataModelBehavior, kivy.event.EventDispatcher`

An implementation of *RecycleDataModelBehavior* that keeps the data in a indexable list. See `data`.

When data changes this class currently dispatches `on_data_changed` with one of the following additional keyword arguments.

none: no keyword argument With no additional argument it means a generic data change.

removed: a slice or integer The value is a slice or integer indicating the indices removed.

appended: a slice The slice in `data` indicating the first and last new items (i.e. the slice pointing to the new items added at the end).

inserted: a integer The index in `data` where a new data item was inserted.

modified: a slice The slice with the indices where the data has been modified. This currently does not allow changing of size etc.

attach_recycleview(rv)

Associates a *RecycleViewBehavior* with this data model.

data

Stores the model's data using a list.

The data for a item at index *i* can also be accessed with `RecycleDataModel[i]`.

detach_recycleview()

Removes the `RecycleViewBehavior` associated with this data model.

property observable_dict

A dictionary instance, which when modified will trigger a `data` and consequently an `on_data_changed` dispatch.

class kivy.uix.recycleview.datamodel.RecycleDataModelBehavior

Bases: `builtins.object`

`RecycleDataModelBehavior` is the base class for the models that describes and provides the data for the `RecycleViewBehavior`.

Events

`on_data_changed`: Fired when the data changes. The event may dispatch keyword arguments specific to each implementation of the data model. When dispatched, the event and keyword arguments are forwarded to `refresh_from_data()`.

attach_recycleview(*rv*)

Associates a `RecycleViewBehavior` with this data model.

detach_recycleview()

Removes the `RecycleViewBehavior` associated with this data model.

recycleview

The `RecycleViewBehavior` instance associated with this data model.

45.2.3 RecycleView Layouts

New in version 1.10.0.

The Layouts handle the presentation of views for the `RecycleView`.

Warning: This module is highly experimental, its API may change in the future and the documentation is not complete at this time.

exception kivy.uix.recycleview.layout.LayoutChangeException

Bases: `Exception`

class kivy.uix.recycleview.layout.LayoutSelectionBehavior(kwargs)**

Bases: `kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior`

The `LayoutSelectionBehavior` can be combined with `RecycleLayoutManagerBehavior` to allow its derived classes selection behaviors similarly to how `CompoundSelectionBehavior` can be used to add selection behaviors to normal layout.

`RecycleLayoutManagerBehavior` manages its children differently than normal layouts or widgets so this class adapts `CompoundSelectionBehavior` based selection to work with `RecycleLayoutManagerBehavior` as well.

Similarly to `CompoundSelectionBehavior`, one can select using the keyboard or touch, which calls `select_node()` or `deselect_node()`, or one can call these methods directly. When a item is selected or deselected `apply_selection()` is called. See `apply_selection()`.

apply_selection(*index, view, is_selected*)

Applies the selection to the view. This is called internally when a view is displayed and it needs to be shown as selected or as not selected.

It is called when `select_node()` or `deselect_node()` is called or when a view needs to be refreshed. Its function is purely to update the view to reflect the selection state. So the function may be called multiple times even if the selection state may not have changed.

If the view is a instance of `RecycleDataViewBehavior`, its `apply_selection()` method will be called every time the view needs to refresh the selection state. Otherwise, the this method is responsible for applying the selection.

Parameters

index: int The index of the data item that is associated with the view.

view: widget The widget that is the view of this data item.

is_selected: bool Whether the item is selected.

deselect_node(*node*)

Deselects a possibly selected node.

It is called by the controller when it deselects a node and can also be called from the outside to deselect a node directly. The derived widget should overwrite this method and change the node to its unselected state when this is called

Parameters

node The node to be deselected.

Warning: This method must be called by the derived widget using super if it is overwritten.

get_index_of_node(*node, selectable_nodes*)

(internal) Returns the index of the *node* within the *selectable_nodes* returned by `get_selectable_nodes()`.

get_selectable_nodes()

(internal) Returns a list of the nodes that can be selected. It can be overwritten by the derived widget to return the correct list.

This list is used to determine which nodes to select with group selection. E.g. the last element in the list will be selected when home is pressed, pagedown will move (or add to, if shift is held) the selection from the current position by negative `page_count` nodes starting from the position of the currently selected node in this list and so on. Still, nodes can be selected even if they are not in this list.

Note: It is safe to dynamically change this list including removing, adding, or re-arranging its elements. Nodes can be selected even if they are not on this list. And selected nodes removed from the list will remain selected until `deselect_node()` is called.

Warning: Layouts display their children in the reverse order. That is, the contents of `children` is displayed form right to left, bottom to top. Therefore, internally, the indices of the elements returned by this function are reversed to make it work by default for most layouts so that the final result is consistent e.g. home, although it will select the last

element in this list visually, will select the first element when counting from top to bottom and left to right. If this behavior is not desired, a reversed list should be returned instead.

Defaults to returning `children`.

`goto_node(key, last_node, last_node_idx)`

(internal) Used by the controller to get the node at the position indicated by key. The key can be keyboard inputs, e.g. pageup, or scroll inputs from the mouse scroll wheel, e.g. scrollup. 'last_node' is the last node selected and is used to find the resulting node. For example, if the key is up, the returned node is one node up from the last node.

It can be overwritten by the derived widget.

Parameters

`key` str, the string used to find the desired node. It can be any of the keyboard keys, as well as the mouse scrollup, scrolldown, scrollright, and scrollleft strings. If letters are typed in quick succession, the letters will be combined before it's passed in as key and can be used to find nodes that have an associated string that starts with those letters.

`last_node` The last node that was selected.

`last_node_idx` The cached index of the last node selected in the `get_selectable_nodes()` list. If the list hasn't changed it saves having to look up the index of `last_node` in that list.

Returns tuple, the node targeted by key and its index in the `get_selectable_nodes()` list. Returning `(last_node, last_node_idx)` indicates a node wasn't found.

`key_selection`

The key used to check whether a view of a data item can be selected with touch or the keyboard.

`key_selection` is the key in data, which if present and True will enable selection for this item from the keyboard or with a touch. When None, the default, no item will be selectable.

`key_selection` is a `StringProperty` and defaults to None.

Note: All data items can be selected directly using `select_node()` or `deselect_node()`, even if `key_selection` is False.

`select_node(node)`

Selects a node.

It is called by the controller when it selects a node and can be called from the outside to select a node directly. The derived widget should overwrite this method and change the node state to selected when called.

Parameters

`node` The node to be selected.

Returns bool, True if the node was selected, False otherwise.

Warning: This method must be called by the derived widget using super if it is overwritten.

```
class kivy.uix.recycleview.layout.RecycleLayoutManagerBehavior
Bases: builtins.object
```

A RecycleLayoutManagerBehavior is responsible for positioning views into the RecycleView. data within a RecycleView. It adds new views into the data when it becomes visible to the user, and removes them when they leave the visible area.

compute_visible_views(*data, viewport*)

viewport is in coordinates of the layout manager.

get_view_index_at(*pos*)

Return the view *index* on which position, *pos*, falls.

pos is in coordinates of the layout manager.

goto_view(*index*)

Moves the views so that the view corresponding to *index* is visible.

key_viewclass

See RecyclerView.key_viewclass.

refresh_view_layout(*index, layout, view, viewport*)

See :meth:`~kivy.uix.recycleview.views.RecycleDataAdapter.refresh_view_layout`.

set_visible_views(*indices, data, viewport*)

viewport is in coordinates of the layout manager.

viewclass

See RecyclerView.viewclass.

45.2.4 RecycleView Views

New in version 1.10.0.

The adapter part of the RecycleView which together with the layout is the view part of the model-view-controller pattern.

The view module handles converting the data to a view using the adapter class which is then displayed by the layout. A view can be any Widget based class. However, inheriting from RecycleDataAdapterBehavior adds methods for converting the data to a view.

TODO:

- Make view caches specific to each view class type.

```
class kivy.uix.recycleview.views.RecycleDataAdapter(**kwargs)
Bases: kivy.event.EventDispatcher
```

The class that converts data to a view.

— Internal details — A view can have 3 states.

- It can be completely in sync with the data, which occurs when the view is displayed. These are stored in `views`.
- It can be dirty, which occurs when the view is in sync with the data, except for the size/pos parameters which is controlled by the layout. This occurs when the view is not currently displayed but the data has not changed. These views are stored in `dirty_views`.
- Finally the view can be dead which occurs when the data changes and the view was not updated or when a view is just created. Such views are typically added to the internal cache.

Typically what happens is that the layout manager lays out the data and then asks for views, using `set_visible_views, ()` for some specific data items that it displays.

These views are gotten from the current views, dirty or global cache. Then depending on the view state `refresh_view_attrs()` is called to bring the view up to date with the data (except for sizing parameters). Finally, the layout manager gets these views, updates their size and displays them.

attach_recycleview(*rv*)

Associates a `RecycleViewBehavior` with this instance. It is stored in `recycleview`.

create_view(*index, data_item, viewclass*)

(internal) Creates and initializes the view for the data at *index*.

The returned view is synced with the data, except for the pos/size information.

detach_recycleview()

Removes the `RecycleViewBehavior` associated with this instance and clears `recycleview`.

get_view(*index, data_item, viewclass*)

(internal) Returns a view instance for the data at *index*

It looks through the various caches and finally creates a view if it doesn't exist. The returned view is synced with the data, except for the pos/size information.

If found in the cache it's removed from the source before returning. It doesn't check the current views.

get_visible_view(*index*)

Returns the currently visible view associated with *index*.

If no view is currently displayed for *index* it returns `None`.

invalidate()

Moves all the current views into the global cache.

As opposed to making a view dirty where the view is in sync with the data except for sizing information, this will completely disconnect the view from the data, as it is assumed the data has gone out of sync with the view.

This is typically called when the data changes.

make_view_dirty(*view, index*)

(internal) Used to flag this view as dirty, ready to be used for others. See `make_views_dirty()`.

make_views_dirty()

Makes all the current views dirty.

Dirty views are still in sync with the corresponding data. However, the size information may go out of sync. Therefore a dirty view can be reused by the same index by just updating the sizing information.

Once the underlying data of this index changes, the view should be removed from the dirty views and moved to the global cache with `invalidate()`.

This is typically called when the layout manager needs to re-layout all the data.

recycleview

The `RecycleViewBehavior` associated with this instance.

refresh_view_attrs(*index, data_item, view*)

(internal) Syncs the view and brings it up to date with the data.

This method calls `RecycleDataViewBehavior.refresh_view_attrs()` if the view inherits from `RecycleDataViewBehavior`. See that method for more details.

Note: Any sizing and position info is skipped when syncing with the data.

refresh_view_layout(*index, layout, view, viewport*)

Updates the sizing information of the view.

viewport is in coordinates of the layout manager.

This method calls `RecycleDataViewBehavior.refresh_view_attrs()` if the view inherits from `RecycleDataViewBehavior`. See that method for more details.

Note: Any sizing and position info is skipped when syncing with the data.

set_visible_views(*indices, data, viewclasses*)

Gets a 3-tuple of the new, remaining, and old views for the current viewport.

The new views are synced to the data except for the size/pos properties. The old views need to be removed from the layout, and the new views added.

The new views are not necessarily *new*, but are all the currently visible views.

class `kivy.uix.recycleview.views.RecycleDataViewBehavior`

Bases: `builtins.object`

A optional base class for data views (`RecycleView.viewclass`). If a view inherits from this class, the class's functions will be called when the view needs to be updated due to a data change or layout update.

refresh_view_attrs(*rv, index, data*)

Called by the `RecycleAdapter` when the view is initially populated with the values from the *data* dictionary for this item.

Any pos or size info should be removed because they are set subsequently with `refresh_view_layout`.

Parameters

rv: `RecycleView` instance The `RecycleView` that caused the update.

data: dict The data dict used to populate this view.

refresh_view_layout(*rv, index, layout, viewport*)

Called when the view's size is updated by the layout manager, `RecycleLayoutManagerBehavior`.

Parameters

rv: `RecycleView` instance The `RecycleView` that caused the update.

viewport: 4-tuple The coordinates of the bottom left and width height in layout manager coordinates. This may be larger than this view item.

Raises `LayoutChangeException`: If the sizing or data changed during a call to this method, raising a `LayoutChangeException` exception will force a refresh. Useful when data changed and we don't want to layout further since it'll be overwritten again soon.

class `kivy.uix.recycleview.views.RecycleKVIDsDataViewBehavior`

Bases: `kivy.uix.recycleview.views.RecycleDataViewBehavior`

Similar to `RecycleDataViewBehavior`, except that the data keys can signify properties of an object named with an id in the root KV rule.

E.g. given a KV rule:

```
<MyRule@RecycleKVIDsDataViewBehavior+BoxLayout>:
    Label:
        id: name
    Label:
        id: value
```

Then setting the data list with `rv.data = [{}{'name.text': 'Kivy user', 'value.text': '12'}]` would automatically set the corresponding labels.

So, if the key doesn't have a period, the named property of the root widget will be set to the corresponding value. If there is a period, the named property of the widget with the id listed before the period will be set to the corresponding value.

New in version 2.0.0.

`refresh_view_attrs(rv, index, data)`

Called by the `RecycleAdapter` when the view is initially populated with the values from the `data` dictionary for this item.

Any pos or size info should be removed because they are set subsequently with `refresh_view_layout`.

Parameters

`rv: RecycleView instance` The `RecycleView` that caused the update.

`data: dict` The data dict used to populate this view.

45.3 Accordion

New in version 1.0.8.



The Accordion widget is a form of menu where the options are stacked either vertically or horizontally and the item in focus (when touched) opens up to display its content.

The `Accordion` should contain one or many `AccordionItem` instances, each of which should contain one root content widget. You'll end up with a Tree something like this:

- Accordion
 - AccordionItem
 - * YourContent
 - AccordionItem
 - * BoxLayout
 - Another user content 1
 - Another user content 2

- AccordionItem
 - * Another user content

The current implementation divides the `AccordionItem` into two parts:

1. One container for the title bar
2. One container for the content

The title bar is made from a Kv template. We'll see how to create a new template to customize the design of the title bar.

Warning: If you see message like:

```
[WARNING] [Accordion] not have enough space for displaying all children
[WARNINg] [Accordion] need 440px, got 100px
[WARNINg] [Accordion] layout aborted.
```

That means you have too many children and there is no more space to display the content. This is "normal" and nothing will be done. Try to increase the space for the accordion or reduce the number of children. You can also reduce the `Accordion.min_space`.

45.3.1 Simple example

```
from kivy.uix.accordion import Accordion, AccordionItem
from kivy.uix.label import Label
from kivy.app import App

class AccordionApp(App):
    def build(self):
        root = Accordion()
        for x in range(5):
            item = AccordionItem(title='Title %d' % x)
            item.add_widget(Label(text='Very big content\n' * 10))
            root.add_widget(item)
        return root

if __name__ == '__main__':
    AccordionApp().run()
```

45.3.2 Customize the accordion

You can increase the default size of the title bar:

```
root = Accordion(min_space=60)
```

Or change the orientation to vertical:

```
root = Accordion(orientation='vertical')
```

The `AccordionItem` is more configurable and you can set your own title background when the item is collapsed or opened:

```
item = AccordionItem(background_normal='image_when_collapsed.png',
                      background_selected='image_when_selected.png')
```

class kivy.uix.accordion.Accordion(**kwargs)
Bases: *kivy.uix.widget.Widget*

Accordion class. See module documentation for more information.

add_widget(widget, *args, **kwargs)
Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the *Widgets Programming Guide*.

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

anim_duration

Duration of the animation in seconds when a new accordion item is selected.

anim_duration is a *NumericProperty* and defaults to .25 (250ms).

anim_func

Easing function to use for the animation. Check *kivy.animation.AnimationTransition* for more information about available animation functions.

anim_func is an *ObjectProperty* and defaults to 'out_expo'. You can set a string or a function to use as an easing function.

min_space

Minimum space to use for the title of each item. This value is automatically set for each child every time the layout event occurs.

min_space is a *NumericProperty* and defaults to 44 (px).

orientation

Orientation of the layout.

orientation is an *OptionProperty* and defaults to 'horizontal'. Can take a value of 'vertical' or 'horizontal'.

exception kivy.uix.accordion.AccordionException

Bases: *Exception*

AccordionException class.

```
class kivy.uix.accordion.AccordionItem(**kwargs)
Bases: kivy.uix.floatlayout.FloatLayout
```

AccordionItem class that must be used in conjunction with the [Accordion](#) class. See the module documentation for more information.

accordion

Instance of the [Accordion](#) that the item belongs to.

accordion is an [ObjectProperty](#) and defaults to None.

add_widget(*args, **kwargs)

Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

background_disabled_normal

Background image of the accordion item used for the default graphical representation when the item is collapsed and disabled.

New in version 1.8.0.

background_disabled_normal is a [StringProperty](#) and defaults to 'atlas://data/images/defaulttheme/button_disabled'.

background_disabled_selected

Background image of the accordion item used for the default graphical representation when the item is selected (not collapsed) and disabled.

New in version 1.8.0.

background_disabled_selected is a [StringProperty](#) and defaults to 'atlas://data/images/defaulttheme/button_disabled_pressed'.

background_normal

Background image of the accordion item used for the default graphical representation when the item is collapsed.

background_normal is a [StringProperty](#) and defaults to 'atlas://data/images/defaulttheme/button'.

background_selected

Background image of the accordion item used for the default graphical representation when the item is selected (not collapsed).

background_normal is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/button_pressed’.

collapse

Boolean to indicate if the current item is collapsed or not.

collapse is a *BooleanProperty* and defaults to True.

collapse_alpha

Value between 0 and 1 to indicate how much the item is collapsed (1) or whether it is selected (0). It’s mostly used for animation.

collapse_alpha is a *NumericProperty* and defaults to 1.

container

(internal) Property that will be set to the container of children inside the AccordionItem representation.

container_title

(internal) Property that will be set to the container of title inside the AccordionItem representation.

content_size

(internal) Set by the *Accordion* to the size allocated for the content.

min_space

Link to the *Accordion.min_space* property.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.
See *relativelayout* for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

orientation

Link to the *Accordion.orientation* property.

remove_widget(*args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: Widget Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

title

Title string of the item. The title might be used in conjunction with the *AccordionItemTitle* template. If you are using a custom template, you can use that property as a text entry, or not. By default, it’s used for the title text. See *title_template* and the example below.

title is a *StringProperty* and defaults to “”.

title_args

Default arguments that will be passed to the `kivy.lang.Builder.template()` method.

`title_args` is a *DictProperty* and defaults to {}.

title_template

Template to use for creating the title part of the accordion item. The default template is a simple Label, not customizable (except the text) that supports vertical and horizontal orientation and different backgrounds for collapse and selected mode.

It's better to create and use your own template if the default template does not suffice.


`title` is a *StringProperty* and defaults to 'AccordionItemTitle'. The current default template lives in the `kivy/data/style.kv` file.

Here is the code if you want to build your own template:

```
[AccordionItemTitle@Label]:
    text: ctx.title
    canvas.before:
        Color:
            rgb: 1, 1, 1
        BorderImage:
            source:
                ctx.item.background_normal
            ↵if ctx.item.collapse
            ↵background_selected
            ↵    pos: self.pos
            ↵    size: self.size
            PushMatrix
            Translate:
                xy: self.center_x, self.center_y
            Rotate:
                angle: 90 if ctx.item.orientation == 'horizontal' else_
                ↵0
                axis: 0, 0, 1
            Translate:
                xy: -self.center_x, -self.center_y
    canvas.after:
        PopMatrix
```

45.4 Action Bar

New in version 1.8.0.



The ActionBar widget is like Android's `ActionBar`, where items are stacked horizontally. When the area becomes too small, widgets are moved into the `ActionOverflow` area.

An `ActionBar` contains an `ActionView` with various `ContextualActionViews`. An `ActionView` will contain an `ActionPrevious` having `title`, `app_icon` and `previous_icon` properties. An `ActionView` will contain subclasses of `ActionItems`. Some predefined ones include an `ActionButton`, an `ActionToggleButton`, an `ActionCheck`, an `ActionSeparator` and an `ActionGroup`.

An *ActionGroup* is used to display *ActionItems* in a group. An *ActionView* will always display an *ActionGroup* after other *ActionItems*. An *ActionView* contains an *ActionOverflow*, but this is only made visible when required i.e. the available area is too small to fit all the widgets. A *ContextualActionView* is a subclass of an:klass:*ActionView*.

Changed in version 1.10.1: *ActionGroup* core rewritten from *Spinner* to pure *DropDown*

```
class kivy.uix.actionbar.ActionBar(**kwargs)
Bases: kivy.uix.boxlayout.BoxLayout
```

ActionBar class, which acts as the main container for an *ActionView* instance. The ActionBar determines the overall styling aspects of the bar. *ActionItem*s are not added to this class directly, but to the contained *ActionView* instance.

Events

on_previous Fired when action_previous of action_view is pressed.

Please see the module documentation for more information.

action_view

action_view of the ActionBar.

action_view is an *ObjectProperty* and defaults to None or the last ActionView instance added to the ActionBar.

add_widget(widget, *args, **kwargs)

Changed in version 2.1.0: Renamed argument *view* to *widget*.

background_color

Background color, in the format (r, g, b, a).

background_color is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

background_image

Background image of the ActionBars default graphical representation.

background_image is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/action_bar'.

border

The border to be applied to the *background_image*.

border is a *ListProperty* and defaults to [2, 2, 2, 2]

exception kivy.uix.actionbar.ActionBarException

Bases: Exception

ActionBarException class

```
class kivy.uix.actionbarActionButton(**kwargs)
```

Bases: *kivy.uix.button.Button*, *kivy.uix.actionbar.ActionItem*

ActionButton class, see module documentation for more information.

The text color, width and size_hint_x are set manually via the Kv language file. It covers a lot of cases: with/without an icon, with/without a group and takes care of the padding between elements.

You don't have much control over these properties, so if you want to customize its appearance, we suggest you create your own button representation. You can do this by creating a class that subclasses an existing widget and an *ActionItem*:

```
class MyOwnActionButton(Button, ActionItem):
    pass
```

You can then create your own style using the Kv language.

icon

Source image to use when the Button is part of the ActionBar. If the Button is in a group, the text will be preferred.

icon is a *StringProperty* and defaults to None.

class `kivy.uix.actionbar.ActionCheck(**kwargs)`
Bases: `kivy.uix.actionbar.ActionItem, kivy.uix.checkbox.CheckBox`

ActionCheck class, see module documentation for more information.

class `kivy.uix.actionbar.ActionDropDown(**kwargs)`
Bases: `kivy.uix.dropdown.DropDown`

ActionDropDown class, see module documentation for more information.

class `kivy.uix.actionbar.ActionGroup(**kwargs)`
Bases: `kivy.uix.actionbar.ActionItem, kivy.uix.button.Button`

ActionGroup class, see module documentation for more information.

add_widget(widget, *args, **kwargs)

Changed in version 2.1.0: Renamed argument *item* to *widget*.

clear_widgets(*args, **kwargs)

Remove all (or the specified) children of this widget. If the ‘children’ argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The *children* argument can be used to specify the children you want to remove.

Changed in version 2.1.0: Specifying an empty *children* list leaves the widgets unchanged. Previously it was treated like `None` and all children were removed.

dropdown_width

If non zero, provides the width for the associated DropDown. This is useful when some items in the ActionGroup’s DropDown are wider than usual and you don’t want to make the ActionGroup widget itself wider.

dropdown_width is a *NumericProperty* and defaults to 0.

New in version 1.10.0.

is_open

By default, the DropDown is not open. Set to True to open it.

is_open is a *BooleanProperty* and defaults to False.

mode

Sets the current mode of an ActionGroup. If mode is ‘normal’, the ActionGroups children will be displayed normally if there is enough space, otherwise they will be displayed in a spinner. If mode is ‘spinner’, then the children will always be displayed in a spinner.

mode is an *OptionProperty* and defaults to ‘normal’.

separator_image

Background Image for an ActionSeparator in an ActionView.

separator_image is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/separator’.

separator_width

Width of the ActionSeparator in an ActionView.

separator_width is a *NumericProperty* and defaults to 0.

use_separator

Specifies whether to use a separator after/before this group or not.

use_separator is a *BooleanProperty* and defaults to False.

class kivy.uix.actionbar.ActionItem

Bases: `builtins.object`

ActionItem class, an abstract class for all ActionBar widgets. To create a custom widget for an ActionBar, inherit from this class. See module documentation for more information.

background_down

Background image of the ActionItem used for the default graphical representation when an ActionItem is pressed.

background_down is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/action_item_down'.

background_normal

Background image of the ActionItem used for the default graphical representation when the ActionItem is not pressed.

background_normal is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/action_item'.

important

Determines if an ActionItem is important or not. If an item is important and space is limited, this item will be displayed in preference to others.

important is a *BooleanProperty* and defaults to False.

inside_group

(internal) Determines if an ActionItem is displayed inside an ActionGroup or not.

inside_group is a *BooleanProperty* and defaults to False.

minimum_width

Minimum Width required by an ActionItem.

minimum_width is a *NumericProperty* and defaults to '90sp'.

mipmap

Defines whether the image/icon displayed on top of the button uses a mipmap or not.

mipmap is a *BooleanProperty* and defaults to *True*.

pack_width

(read-only) The actual width to use when packing the items. Equal to the greater of minimum_width and width.

pack_width is an *AliasProperty*.

class kivy.uix.actionbar.ActionOverflow(kwargs)**

Bases: `kivy.uix.actionbar.ActionGroup`

ActionOverflow class, see module documentation for more information.

add_widget(widget, index=0, *args, **kwargs)

Changed in version 2.1.0: Renamed argument *action_item* to *widget*.

overflow_image

Image to be used as an Overflow Image.

overflow_image is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/overflow'.

```
class kivy.uix.actionbar.ActionPrevious(**kwargs)
Bases: kivy.uix.boxlayoutBoxLayout, kivy.uix.actionbar.ActionItem

ActionPrevious class, see module documentation for more information.

app_icon
    Application icon for the ActionView.

    app_icon is a StringProperty and defaults to the window icon if set, otherwise
    'data/logo/kivy-icon-32.png'.

app_icon_height
    Height of app_icon image.

    app_icon_height is a NumericProperty and defaults to 0.

app_icon_width
    Width of app_icon image.

    app_icon_width is a NumericProperty and defaults to 0.

color
    Text color, in the format (r, g, b, a)

    color is a ColorProperty and defaults to [1, 1, 1, 1].
    Changed in version 2.0.0: Changed from ListProperty to ColorProperty.

markup
    If True, the text will be rendered using the MarkupLabel: you can change the style of the
    text using tags. Check the Text Markup documentation for more information.

    markup is a BooleanProperty and defaults to False.

previous_image
    Image for the 'previous' ActionButtons default graphical representation.

    previous_image is a StringProperty and defaults to 'at-
    las://data/images/defaulttheme/previous_normal'.

previous_image_height
    Height of previous_image image.

    app_icon_width is a NumericProperty and defaults to 0.

previous_image_width
    Width of previous_image image.

    width is a NumericProperty and defaults to 0.

title
    Title for ActionView.

    title is a StringProperty and defaults to ''.

with_previous
    Specifies whether the previous_icon will be shown or not. Note that it is up to the user to
    implement the desired behavior using the on_press or similar events.

    with_previous is a BooleanProperty and defaults to True.

class kivy.uix.actionbar.ActionSeparator(**kwargs)
Bases: kivy.uix.actionbar.ActionItem, kivy.uix.widget.Widget

ActionSeparator class, see module documentation for more information.

background_image
    Background image for the separators default graphical representation.
```

`background_image` is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/separator’.

class kivy.uix.actionbar.ActionToggleButton(kwargs)**
Bases: *kivy.uix.actionbar.ActionItem, kivy.uix.togglebutton.ToggleButton*

ActionToggleButton class, see module documentation for more information.

icon

Source image to use when the Button is part of the ActionBar. If the Button is in a group, the text will be preferred.

class kivy.uix.actionbar.ActionView(kwargs)**
Bases: *kivy.uix.boxlayout.BoxLayout*

ActionView class, see module documentation for more information.

action_previous

Previous button for an ActionView.

`action_previous` is an *ObjectProperty* and defaults to None.

add_widget(widget, index=0, *args, **kwargs)

Changed in version 2.1.0: Renamed argument *action_item* to *widget*.

background_color

Background color in the format (r, g, b, a).

`background_color` is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

background_image

Background image of an ActionViews default graphical representation.

`background_image` is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/action_view’.

overflow_group

Widget to be used for the overflow.

`overflow_group` is an *ObjectProperty* and defaults to an instance of *ActionOverflow*.

remove_widget(widget, *args, **kwargs)

Remove a widget from the children of this widget.

Parameters

`widget: Widget` Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

use_separator

Specify whether to use a separator before every ActionGroup or not.


`use_separator` is a *BooleanProperty* and defaults to False.

class kivy.uix.actionbar.ContextualActionView(kwargs)**

Bases: *kivy.uix.actionbar.ActionView*

ContextualActionView class, see the module documentation for more information.

45.5 Anchor Layout



The [AnchorLayout](#) aligns its children to a border (top, bottom, left, right) or center.

To draw a button in the lower-right corner:

```
layout = AnchorLayout(  
    anchor_x='right', anchor_y='bottom')  
btn = Button(text='Hello World')  
layout.add_widget(btn)
```

class kivy.uix.anchorlayout.AnchorLayout(kwargs)**

Bases: [kivy.uix.layout.Layout](#)

Anchor layout class. See the module documentation for more information.

anchor_x

Horizontal anchor.

anchor_x is an [OptionProperty](#) and defaults to ‘center’. It accepts values of ‘left’, ‘center’ or ‘right’.

anchor_y

Vertical anchor.

anchor_y is an [OptionProperty](#) and defaults to ‘center’. It accepts values of ‘top’, ‘center’ or ‘bottom’.

do_layout(*args)

This function is called when a layout is called by a trigger. If you are writing a new Layout subclass, don’t call this function directly but use `_trigger_layout()` instead.

The function is by default called *before* the next frame, therefore the layout isn’t updated immediately. Anything depending on the positions of e.g. children should be scheduled for the next frame.

New in version 1.0.8.


padding

Padding between the widget box and its children, in pixels: [padding_left, padding_top, padding_right, padding_bottom].

padding also accepts a two argument form [padding_horizontal, padding_vertical] and a one argument form [padding].

padding is a *VariableListProperty* and defaults to [0, 0, 0, 0].

45.6 Box Layout



BoxLayout arranges children in a vertical or horizontal box.

To position widgets above/below each other, use a vertical BoxLayout:

```
layout = BoxLayout(orientation='vertical')
btn1 = Button(text='Hello')
btn2 = Button(text='World')
layout.add_widget(btn1)
layout.add_widget(btn2)
```

To position widgets next to each other, use a horizontal BoxLayout. In this example, we use 10 pixel spacing between children; the first button covers 70% of the horizontal space, the second covers 30%:

```
layout = BoxLayout(spacing=10)
btn1 = Button(text='Hello', size_hint=(.7, 1))
btn2 = Button(text='World', size_hint=(.3, 1))
layout.add_widget(btn1)
layout.add_widget(btn2)
```

Position hints are partially working, depending on the orientation:

- If the orientation is *vertical*: *x*, *right* and *center_x* will be used.
- If the orientation is *horizontal*: *y*, *top* and *center_y* will be used.

Kv Example:

```

BoxLayout:
    orientation: 'vertical'
    Label:
        text: 'this on top'
    Label:
        text: 'this right aligned'
        size_hint_x: None
        size: self.texture_size
        pos_hint: {'right': 1}
    Label:
        text: 'this on bottom'

```

You can check the `examples/widgets/boxlayout_poshint.py` for a live example.

Note: The `size_hint` uses the available space after subtracting all the fixed-size widgets. For example, if you have a layout that is 800px wide, and add three buttons like this:

```

btn1 = Button(text='Hello', size=(200, 100), size_hint=(None, None))
btn2 = Button(text='Kivy', size_hint=(.5, 1))
btn3 = Button(text='World', size_hint=(.5, 1))

```

The first button will be 200px wide as specified, the second and third will be 300px each, e.g. (800-200) * 0.5

Changed in version 1.4.1: Added support for `pos_hint`.

class `kivy.uix.boxlayout.BoxLayout(**kwargs)`
Bases: `kivy.uix.layout.Layout`

Box layout class. See module documentation for more information.

add_widget(widget, *args, **kwargs)
Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```

>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)

```

do_layout(*args)

This function is called when a layout is called by a trigger. If you are writing a new Layout subclass, don't call this function directly but use `_trigger_layout()` instead.

The function is by default called *before* the next frame, therefore the layout isn't updated immediately. Anything depending on the positions of e.g. children should be scheduled for the next frame.

New in version 1.0.8.

minimum_height

Automatically computed minimum height needed to contain all children.

New in version 1.10.0.

`minimum_height` is a *NumericProperty* and defaults to 0. It is read only.

minimum_size

Automatically computed minimum size needed to contain all children.

New in version 1.10.0.

`minimum_size` is a *ReferenceListProperty* of (`minimum_width`, `minimum_height`) properties. It is read only.

minimum_width

Automatically computed minimum width needed to contain all children.

New in version 1.10.0.

`minimum_width` is a *NumericProperty* and defaults to 0. It is read only.

orientation

Orientation of the layout.

`orientation` is an *OptionProperty* and defaults to 'horizontal'. Can be 'vertical' or 'horizontal'.

padding

Padding between layout box and children: [padding_left, padding_top, padding_right, padding_bottom].

padding also accepts a two argument form [padding_horizontal, padding_vertical] and a one argument form [padding].

Changed in version 1.7.0: Replaced NumericProperty with VariableListProperty.

`padding` is a *VariableListProperty* and defaults to [0, 0, 0, 0].

remove_widget(widget, *args, **kwargs)

Remove a widget from the children of this widget.

Parameters

`widget: Widget` Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

spacing

Spacing between children, in pixels.

`spacing` is a *NumericProperty* and defaults to 0.

45.7 Bubble

New in version 1.1.0.



The Bubble widget is a form of menu or a small popup where the menu options are stacked either vertically or horizontally.

The **Bubble** contains an arrow pointing in the direction you choose.

45.7.1 Simple example

```
...
Bubble
=====

Test of the widget Bubble.
'''

from kivy.app import App
from kivy.uix.floatlayout import FloatLayout
from kivy.uix.button import Button
from kivy.lang import Builder
from kivy.uix.bubble import Bubble

Builder.load_string('''
<cut_copy_paste>
    size_hint: (None, None)
    size: (160, 120)
    pos_hint: {'center_x': .5, 'y': .6}
    BubbleButton:
        text: 'Cut'
    BubbleButton:
        text: 'Copy'
    BubbleButton:
        text: 'Paste'
''')

class cut_copy_paste(Bubble):
    pass

class BubbleShowcase(FloatLayout):

    def __init__(self, **kwargs):
        super(BubbleShowcase, self).__init__(**kwargs)
        self.but_bubble = Button(text='Press to show bubble')
        self.but_bubble.bind(on_release=self.show_bubble)
        self.add_widget(self.but_bubble)
```

(continues on next page)

```

def show_bubble(self, *l):
    if not hasattr(self, 'bubb'):
        self.bubb = bubb = cut_copy_paste()
        self.add_widget(bubb)
    else:
        values = ('left_top', 'left_mid', 'left_bottom', 'top_left',
                  'top_mid', 'top_right', 'right_top', 'right_mid',
                  'right_bottom', 'bottom_left', 'bottom_mid', 'bottom_right')
    ↵)
    index = values.index(self.bubb.arrow_pos)
    self.bubb.arrow_pos = values[(index + 1) % len(values)]


class TestBubbleApp(App):

    def build(self):
        return BubbleShowcase()


if __name__ == '__main__':
    TestBubbleApp().run()

```

45.7.2 Customize the Bubble

You can choose the direction in which the arrow points:

```
Bubble(arrow_pos='top_mid')
```

The widgets added to the Bubble are ordered horizontally by default, like a Boxlayout. You can change that by:

```
orientation = 'vertical'
```

To add items to the bubble:

```
bubble = Bubble(orientation = 'vertical')
bubble.add_widget(your_widget_instance)
```

To remove items:

```
bubble.remove_widget(widget)
or
bubble.clear_widgets()
```

To access the list of children, use content.children:

```
bubble.content.children
```

Warning: This is important! Do not use bubble.children

To change the appearance of the bubble:

```
bubble.background_color = (1, 0, 0, .5) #50% translucent red
bubble.border = [0, 0, 0, 0]
background_image = 'path/to/background/image'
arrow_image = 'path/to/arrow/image'
```

class kivy.uix.bubble.Bubble(**kwargs)
Bases: *kivy.uix.gridlayout.GridLayout*

Bubble class. See module documentation for more information.

add_widget(widget, *args, **kwargs)
Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the *Widgets Programming Guide*.

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

arrow_image

Image of the arrow pointing to the bubble.

arrow_image is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/bubble_arrow'.

arrow_pos

Specifies the position of the arrow relative to the bubble. Can be one of: left_top, left_mid, left_bottom, top_left, top_mid, top_right, right_top, right_mid, right_bottom, bottom_left, bottom_mid, bottom_right.

arrow_pos is a *OptionProperty* and defaults to 'bottom_mid'.

background_color

Background color, in the format (r, g, b, a). To use it you have to set either *background_image* or *arrow_image* first.

background_color is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

background_image

Background image of the bubble.

background_image is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/bubble'.

border

Border used for *BorderImage* graphics instruction. Used with the *background_image*. It should be used when using custom backgrounds.

It must be a list of 4 values: (bottom, right, top, left). Read the BorderImage instructions for more information about how to use it.

border is a *ListProperty* and defaults to (16, 16, 16, 16)

border_auto_scale

Specifies the *kivy.graphics.BorderImage.auto_scale* value on the background BorderImage.

New in version 1.11.0.

border_auto_scale is a *OptionProperty* and defaults to 'both_lower'.

clear_widgets(*args, **kwargs)

Remove all (or the specified) children of this widget. If the 'children' argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The *children* argument can be used to specify the children you want to remove.

Changed in version 2.1.0: Specifying an empty *children* list leaves the widgets unchanged. Previously it was treated like *None* and all children were removed.

content

This is the object where the main content of the bubble is held.

content is a *ObjectProperty* and defaults to 'None'.

limit_to

Specifies the widget to which the bubbles position is restricted.

New in version 1.6.0.

limit_to is a *ObjectProperty* and defaults to 'None'.

orientation

This specifies the manner in which the children inside bubble are arranged. Can be one of 'vertical' or 'horizontal'.

orientation is a *OptionProperty* and defaults to 'horizontal'.

remove_widget(widget, *args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: Widget Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

show_arrow

Indicates whether to show arrow.

New in version 1.8.0.

show_arrow is a *BooleanProperty* and defaults to *True*.


```
class kivy.uix.bubble.BubbleButton(**kwargs)
Bases: kivy.uix.button.Button
```

A button intended for use in a Bubble widget. You can use a “normal” button class, but it will not look good unless the background is changed.

Rather use this BubbleButton widget that is already defined and provides a suitable background for you.

```
class kivy.uix.bubble.BubbleContent(**kwargs)
Bases: kivy.uix.gridlayout.GridLayout
```

45.8 Button



The **Button** is a **Label** with associated actions that are triggered when the button is pressed (or released after a click/touch). To configure the button, the same properties (padding, font_size, etc) and *sizing system* are used as for the **Label** class:

```
button = Button(text='Hello world', font_size=14)
```

To attach a callback when the button is pressed (clicked/touched), use `bind`:

```
def callback(instance):
    print('The button <%s> is being pressed' % instance.text)

btn1 = Button(text='Hello world 1')
btn1.bind(on_press=callback)
btn2 = Button(text='Hello world 2')
btn2.bind(on_press=callback)
```

If you want to be notified every time the button state changes, you can bind to the `Button.state` property:

```
def callback(instance, value):
    print('My button <%s> state is <%s>' % (instance, value))
btn1 = Button(text='Hello world 1')
btn1.bind(state=callback)
```

Kv Example:

```
Button:
    text: 'press me'
    on_press: print("ouch! More gently please")
    on_release: print("ahhh")
    on_state:
        print("my current state is {}".format(self.state))
```

```
class kivy.uix.button.Button(**kwargs)
Bases: kivy.uix.behaviors.button.ButtonBehavior, kivy.uix.label.Label
```

Button class, see module documentation for more information.

Changed in version 1.8.0: The behavior / logic of the button has been moved to `ButtonBehaviors`.

background_color

Background color, in the format (r, g, b, a).

This acts as a *multiplier* to the texture colour. The default texture is grey, so just setting the background color will give a darker result. To set a plain color, set the `background_normal` to ''.

New in version 1.0.8.

The `background_color` is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

background_disabled_down

Background image of the button used for the default graphical representation when the button is disabled and pressed.

New in version 1.8.0.

`background_disabled_down` is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/button_disabled_pressed'.

background_disabled_normal

Background image of the button used for the default graphical representation when the button is disabled and not pressed.

New in version 1.8.0.

`background_disabled_normal` is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/button_disabled'.

background_down

Background image of the button used for the default graphical representation when the button is pressed.

New in version 1.0.4.

`background_down` is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/button_pressed'.

background_normal

Background image of the button used for the default graphical representation when the button is not pressed.

New in version 1.0.4.

`background_normal` is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/button'.

border

Border used for `BorderImage` graphics instruction. Used with `background_normal` and `background_down`. Can be used for custom backgrounds.

It must be a list of four values: (bottom, right, top, left). Read the `BorderImage` instruction for more information about how to use it.

`border` is a *ListProperty* and defaults to (16, 16, 16, 16)

45.9 Camera

The `Camera` widget is used to capture and display video from a camera. Once the widget is created, the texture inside the widget will be automatically updated. Our `CameraBase` implementation is used under the hood:

```
cam = Camera()
```

By default, the first camera found on your system is used. To use a different camera, set the index property:

```
cam = Camera(index=1)
```

You can also select the camera resolution:

```
cam = Camera(resolution=(320, 240))
```

Warning: The camera texture is not updated as soon as you have created the object. The camera initialization is asynchronous, so there may be a delay before the requested texture is created.

`class kivy.uix.camera.Camera(**kwargs)`

Bases: `kivy.uix.image.Image`

Camera class. See module documentation for more information.

index

Index of the used camera, starting from 0.

`index` is a `NumericProperty` and defaults to -1 to allow auto selection.

play

Boolean indicating whether the camera is playing or not. You can start/stop the camera by setting this property:

```
# start the camera playing at creation
cam = Camera(play=True)

# create the camera, and start later (default)
cam = Camera(play=False)
# and later
cam.play = True
```

`play` is a `BooleanProperty` and defaults to False.

resolution

Preferred resolution to use when invoking the camera. If you are using [-1, -1], the resolution will be the default one:

```
# create a camera object with the best image available
cam = Camera()

# create a camera object with an image of 320x240 if possible
cam = Camera(resolution=(320, 240))
```

Warning: Depending on the implementation, the camera may not respect this property.

resolution is a *ListProperty* and defaults to [-1, -1].

45.10 Carousel

New in version 1.4.0.

The *Carousel* widget provides the classic mobile-friendly carousel view where you can swipe between slides. You can add any content to the carousel and have it move horizontally or vertically. The carousel can display pages in a sequence or a loop.

Example:

```
from kivy.app import App
from kivy.uix.carousel import Carousel
from kivy.uix.image import AsyncImage

class CarouselApp(App):
    def build(self):
        carousel = Carousel(direction='right')
        for i in range(10):
            src = "http://placehold.it/480x270.png&text=slide-%d&.png" % i
            image = AsyncImage(source=src, allow_stretch=True)
            carousel.add_widget(image)
        return carousel

CarouselApp().run()
```

Kv Example:

```
Carousel:
    direction: 'right'
    AsyncImage:
        source: 'http://placehold.it/480x270.png&text=slide-1.png'
    AsyncImage:
        source: 'http://placehold.it/480x270.png&text=slide-2.png'
    AsyncImage:
        source: 'http://placehold.it/480x270.png&text=slide-3.png'
    AsyncImage:
        source: 'http://placehold.it/480x270.png&text=slide-4.png'
```

Changed in version 1.5.0: The carousel now supports active children, like the *ScrollView*. It will detect a swipe gesture according to the *Carousel.scroll_timeout* and *Carousel.scroll_distance* properties.

In addition, the slide container is no longer exposed by the API. The impacted properties are *Carousel.slides*, *Carousel.current_slide*, *Carousel.previous_slide* and *Carousel.next_slide*.

```
class kivy.uix.carousel.Carousel(**kwargs)
Bases: kivy.uix.stencilview.StencilView
```

Carousel class. See module documentation for more information.

add_widget(widget, index=0, *args, **kwargs)
Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

anim_cancel_duration

Defines the duration of the animation when a swipe movement is not accepted. This is generally when the user does not make a large enough swipe. See [min_move](#).

anim_cancel_duration is a [NumericProperty](#) and defaults to 0.3.

anim_move_duration

Defines the duration of the Carousel animation between pages.

anim_move_duration is a [NumericProperty](#) and defaults to 0.5.

anim_type

Type of animation to use while animating to the next/previous slide. This should be the name of an [AnimationTransition](#) function.

anim_type is a [StringProperty](#) and defaults to 'out_quad'.

New in version 1.8.0.

clear_widgets(children=None, *args, **kwargs)

Remove all (or the specified) **children** of this widget. If the 'children' argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The *children* argument can be used to specify the children you want to remove.

Changed in version 2.1.0: Specifying an empty *children* list leaves the widgets unchanged. Previously it was treated like **None** and all children were removed.

current_slide

The currently shown slide.

current_slide is an [AliasProperty](#).

Changed in version 1.5.0: The property no longer exposes the slides container. It returns the widget you have added.

direction

Specifies the direction in which the slides are ordered. This corresponds to the direction from which the user swipes to go from one slide to the next. It can be *right*, *left*, *top*, or *bottom*. For example, with the default value of *right*, the second slide is to the right of the first and the user would swipe from the right towards the left to get to the second slide.

direction is an *OptionProperty* and defaults to ‘right’.

ignore_perpendicular_swipes

Ignore swipes on axis perpendicular to direction.

ignore_perpendicular_swipes is a *BooleanProperty* and defaults to False.

New in version 1.10.0.

index

Get/Set the current slide based on the index.

index is an *AliasProperty* and defaults to 0 (the first item).

load_next(mode='next')

Animate to the next slide.

New in version 1.7.0.

load_previous()

Animate to the previous slide.

New in version 1.7.0.

load_slide(slide)

Animate to the slide that is passed as the argument.

Changed in version 1.8.0.

loop

Allow the Carousel to loop infinitely. If True, when the user tries to swipe beyond last page, it will return to the first. If False, it will remain on the last page.

loop is a *BooleanProperty* and defaults to False.

min_move

Defines the minimum distance to be covered before the touch is considered a swipe gesture and the Carousel content changed. This is expressed as a fraction of the Carousel’s width. If the movement doesn’t reach this minimum value, the movement is cancelled and the content is restored to its original position.

min_move is a *NumericProperty* and defaults to 0.2.

next_slide

The next slide in the Carousel. It is None if the current slide is the last slide in the Carousel. This ordering reflects the order in which the slides are added: their presentation varies according to the *direction* property.

next_slide is an *AliasProperty*.

Changed in version 1.5.0: The property no longer exposes the slides container. It returns the widget you have added.

on_touch_down(touch)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.

See *relativelayout* for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

previous_slide

The previous slide in the Carousel. It is None if the current slide is the first slide in the Carousel. This ordering reflects the order in which the slides are added: their presentation varies according to the [direction](#) property.

previous_slide is an [AliasProperty](#).

Changed in version 1.5.0: This property no longer exposes the slides container. It returns the widget you have added.

remove_widget(widget, *args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: Widget Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

scroll_distance

Distance to move before scrolling the [Carousel](#) in pixels. As soon as the distance has been traveled, the [Carousel](#) will start to scroll, and no touch event will go to children. It is advisable that you base this value on the dpi of your target device's screen.

scroll_distance is a [NumericProperty](#) and defaults to 20dp.

New in version 1.5.0.

scroll_timeout

Timeout allowed to trigger the [scroll_distance](#), in milliseconds. If the user has not moved [scroll_distance](#) within the timeout, no scrolling will occur and the touch event will go to the children.

scroll_timeout is a [NumericProperty](#) and defaults to 200 (milliseconds)

New in version 1.5.0.


slides

List of slides inside the Carousel. The slides are the widgets added to the Carousel using the [add_widget](#) method.

slides is a [ListProperty](#) and is read-only.

45.11 CheckBox

New in version 1.4.0.



CheckBox is a specific two-state button that can be either checked or unchecked. If the CheckBox is in a Group, it becomes a Radio button. As with the [ToggleButton](#), only one Radio button at a time can be selected when the `CheckBox.group` is set.

An example usage:

```
from kivy.uix.checkbox import CheckBox

# ...

def on_checkbox_active(checkbox, value):
    if value:
        print('The checkbox', checkbox, 'is active')
    else:
        print('The checkbox', checkbox, 'is inactive')

checkbox = CheckBox()
checkbox.bind(active=on_checkbox_active)

class kivy.uix.checkbox.CheckBox(**kwargs)
    Bases: kivy.uix.behaviors.togglebutton.ToggleButtonBehavior, kivy.uix.widget.Widget
```

CheckBox class, see module documentation for more information.

active

Indicates if the switch is active or inactive.

`active` is a boolean and reflects and sets whether the underlying `state` is 'down' (True) or 'normal' (False). It is a [AliasProperty](#), which accepts boolean values and defaults to False.

Changed in version 1.11.0: It changed from a BooleanProperty to a AliasProperty.

background_checkbox_disabled_down

Background image of the checkbox used for the default graphical representation when the checkbox is disabled and active.

New in version 1.9.0.

`background_checkbox_disabled_down` is a [StringProperty](#) and defaults to 'atlas://data/images/defaulttheme/checkbox_disabled_on'.

background_checkbox_disabled_normal

Background image of the checkbox used for the default graphical representation when the checkbox is disabled and not active.

New in version 1.9.0.

background_checkbox_disabled_normal is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox_disabled_off’.

background_checkbox_down

Background image of the checkbox used for the default graphical representation when the checkbox is active.

New in version 1.9.0.

background_checkbox_down is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox_on’.

background_checkbox_normal

Background image of the checkbox used for the default graphical representation when the checkbox is not active.

New in version 1.9.0.

background_checkbox_normal is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox_off’.

background_radio_disabled_down

Background image of the radio button used for the default graphical representation when the radio button is disabled and active.

New in version 1.9.0.

background_radio_disabled_down is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox_radio_disabled_on’.

background_radio_disabled_normal

Background image of the radio button used for the default graphical representation when the radio button is disabled and not active.

New in version 1.9.0.

background_radio_disabled_normal is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox_radio_disabled_off’.

background_radio_down

Background image of the radio button used for the default graphical representation when the radio button is active.

New in version 1.9.0.

background_radio_down is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox_radio_on’.

background_radio_normal

Background image of the radio button used for the default graphical representation when the radio button is not active.

New in version 1.9.0.

background_radio_normal is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/checkbox_radio_off’.

color

Color is used for tinting the default graphical representation of checkbox and radio button (images).

Color is in the format (r, g, b, a).

New in version 1.10.0.

`color` is a *ColorProperty* and defaults to '[1, 1, 1, 1]’.

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

45.12 Code Input

New in version 1.5.0.

```
if __name__ == '__main__':
    from kivy.app import App
    from kivy.uix.boxlayout import BoxLayout

    class TextInputApp(App):

        def build(self):
            root = BoxLayout(orientation='vertical')
            textinput = TextInput(multiline=True)
            textinput.text = __doc__
            root.add_widget(textinput)
            textinput2 = TextInput(text='monoline textinput',
                                  size_hint=(1, None), height=30)
            root.add_widget(textinput2)
            return root

    TextInputApp().run()
```

BoxLayout:
Double as a Tabbed Panel Demo!

TabbedPanel:
tab_pos: "top_right"
default_tab_text: "List View"
default_tab_content: list_view_tab

TabbedPanelHeader:
text: 'Icon View'
content: icon_view_tab

FileChooserListView:
id: list_view_tab

FileChooserIconView:
id: icon_view_tab
show_hidden: True

Note: This widget requires `pygments` package to run. Install it with `pip`.

The `CodeInput` provides a box of editable highlighted text like the one shown in the image.

It supports all the features provided by the `TextInput` as well as code highlighting for `languages supported by pygments` along with `KivyLexer` for `kivy.lang` highlighting.

45.12.1 Usage example

To create a `CodeInput` with highlighting for *KV language*:

```
from kivy.uix.codeinput import CodeInput
from kivy.extras.highlight import KivyLexer
codeinput = CodeInput(lexer=KivyLexer())
```

To create a `CodeInput` with highlighting for *Cython*:

```
from kivy.uix.codeinput import CodeInput
from pygments.lexers import CythonLexer
codeinput = CodeInput(lexer=CythonLexer())
```

class kivy.uix.codeinput.CodeInput(kwargs)**
Bases: `kivy.uix.behaviors.codenavigation.CodeNavigationBehavior, kivy.uix.TextInput`

`CodeInput` class, used for displaying highlighted code.

lexer

This holds the selected Lexer used by pygments to highlight the code.

lexer is an *ObjectProperty* and defaults to *PythonLexer*.

style

The pygments style object to use for formatting.

When *style_name* is set, this will be changed to the corresponding style object.

style is a *ObjectProperty* and defaults to *None*

style_name


Name of the pygments style to use for formatting.

style_name is an *OptionProperty* and defaults to 'default'.

45.13 Color Picker

New in version 1.7.0.

Warning: This widget is experimental. Its use and API can change at any time until this warning is removed.



The ColorPicker widget allows a user to select a color from a chromatic wheel where pinch and zoom can be used to change the wheel's saturation. Sliders and TextInput are also provided for entering the RGBA/HSV/HEX values directly.

Usage:

```
clr_picker = ColorPicker()
parent.add_widget(clr_picker)

# To monitor changes, we can bind to color property changes
def on_color(instance, value):
    print("RGBA = ", str(value)) # or instance.color
    print("HSV = ", str(instance.hsv))
```

(continues on next page)

```
print("HEX = ", str(instance.hex_color))
clr_picker.bind(color=on_color)
```

class kivy.uix.colorpicker.ColorPicker(kwargs)**
Bases: *kivy.uix.relativelayout.RelativeLayout*

See module documentation.

color

The *color* holds the color currently selected in rgba format.

color is a *ListProperty* and defaults to (1, 1, 1, 1).

font_name

Specifies the font used on the ColorPicker.

font_name is a *StringProperty* and defaults to 'data/fonts/RobotoMono-Regular.ttf'.

hex_color

The *hex_color* holds the currently selected color in hex.

hex_color is an *AliasProperty* and defaults to #ffffffff.

hsv

The *hsv* holds the color currently selected in hsv format.

hsv is a *ListProperty* and defaults to (1, 1, 1).

wheel

The *wheel* holds the color wheel.

wheel is an *ObjectProperty* and defaults to None.

class kivy.uix.colorpicker.ColorWheel(kwargs)**
Bases: *kivy.uix.widget.Widget*

Chromatic wheel for the ColorPicker.

Changed in version 1.7.1: *font_size*, *font_name* and *foreground_color* have been removed. The sizing is now the same as others widget, based on 'sp'. Orientation is also automatically determined according to the width/height ratio.

a

The Alpha value of the color currently selected.

a is a *BoundedNumericProperty* and can be a value from 0 to 1.

b

The Blue value of the color currently selected.

b is a *BoundedNumericProperty* and can be a value from 0 to 1.

color

The *color* holds the color currently selected.

color is a *ReferenceListProperty* and contains a list of *r*, *g*, *b*, *a* values.

g

The Green value of the color currently selected.

g is a *BoundedNumericProperty* and can be a value from 0 to 1.

on_touch_down (touch)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.
See [relativelayout](#) for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

r

The Red value of the color currently selected.

r is a [BoundedNumericProperty](#) and can be a value from 0 to 1. It defaults to 0.

45.14 Drop-Down List

New in version 1.4.0.

A versatile drop-down list that can be used with custom widgets. It allows you to display a list of widgets under a displayed widget. Unlike other toolkits, the list of widgets can contain any type of widget: simple buttons, images etc.

The positioning of the drop-down list is fully automatic: we will always try to place the dropdown list in a way that the user can select an item in the list.

45.14.1 Basic example

A button with a dropdown list of 10 possible values. All the buttons within the dropdown list will trigger the dropdown [DropDown.select\(\)](#) method. After being called, the main button text will display the selection of the dropdown.

```
from kivy.uix.dropdown import DropDown
from kivy.uix.button import Button
from kivy.base import runTouchApp

# create a dropdown with 10 buttons
dropdown = DropDown()
for index in range(10):
    # When adding widgets, we need to specify the height manually
    # (disabling the size_hint_y) so the dropdown can calculate
    # the area it needs.

    btn = Button(text='Value %d' % index, size_hint_y=None, height=44)

    # for each button, attach a callback that will call the select() method
    # on the dropdown. We'll pass the text of the button as the data of the
    # selection.
    btn.bind(on_release=lambda btn: dropdown.select(btn.text))

    dropdown.add_widget(btn)

runTouchApp(dropdown)
```

(continues on next page)

```

# then add the button inside the dropdown
dropdown.add_widget(btn)

# create a big main button
mainbutton = Button(text='Hello', size_hint=(None, None))

# show the dropdown menu when the main button is released
# note: all the bind() calls pass the instance of the caller (here, the
# mainbutton instance) as the first argument of the callback (here,
# dropdown.open.).
mainbutton.bind(on_release=dropdown.open)

# one last thing, listen for the selection in the dropdown list and
# assign the data to the button text.
dropdown.bind(on_select=lambda instance, x: setattr(mainbutton, 'text', x))

runTouchApp(mainbutton)

```

45.14.2 Extending dropdown in Kv

You could create a dropdown directly from your kv:

```

#:kivy 1.4.0
<CustomDropDown>:
    Button:
        text: 'My first Item'
        size_hint_y: None
        height: 44
        on_release: root.select('item1')
    Label:
        text: 'Unselectable item'
        size_hint_y: None
        height: 44
    Button:
        text: 'My second Item'
        size_hint_y: None
        height: 44
        on_release: root.select('item2')

```

And then, create the associated python class and use it:

```

class CustomDropDown(DropDown):
    pass

dropdown = CustomDropDown()
mainbutton = Button(text='Hello', size_hint=(None, None))
mainbutton.bind(on_release=dropdown.open)
dropdown.bind(on_select=lambda instance, x: setattr(mainbutton, 'text', x))

```

```

class kivy.uix.dropdown.DropDown(**kwargs)
Bases: kivy.uix.scrollview.ScrollView

```

DropDown class. See module documentation for more information.

Events

on_select: data Fired when a selection is done. The data of the selection is passed in as the first argument and is what you pass in the `select()` method as the first argument.

on_dismiss: New in version 1.8.0.

Fired when the DropDown is dismissed, either on selection or on touching outside the widget.

add_widget(*args, **kwargs)

Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

attach_to

(internal) Property that will be set to the widget to which the drop down list is attached.

The `open()` method will automatically set this property whilst `dismiss()` will set it back to None.

auto_dismiss

By default, the dropdown will be automatically dismissed when a touch happens outside of it, this option allows to disable this feature

`auto_dismiss` is a *BooleanProperty* and defaults to True.

New in version 1.8.0.

auto_width

By default, the width of the dropdown will be the same as the width of the attached widget. Set to False if you want to provide your own width.

`auto_width` is a *BooleanProperty* and defaults to True.

clear_widgets(*args, **kwargs)

Remove all (or the specified) `children` of this widget. If the 'children' argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The `children` argument can be used to specify the children you want to remove.

Changed in version 2.1.0: Specifying an empty `children` list leaves the widgets unchanged. Previously it was treated like `None` and all children were removed.

container

(internal) Property that will be set to the container of the dropdown list. It is a `GridLayout` by default.

dismiss(*args)

Remove the dropdown widget from the window and detach it from the attached widget.

dismiss_on_select

By default, the dropdown will be automatically dismissed when a selection has been done. Set to False to prevent the dismiss.

`dismiss_on_select` is a `BooleanProperty` and defaults to True.

max_height

Indicate the maximum height that the dropdown can take. If None, it will take the maximum height available until the top or bottom of the screen is reached.

`max_height` is a `NumericProperty` and defaults to None.

min_state_time

Minimum time before the `DropDown` is dismissed. This is used to allow for the widget inside the dropdown to display a down state or for the `DropDown` itself to display a animation for closing.

`min_state_time` is a `NumericProperty` and defaults to the `Config` value `min_state_time`.

New in version 1.10.0.

on_motion(etype, me)

Called when a motion event is received.

Parameters

`etype: str` Event type, one of "begin", "update" or "end"

`me: MotionEvent` Received motion event

Returns `bool` True to stop event dispatching

New in version 2.1.0.

Warning: This is an experimental method and it remains so while this warning is present.

on_touch_down(touch)

Receive a touch down event.

Parameters

`touch: MotionEvent class` Touch received. The touch is in parent coordinates.

See `relativelayout` for a discussion on coordinate systems.

Returns `bool` If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See `on_touch_down()` for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

open(widget)

Open the dropdown list and attach it to a specific widget. Depending on the position of the widget within the window and the height of the dropdown, the dropdown might be above or below that widget.

remove_widget(*args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: Widget Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

select(data)

Call this method to trigger the *on_select* event with the *data* selection. The *data* can be anything you want.

45.15 EffectWidget

New in version 1.9.0.

The **EffectWidget** is able to apply a variety of fancy graphical effects to its children. It works by rendering to a series of **Fbo** instances with custom opengl fragment shaders. As such, effects can freely do almost anything, from inverting the colors of the widget, to anti-aliasing, to emulating the appearance of a crt monitor!

Warning: This code is still experimental, and its API is subject to change in a future version.

The basic usage is as follows:

```
w = EffectWidget()
w.add_widget(Button(text='Hello!'))
w.effects = [InvertEffect(), HorizontalBlurEffect(size=2.0)]
```

The equivalent in kv would be:

```
#: import ew kivy.uix.effectwidget
EffectWidget:
    effects: ew.InvertEffect(), ew.HorizontalBlurEffect(size=2.0)
    Button:
        text: 'Hello!'
```

The effects can be a list of effects of any length, and they will be applied sequentially.

The module comes with a range of prebuilt effects, but the interface is designed to make it easy to create your own. Instead of writing a full glsl shader, you provide a single function that takes some inputs based on the screen (current pixel color, current widget texture etc.). See the sections below for more information.

45.15.1 Usage Guidelines

It is not efficient to resize an *EffectWidget*, as the *Fbo* is recreated on each resize event. If you need to resize frequently, consider doing things a different way.

Although some effects have adjustable parameters, it is *not* efficient to animate these, as the entire shader is reconstructed every time. You should use glsl uniform variables instead. The *AdvancedEffectBase* may make this easier.

Note: The *EffectWidget* cannot draw outside its own widget area (pos -> pos + size). Any child widgets overlapping the boundary will be cut off at this point.

45.15.2 Provided Effects

The module comes with several pre-written effects. Some have adjustable properties (e.g. blur radius). Please see the individual effect documentation for more details.

- *MonochromeEffect* - makes the widget grayscale.
- *InvertEffect* - inverts the widget colors.
- *ChannelMixEffect* - swaps color channels.
- *ScanlinesEffect* - displays flickering scanlines.
- *PixelateEffect* - pixelates the image.
- *HorizontalBlurEffect* - Gaussuan blurs horizontally.
- *VerticalBlurEffect* - Gaussuan blurs vertically.
- *FXAAEffect* - applies a very basic anti-aliasing.

45.15.3 Creating Effects

Effects are designed to make it easy to create and use your own transformations. You do this by creating and using an instance of *EffectBase* with your own custom *EffectBase.gsl* property.

The *gsl* property is a string representing part of a glsl fragment shader. You can include as many functions as you like (the string is simply spliced into the whole shader), but it must implement a function *effect* as below:

```
vec4 effect(vec4 color, sampler2D texture, vec2 tex_coords, vec2 coords)
{
    // ... your code here
    return something; // must be a vec4 representing the new color
}
```

The full shader will calculate the normal pixel color at each point, then call your *effect* function to transform it. The parameters are:

- **color**: The normal color of the current pixel (i.e. texture sampled at *tex_coords*).
- **texture**: The texture containing the widget's normal background.
- **tex_coords**: The normal *texture_coords* used to access texture.
- **coords**: The pixel indices of the current pixel.

The shader code also has access to two useful uniform variables, `time` containing the time (in seconds) since the program start, and `resolution` containing the shape (x pixels, y pixels) of the widget.

For instance, the following simple string (taken from the `InvertEffect`) would invert the input color but set alpha to 1.0:

```
vec4 effect(vec4 color, sampler2D texture, vec2 tex_coords, vec2 coords)
{
    return vec4(1.0 - color.xyz, 1.0);
}
```

You can also set the glsl by automatically loading the string from a file, simply set the `EffectBase.source` property of an effect.

class `kivy.uix.effectwidget.AdvancedEffectBase(*args, **kwargs)`
Bases: `kivy.uix.effectwidget.EffectBase`

An `EffectBase` with additional behavior to easily set and update uniform variables in your shader.

This class is provided for convenience when implementing your own effects: it is not used by any of those provided with Kivy.

In addition to your base glsl string that must be provided as normal, the `AdvancedEffectBase` has an extra property `uniforms`, a dictionary of name-value pairs. Whenever a value is changed, the new value for the uniform variable is uploaded to the shader.

You must still manually declare your uniform variables at the top of your glsl string.

set_fbo_shader(*args)

Sets the `Fbo`'s shader by splicing the `glsl` string into a full fragment shader.

The full shader is made up of `shader_header + shader_uniforms + self.glsl + shader_footer_effect`.

uniforms

A dictionary of uniform variable names and their values. These are automatically uploaded to the `fbo` shader if appropriate.

`uniforms` is a `DictProperty` and defaults to {}.

class `kivy.uix.effectwidget.ChannelMixEffect(*args, **kwargs)`
Bases: `kivy.uix.effectwidget.EffectBase`

Mixes the color channels of the input according to the `order` property. Channels may be arbitrarily rearranged or repeated.

order

The new sorted order of the rgb channels.

`order` is a `ListProperty` and defaults to [1, 2, 0], corresponding to (g, b, r).

class `kivy.uix.effectwidget.EffectBase(*args, **kwargs)`
Bases: `kivy.event.EventDispatcher`

The base class for GLSL effects. It simply returns its input.

See the module documentation for more details.

fbo

The fbo currently using this effect. The `EffectBase` automatically handles this.

`fbo` is an `ObjectProperty` and defaults to None.

glsl

The glsl string defining your effect function. See the module documentation for more details.

`glsl` is a *StringProperty* and defaults to a trivial effect that returns its input.

`set_fbo_shader(*args)`

Sets the *Fbo*'s shader by splicing the `glsl` string into a full fragment shader.

The full shader is made up of `shader_header + shader_uniforms + self.glsl + shader_footer_effect`.

`source`

The (optional) filename from which to load the `glsl` string.

`source` is a *StringProperty* and defaults to ''.

`class kivy.uix.effectwidget.EffectWidget(**kwargs)`

Bases: `kivy.uix.relativelayout.RelativeLayout`

Widget with the ability to apply a series of graphical effects to its children. See the module documentation for more information on setting effects and creating your own.

`add_widget(*args, **kwargs)`

Add a new widget as a child of this widget.

Parameters

`widget: Widget` Widget to add to our list of children.

`index: int, defaults to 0` Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the *Widgets Programming Guide*.

New in version 1.0.5.

`canvas: str, defaults to None` Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

`background_color`

This defines the background color to be used for the fbo in the EffectWidget.

`background_color` is a *ListProperty* defaults to (0, 0, 0, 0)

`clear_widgets(*args, **kwargs)`

Remove all (or the specified) `children` of this widget. If the 'children' argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The `children` argument can be used to specify the children you want to remove.

Changed in version 2.1.0: Specifying an empty `children` list leaves the widgets unchanged. Previously it was treated like `None` and all children were removed.

`effects`

List of all the effects to be applied. These should all be instances or subclasses of *EffectBase*.

`effects` is a *ListProperty* and defaults to [].

fbo_list

(internal) List of all the fbos that are being used to apply the effects.

fbo_list is a `ListProperty` and defaults to [].

refresh_fbo_setup(*args)

(internal) Creates and assigns one `Fbo` per effect, and makes sure all sizes etc. are correct and consistent.

remove_widget(*args, **kwargs)

Remove a widget from the children of this widget.

Parameters

`widget: Widget` Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

texture

The output texture of the final `Fbo` after all effects have been applied.

texture is an `ObjectProperty` and defaults to None.

class kivy.uix.effectwidget.FXAAEffect(*args, **kwargs)

Bases: `kivy.uix.effectwidget.EffectBase`

Applies very simple anti-aliasing via fxaa.

class kivy.uix.effectwidget.HorizontalBlurEffect(*args, **kwargs)

Bases: `kivy.uix.effectwidget.EffectBase`

Blurs the input horizontally, with the width given by `size`.

size

The blur width in pixels.

`size` is a `NumericProperty` and defaults to 4.0.

class kivy.uix.effectwidget.InvertEffect(*args, **kwargs)

Bases: `kivy.uix.effectwidget.EffectBase`

Inverts the colors in the input.

class kivy.uix.effectwidget.MonochromeEffect(*args, **kwargs)

Bases: `kivy.uix.effectwidget.EffectBase`

Returns its input colors in monochrome.

class kivy.uix.effectwidget.PixelateEffect(*args, **kwargs)

Bases: `kivy.uix.effectwidget.EffectBase`

Pixelates the input according to its `pixel_size`

pixel_size

Sets the size of a new ‘pixel’ in the effect, in terms of number of ‘real’ pixels.

`pixel_size` is a `NumericProperty` and defaults to 10.

class kivy.uix.effectwidget.ScanlinesEffect(*args, **kwargs)

Bases: `kivy.uix.effectwidget.EffectBase`

Adds scanlines to the input.

```
class kivy.uix.effectwidget.VerticalBlurEffect(*args, **kwargs)
Bases: kivy.uix.effectwidget.EffectBase
```

Blurs the input vertically, with the width given by **size**.

size

The blur width in pixels.

size is a *NumericProperty* and defaults to 4.0.

45.16 FileChooser

The FileChooser module provides various classes for describing, displaying and browsing file systems.


45.16.1 Simple widgets

There are two ready-to-use widgets that provide views of the file system. Each of these present the files and folders in a different style.

The *FileChooserListView* displays file entries as text items in a vertical list, where folders can be collapsed and expanded.

Name	Size
.. /	
> build	
> doc	
> examples	
> kivy	
AUTHORS	2 KB
CONTRIBUTING.md	3 KB
LICENSE	1 KB
MANIFEST.in	319 B
Makefile	4 KB
README.md	4 KB
setup.cfg	69 B
setup.py	35 KB

The *FileChooserIconView* presents icons and text from left to right, wrapping them as required.



They both provide for scrolling, selection and basic user interaction. Please refer to the [FileChooserController](#) for details on supported events and properties.

45.16.2 Widget composition

FileChooser classes adopt a [MVC](#) design. They are exposed so that you can extend and customize your file chooser according to your needs.

The FileChooser classes can be categorized as follows:

- Models are represented by concrete implementations of the [FileSystemAbstract](#) class, such as the [FileSystemLocal](#).
- Views are represented by the [FileChooserListLayout](#) and [FileChooserIconLayout](#) classes. These are used by the [FileChooserListView](#) and [FileChooserIconView](#) widgets respectively.
- Controllers are represented by concrete implementations of the [FileChooserController](#), namely the [FileChooser](#), [FileChooserIconView](#) and [FileChooserListView](#) classes.

This means you can define your own views or provide [FileSystemAbstract](#) implementations for alternative file systems for use with these widgets. The [FileChooser](#) can be used as a controller for handling multiple, synchronized views of the same path. By combining these elements, you can add your own views and file systems and have them easily interact with the existing components.

45.16.3 Usage example

main.py

```
from kivy.app import App
from kivy.uix.floatlayout import FloatLayout
from kivy.factory import Factory
from kivy.properties import ObjectProperty
from kivy.uix.popup import Popup

import os

class LoadDialog(FloatLayout):
    load = ObjectProperty(None)
    cancel = ObjectProperty(None)

class SaveDialog(FloatLayout):
    save = ObjectProperty(None)
    text_input = ObjectProperty(None)
    cancel = ObjectProperty(None)

class Root(FloatLayout):
    loadfile = ObjectProperty(None)
    savefile = ObjectProperty(None)
    text_input = ObjectProperty(None)

    def dismiss_popup(self):
        self._popup.dismiss()

    def show_load(self):
        content = LoadDialog(load=self.load, cancel=self.dismiss_popup)
        self._popup = Popup(title="Load file", content=content,
                            size_hint=(0.9, 0.9))
        self._popup.open()

    def show_save(self):
        content = SaveDialog(save=self.save, cancel=self.dismiss_popup)
        self._popup = Popup(title="Save file", content=content,
                            size_hint=(0.9, 0.9))
        self._popup.open()

    def load(self, path, filename):
        with open(os.path.join(path, filename[0])) as stream:
            self.text_input.text = stream.read()

        self.dismiss_popup()

    def save(self, path, filename):
        with open(os.path.join(path, filename), 'w') as stream:
            stream.write(self.text_input.text)

        self.dismiss_popup()
```

(continues on next page)

```

class Editor(App):
    pass

Factory.register('Root', cls=Root)
Factory.register('LoadDialog', cls=LoadDialog)
Factory.register('SaveDialog', cls=SaveDialog)

if __name__ == '__main__':
    Editor().run()

```

editor.kv

```

#:kivy 1.1.0

Root:
    text_input: text_input

    BoxLayout:
        orientation: 'vertical'
        BoxLayout:
            size_hint_y: None
            height: 30
            Button:
                text: 'Load'
                on_release: root.show_load()
            Button:
                text: 'Save'
                on_release: root.show_save()

        BoxLayout:
            TextInput:
                id: text_input
                text: ''

            RstDocument:
                text: text_input.text
                show_errors: True

<LoadDialog>:
    BoxLayout:
        size: root.size
        pos: root.pos
        orientation: "vertical"
        FileChooserListView:
            id: filechooser

        BoxLayout:
            size_hint_y: None
            height: 30

```

(continues on next page)

```

Button:
    text: "Cancel"
    on_release: root.cancel()

Button:
    text: "Load"
    on_release: root.load(filechooser.path, filechooser.
selection)

<SaveDialog>:
    text_input: text_input
    BoxLayout:
        size: root.size
        pos: root.pos
        orientation: "vertical"
        FileChooserListView:
            id: filechooser
            on_selection: text_input.text = self.selection and self.
selection[0] or ''
        TextInput:
            id: text_input
            size_hint_y: None
            height: 30
            multiline: False

    BoxLayout:
        size_hint_y: None
        height: 30
        Button:
            text: "Cancel"
            on_release: root.cancel()

        Button:
            text: "Save"
            on_release: root.save(filechooser.path, text_input.text)

```

New in version 1.0.5.

Changed in version 1.2.0: In the chooser template, the *controller* is no longer a direct reference but a weak-reference. If you are upgrading, you should change the notation *root.controller.xxx* to *root.controller().xxx*.

class kivy.uix.filechooser.FileChooser(kwargs)**
Bases: *kivy.uix.filechooserFileChooserController*

Implementation of a *FileChooserController* which supports switching between multiple, synced layout views.

The FileChooser can be used as follows:

```

BoxLayout:
    orientation: 'vertical'

    BoxLayout:
        size_hint_y: None

```

(continues on next page)

```

height: sp(52)

Button:
    text: 'Icon View'
    on_press: fc.view_mode = 'icon'
Button:
    text: 'List View'
    on_press: fc.view_mode = 'list'

FileChooser:
    id: fc
    FileChooserIconLayout
    FileChooserListLayout

```

New in version 1.9.0.

`add_widget(widget, *args, **kwargs)`

Add a new widget as a child of this widget.

Parameters

`widget: Widget` Widget to add to our list of children.

`index: int, defaults to 0` Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

`canvas: str, defaults to None` Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```

>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)

```

`manager`

Reference to the [ScreenManager](#) instance.

`manager` is an [ObjectProperty](#).

`view_list`

List of views added to this FileChooser.

`view_list` is an [AliasProperty](#) of type `list`.

`view_mode`

Current layout view mode.

`view_mode` is an [AliasProperty](#) of type `str`.

`class kivy.uix.filechooser.FileChooserController(**kwargs)`

Bases: [kivy.uix.relativelayout.RelativeLayout](#)

Base for implementing a FileChooser. Don't use this class directly, but prefer using an implementation such as the [FileChooser](#), [FileChooserListView](#) or [FileChooserIconView](#).

Events

on_entry_added: entry, parent Fired when a root-level entry is added to the file list.

If you return True from this event, the entry is not added to FileChooser.

on_entries_cleared Fired when the entries list is cleared, usually when the root is refreshed.

on_subentry_to_entry: entry, parent Fired when a sub-entry is added to an existing entry or when entries are removed from an entry e.g. when a node is closed.

on_submit: selection, touch Fired when a file has been selected with a double-tap.

cancel(*args)

Cancel any background action started by filechooser, such as loading a new directory.

New in version 1.2.0.

dirselect

Determines whether directories are valid selections or not.

dirselect is a [BooleanProperty](#) and defaults to False.

New in version 1.1.0.

entry_released(entry, touch)

(internal) This method must be called by the template when an entry is touched by the user.

New in version 1.1.0.

entry_touched(entry, touch)

(internal) This method must be called by the template when an entry is touched by the user.

file_encodings

Possible encodings for decoding a filename to unicode. In the case that the user has a non-ascii filename, undecodable without knowing its initial encoding, we have no other choice than to guess it.

Please note that if you encounter an issue because of a missing encoding here, we'll be glad to add it to this list.

file_encodings is a [ListProperty](#) and defaults to ['utf-8', 'latin1', 'cp1252'].

New in version 1.3.0.

Deprecated since version 1.8.0: This property is no longer used as the filechooser no longer decodes the file names.

file_system

The file system object used to access the file system. This should be a subclass of [FileSystemAbstract](#).

file_system is an [ObjectProperty](#) and defaults to [FileSystemLocal\(\)](#)

New in version 1.8.0.

files

The list of files in the directory specified by path after applying the filters.

files is a read-only [ListProperty](#).

filter_dirs

Indicates whether filters should also apply to directories. filter_dirs is a [BooleanProperty](#) and defaults to False.

filters

filters specifies the filters to be applied to the files in the directory. filters is a *ListProperty* and defaults to []. This is equivalent to '*' i.e. nothing is filtered.

The filters are not reset when the path changes. You need to do that yourself if desired.

There are two kinds of filters: patterns and callbacks.

1. Patterns

e.g. ['*.png']. You can use the following patterns:

Pattern	Meaning
*	matches everything
?	matches any single character
[seq]	matches any character in seq
[!seq]	matches any character not in seq

2. Callbacks

You can specify a function that will be called for each file. The callback will be passed the folder and file name as the first and second parameters respectively. It should return True to indicate a match and False otherwise.

Changed in version 1.4.0: Added the option to specify the filter as a callback.

font_name

Filename of the font to use in UI components. The path can be absolute or relative. Relative paths are resolved by the *resource_find()* function.

font_name is a *StringProperty* and defaults to 'Roboto'. This value is taken from *Config*.

get_nice_size(*fn*)

Pass the filepath. Returns the size in the best human readable format or '' if it is a directory (Don't recursively calculate size).

layout

Reference to the layout widget instance.

layout is an *ObjectProperty*.

New in version 1.9.0.

multiselect

Determines whether the user is able to select multiple files or not.

multiselect is a *BooleanProperty* and defaults to False.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.

See *relativelayout* for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_up(*touch*)

Receive a touch up event. The touch is in parent coordinates.

See *on_touch_down()* for more information.

path

path is a *StringProperty* and defaults to the current working directory as a unicode string. It specifies the path on the filesystem that this controller should refer to.

Warning: If a unicode path is specified, all the files returned will be in unicode, allowing the display of unicode files and paths. If a bytes path is specified, only files and paths with ascii names will be displayed properly: non-ascii filenames will be displayed and listed with questions marks (?) instead of their unicode characters.

progress_cls

Class to use for displaying a progress indicator for filechooser loading.

progress_cls is an *ObjectProperty* and defaults to **FileChooserProgress**.

New in version 1.2.0.

Changed in version 1.8.0: If set to a string, the *Factory* will be used to resolve the class name.

rootpath

Root path to use instead of the system root path. If set, it will not show a “..” directory to go up to the root path. For example, if you set rootpath to /users/foo, the user will be unable to go to /users or to any other directory not starting with /users/foo.

rootpath is a *StringProperty* and defaults to None.

New in version 1.2.0.

Note: Similarly to *path*, whether *rootpath* is specified as bytes or a unicode string determines the type of the filenames and paths read.

selection

Contains the list of files that are currently selected.

selection is a read-only *ListProperty* and defaults to [].

show_hidden

Determines whether hidden files and folders should be shown.

show_hidden is a *BooleanProperty* and defaults to False.

sort_func

Provides a function to be called with a list of filenames as the first argument and the filesystem implementation as the second argument. It returns a list of filenames sorted for display in the view.

sort_func is an *ObjectProperty* and defaults to a function returning alphanumerically named folders first.

Changed in version 1.8.0: The signature needs now 2 arguments: first the list of files, second the filesystem class to use.

class kivy.uix.filechooser.FileChooserIconLayout(kwargs)**

Bases: *kivy.uix.filechooser.FileChooserLayout*

File chooser layout using an icon view.

New in version 1.9.0.

class kivy.uix.filechooser.FileChooserIconView(kwargs)**

Bases: *kivy.uix.filechooser.FileChooserController*

Implementation of a [FileChooserController](#) using an icon view.

New in version 1.9.0.

class `kivy.uix.filechooser.FileChooserListLayout(**kwargs)`
Bases: `kivy.uix.filechooser.FileChooserLayout`

File chooser layout using a list view.

New in version 1.9.0.

class `kivy.uix.filechooser.FileChooserListView(**kwargs)`
Bases: `kivy.uix.filechooser.FileChooserController`

Implementation of a [FileChooserController](#) using a list view.

New in version 1.9.0.

class `kivy.uix.filechooser.FileChooserProgressBase(**kwargs)`
Bases: `kivy.uix.floatlayout.FloatLayout`

Base for implementing a progress view. This view is used when too many entries need to be created and are delayed over multiple frames.

New in version 1.2.0.

cancel(*args)

Cancel any action from the FileChooserController.

index

Current index of `total` entries to be loaded.

on_touch_down(touch)

Receive a touch down event.

Parameters

`touch: MotionEvent class` Touch received. The touch is in parent coordinates.
See [relativelayout](#) for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

path

Current path of the FileChooser, read-only.

total

Total number of entries to load.

class `kivy.uix.filechooser.FileSystemAbstract`
Bases: `builtins.object`

Class for implementing a File System view that can be used with the [FileChooser](#).

New in version 1.8.0.

getsize(fn)

Return the size in bytes of a file

is_dir(*fn*)

Return True if the argument passed to this method is a directory

is_hidden(*fn*)

Return True if the file is hidden

listdir(*fn*)

Return the list of files in the directory *fn*

class kivy.uix.filechooser.FileSystemLocal

Bases: *kivy.uix.filechooser.FileSystemAbstract*

Implementation of *FileSystemAbstract* for local files.

New in version 1.8.0.

getsize(*fn*)

Return the size in bytes of a file

is_dir(*fn*)

Return True if the argument passed to this method is a directory

is_hidden(*fn*)

Return True if the file is hidden

listdir(*fn*)

Return the list of files in the directory *fn*

45.17 Float Layout

FloatLayout honors the *pos_hint* and the *size_hint* properties of its children.



For example, a *FloatLayout* with a size of (300, 300) is created:

```
layout = FloatLayout(size=(300, 300))
```

By default, all widgets have their *size_hint*=(1, 1), so this button will adopt the same size as the layout:

```
button = Button(text='Hello world')
layout.add_widget(button)
```

To create a button 50% of the width and 25% of the height of the layout and positioned at (20, 20), you can do:

```
button = Button(  
    text='Hello world',  
    size_hint=(.5, .25),  
    pos=(20, 20))
```

If you want to create a button that will always be the size of layout minus 20% on each side:

```
button = Button(text='Hello world', size_hint=(.6, .6),  
    pos_hint={'x':.2, 'y':.2})
```

Note: This layout can be used for an application. Most of the time, you will use the size of Window.

Warning: If you are not using pos_hint, you must handle the positioning of the children: if the float layout is moving, you must handle moving the children too.

class kivy.uix.floatlayout.**FloatLayout**(**kwargs)
Bases: *kivy.uix.layout.Layout*

Float layout class. See module documentation for more information.

add_widget(widget, *args, **kwargs)

Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the *Widgets Programming Guide*.

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button  
>>> from kivy.uix.slider import Slider  
>>> root = Widget()  
>>> root.add_widget(Button())  
>>> slider = Slider()  
>>> root.add_widget(slider)
```

do_layout(*args, **kwargs)

This function is called when a layout is called by a trigger. If you are writing a new Layout subclass, don't call this function directly but use `_trigger_layout()` instead.

The function is by default called *before* the next frame, therefore the layout isn't updated immediately. Anything depending on the positions of e.g. children should be scheduled for the next frame.

New in version 1.0.8.

`remove_widget(widget, *args, **kwargs)`

Remove a widget from the children of this widget.

Parameters

`widget: Widget` Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

45.18 Gesture Surface

New in version 1.9.0.

Warning: This is experimental and subject to change as long as this warning notice is present.

See `kivy/examples/demo/multistroke/main.py` for a complete application example.

`class kivy.uix.gesturesurface.GestureContainer(touch, **kwargs)`

Bases: `kivy.event.EventDispatcher`

Container object that stores information about a gesture. It has various properties that are updated by `GestureSurface` as drawing progresses.

Arguments

`touch` Touch object (as received by `on_touch_down`) used to initialize the gesture container. Required.

Properties

`active` Set to False once the gesture is complete (meets `max_stroke` setting or `GestureSurface.temporal_window`)

`active` is a `BooleanProperty`

`active_strokes` Number of strokes currently active in the gesture, ie concurrent touches associated with this gesture.

`active_strokes` is a `NumericProperty`

`max_strokes` Max number of strokes allowed in the gesture. This is set by `GestureSurface.max_strokes` but can be overridden for example from `on_gesture_start`.

`max_strokes` is a `NumericProperty`

`was_merged` Indicates that this gesture has been merged with another gesture and should be considered discarded.

`was_merged` is a `BooleanProperty`

`bbox` Dictionary with keys minx, miny, maxx, maxy. Represents the size of the gesture bounding box.

`bbox` is a `DictProperty`

width Represents the width of the gesture.

width is a *NumericProperty*

height Represents the height of the gesture.

height is a *NumericProperty*

accept_stroke(*count*=1)

Returns True if this container can accept *count* new strokes

add_stroke(*touch, line*)

Associate a list of points with a touch.uid; the line itself is created by the caller, but subsequent move/up events look it up via us. This is done to avoid problems during merge.

complete_stroke()

Called on touch up events to keep track of how many strokes are active in the gesture (we only want to dispatch event when the *last* stroke in the gesture is released)

get_vectors(kwargs)**

Return strokes in a format that is acceptable for *kivy.multistroke.Recognizer* as a gesture candidate or template. The result is cached automatically; the cache is invalidated at the start and end of a stroke and if *update_bbox* is called. If you are going to analyze a gesture mid-stroke, you may need to set the *no_cache* argument to True.

handles(*touch*)

Returns True if this container handles the given touch

single_points_test()

Returns True if the gesture consists only of single-point strokes, we must discard it in this case, or an exception will be raised

update_bbox(*touch*)

Update gesture bbox from a touch coordinate

class kivy.uix.gesturesurface.GestureSurface(kwargs)**

Bases: *kivy.uix.floatlayout.FloatLayout*

Simple gesture surface to track/draw touch movements. Typically used to gather user input suitable for *kivy.multistroke.Recognizer*.

Properties

temporal_window Time to wait from the last touch_up event before attempting to recognize the gesture. If you set this to 0, the *on_gesture_complete* event is not fired unless the *max_strokes* condition is met.

temporal_window is a *NumericProperty* and defaults to 2.0

max_strokes Max number of strokes in a single gesture; if this is reached, recognition will start immediately on the final touch_up event. If this is set to 0, the *on_gesture_complete* event is not fired unless the *temporal_window* expires.

max_strokes is a *NumericProperty* and defaults to 2.0

bbox_margin Bounding box margin for detecting gesture collisions, in pixels.

bbox_margin is a *NumericProperty* and defaults to 30

draw_timeout Number of seconds to keep lines/bbox on canvas after the *on_gesture_complete* event is fired. If this is set to 0, gestures are immediately removed from the surface when complete.

draw_timeout is a *NumericProperty* and defaults to 3.0

color Color used to draw the gesture, in RGB. This option does not have an effect if *use_random_color* is True.

`color` is a [ColorProperty](#) and defaults to [1, 1, 1, 1] (white)

Changed in version 2.0.0: Changed from [ListProperty](#) to [ColorProperty](#).

`use_random_color` Set to True to pick a random color for each gesture, if you do this then `color` is ignored. Defaults to False.

`use_random_color` is a [BooleanProperty](#) and defaults to False

`line_width` Line width used for tracing touches on the surface. Set to 0 if you only want to detect gestures without drawing anything. If you use 1.0, OpenGL GL_LINE is used for drawing; values > 1 will use an internal drawing method based on triangles (less efficient), see [kivy.graphics](#).

`line_width` is a [NumericProperty](#) and defaults to 2

`draw_bbox` Set to True if you want to draw bounding box behind gestures. This only works if `line_width` >= 1. Default is False.

`draw_bbox` is a [BooleanProperty](#) and defaults to True

`bbox_alpha` Opacity for bounding box if `draw_bbox` is True. Default 0.1

`bbox_alpha` is a [NumericProperty](#) and defaults to 0.1

Events

`on_gesture_start GestureContainer` Fired when a new gesture is initiated on the surface, i.e. the first `on_touch_down` that does not collide with an existing gesture on the surface.

`on_gesture_extend GestureContainer` Fired when a `touch_down` event occurs within an existing gesture.

`on_gesture_merge GestureContainer, GestureContainer` Fired when two gestures collide and get merged to one gesture. The first argument is the gesture that has been merged (no longer valid); the second is the combined (resulting) gesture.

`on_gesture_complete GestureContainer` Fired when a set of strokes is considered a complete gesture, this happens when `temporal_window` expires or `max_strokes` is reached. Typically you will bind to this event and use the provided `GestureContainer get_vectors()` method to match against your gesture database.

`on_gesture_cleanup GestureContainer` Fired `draw_timeout` seconds after `on_gesture_complete`, The gesture will be removed from the canvas (if `line_width` > 0 or `draw_bbox` is True) and the internal gesture list before this.

`on_gesture_discard GestureContainer` Fired when a gesture does not meet the minimum size requirements for recognition (width/height < 5, or consists only of single-point strokes).

`find_colliding_gesture(touch)`

Checks if a touch x/y collides with the bounding box of an existing gesture. If so, return it (otherwise returns None)

`get_gesture(touch)`

Returns GestureContainer associated with given touch

`init_gesture(touch)`

Create a new gesture from touch, i.e. it's the first on surface, or was not close enough to any existing gesture (yet)

merge_gestures(*g, other*)

Merges two gestures together, the oldest one is retained and the newer one gets the *GestureContainer.was_merged* flag raised.

on_touch_down(*touch*)

When a new touch is registered, the first thing we do is to test if it collides with the bounding box of another known gesture. If so, it is assumed to be part of that gesture.

on_touch_move(*touch*)

When a touch moves, we add a point to the line on the canvas so the path is updated. We must also check if the new point collides with the bounding box of another gesture - if so, they should be merged.

on_touch_up(*touch*)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

45.19 Grid Layout



New in version 1.0.4.

The **GridLayout** arranges children in a matrix. It takes the available space and divides it into columns and rows, then adds widgets to the resulting “cells”.

Changed in version 1.0.7: The implementation has changed to use the widget size_hint for calculating column/row sizes. *uniform_width* and *uniform_height* have been removed and other properties have added to give you more control.

45.19.1 Background

Unlike many other toolkits, you cannot explicitly place a widget in a specific column/row. Each child is automatically assigned a position determined by the layout configuration and the child's index in the children list.

A GridLayout must always have at least one input constraint: `GridLayout.cols` or `GridLayout.rows`. If you do not specify cols or rows, the Layout will throw an exception.

45.19.2 Column Width and Row Height


The column width/row height are determined in 3 steps:

- The initial size is given by the `col_default_width` and `row_default_height` properties. To customize the size of a single column or row, use `cols_minimum` or `rows_minimum`.
- The `size_hint_x`/`size_hint_y` of the children are taken into account. If no widgets have a size hint, the maximum size is used for all children.
- You can force the default size by setting the `col_force_default` or `row_force_default` property. This will force the layout to ignore the `width` and `size_hint` properties of children and use the default size.

45.19.3 Using a GridLayout

In the example below, all widgets will have an equal size. By default, the `size_hint` is (1, 1), so a Widget will take the full size of the parent:

```
layout = GridLayout(cols=2)
layout.add_widget(Button(text='Hello 1'))
layout.add_widget(Button(text='World 1'))
layout.add_widget(Button(text='Hello 2'))
layout.add_widget(Button(text='World 2'))
```



Now, let's fix the size of Hello buttons to 100px instead of using `size_hint_x=1`:

```
layout = GridLayout(cols=2)
layout.add_widget(Button(text='Hello 1', size_hint_x=None, width=100))
layout.add_widget(Button(text='World 1'))
```

(continues on next page)

(continued from previous page)

```
layout.add_widget(Button(text='Hello 2', size_hint_x=None, width=100))
layout.add_widget(Button(text='World 2'))
```



Next, let's fix the row height to a specific size:

```
layout = GridLayout(cols=2, row_force_default=True, row_default_height=40)
layout.add_widget(Button(text='Hello 1', size_hint_x=None, width=100))
layout.add_widget(Button(text='World 1'))
layout.add_widget(Button(text='Hello 2', size_hint_x=None, width=100))
layout.add_widget(Button(text='World 2'))
```



class kivy.uix.gridlayout.GridLayout(kwargs)**
Bases: *kivy.uix.layout.Layout*

Grid layout class. See module documentation for more information.

col_default_width

Default minimum size to use for a column.

New in version 1.0.7.

col_default_width is a *NumericProperty* and defaults to 0.

col_force_default

If True, ignore the width and size_hint_x of the child and use the default column width.

New in version 1.0.7.

col_force_default is a *BooleanProperty* and defaults to False.

cols

Number of columns in the grid.

Changed in version 1.0.8: Changed from a NumericProperty to BoundedNumericProperty.
You can no longer set this to a negative value.

cols is a *NumericProperty* and defaults to None.

cols_minimum

Dict of minimum width for each column. The dictionary keys are the column numbers, e.g. 0, 1, 2...

New in version 1.0.7.

cols_minimum is a *DictProperty* and defaults to {}.

do_layout(*args)

This function is called when a layout is called by a trigger. If you are writing a new Layout subclass, don't call this function directly but use *_trigger_layout()* instead.

The function is by default called *before* the next frame, therefore the layout isn't updated immediately. Anything depending on the positions of e.g. children should be scheduled for the next frame.

New in version 1.0.8.

minimum_height

Automatically computed minimum height needed to contain all children.

New in version 1.0.8.

minimum_height is a *NumericProperty* and defaults to 0. It is read only.

minimum_size

Automatically computed minimum size needed to contain all children.

New in version 1.0.8.

minimum_size is a *ReferenceListProperty* of (*minimum_width*, *minimum_height*) properties. It is read only.

minimum_width

Automatically computed minimum width needed to contain all children.

New in version 1.0.8.

minimum_width is a *NumericProperty* and defaults to 0. It is read only.

orientation

Orientation of the layout.

orientation is an *OptionProperty* and defaults to 'lr-tb'.

Valid orientations are 'lr-tb', 'tb-lr', 'rl-tb', 'tb-rl', 'lr-bt', 'bt-lr', 'rl-bt' and 'bt-rl'.

New in version 2.0.0.

Note: 'lr' means Left to Right. 'rl' means Right to Left. 'tb' means Top to Bottom. 'bt' means Bottom to Top.

padding

Padding between the layout box and its children: [padding_left, padding_top, padding_right, padding_bottom].

padding also accepts a two argument form [padding_horizontal, padding_vertical] and a one argument form [padding].

Changed in version 1.7.0: Replaced NumericProperty with VariableListProperty.

padding is a *VariableListProperty* and defaults to [0, 0, 0, 0].

row_default_height

Default minimum size to use for row.

New in version 1.0.7.

row_default_height is a *NumericProperty* and defaults to 0.

row_force_default

If True, ignore the height and size_hint_y of the child and use the default row height.

New in version 1.0.7.

row_force_default is a *BooleanProperty* and defaults to False.

rows

Number of rows in the grid.

Changed in version 1.0.8: Changed from a NumericProperty to a BoundedNumericProperty.
You can no longer set this to a negative value.

rows is a *NumericProperty* and defaults to None.

rows_minimum

Dict of minimum height for each row. The dictionary keys are the row numbers, e.g. 0, 1, 2...

New in version 1.0.7.

rows_minimum is a *DictProperty* and defaults to {}.

spacing

Spacing between children: [spacing_horizontal, spacing_vertical].

spacing also accepts a one argument form [spacing].

spacing is a *VariableListProperty* and defaults to [0, 0].

exception kivy.uix.gridlayout.GridLayoutException

Bases: Exception

Exception for errors if the grid layout manipulation fails.

45.20 Image

The *Image* widget is used to display an image:

Example in python:

```
wimg = Image(source='mylogo.png')
```

Kv Example:

```
Image:  
    source: 'mylogo.png'  
    size: self.texture_size
```

45.20.1 Asynchronous Loading

To load an image asynchronously (for example from an external webserver), use the [`AsyncImage`](#) subclass:

```
aimg = AsyncImage(source='http://mywebsite.com/logo.png')
```

This can be useful as it prevents your application from waiting until the image is loaded. If you want to display large images or retrieve them from URL's, using [`AsyncImage`](#) will allow these resources to be retrieved on a background thread without blocking your application.

45.20.2 Alignment

By default, the image is centered and fits inside the widget bounding box. If you don't want that, you can set `allow_stretch` to True and `keep_ratio` to False.

You can also inherit from Image and create your own style. For example, if you want your image to be greater than the size of your widget, you could do:

```
class FullImage(Image):
    pass
```

And in your kivy language file:

```
<-FullImage>:
    canvas:
        Color:
            rgb: (1, 1, 1)
        Rectangle:
            texture: self.texture
            size: self.width + 20, self.height + 20
            pos: self.x - 10, self.y - 10
```

class `kivy.uix.image.AsyncImage(**kwargs)`

Bases: [`kivy.uix.image.Image`](#)

Asynchronous Image class. See the module documentation for more information.

Note: The `AsyncImage` is a specialized form of the `Image` class. You may want to refer to the [`loader`](#) documentation and in particular, the [`ProxyImage`](#) for more detail on how to handle events around asynchronous image loading.

Note: `AsyncImage` currently does not support properties `anim_loop` and `mipmap` and setting those properties will have no effect.

remove_from_cache()

Remove image from cache.

New in version 2.0.0.

class `kivy.uix.image.Image(**kwargs)`

Bases: [`kivy.uix.widget.Widget`](#)

Image class, see module documentation for more information.

allow_stretch

If True, the normalized image size will be maximized to fit in the image box. Otherwise, if the box is too tall, the image will not be stretched more than 1:1 pixels.

New in version 1.0.7.

allow_stretch is a *BooleanProperty* and defaults to False.

anim_delay

Delay the animation if the image is sequenced (like an animated gif). If anim_delay is set to -1, the animation will be stopped.

New in version 1.0.8.

anim_delay is a *NumericProperty* and defaults to 0.25 (4 FPS).

anim_loop

Number of loops to play then stop animating. 0 means keep animating.

New in version 1.9.0.

anim_loop is a *NumericProperty* and defaults to 0.

color

Image color, in the format (r, g, b, a). This attribute can be used to ‘tint’ an image. Be careful: if the source image is not gray/white, the color will not really work as expected.

New in version 1.0.6.

color is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

image_ratio

Ratio of the image (width / float(height)).

image_ratio is an *AliasProperty* and is read-only.

keep_data

If True, the underlying _coreimage will store the raw image data. This is useful when performing pixel based collision detection.

New in version 1.3.0.

keep_data is a *BooleanProperty* and defaults to False.

keep_ratio

If False along with allow_stretch being True, the normalized image size will be maximized to fit in the image box and ignores the aspect ratio of the image. Otherwise, if the box is too tall, the image will not be stretched more than 1:1 pixels.

New in version 1.0.8.

keep_ratio is a *BooleanProperty* and defaults to True.

mipmap

Indicate if you want OpenGL mipmaping to be applied to the texture. Read *Mipmapping* for more information.

New in version 1.0.7.

mipmap is a *BooleanProperty* and defaults to False.

nocache

If this property is set True, the image will not be added to the internal cache. The cache will simply ignore any calls trying to append the core image.

New in version 1.6.0.

nocache is a *BooleanProperty* and defaults to False.

norm_image_size

Normalized image size within the widget box.

This size will always fit the widget size and will preserve the image ratio.

norm_image_size is an *AliasProperty* and is read-only.

reload()

Reload image from disk. This facilitates re-loading of images from disk in case the image content changes.

New in version 1.3.0.

Usage:

```
im = Image(source = '1.jpg')
# -- do something --
im.reload()
# image will be re-loaded from disk
```

remove_from_cache()

Remove image from cache.

New in version 2.0.0.

source

Filename / source of your image.

source is a *StringProperty* and defaults to None.

texture

Texture object of the image. The texture represents the original, loaded image texture. It is stretched and positioned during rendering according to the *allow_stretch* and *keep_ratio* properties.

Depending of the texture creation, the value will be a *Texture* or a *TextureRegion* object.

texture is an *ObjectProperty* and defaults to None.

texture_size

Texture size of the image. This represents the original, loaded image texture size.

Warning: The texture size is set after the texture property. So if you listen to the change on *texture*, the property *texture_size* will not be up-to-date. Use *self.texture.size* instead.

45.21 Label



The `Label` widget is for rendering text:

```
# hello world text
l = Label(text='Hello world')

# unicode text; can only display glyphs that are available in the font
l = Label(text='Hello world ' + chr(2764))

# multiline text
l = Label(text='Multi\nLine')

# size
l = Label(text='Hello world', font_size='20sp')
```

45.21.1 Sizing and text content

By default, the size of `Label` is not affected by `text` content and the text is not affected by the size. In order to control sizing, you must specify `text_size` to constrain the text and/or bind `size` to `texture_size` to grow with the text.

For example, this label's size will be set to the text content (plus `padding`):

```
Label:
  size: self.texture_size
```

This label's text will wrap at the specified width and be clipped to the height:

```
Label:
  text_size: cm(6), cm(4)
```

Note: The `shorten` and `max_lines` attributes control how overflowing text behaves.

Combine these concepts to create a Label that can grow vertically but wraps the text at a certain width:

```
Label:
  text_size: root.width, None
  size: self.texture_size
```

How to have a custom background color in the label:

```
# Define your background color Template
<BackgroundColor@Widget>
    background_color: 1, 1, 1, 1
    canvas.before:
        Color:
            rgba: root.background_color
        Rectangle:
            size: self.size
            pos: self.pos
# Now you can simply Mix the `BackgroundColor` class with almost
# any other widget... to give it a background.
<BackgroundLabel@Label+BackgroundColor>
    background_color: 0, 0, 0, 0
    # Default the background color for this label
    # to r 0, g 0, b 0, a 0
# Use the BackgroundLabel any where in your kv code like below
BackgroundLabel
    text: 'Hello'
    background_color: 1, 0, 0, 1
```

45.21.2 Text alignment and wrapping

The `Label` has `halign` and `valign` properties to control the alignment of its text. However, by default the text image (`texture`) is only just large enough to contain the characters and is positioned in the center of the Label. The `valign` property will have no effect and `halign` will only have an effect if your text has newlines; a single line of text will appear to be centered even though `halign` is set to left (by default).

In order for the alignment properties to take effect, set the `text_size`, which specifies the size of the bounding box within which text is aligned. For instance, the following code binds this size to the size of the Label, so text will be aligned within the widget bounds. This will also automatically wrap the text of the Label to remain within this area.

```
Label:
    text_size: self.size
    halign: 'right'
    valign: 'middle'
```

45.21.3 Markup text

New in version 1.1.0.

You can change the style of the text using `Text Markup`. The syntax is similar to the bbcode syntax but only the inline styling is allowed:

```
# hello world with world in bold
l = Label(text='Hello [b]World[/b]', markup=True)

# hello in red, world in blue
l = Label(text='[color=ff3333]Hello[/color][color=3333ff]World[/color]',
          markup = True)
```

If you need to escape the markup from the current text, use `kivy.utils.escape_markup()`:

```
text = 'This is an important message [1]'  
l = Label(text='[b]' + escape_markup(text) + '[/b]', markup=True)
```

The following tags are available:

[b][/b] Activate bold text

[i][/i] Activate italic text

[u][/u] Underlined text

[s][/s] Strikethrough text

[font=<str>][/font] Change the font (note: this refers to a TTF file or registered alias)

[font_context=<str>][/font_context] Change context for the font, use string value “none” for isolated context (this is equivalent to *None*; if you created a font context named ‘*none*’, it cannot be referred to using markup)

[font_family=<str>][/font_family] Font family to request for drawing. This is only valid when using a font context, see [kivy.uix.label.Label](#) for details.

[font_features=<str>][/font_features] OpenType font features, in CSS format, this is passed straight through to Pango. The effects of requesting a feature depends on loaded fonts, library versions, etc. Pango only, requires v1.38 or later.

[size=<integer>][/size] Change the font size

[color=#<color>][/color] Change the text color

[ref=<str>][/ref] Add an interactive zone. The reference + bounding box inside the reference will be available in [Label.refs](#)

[anchor=<str>] Put an anchor in the text. You can get the position of your anchor within the text with [Label.anchors](#)

[sub][/sub] Display the text at a subscript position relative to the text before it.

[sup][/sup] Display the text at a superscript position relative to the text before it.

[text_language=<str>][/text_language] Language of the text, this is an RFC-3066 format language tag (as string), for example “en_US”, “zh_CN”, “fr” or “ja”. This can impact font selection and metrics. Use the string “None” to revert to locale detection. Pango only.

If you want to render the markup text with a [or] or & character, you need to escape them. We created a simple syntax:

```
[ -> &bl;  
] -> &br;  
& -> &amp;
```

Then you can write:

```
"[size=24>Hello &bl;World&br;[/size]"
```

45.21.4 Interactive zone in text

New in version 1.1.0.

You can now have definable “links” using text markup. The idea is to be able to detect when the user clicks on part of the text and to react. The tag [ref=xxx] is used for that.

In this example, we are creating a reference on the word “World”. When this word is clicked, the function print_it will be called with the name of the reference:

```
def print_it(instance, value):
    print('User clicked on', value)
widget = Label(text='Hello [ref=world]World[/ref]', markup=True)
widget.bind(on_ref_press=print_it)
```

For prettier rendering, you could add a color for the reference. Replace the text= in the previous example with:

```
'Hello [ref=world][color=0000ff]World[/color][/ref]'
```

45.21.5 Catering for Unicode languages

The font kivy uses does not contain all the characters required for displaying all languages. When you use the built-in widgets, this results in a block being drawn where you expect a character.

If you want to display such characters, you can chose a font that supports them and deploy it universally via kv:

```
<Label>:
    font_name: '/<path>/<to>/<font>'
```

Note that this needs to be done before your widgets are loaded as kv rules are only applied at load time.

45.21.6 Usage example

The following example marks the anchors and references contained in a label:

```
from kivy.app import App
from kivy.uix.label import Label
from kivy.clock import Clock
from kivy.graphics import Color, Rectangle

class TestApp(App):

    @staticmethod
    def get_x(label, ref_x):
        """ Return the x value of the ref/anchor relative to the canvas """
        return label.center_x - label.texture_size[0] * 0.5 + ref_x

    @staticmethod
    def get_y(label, ref_y):
        """ Return the y value of the ref/anchor relative to the canvas """
        # Note the inversion of direction, as y values start at the top of
        # the texture and increase downwards
```

(continues on next page)

(continued from previous page)

```
    return label.center_y + label.texture_size[1] * 0.5 - ref_y

def show_marks(self, label):
    # Indicate the position of the anchors with a red top marker
    for name, anc in label.anchors.items():
        with label.canvas:
            Color(1, 0, 0)
            Rectangle(pos=(self.get_x(label, anc[0]),
                           self.get_y(label, anc[1])),
                      size=(3, 3))

    # Draw a green surround around the refs. Note the sizes y inversion
    for name, boxes in label.refs.items():
        for box in boxes:
            with label.canvas:
                Color(0, 1, 0, 0.25)
                Rectangle(pos=(self.get_x(label, box[0]),
                               self.get_y(label, box[1])),
                          size=(box[2] - box[0],
                                box[1] - box[3]))

def build(self):
    label = Label(
        text='[anchor=a]a\nChars [anchor=b]b\n[ref=myref]ref[/ref]',
        markup=True)
    Clock.schedule_once(lambda dt: self.show_marks(label), 1)
    return label

TestApp().run()
```

class kivy.uix.label.Label(kwargs)**
Bases: *kivy.uix.widget.Widget*

Label class, see module documentation for more information.

Events

on_ref_press Fired when the user clicks on a word referenced with a [ref] tag in a text markup.

anchors

New in version 1.1.0.

Position of all the [anchor=xxx] markup in the text. These coordinates are relative to the top left corner of the text, with the y value increasing downwards. Anchors names should be unique and only the first occurrence of any duplicate anchors will be recorded.

You can place anchors in your markup text as follows:

```
text = """
    [anchor=title1][size=24]This is my Big title.[/size]
    [anchor=content]Hello world
"""
```

Then, all the [anchor=] references will be removed and you'll get all the anchor positions in this property (only after rendering):

```
>>> widget = Label(text=text, markup=True)
>>> widget.texture_update()
>>> widget.anchors
{ "content": (20, 32), "title1": (20, 16)}
```

Note: This works only with markup text. You need `markup` set to True.

base_direction

Base direction of text, this impacts horizontal alignment when `halign` is `auto` (the default). Available options are: `None`, `"ltr"` (left to right), `"rtl"` (right to left) plus `"weak_ltr"` and `"weak_rtl"`.

Note: This feature requires the Pango text provider.

Note: Weak modes are currently not implemented in Kivy text layout, and have the same effect as setting strong mode.

New in version 1.11.0.

`base_direction` is an *OptionProperty* and defaults to `None` (autodetect RTL if possible, otherwise LTR).

bold

Indicates use of the bold version of your font.

Note: Depending of your font, the bold attribute may have no impact on your text rendering.

`bold` is a *BooleanProperty* and defaults to False.

color

Text color, in the format `(r, g, b, a)`.

`color` is a *ColorProperty* and defaults to `[1, 1, 1, 1]`.

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

disabled_color

The color of the text when the widget is disabled, in the `(r, g, b, a)` format.

New in version 1.8.0.

`disabled_color` is a *ColorProperty* and defaults to `[1, 1, 1, .3]`.

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

disabled_outline_color

The color of the text outline when the widget is disabled, in the `(r, g, b)` format.

Note: This feature requires the SDL2 text provider.

New in version 1.10.0.

`disabled_outline_color` is a *ColorProperty* and defaults to `[0, 0, 0]`.

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*. Alpha component is ignored and assigning value to it has no effect.

ellipsis_options

Font options for the ellipsis string('...') used to split the text.

Accepts a dict as option name with the value. Only applied when *markup* is true and text is shortened. All font options which work for *Label* will work for *ellipsis_options*. Defaults for the options not specified are taken from the surrounding text.

Label:

```
text: 'Some very long line which will be cut'  
markup: True  
shorten: True  
ellipsis_options: {'color':(1,0.5,0.5,1), 'underline':True}
```

New in version 2.0.0.

ellipsis_options is a *DictProperty* and defaults to {} (the empty dict).

font_blended

Whether blended or solid font rendering should be used.

Note: This feature requires the SDL2 text provider.

New in version 1.10.0.

font_blended is a *BooleanProperty* and defaults to True.

font_context

Font context. *None* means the font is used in isolation, so you are guaranteed to be drawing with the TTF file resolved by *font_name*. Specifying a value here will load the font file into a named context, enabling fallback between all fonts in the same context. If a font context is set, you are not guaranteed that rendering will actually use the specified TTF file for all glyphs (Pango will pick the one it thinks is best).

If Kivy is linked against a system-wide installation of FontConfig, you can load the system fonts by specifying a font context starting with the special string *system://*. This will load the system fontconfig configuration, and add your application-specific fonts on top of it (this imposes a significant risk of family name collision, Pango may not use your custom font file, but pick one from the system)

Note: This feature requires the Pango text provider.

New in version 1.11.0.

font_context is a *StringProperty* and defaults to None.

font_family

Font family, this is only applicable when using *font_context* option. The specified font family will be requested, but note that it may not be available, or there could be multiple fonts registered with the same family. The value can be a family name (string) available in the font context (for example a system font in a *system://* context, or a custom font file added using `kivy.core.text.FontContextManager`). If set to *None*, font selection is controlled by the *font_name* setting.

Note: If using *font_name* to reference a custom font file, you should leave this as *None*.

The family name is managed automatically in this case.

Note: This feature requires the Pango text provider.

New in version 1.11.0.

font_family is a *StringProperty* and defaults to None.

font_features

OpenType font features, in CSS format, this is passed straight through to Pango. The effects of requesting a feature depends on loaded fonts, library versions, etc. For a complete list of features, see:

https://en.wikipedia.org/wiki/List_of_typographic_features

Note: This feature requires the Pango text provider, and Pango library v1.38 or later.

New in version 1.11.0.

font_features is a *StringProperty* and defaults to an empty string.

font_hinting

What hinting option to use for font rendering. Can be one of ‘normal’, ‘light’, ‘mono’ or None.

Note: This feature requires SDL2 or Pango text provider.

New in version 1.10.0.

font_hinting is an *OptionProperty* and defaults to ‘normal’.

font_kerning

Whether kerning is enabled for font rendering. You should normally only disable this if rendering is broken with a particular font file.

Note: This feature requires the SDL2 text provider.

New in version 1.10.0.

font_kerning is a *BooleanProperty* and defaults to True.

font_name

Filename of the font to use. The path can be absolute or relative. Relative paths are resolved by the *resource_find()* function.

Warning: Depending of your text provider, the font file can be ignored. However, you can mostly use this without problems.

If the font used lacks the glyphs for the particular language/symbols you are using, you will see ‘[]’ blank box characters instead of the actual glyphs. The solution is to use a font that has the glyphs you need to display. For example, to display ດ, use a font such as freesans.ttf that has the glyph.

font_name is a *StringProperty* and defaults to ‘Roboto’. This value is taken from *Config*.

font_size

Font size of the text, in pixels.

font_size is a *NumericProperty* and defaults to 15sp.

halign

Horizontal alignment of the text.

halign is an *OptionProperty* and defaults to ‘auto’. Available options are : auto, left, center, right and justify. Auto will attempt to autodetect horizontal alignment for RTL text (Pango only), otherwise it behaves like *left*.

Warning: This doesn't change the position of the text texture of the Label (centered), only the position of the text in this texture. You probably want to bind the size of the Label to the *texture_size* or set a *text_size*.

Changed in version 1.10.1: Added *auto* option

Changed in version 1.6.0: A new option was added to *halign*, namely *justify*.

is_shortened

This property indicates if *text* was rendered with or without shortening when *shorten* is True.

New in version 1.10.0.

is_shortened is a *BooleanProperty* and defaults to False.

italic

Indicates use of the italic version of your font.

Note: Depending of your font, the italic attribute may have no impact on your text rendering.

italic is a *BooleanProperty* and defaults to False.

line_height

Line Height for the text. e.g. *line_height* = 2 will cause the spacing between lines to be twice the size.

line_height is a *NumericProperty* and defaults to 1.0.

New in version 1.5.0.

markup

New in version 1.1.0.

If True, the text will be rendered using the *MarkupLabel*: you can change the style of the text using tags. Check the *Text Markup* documentation for more information.

markup is a *BooleanProperty* and defaults to False.

max_lines

Maximum number of lines to use, defaults to 0, which means unlimited. Please note that *shorten* take over this property. (with shorten, the text is always one line.)

New in version 1.8.0.

max_lines is a *NumericProperty* and defaults to 0.

mipmap

Indicates whether OpenGL mipmaping is applied to the texture or not. Read *Mipmapping* for more information.

New in version 1.0.7.

mipmap is a *BooleanProperty* and defaults to False.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: *MotionEvent* class Touch received. The touch is in parent coordinates.
See *relativelayout* for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

outline_color

The color of the text outline, in the (r, g, b) format.

Note: This feature requires the SDL2 text provider.

New in version 1.10.0.

outline_color is a *ColorProperty* and defaults to [0, 0, 0, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*. Alpha component is ignored and assigning value to it has no effect.

outline_width

Width in pixels for the outline around the text. No outline will be rendered if the value is None.

Note: This feature requires the SDL2 text provider.

New in version 1.10.0.

outline_width is a *NumericProperty* and defaults to None.

padding

Padding of the text in the format (*padding_x*, *padding_y*)

padding is a *ReferenceListProperty* of (*padding_x*, *padding_y*) properties.

padding_x

Horizontal padding of the text inside the widget box.

padding_x is a *NumericProperty* and defaults to 0.

Changed in version 1.9.0: *padding_x* has been fixed to work as expected. In the past, the text was padded by the negative of its values.

padding_y

Vertical padding of the text inside the widget box.

padding_y is a *NumericProperty* and defaults to 0.

Changed in version 1.9.0: *padding_y* has been fixed to work as expected. In the past, the text was padded by the negative of its values.

refs

New in version 1.1.0.

List of [*ref=xxx*] markup items in the text with the bounding box of all the words contained in a ref, available only after rendering.

For example, if you wrote:

```
Check out my [ref=hello]link[/ref]
```

The refs will be set with:

```
{'hello': ((64, 0, 78, 16), )}
```

The references marked “hello” have a bounding box at (x1, y1, x2, y2). These coordinates are relative to the top left corner of the text, with the y value increasing downwards. You can define multiple refs with the same name: each occurrence will be added as another (x1, y1, x2, y2) tuple to this list.

The current Label implementation uses these references if they exist in your markup text, automatically doing the collision with the touch and dispatching an *on_ref_press* event.

You can bind a ref event like this:

```
def print_it(instance, value):
    print('User click on', value)
widget = Label(text='Hello [ref=world]World[/ref]', markup=True)
widget.bind(on_ref_press=print_it)
```

Note: This works only with markup text. You need *markup* set to True.

shorten

Indicates whether the label should attempt to shorten its textual contents as much as possible if a *text_size* is given. Setting this to True without an appropriately set *text_size* will lead to unexpected results.

shorten_from and *split_str* control the direction from which the *text* is split, as well as where in the *text* we are allowed to split.

shorten is a *BooleanProperty* and defaults to False.

shorten_from

The side from which we should shorten the text from, can be left, right, or center.

For example, if left, the ellipsis will appear towards the left side and we will display as much text starting from the right as possible. Similar to *shorten*, this option only applies when *text_size* [0] is not None, In this case, the string is shortened to fit within the specified width.

New in version 1.9.0.

shorten_from is a *OptionProperty* and defaults to *center*.

split_str

The string used to split the *text* while shortening the string when *shorten* is True.

For example, if it’s a space, the string will be broken into words and as many whole words that can fit into a single line will be displayed. If *split_str* is the empty string, “”, we split on every character fitting as much text as possible into the line.

New in version 1.9.0.

split_str is a *StringProperty* and defaults to “” (the empty string).

strikethrough

Adds a strikethrough line to the text.

Note: This feature requires the SDL2 text provider.

New in version 1.10.0.

strikethrough is a *BooleanProperty* and defaults to False.

strip

Whether leading and trailing spaces and newlines should be stripped from each displayed line. If True, every line will start at the right or left edge, depending on *halign*. If *halign* is *justify* it is implicitly True.

New in version 1.9.0.

strip is a *BooleanProperty* and defaults to False.

text

Text of the label.

Creation of a simple hello world:

```
widget = Label(text='Hello world')
```

text is a *StringProperty* and defaults to ''.

text_language

Language of the text, if None Pango will determine it from locale. This is an RFC-3066 format language tag (as a string), for example “en_US”, “zh_CN”, “fr” or “ja”. This can impact font selection, metrics and rendering. For example, the same bytes of text can look different for *ur* and *ar* languages, though both use Arabic script.

Note: This feature requires the Pango text provider.

New in version 1.11.0.

text_language is a *StringProperty* and defaults to None.

text_size

By default, the label is not constrained to any bounding box. You can set the size constraint of the label with this property. The text will autowrap into the constraints. So although the font size will not be reduced, the text will be arranged to fit into the box as best as possible, with any text still outside the box clipped.

This sets and clips *texture_size* to *text_size* if not None.

New in version 1.0.4.

For example, whatever your current widget size is, if you want the label to be created in a box with width=200 and unlimited height:

```
Label(text='Very big big line', text_size=(200, None))
```

Note: This *text_size* property is the same as the *usersize* property in the *Label* class. (It is named *size=* in the constructor.)

text_size is a *ListProperty* and defaults to (None, None), meaning no size restriction by default.

texture

Texture object of the text. The text is rendered automatically when a property changes. The OpenGL texture created in this operation is stored in this property. You can use this **texture** for any graphics elements.

Depending on the texture creation, the value will be a **Texture** or **TextureRegion** object.

Warning: The **texture** update is scheduled for the next frame. If you need the texture immediately after changing a property, you have to call the **texture_update()** method before accessing **texture**:

```
l = Label(text='Hello world')
# l.texture is good
l.font_size = '50sp'
# l.texture is not updated yet
l.texture_update()
# l.texture is good now.
```

texture is an **ObjectProperty** and defaults to None.

texture_size

Texture size of the text. The size is determined by the font size and text. If **text_size** is [None, None], the texture will be the size required to fit the text, otherwise it's clipped to fit **text_size**.

When **text_size** is [None, None], one can bind to **texture_size** and rescale it proportionally to fit the size of the label in order to make the text fit maximally in the label.

Warning: The **texture_size** is set after the **texture** property. If you listen for changes to **texture**, **texture_size** will not be up-to-date in your callback. Bind to **texture_size** instead.

texture_update(*args)

Force texture recreation with the current Label properties.

After this function call, the **texture** and **texture_size** will be updated in this order.

underline

Adds an underline to the text.

Note: This feature requires the SDL2 text provider.

New in version 1.10.0.

underline is a **BooleanProperty** and defaults to False.

unicode_errors

How to handle unicode decode errors. Can be 'strict', 'replace' or 'ignore'.

New in version 1.9.0.

unicode_errors is an **OptionProperty** and defaults to 'replace'.

valign

Vertical alignment of the text.

valign is an **OptionProperty** and defaults to 'bottom'. Available options are : 'bottom', 'middle' (or 'center') and 'top'.

Changed in version 1.10.0: The ‘center’ option has been added as an alias of ‘middle’.

Warning: This doesn’t change the position of the text texture of the Label (centered), only the position of the text within this texture. You probably want to bind the size of the Label to the `texture_size` or set a `text_size` to change this behavior.

45.22 Layout

Layouts are used to calculate and assign widget positions.

The `Layout` class itself cannot be used directly. You should use one of the following layout classes:

- Anchor layout: `kivy.uix.anchorlayout.AnchorLayout`
- Box layout: `kivy.uix.boxlayout.BoxLayout`
- Float layout: `kivy.uix.floatlayout.FloatLayout`
- Grid layout: `kivy.uix.gridlayout.GridLayout`
- Page Layout: `kivy.uix.pagelayout.PageLayout`
- Relative layout: `kivy.uix.relativelayout.RelativeLayout`
- Scatter layout: `kivy.uix.scatterlayout.ScatterLayout`
- Stack layout: `kivy.uix.stacklayout.StackLayout`

45.22.1 Understanding the `size_hint` Property in `Widget`

The `size_hint` is a tuple of values used by layouts to manage the sizes of their children. It indicates the size relative to the layout’s size instead of an absolute size (in pixels/points/cm/etc). The format is:

```
widget.size_hint = (width_proportion, height_proportion)
```

The proportions are specified as floating point numbers in the range 0-1. For example, 0.5 represents 50%, 1 represents 100%.

If you want a widget’s width to be half of the parent’s width and the height to be identical to the parent’s height, you would do:

```
widget.size_hint = (0.5, 1.0)
```

If you don’t want to use a `size_hint` for either the width or height, set the value to None. For example, to make a widget that is 250px wide and 30% of the parent’s height, do:

```
widget.size_hint = (None, 0.3)
widget.width = 250
```

Being *Kivy properties*, these can also be set via constructor arguments:

```
widget = Widget(size_hint=(None, 0.3), width=250)
```

Changed in version 1.4.1: The `reposition_child` internal method (made public by mistake) has been removed.

```
class kivy.uix.layout.Layout(**kwargs)
Bases: kivy.uix.widget.Widget
```

Layout interface class, used to implement every layout. See module documentation for more information.

```
add_widget(widget, *args, **kwargs)
```

Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

```
do_layout(*args)
```

This function is called when a layout is called by a trigger. If you are writing a new Layout subclass, don't call this function directly but use `_trigger_layout()` instead.

The function is by default called *before* the next frame, therefore the layout isn't updated immediately. Anything depending on the positions of e.g. children should be scheduled for the next frame.

New in version 1.0.8.

```
layout_hint_with_bounds(sh_sum, available_space, min_bounded_size, sh_min_vals,
sh_max_vals, hint)
```

(internal) Computes the appropriate (size) hint for all the widgets given (potential) min or max bounds on the widgets' size. The `hint` list is updated with appropriate sizes.

It walks through the hints and for any widgets whose hint will result in violating min or max constraints, it fixes the hint. Any remaining or missing space after all the widgets are fixed get distributed to the widgets making them smaller or larger according to their size hint.

This algorithm knows nothing about the widgets other than what is passed through the input params, so it's fairly generic for laying things out according to constraints using size hints.

Parameters

sh_sum: float The sum of the size hints (basically `sum(size_hint)`).

available_space: float The amount of pixels available for all the widgets whose size hint is not None. Cannot be zero.

min_bounded_size: float The minimum amount of space required according to the `size_hint_min` of the widgets (basically `sum(size_hint_min)`).

sh_min_vals: list or iterable Items in the iterable are the `size_hint_min` for each widget. Can be None. The length should be the same as `hint`

sh_max_vals: list or iterable Items in the iterable are the `size_hint_max` for each widget. Can be None. The length should be the same as `hint`

hint: list A list whose size is the same as the length of `sh_min_vals` and `sh_max_vals` whose each element is the corresponding size hint value of that element. This list is updated in place with correct size hints that ensure the constraints are not violated.

Returns Nothing. `hint` is updated in place.

remove_widget(widget, *args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: Widget Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

45.23 ModalView

New in version 1.4.0.

The `ModalView` widget is used to create modal views. By default, the view will cover the whole “main” window.

Remember that the default size of a Widget is `size_hint=(1, 1)`. If you don’t want your view to be fullscreen, either use size hints with values lower than 1 (for instance `size_hint=(.8, .8)`) or deactivate the `size_hint` and use fixed size attributes.

45.23.1 Examples

Example of a simple 400x400 Hello world view:

```
view = ModalView(size_hint=(None, None), size=(400, 400))
view.add_widget(Label(text='Hello world'))
```

By default, any click outside the view will dismiss it. If you don’t want that, you can set `ModalView.auto_dismiss` to False:

```
view = ModalView(auto_dismiss=False)
view.add_widget(Label(text='Hello world'))
view.open()
```

To manually dismiss/close the view, use the `ModalView.dismiss()` method of the `ModalView` instance:

```
view.dismiss()
```

Both `ModalView.open()` and `ModalView.dismiss()` are bindable. That means you can directly bind the function to an action, e.g. to a button's `on_press`

```
# create content and add it to the view
content = Button(text='Close me!')
view = ModalView(auto_dismiss=False)
view.add_widget(content)

# bind the on_press event of the button to the dismiss function
content.bind(on_press=view.dismiss)

# open the view
view.open()
```

45.23.2 ModalView Events

There are four events available: `on_pre_open` and `on_open` which are raised when the view is opening; `on_pre_dismiss` and `on_dismiss` which are raised when the view is closed.

For `on_dismiss`, you can prevent the view from closing by explicitly returning `True` from your callback:

```
def my_callback(instance):
    print('ModalView', instance, 'is being dismissed, but is prevented!')
    return True
view = ModalView()
view.add_widget(Label(text='Hello world'))
view.bind(on_dismiss=my_callback)
view.open()
```

Changed in version 1.5.0: The `ModalView` can be closed by hitting the escape key on the keyboard if the `ModalView.auto_dismiss` property is `True` (the default).

`class kivy.uix.modalview.ModalView(**kwargs)`
Bases: `kivy.uix.anchorlayout.AnchorLayout`

`ModalView` class. See module documentation for more information.

Events

`on_pre_open`: Fired before the `ModalView` is opened. When this event is fired `ModalView` is not yet added to window.

`on_open`: Fired when the `ModalView` is opened.

`on_pre_dismiss`: Fired before the `ModalView` is closed.

`on_dismiss`: Fired when the `ModalView` is closed. If the callback returns `True`, the dismiss will be canceled.

Changed in version 1.11.0: Added events `on_pre_open` and `on_pre_dismiss`.

Changed in version 2.0.0: Added property 'overlay_color'.

Changed in version 2.1.0: Marked `attach_to` property as deprecated.

attach_to

If a widget is set on `attach_to`, the view will attach to the nearest parent window of the widget. If none is found, it will attach to the main/global Window.

`attach_to` is an *ObjectProperty* and defaults to None.

auto_dismiss

This property determines if the view is automatically dismissed when the user clicks outside it.

`auto_dismiss` is a *BooleanProperty* and defaults to True.

background

Background image of the view used for the view background.

`background` is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/modalview-background’.

background_color

Background color, in the format (r, g, b, a).

This acts as a *multiplier* to the texture colour. The default texture is grey, so just setting the background color will give a darker result. To set a plain color, set the `background_normal` to ''.

The `background_color` is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed behavior to affect the background of the widget itself, not the overlay dimming. Changed from *ListProperty* to *ColorProperty*.

border

Border used for *BorderImage* graphics instruction. Used for the `background_normal` and the `background_down` properties. Can be used when using custom backgrounds.

It must be a list of four values: (bottom, right, top, left). Read the *BorderImage* instructions for more information about how to use it.

`border` is a *ListProperty* and defaults to (16, 16, 16, 16).

dismiss(*args, **kwargs)

Close the view if it is open.

If you really want to close the view, whatever the `on_dismiss` event returns, you can use the `force` keyword argument:

```
view = ModalView()  
view.dismiss(force=True)
```

When the view is dismissed, it will be faded out before being removed from the parent. If you don't want this animation, use:

```
view.dismiss(animation=False)
```

on_anim_alpha(_instance, value)

animation progress callback.

on_dismiss()

default dismiss event handler.

on_motion(etype, me)

Called when a motion event is received.

Parameters

`etype: str` Event type, one of “begin”, “update” or “end”

`me: MotionEvent` Received motion event

Returns `bool` True to stop event dispatching

New in version 2.1.0.

Warning: This is an experimental method and it remains so while this warning is present.

on_open()
default open event handler.

on_pre_dismiss()
default pre-dismiss event handler.

on_pre_open()
default pre-open event handler.

on_touch_down(touch)
touch down event handler.

on_touch_move(touch)
touch moved event handler.

on_touch_up(touch)
touch up event handler.

open(*args, **kwargs)
Display the modal in the Window.

When the view is opened, it will be faded in with an animation. If you don't want the animation, use:

```
view.open(animation=False)
```

overlay_color

Overlay color in the format (r, g, b, a). Used for dimming the window behind the modal view.

overlay_color is a *ColorProperty* and defaults to [0, 0, 0, .7].

New in version 2.0.0.

45.24 PageLayout

The *PageLayout* class is used to create a simple multi-page layout, in a way that allows easy flipping from one page to another using borders.

PageLayout does not currently honor the *size_hint*, *size_hint_min*, *size_hint_max*, or *pos_hint* properties.

New in version 1.8.0.

Example:

```
PageLayout:  
    Button:  
        text: 'page1'  
    Button:  
        text: 'page2'  
    Button:  
        text: 'page3'
```

Transitions from one page to the next are made by swiping in from the border areas on the right or left hand side. If you wish to display multiple widgets in a page, we suggest you use a containing layout. Ideally, each page should consist of a single `layout` widget that contains the remaining widgets on that page.

```
class kivy.uix.pagelayout.PageLayout(**kwargs)
    Bases: kivy.uix.layout.Layout
```

PageLayout class. See module documentation for more information.

anim_kwarg

The animation kwargs used to construct the animation

`anim_kwarg` is a `DictProperty` and defaults to `{'d': .5, 't': 'in_quad'}`.

New in version 1.11.0.

border

The width of the border around the current page used to display the previous/next page swipe areas when needed.

`border` is a `NumericProperty` and defaults to `50dp`.

do_layout(*args)

This function is called when a layout is called by a trigger. If you are writing a new Layout subclass, don't call this function directly but use `_trigger_layout()` instead.

The function is by default called *before* the next frame, therefore the layout isn't updated immediately. Anything depending on the positions of e.g. children should be scheduled for the next frame.

New in version 1.0.8.

on_touch_down(touch)

Receive a touch down event.

Parameters

`touch: MotionEvent class` Touch received. The touch is in parent coordinates.
See `relativelayout` for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See `on_touch_down()` for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See `on_touch_down()` for more information.

page

The currently displayed page.

`page` is a `NumericProperty` and defaults to `0`.

swipe_threshold

The threshold used to trigger swipes as ratio of the widget size.

`swipe_threshold` is a `NumericProperty` and defaults to `.5`.

45.25 Popup

New in version 1.0.7.



The `Popup` widget is used to create modal popups. By default, the popup will cover the whole “parent” window. When you are creating a popup, you must at least set a `Popup.title` and `Popup.content`.

Remember that the default size of a Widget is `size_hint=(1, 1)`. If you don’t want your popup to be fullscreen, either use size hints with values less than 1 (for instance `size_hint=(.8, .8)`) or deactivate the `size_hint` and use fixed size attributes.

Changed in version 1.4.0: The `Popup` class now inherits from `ModalView`. The `Popup` offers a default layout with a title and a separation bar.

45.25.1 Examples

Example of a simple 400x400 Hello world popup:

```
popup = Popup(title='Test popup',
              content=Label(text='Hello world'),
              size_hint=(None, None), size=(400, 400))
```

By default, any click outside the popup will dismiss/close it. If you don’t want that, you can set `auto_dismiss` to False:

```
popup = Popup(title='Test popup', content=Label(text='Hello world'),
              auto_dismiss=False)
popup.open()
```

To manually dismiss/close the popup, use `dismiss`:

```
popup.dismiss()
```

Both `open()` and `dismiss()` are bindable. That means you can directly bind the function to an action, e.g. to a button’s `on_press`:

```

# create content and add to the popup
content = Button(text='Close me!')
popup = Popup(content=content, auto_dismiss=False)

# bind the on_press event of the button to the dismiss function
content.bind(on_press=popup.dismiss)

# open the popup
popup.open()

```

Same thing in KV language only with Factory:

```

#:import Factory kivy.factory.Factory
<MyPopup@Popup>:
    auto_dismiss: False
    Button:
        text: 'Close me!'
        on_release: root.dismiss()

    Button:
        text: 'Open popup'
        on_release: Factory.MyPopup().open()

```

Note: Popup is a special widget. Don't try to add it as a child to any other widget. If you do, Popup will be handled like an ordinary widget and won't be created hidden in the background.

BoxLayout:
MyPopup: # bad!

45.25.2 Popup Events

There are two events available: *on_open* which is raised when the popup is opening, and *on_dismiss* which is raised when the popup is closed. For *on_dismiss*, you can prevent the popup from closing by explicitly returning True from your callback:

```

def my_callback(instance):
    print('Popup', instance, 'is being dismissed but is prevented!')
    return True
popup = Popup(content=Label(text='Hello world'))
popup.bind(on_dismiss=my_callback)
popup.open()

```

```

class kivy.uix.popup.Popup(**kwargs)
Bases: kivy.uix.modalview.ModalView

```

Popup class. See module documentation for more information.

Events

on_open: Fired when the Popup is opened.

on_dismiss: Fired when the Popup is closed. If the callback returns True, the dismiss will be canceled.

`add_widget(widget, *args, **kwargs)`

Add a new widget as a child of this widget.

Parameters

`widget: Widget` Widget to add to our list of children.

`index: int, defaults to 0` Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

`canvas: str, defaults to None` Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

`content`

Content of the popup that is displayed just under the title.

`content` is an [ObjectProperty](#) and defaults to None.

`on_touch_down(touch)`

touch down event handler.

`separator_color`

Color used by the separator between title and content.

New in version 1.1.0.

`separator_color` is a [ColorProperty](#) and defaults to [47 / 255., 167 / 255., 212 / 255., 1.].

Changed in version 2.0.0: Changed from [ListProperty](#) to [ColorProperty](#).

`separator_height`

Height of the separator.

New in version 1.1.0.

`separator_height` is a [NumericProperty](#) and defaults to 2dp.

`title`

String that represents the title of the popup.

`title` is a [StringProperty](#) and defaults to 'No title'.

`title_align`

Horizontal alignment of the title.

New in version 1.9.0.

`title_align` is a [OptionProperty](#) and defaults to 'left'. Available options are left, center, right and justify.

title_color

Color used by the Title.

New in version 1.8.0.

title_color is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

title_font

Font used to render the title text.

New in version 1.9.0.

title_font is a *StringProperty* and defaults to 'Roboto'. This value is taken from *Config*.

title_size

Represents the font size of the popup title.

New in version 1.6.0.

title_size is a *NumericProperty* and defaults to '14sp'.

exception kivy.uix.popup.PopupException

Bases: *Exception*

Popup exception, fired when multiple content widgets are added to the popup.

New in version 1.4.0.

45.26 Progress Bar

New in version 1.0.8.



The *ProgressBar* widget is used to visualize the progress of some task. Only the horizontal mode is currently supported: the vertical mode is not yet available.

The progress bar has no interactive elements and is a display-only widget.

To use it, simply assign a value to indicate the current progress:

```
from kivy.uix.progressbar import ProgressBar
pb = ProgressBar(max=1000)

# this will update the graphics automatically (75% done)
pb.value = 750
```

class kivy.uix.progressbar.ProgressBar(kwargs)**

Bases: *kivy.uix.widget.Widget*

Class for creating a progress bar widget.

See module documentation for more details.

max

Maximum value allowed for *value*.

max is a *NumericProperty* and defaults to 100.

value

Current value used for the slider.

`value` is an *AliasProperty* that returns the value of the progress bar. If the value is < 0 or > `max`, it will be normalized to those boundaries.

Changed in version 1.6.0: The value is now limited to between 0 and `max`.

value_normalized

Normalized value inside the range 0-1:

```
>>> pb = ProgressBar(value=50, max=100)
>>> pb.value
50
>>> pb.value_normalized
0.5
```

`value_normalized` is an *AliasProperty*.

45.27 RecycleBoxLayout

New in version 1.10.0.

Warning: This module is highly experimental, its API may change in the future and the documentation is not complete at this time.

The RecycleBoxLayout is designed to provide a *BoxLayout* type layout when used with the *RecycleView* widget. Please refer to the *recycleview* module documentation for more information.

```
class kivy.uix.recycleboxlayout.RecycleBoxLayout(**kwargs)
    Bases: kivy.uix.recyclelayout.RecycleLayout, kivy.uix.boxlayout.BoxLayout
    compute_visible_views(data, viewport)
        viewport is in coordinates of the layout manager.
    get_view_index_at(pos)
        Return the view index on which position, pos, falls.
        pos is in coordinates of the layout manager.
```

45.28 RecycleGridLayout

New in version 1.10.0.

Warning: This module is highly experimental, its API may change in the future and the documentation is not complete at this time.

The RecycleGridLayout is designed to provide a *GridLayout* type layout when used with the *RecycleView* widget. Please refer to the *recycleview* module documentation for more information.

```

class kivy.uix.recyclegridlayout.RecycleGridLayout(**kwargs)
    Bases: kivy.uix.recyclelayout.RecycleLayout, kivy.uix.gridlayout.GridLayout

compute_visible_views(data, viewport)
    viewport is in coordinates of the layout manager.

get_view_index_at(pos)
    Return the view index on which position, pos, falls.
    pos is in coordinates of the layout manager.

```

45.29 RecycleLayout

New in version 1.10.0.

Warning: This module is highly experimental, its API may change in the future and the documentation is not complete at this time.

```

class kivy.uix.recyclelayout.RecycleLayout(**kwargs)
    Bases: kivy.uix.recycleview.layout.RecycleLayoutManagerBehavior, kivy.uix.layout.Layout

RecycleLayout provides the default layout for RecycleViews.

default_height
    Default height for items
    default_height is a NumericProperty and default to 100.

default_pos_hint
    Default pos_hint value for items
    default_pos_hint is a DictProperty and defaults to {}.

default_size
    size (width, height). Each value can be None.
    default_size is an ReferenceListProperty to [default_width, default_height].

default_size_hint
    size (width, height). Each value can be None.
    default_size_hint is an ReferenceListProperty to [default_size_hint_x, default_size_hint_y].

default_size_hint_max
    Default value for size_hint_max of items
    default_size_max is a ReferenceListProperty to [default_size_hint_x_max, default_size_hint_y_max].

default_size_hint_min
    Default value for size_hint_min of items
    default_size_min is a ReferenceListProperty to [default_size_hint_x_min, default_size_hint_y_min].

default_size_hint_x
    Default size_hint_x for items

```

default_size_hint_x is a *NumericProperty* and default to None.

default_size_hint_x_max

Default value for size_hint_x_max of items

default_pos_hint_x_max is a *NumericProperty* and defaults to None.

default_size_hint_x_min

Default value for size_hint_x_min of items

default_pos_hint_x_min is a *NumericProperty* and defaults to None.

default_size_hint_y

Default size_hint_y for items

default_size_hint_y is a *NumericProperty* and default to None.

default_size_hint_y_max

Default value for size_hint_y_max of items

default_pos_hint_y_max is a *NumericProperty* and defaults to None.

default_size_hint_y_min

Default value for size_hint_y_min of items

default_pos_hint_y_min is a *NumericProperty* and defaults to None.

default_width

Default width for items

default_width is a *NumericProperty* and default to 100

do_layout(*args)

This function is called when a layout is called by a trigger. If you are writing a new Layout subclass, don't call this function directly but use *_trigger_layout()* instead.

The function is by default called *before* the next frame, therefore the layout isn't updated immediately. Anything depending on the positions of e.g. children should be scheduled for the next frame.

New in version 1.0.8.

initial_height

Initial height for the items.

initial_height is a *NumericProperty* and defaults to 100.

initial_size

Initial size of items

initial_size is a *ReferenceListProperty* to [*initial_width*, *initial_height*].

initial_width

Initial width for the items.

initial_width is a *NumericProperty* and defaults to 100.

key_pos_hint

If set, which key in the dict should be used to set the pos_hint of items.

key_pos_hint is a *StringProperty* and defaults to None.

key_size

If set, which key in the dict should be used to set the size property of the item.

key_size is a *StringProperty* and defaults to None.

key_size_hint

If set, which key in the dict should be used to set the size_hint property of the item.

key_size_hint is a *StringProperty* and defaults to None.

key_size_hint_max

If set, which key in the dict should be used to set the size_hint_max property of the item.

key_size_hint_max is a *StringProperty* and defaults to None.

key_size_hint_min

If set, which key in the dict should be used to set the size_hint_min property of the item.

key_size_hint_min is a *StringProperty* and defaults to None.

refresh_view_layout(index, layout, view, viewport)

See :meth:`~kivy.uix.recycleview.views.RecycleDataAdapter.refresh_view_layout`.

set_visible_views(indices, data, viewport)

viewport is in coordinates of the layout manager.

45.30 Relative Layout

New in version 1.4.0.

This layout allows you to set relative coordinates for children. If you want absolute positioning, use the *FloatLayout*.

The *RelativeLayout* class behaves just like the regular *FloatLayout* except that its child widgets are positioned relative to the layout.

When a widget with position = (0,0) is added to a *RelativeLayout*, the child widget will also move when the position of the *RelativeLayout* is changed. The child widgets coordinates remain (0,0) as they are always relative to the parent layout.

45.30.1 Coordinate Systems

Window coordinates

By default, there's only one coordinate system that defines the position of widgets and touch events dispatched to them: the window coordinate system, which places (0, 0) at the bottom left corner of the window. Although there are other coordinate systems defined, e.g. local and parent coordinates, these coordinate systems are identical to the window coordinate system as long as a relative layout type widget is not in the widget's parent stack. When widget.pos is read or a touch is received, the coordinate values are in parent coordinates. But as mentioned, these are identical to window coordinates, even in complex widget stacks as long as there's no relative layout type widget in the widget's parent stack.

For example:

```
BoxLayout:  
    Label:  
        text: 'Left'  
    Button:  
        text: 'Middle'  
        on_touch_down: print('Middle: {}'.format(args[1].pos))  
BoxLayout:  
    on_touch_down: print('Box: {}'.format(args[1].pos))  
    Button:
```

(continues on next page)

(continued from previous page)

```
text: 'Right'  
on_touch_down: print('Right: {}'.format(args[1].pos))
```

When the middle button is clicked and the touch propagates through the different parent coordinate systems, it prints the following:

```
>>> Box: (430.0, 282.0)  
>>> Right: (430.0, 282.0)  
>>> Middle: (430.0, 282.0)
```

As claimed, the touch has identical coordinates to the window coordinates in every coordinate system. `collide_point()` for example, takes the point in window coordinates.

Parent coordinates

Other `RelativeLayout` type widgets are `Scatter`, `ScatterLayout`, and `ScrollView`. If such a special widget is in the parent stack, only then does the parent and local coordinate system diverge from the window coordinate system. For each such widget in the stack, a coordinate system with (0, 0) of that coordinate system being at the bottom left corner of that widget is created. **Position and touch coordinates received and read by a widget are in the coordinate system of the most recent special widget in its parent stack (not including itself) or in window coordinates if there are none** (as in the first example). We call these coordinates parent coordinates.

For example:

```
BoxLayout:  
    Label:  
        text: 'Left'  
    Button:  
        text: 'Middle'  
        on_touch_down: print('Middle: {}'.format(args[1].pos))  
    RelativeLayout:  
        on_touch_down: print('Relative: {}'.format(args[1].pos))  
    Button:  
        text: 'Right'  
        on_touch_down: print('Right: {}'.format(args[1].pos))
```

Clicking on the middle button prints:

```
>>> Relative: (396.0, 298.0)  
>>> Right: (-137.33, 298.0)  
>>> Middle: (396.0, 298.0)
```

As the touch propagates through the widgets, for each widget, the touch is received in parent coordinates. Because both the relative and middle widgets don't have these special widgets in their parent stack, the touch is the same as window coordinates. Only the right widget, which has a `RelativeLayout` in its parent stack, receives the touch in coordinates relative to that `RelativeLayout` which is different than window coordinates.

Local and Widget coordinates

When expressed in parent coordinates, the position is expressed in the coordinates of the most recent special widget in its parent stack, not including itself. When expressed in local or widget coordinates, the widgets themselves are also included.

Changing the above example to transform the parent coordinates into local coordinates:

```
BoxLayout:  
    Label:  
        text: 'Left'  
    Button:  
        text: 'Middle'  
        on_touch_down: print('Middle: {}'.format(self.to_local(*args[1].  
→pos)))  
    RelativeLayout:  
        on_touch_down: print('Relative: {}'.format(self.to_local(*args[1].  
→pos)))  
        Button:  
            text: 'Right'  
            on_touch_down: print('Right: {}'.format(self.to_local(*args[1].  
→pos)))
```

Now, clicking on the middle button prints:

```
>>> Relative: (-135.33, 301.0)  
>>> Right: (-135.33, 301.0)  
>>> Middle: (398.0, 301.0)
```

This is because now the relative widget also expresses the coordinates relative to itself.

Note: Although all widgets including `RelativeLayout` receive their touch events in `on_touch_xxx` in parent coordinates, these special widgets will transform the touch position to be in local coordinates before it calls `super`. This may only be noticeable in a complex inheritance class.

Coordinate transformations

`Widget` provides 4 functions to transform coordinates between the various coordinate systems. For now, we assume that the `relative` keyword of these functions is `False`. `to_widget()` takes the coordinates expressed in window coordinates and returns them in local (widget) coordinates. `to_window()` takes the coordinates expressed in local coordinates and returns them in window coordinates. `to_parent()` takes the coordinates expressed in local coordinates and returns them in parent coordinates. `to_local()` takes the coordinates expressed in parent coordinates and returns them in local coordinates.

Each of the 4 transformation functions take a `relative` parameter. When the relative parameter is True, the coordinates are returned or originate in true relative coordinates - relative to a coordinate system with its (0, 0) at the bottom left corner of the widget in question.

45.30.2 Common Pitfalls

As all positions within a `RelativeLayout` are relative to the position of the layout itself, the position of the layout should never be used in determining the position of sub-widgets or the layout's `canvas`.

Take the following kv code for example:




Fig. 1: expected result




Fig. 2: actual result

```
FloatLayout:  
    Widget:  
        size_hint: None, None  
        size: 200, 200  
        pos: 200, 200  
  
        canvas:  
            Color:  
                rgba: 1, 1, 1, 1  
            Rectangle:  
                pos: self.pos  
                size: self.size  
  
    RelativeLayout:  
        size_hint: None, None
```

(continues on next page)

```

size: 200, 200
pos: 200, 200

canvas:
    Color:
        rgba: 1, 0, 0, 0.5
    Rectangle:
        pos: self.pos # incorrect
        size: self.size

```

You might expect this to render a single pink rectangle; however, the content of the `RelativeLayout` is already transformed, so the use of `pos: self.pos` will double that transformation. In this case, using `pos: 0, 0` or omitting `pos` completely will provide the expected result.

This also applies to the position of sub-widgets. Instead of positioning a `Widget` based on the layout's own position:

```

RelativeLayout:
    Widget:
        pos: self.parent.pos
    Widget:
        center: self.parent.center

```

use the `pos_hint` property:

```

RelativeLayout:
    Widget:
        pos_hint: {'x': 0, 'y': 0}
    Widget:
        pos_hint: {'center_x': 0.5, 'center_y': 0.5}

```

Changed in version 1.7.0: Prior to version 1.7.0, the `RelativeLayout` was implemented as a `FloatLayout` inside a `Scatter`. This behaviour/widget has been renamed to `ScatterLayout`. The `RelativeLayout` now only supports relative positions (and can't be rotated, scaled or translated on a multitouch system using two or more fingers). This was done so that the implementation could be optimized and avoid the heavier calculations of `Scatter` (e.g. inverse matrix, recalculating multiple properties etc.)

class kivy.uix.relativelayout.RelativeLayout(kw)**
Bases: `kivy.uix.floatlayout.FloatLayout`

RelativeLayout class, see module documentation for more information.

do_layout(*args)

This function is called when a layout is called by a trigger. If you are writing a new Layout subclass, don't call this function directly but use `_trigger_layout()` instead.

The function is by default called *before* the next frame, therefore the layout isn't updated immediately. Anything depending on the positions of e.g. children should be scheduled for the next frame.

New in version 1.0.8.

on_motion(etype, me)

Called when a motion event is received.

Parameters

`etype: str` Event type, one of "begin", "update" or "end"

me: MotionEvent Received motion event

Returns *bool* True to stop event dispatching

New in version 2.1.0.

Warning: This is an experimental method and it remains so while this warning is present.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.

See [relativelayout](#) for a discussion on coordinate systems.

Returns *bool* If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(*touch*)

Receive a touch move event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_touch_up(*touch*)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

to_local(*x, y, **k*)

Transform parent coordinates to local (current widget) coordinates.

See [relativelayout](#) for details on the coordinate systems.

Parameters

relative: bool, defaults to False Change to True if you want to translate coordinates to relative widget coordinates.

to_parent(*x, y, **k*)

Transform local (current widget) coordinates to parent coordinates.

See [relativelayout](#) for details on the coordinate systems.

Parameters

relative: bool, defaults to False Change to True if you want to translate relative positions from a widget to its parent coordinates.

45.31 reStructuredText renderer

New in version 1.1.0.

[reStructuredText](#) is an easy-to-read, what-you-see-is-what-you-get plaintext markup syntax and parser system.

Note: This widget requires the `docutils` package to run. Install it with `pip` or include it as one of your deployment requirements.

Warning: This widget is highly experimental. The styling and implementation should not be considered stable until this warning has been removed.

45.31.1 Usage with Text

```
text = """
.. _top:

Hello world
=====

This is an **emphasized text**, some ``interpreted text``.
And this is a reference to top_::

    $ print("Hello world")

"""
document = RstDocument(text=text)
```

The rendering will output:

Hello world

This is an **emphasized text**, some interpreted text. And this is a reference to [top](#):

```
$ print "Hello world"
```

45.31.2 Usage with Source

You can also render a rst file using the [source](#) property:

```
document = RstDocument(source='index.rst')
```

You can reference other documents using the role `:doc:`. For example, in the document `index.rst` you can write:

```
Go to my next document: :doc:`moreinfo.rst`
```

It will generate a link that, when clicked, opens the `moreinfo.rst` document.

class kivy.uix.rst.RstDocument(kwargs)**
Bases: [kivy.uix.scrollview.ScrollView](#)

Base widget used to store an Rst document. See module documentation for more information.

background_color

Specifies the background_color to be used for the RstDocument.

New in version 1.8.0.

`background_color` is an [AliasProperty](#) for colors['background'].

base_font_size

Font size for the biggest title, 31 by default. All other font sizes are derived from this.

New in version 1.8.0.

colors

Dictionary of all the colors used in the RST rendering.

Warning: This dictionary is needs special handling. You also need to call `RstDocument.render()` if you change them after loading.

`colors` is a *DictProperty*.

document_root

Root path where :doc: will search for rst documents. If no path is given, it will use the directory of the first loaded source file.

`document_root` is a *StringProperty* and defaults to None.

goto(ref, *args)

Scroll to the reference. If it's not found, nothing will be done.

For this text:

```
.. _myref:  
  
This is something I always wanted.
```

You can do:

```
from kivy.clock import Clock  
from functools import partial  
  
doc = RstDocument(...)  
Clock.schedule_once(partial(doc.goto, 'myref'), 0.1)
```

Note: It is preferable to delay the call of the goto if you just loaded the document because the layout might not be finished or the size of the RstDocument has not yet been determined. In either case, the calculation of the scrolling would be wrong.

You can, however, do a direct call if the document is already loaded.

New in version 1.3.0.

preload(filename, encoding='utf-8', errors='strict')

Preload a rst file to get its toctree and its title.

The result will be stored in `toctrees` with the `filename` as key.

render()

Force document rendering.

resolve_path(filename)

Get the path for this filename. If the filename doesn't exist, it returns the `document_root + filename`.

show_errors

Indicate whether RST parsers errors should be shown on the screen or not.

`show_errors` is a *BooleanProperty* and defaults to False.

source

Filename of the RST document.

source is a *StringProperty* and defaults to None.

source_encoding

Encoding to be used for the *source* file.

source_encoding is a *StringProperty* and defaults to *utf-8*.

Note: It is your responsibility to ensure that the value provided is a valid codec supported by python.

source_error

Error handling to be used while encoding the *source* file.

source_error is an *OptionProperty* and defaults to *strict*. Can be one of ‘strict’, ‘ignore’, ‘replace’, ‘xmlcharrefreplace’ or ‘backslashreplac’.

text

RST markup text of the document.

text is a *StringProperty* and defaults to None.

title

Title of the current document.

title is a *StringProperty* and defaults to “”. It is read-only.

toctrees

Toctree of all loaded or preloaded documents. This dictionary is filled when a rst document is explicitly loaded or where *preload()* has been called.

If the document has no filename, e.g. when the document is loaded from a text file, the key will be “”.

toctrees is a *DictProperty* and defaults to {}.

underline_color

underline color of the titles, expressed in html color notation

underline_color is a *StringProperty* and defaults to ‘204a9699’.

45.32 Sandbox

New in version 1.8.0.

Warning: This is experimental and subject to change as long as this warning notice is present.

This is a widget that runs itself and all of its children in a Sandbox. That means if a child raises an Exception, it will be caught. The Sandbox itself runs its own Clock, Cache, etc.

The SandBox widget is still experimental and required for the Kivy designer. When the user designs their own widget, if they do something wrong (wrong size value, invalid python code), it will be caught correctly without breaking the whole application. Because it has been designed that way, we are still enhancing this widget and the *kivy.context* module. Don’t use it unless you know what you are doing.

```
class kivy.uix.sandbox.Sandbox(**kwargs)
Bases: kivy.uix.floatlayout.FloatLayout
```

Sandbox widget, used to trap all the exceptions raised by child widgets.

```
add_widget(*args, **kwargs)
```

Add a new widget as a child of this widget.

Parameters

widget: **Widget** Widget to add to our list of children.

index: **int, defaults to 0** Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

canvas: **str, defaults to None** Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

```
clear_widgets(*args, **kwargs)
```

Remove all (or the specified) **children** of this widget. If the 'children' argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The *children* argument can be used to specify the children you want to remove.

Changed in version 2.1.0: Specifying an empty *children* list leaves the widgets unchanged. Previously it was treated like **None** and all children were removed.

```
on_context_created()
```

Override this method in order to load your kv file or do anything else with the newly created context.

```
on_exception(exception, _traceback=None)
```

Override this method in order to catch all the exceptions from children.

If you return True, it will not reraise the exception. If you return False, the exception will be raised to the parent.

```
on_motion(etype, me)
```

Called when a motion event is received.

Parameters

etype: **str** Event type, one of "begin", "update" or "end"

me: **MotionEvent** Received motion event

Returns *bool* True to stop event dispatching

New in version 2.1.0.

Warning: This is an experimental method and it remains so while this warning is present.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: **MotionEvent class** Touch received. The touch is in parent coordinates.
See [relativelayout](#) for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(*touch*)

Receive a touch move event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_touch_up(*touch*)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

remove_widget(*args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: **Widget** Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

45.33 Scatter

Scatter is used to build interactive widgets that can be translated, rotated and scaled with two or more fingers on a multitouch system.

Scatter has its own matrix transformation: the modelview matrix is changed before the children are drawn and the previous matrix is restored when the drawing is finished. That makes it possible to perform rotation, scaling and translation over the entire children tree without changing any widget properties. That specific behavior makes the scatter unique, but there are some advantages / constraints that you should consider:

1. The children are positioned relative to the scatter similarly to a [RelativeLayout](#). So when dragging the scatter, the position of the children don't change, only the position of the scatter does.
2. The scatter size has no impact on the size of its children.
3. If you want to resize the scatter, use scale, not size (read #2). Scale transforms both the scatter and its children, but does not change size.
4. The scatter is not a layout. You must manage the size of the children yourself.

For touch events, the scatter converts from the parent matrix to the scatter matrix automatically in `on_touch_down`/`move`/`up` events. If you are doing things manually, you will need to use `to_parent()` and `to_local()`.

45.33.1 Usage

By default, the Scatter does not have a graphical representation: it is a container only. The idea is to combine the Scatter with another widget, for example an `Image`:

```
scatter = Scatter()  
image = Image(source='sun.jpg')  
scatter.add_widget(image)
```

45.33.2 Control Interactions

By default, all interactions are enabled. You can selectively disable them using the `do_rotation`, `do_translation` and `do_scale` properties.

Disable rotation:

```
scatter = Scatter(do_rotation=False)
```

Allow only translation:

```
scatter = Scatter(do_rotation=False, do_scale=False)
```

Allow only translation on x axis:

```
scatter = Scatter(do_rotation=False, do_scale=False,  
                 do_translation_y=False)
```

45.33.3 Automatic Bring to Front

If the `Scatter.auto_bring_to_front` property is True, the scatter widget will be removed and re-added to the parent when it is touched (brought to front, above all other widgets in the parent). This is useful when you are manipulating several scatter widgets and don't want the active one to be partially hidden.

45.33.4 Scale Limitation

We are using a 32-bit matrix in double representation. That means we have a limit for scaling. You cannot do infinite scaling down/up with our implementation. Generally, you don't hit the minimum scale (because you don't see it on the screen), but the maximum scale is 9.99506983235e+19 (2^66).

You can also limit the minimum and maximum scale allowed:

```
scatter = Scatter(scale_min=.5, scale_max=3.)
```

45.33.5 Behavior

Changed in version 1.1.0: If no control interactions are enabled, then the touch handler will never return True.

class `kivy.uix.scatter.Scatter(**kwargs)`
Bases: `kivy.uix.widget.Widget`

Scatter class. See module documentation for more information.

Events

`on_transform_with_touch`: Fired when the scatter has been transformed by user touch or multitouch, such as panning or zooming.

`on_bring_to_front`: Fired when the scatter is brought to the front.

Changed in version 1.9.0: Event `on_bring_to_front` added.

Changed in version 1.8.0: Event `on_transform_with_touch` added.

apply_transform(*trans*, *post_multiply=False*, *anchor=(0, 0)*)

Transforms the scatter by applying the “*trans*” transformation matrix (on top of its current transformation state). The resultant matrix can be found in the `transform` property.

Parameters

`trans`: **Matrix**. Transformation matrix to be applied to the scatter widget.

`anchor`: tuple, defaults to (0, 0). The point to use as the origin of the transformation (uses local widget space).

`post_multiply`: bool, defaults to False. If True, the transform matrix is post multiplied (as if applied before the current transform).

Usage example:

```
from kivy.graphics.transformation import Matrix
mat = Matrix().scale(3, 3, 3)
scatter_instance.apply_transform(mat)
```

auto_bring_to_front

If True, the widget will be automatically pushed on the top of parent widget list for drawing.

`auto_bring_to_front` is a *BooleanProperty* and defaults to True.

bbox

Bounding box of the widget in parent space:

```
((x, y), (w, h))
# x, y = lower left corner
```

`bbox` is an *AliasProperty*.

collide_point(*x*, *y*)

Check if a point (*x*, *y*) is inside the widget’s axis aligned bounding box.

Parameters

`x`: numeric x position of the point (in parent coordinates)

`y`: numeric y position of the point (in parent coordinates)

Returns A bool. True if the point is inside the bounding box, False otherwise.

```
>>> Widget(pos=(10, 10), size=(50, 50)).collide_point(40, 40)
True
```

do_collide_after_children

If True, the collision detection for limiting the touch inside the scatter will be done after dispatching the touch to the children. You can put children outside the bounding box of the scatter and still be able to touch them.

do_collide_after_children is a *BooleanProperty* and defaults to False.

New in version 1.3.0.

do_rotation

Allow rotation.

do_rotation is a *BooleanProperty* and defaults to True.

do_scale

Allow scaling.

do_scale is a *BooleanProperty* and defaults to True.

do_translation

Allow translation on the X or Y axis.

do_translation is an *AliasProperty* of (*do_translation_x* + *do_translation_y*)

do_translation_x

Allow translation on the X axis.

do_translation_x is a *BooleanProperty* and defaults to True.

do_translation_y

Allow translation on Y axis.

do_translation_y is a *BooleanProperty* and defaults to True.

on_bring_to_front(*touch*)

Called when a touch event causes the scatter to be brought to the front of the parent (only if *auto_bring_to_front* is True)

Parameters

touch: The touch object which brought the scatter to front.

New in version 1.9.0.

on_motion(*etype*, *me*)

Called when a motion event is received.

Parameters

etype: str Event type, one of "begin", "update" or "end"

me: *MotionEvent* Received motion event

Returns bool True to stop event dispatching

New in version 2.1.0.

Warning: This is an experimental method and it remains so while this warning is present.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.
See [relativelayout](#) for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_transform_with_touch(touch)

Called when a touch event has transformed the scatter widget. By default this does nothing, but can be overridden by derived classes that need to react to transformations caused by user input.

Parameters

touch: The touch object which triggered the transformation.

New in version 1.8.0.

rotation

Rotation value of the scatter in degrees moving in a counterclockwise direction.

rotation is an [AliasProperty](#) and defaults to 0.0.

scale

Scale value of the scatter.

scale is an [AliasProperty](#) and defaults to 1.0.

scale_max

Maximum scaling factor allowed.

scale_max is a [NumericProperty](#) and defaults to 1e20.

scale_min

Minimum scaling factor allowed.

scale_min is a [NumericProperty](#) and defaults to 0.01.

to_local(x, y, **k)

Transform parent coordinates to local (current widget) coordinates.

See [relativelayout](#) for details on the coordinate systems.

Parameters

relative: bool, defaults to False Change to True if you want to translate coordinates to relative widget coordinates.

to_parent(x, y, **k)

Transform local (current widget) coordinates to parent coordinates.

See [relativelayout](#) for details on the coordinate systems.

Parameters

relative: bool, defaults to False Change to True if you want to translate relative positions from a widget to its parent coordinates.

transform

Transformation matrix.

transform is an *ObjectProperty* and defaults to the identity matrix.

Note: This matrix reflects the current state of the transformation matrix but setting it directly will erase previously applied transformations. To apply a transformation considering context, please use the *apply_transform* method.

transform_inv

Inverse of the transformation matrix.

transform_inv is an *ObjectProperty* and defaults to the identity matrix.

translation_touches

Determine whether translation was triggered by a single or multiple touches. This only has effect when *do_translation* = True.

translation_touches is a *NumericProperty* and defaults to 1.

New in version 1.7.0.

```
class kivy.uix.scatter.ScatterPlane(**kwargs)
Bases: kivy.uix.scatter.Scatter
```

This is essentially an unbounded Scatter widget. It's a convenience class to make it easier to handle infinite planes.

collide_point(x, y)

Check if a point (x, y) is inside the widget's axis aligned bounding box.

Parameters

x: numeric x position of the point (in parent coordinates)

y: numeric y position of the point (in parent coordinates)

Returns A bool. True if the point is inside the bounding box, False otherwise.

```
>>> Widget(pos=(10, 10), size=(50, 50)).collide_point(40, 40)
True
```

45.34 Scatter Layout

New in version 1.6.0.

This layout behaves just like a *RelativeLayout*. When a widget is added with position = (0,0) to a *ScatterLayout*, the child widget will also move when you change the position of the *ScatterLayout*. The child widget's coordinates remain (0,0) as they are relative to the parent layout.

However, since *ScatterLayout* is implemented using a *Scatter* widget, you can also translate, rotate and scale the layout using touches or clicks, just like in the case of a normal Scatter widget, and the child widgets will behave as expected.

In contrast to a Scatter, the Layout favours 'hint' properties, such as size_hint, size_hint_x, size_hint_y and pos_hint.

Note: The *ScatterLayout* is implemented as a *FloatLayout* inside a *Scatter*.

Warning: Since the actual `ScatterLayout` is a `Scatter`, its `add_widget` and `remove_widget` functions are overridden to add children to the embedded `FloatLayout` (accessible as the `content` property of `Scatter`) automatically. So if you want to access the added child elements, you need `self.content.children` instead of `self.children`.

Warning: The `ScatterLayout` was introduced in 1.7.0 and was called `RelativeLayout` in prior versions. The `RelativeLayout` is now an optimized implementation that uses only a positional transform to avoid some of the heavier calculation involved for `Scatter`.

`class kivy.uix.scatterlayout.ScatterLayout(**kw)`

Bases: `kivy.uix.scatter.Scatter`

ScatterLayout class, see module documentation for more information.

`add_widget(*args, **kwargs)`

Add a new widget as a child of this widget.

Parameters

`widget: Widget` Widget to add to our list of children.

`index: int, defaults to 0` Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

`canvas: str, defaults to None` Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

`clear_widgets(*args, **kwargs)`

Remove all (or the specified) children of this widget. If the 'children' argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The `children` argument can be used to specify the children you want to remove.

Changed in version 2.1.0: Specifying an empty `children` list leaves the widgets unchanged. Previously it was treated like `None` and all children were removed.

`remove_widget(*args, **kwargs)`

Remove a widget from the children of this widget.

Parameters

`widget: Widget` Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

class kivy.uix.scatterlayout.ScatterPlaneLayout(**kwargs)

Bases: *kivy.uix.scatter.ScatterPlane*

ScatterPlaneLayout class, see module documentation for more information.

Similar to ScatterLayout, but based on ScatterPlane - so the input is not bounded.

New in version 1.9.0.

collide_point(x, y)

Check if a point (x, y) is inside the widget's axis aligned bounding box.

Parameters

x: numeric x position of the point (in parent coordinates)

y: numeric y position of the point (in parent coordinates)

Returns A bool. True if the point is inside the bounding box, False otherwise.

```
>>> Widget(pos=(10, 10), size=(50, 50)).collide_point(40, 40)
True
```

45.35 Screen Manager

New in version 1.4.0.

The screen manager is a widget dedicated to managing multiple screens for your application. The default *ScreenManager* displays only one *Screen* at a time and uses a *TransitionBase* to switch from one Screen to another.

Multiple transitions are supported based on changing the screen coordinates / scale or even performing fancy animation using custom shaders.

45.35.1 Basic Usage

Let's construct a Screen Manager with 4 named screens. When you are creating a screen, **you absolutely need to give a name to it**:

```
from kivy.uix.screenmanager import ScreenManager, Screen

# Create the manager
sm = ScreenManager()

# Add few screens
for i in range(4):
    screen = Screen(name='Title %d' % i)
    sm.add_widget(screen)
```

(continues on next page)

(continued from previous page)

```
# By default, the first screen added into the ScreenManager will be
# displayed. You can then change to another screen.

# Let's display the screen named 'Title 2'
# A transition will automatically be used.
sm.current = 'Title 2'
```

The default `ScreenManager.transition` is a `SlideTransition` with options `direction` and `duration`.

Please note that by default, a `Screen` displays nothing: it's just a `RelativeLayout`. You need to use that class as a root widget for your own screen, the best way being to subclass.

Warning: As `Screen` is a `RelativeLayout`, it is important to understand the [Common Pitfalls](#).

Here is an example with a ‘Menu Screen’ and a ‘Settings Screen’:

```
from kivy.app import App
from kivy.lang import Builder
from kivy.uix.screenmanager import ScreenManager, Screen

# Create both screens. Please note the root.manager.current: this is how
# you can control the ScreenManager from kv. Each screen has by default a
# property manager that gives you the instance of the ScreenManager used.
Builder.load_string("""
<MenuScreen>:
    BoxLayout:
        Button:
            text: 'Goto settings'
            on_press: root.manager.current = 'settings'
        Button:
            text: 'Quit'

<SettingsScreen>:
    BoxLayout:
        Button:
            text: 'My settings button'
        Button:
            text: 'Back to menu'
            on_press: root.manager.current = 'menu'
""")

# Declare both screens
class MenuScreen(Screen):
    pass

class SettingsScreen(Screen):
    pass

class TestApp(App):

    def build(self):
        # Create the screen manager
```

(continues on next page)

(continued from previous page)

```
sm = ScreenManager()
sm.add_widget(MenuScreen(name='menu'))
sm.add_widget(SettingsScreen(name='settings'))

return sm

if __name__ == '__main__':
    TestApp().run()
```

45.35.2 Changing Direction

A common use case for *ScreenManager* involves using a *SlideTransition* which slides right to the next screen and slides left to the previous screen. Building on the previous example, this can be accomplished like so:

```
Builder.load_string("""
<MenuScreen>:
    BoxLayout:
        Button:
            text: 'Goto settings'
            on_press:
                root.manager.transition.direction = 'left'
                root.manager.current = 'settings'
        Button:
            text: 'Quit'

<SettingsScreen>:
    BoxLayout:
        Button:
            text: 'My settings button'
        Button:
            text: 'Back to menu'
            on_press:
                root.manager.transition.direction = 'right'
                root.manager.current = 'menu'
""")
```

45.35.3 Advanced Usage

From 1.8.0, you can now switch dynamically to a new screen, change the transition options and remove the previous one by using *switch_to()*:

```
sm = ScreenManager()
screens = [Screen(name='Title {}'.format(i)) for i in range(4)]

sm.switch_to(screens[0])
# later
sm.switch_to(screens[1], direction='right')
```

Note that this method adds the screen to the *ScreenManager* instance and should not be used if your screens have already been added to this instance. To switch to a screen which is already added, you should use the *current* property.

45.35.4 Changing transitions

You have multiple transitions available by default, such as:

- *NoTransition* - switches screens instantly with no animation
- *SlideTransition* - slide the screen in/out, from any direction
- *CardTransition* - new screen slides on the previous or the old one slides off the new one depending on the mode
- *SwapTransition* - implementation of the iOS swap transition
- *FadeTransition* - shader to fade the screen in/out
- *WipeTransition* - shader to wipe the screens from right to left
- *FallOutTransition* - shader where the old screen ‘falls’ and becomes transparent, revealing the new one behind it.
- *RiseInTransition* - shader where the new screen rises from the screen centre while fading from transparent to opaque.

You can easily switch transitions by changing the *ScreenManager.transition* property:

```
sm = ScreenManager(transition=FadeTransition())
```

Note: Currently, none of Shader based Transitions use anti-aliasing. This is because they use the FBO which doesn't have any logic to handle supersampling. This is a known issue and we are working on a transparent implementation that will give the same results as if it had been rendered on screen.

To be more concrete, if you see sharp edged text during the animation, it's normal.

class kivy.uix.screenmanager.CardTransition
Bases: *kivy.uix.screenmanager.SlideTransition*

Card transition that looks similar to Android 4.x application drawer interface animation.

It supports 4 directions like SlideTransition: left, right, up and down, and two modes, pop and push. If push mode is activated, the previous screen does not move, and the new one slides in from the given direction. If the pop mode is activated, the previous screen slides out, when the new screen is already on the position of the ScreenManager.

New in version 1.10.

mode

Indicates if the transition should push or pop the screen on/off the ScreenManager.

- ‘push’ means the screen slides in in the given direction
- ‘pop’ means the screen slides out in the given direction

mode is an *OptionProperty* and defaults to ‘push’.

start(manager)

(internal) Starts the transition. This is automatically called by the *ScreenManager*.

class kivy.uix.screenmanager.FadeTransition
Bases: *kivy.uix.screenmanager.ShaderTransition*

Fade transition, based on a fragment Shader.

class kivy.uix.screenmanager.FallOutTransition
Bases: *kivy.uix.screenmanager.ShaderTransition*

Transition where the new screen ‘falls’ from the screen centre, becoming smaller and more transparent until it disappears, and revealing the new screen behind it. Mimics the popular/standard Android transition.

New in version 1.8.0.

duration

Duration in seconds of the transition, replacing the default of [TransitionBase](#).

duration is a [NumericProperty](#) and defaults to .15 (= 150ms).

class kivy.uix.screenmanager.NoTransition

Bases: [kivy.uix.screenmanager.TransitionBase](#)

No transition, instantly switches to the next screen with no delay or animation.

New in version 1.8.0.

class kivy.uix.screenmanager.RiseInTransition

Bases: [kivy.uix.screenmanager.ShaderTransition](#)

Transition where the new screen rises from the screen centre, becoming larger and changing from transparent to opaque until it fills the screen. Mimics the popular/standard Android transition.

New in version 1.8.0.

duration

Duration in seconds of the transition, replacing the default of [TransitionBase](#).

duration is a [NumericProperty](#) and defaults to .2 (= 200ms).

class kivy.uix.screenmanager.Screen(kw)**

Bases: [kivy.uix.relativelayout.RelativeLayout](#)

Screen is an element intended to be used with a [ScreenManager](#). Check module documentation for more information.

Events

on_pre_enter: () Event fired when the screen is about to be used: the entering animation is started.

on_enter: () Event fired when the screen is displayed: the entering animation is complete.

on_pre_leave: () Event fired when the screen is about to be removed: the leaving animation is started.

on_leave: () Event fired when the screen is removed: the leaving animation is finished.

Changed in version 1.6.0: Events *on_pre_enter*, *on_enter*, *on_pre_leave* and *on_leave* were added.

manager

[ScreenManager](#) object, set when the screen is added to a manager.

manager is an [ObjectProperty](#) and defaults to None, read-only.

name

Name of the screen which must be unique within a [ScreenManager](#). This is the name used for [ScreenManager.current](#).

name is a [StringProperty](#) and defaults to “”.

transition_progress

Value that represents the completion of the current transition, if any is occurring.

If a transition is in progress, whatever the mode, the value will change from 0 to 1. If you want to know if it's an entering or leaving animation, check the `transition_state`.

`transition_progress` is a `NumericProperty` and defaults to 0.

`transition_state`

Value that represents the state of the transition:

- 'in' if the transition is going to show your screen
- 'out' if the transition is going to hide your screen

After the transition is complete, the state will retain its last value (in or out).

`transition_state` is an `OptionProperty` and defaults to 'out'.

class `kivy.uix.screenmanager.ScreenManager(**kwargs)`

Bases: `kivy.uix.floatlayout.FloatLayout`

Screen manager. This is the main class that will control your `Screen` stack and memory.

By default, the manager will show only one screen at a time.

add_widget(widget, *args, **kwargs)

Changed in version 2.1.0: Renamed argument `screen` to `widget`.

clear_widgets(children=None, *args, **kwargs)

Changed in version 2.1.0: Renamed argument `screens` to `children`.

`current`

Name of the screen currently shown, or the screen to show.

```
from kivy.uix.screenmanager import ScreenManager, Screen

sm = ScreenManager()
sm.add_widget(Screen(name='first'))
sm.add_widget(Screen(name='second'))

# By default, the first added screen will be shown. If you want to
# show another one, just set the 'current' property.
sm.current = 'second'
```

`current` is a `StringProperty` and defaults to None.

`current_screen`

Contains the currently displayed screen. You must not change this property manually, use `current` instead.

`current_screen` is an `ObjectProperty` and defaults to None, read-only.

get_screen(name)

Return the screen widget associated with the name or raise a `ScreenManagerException` if not found.

has_screen(name)

Return True if a screen with the `name` has been found.

New in version 1.6.0.

next()

Return the name of the next screen from the screen list.

on_motion(etype, me)

Called when a motion event is received.

Parameters

etype: str Event type, one of “begin”, “update” or “end”

me: **MotionEvent** Received motion event

Returns bool True to stop event dispatching

New in version 2.1.0.

Warning: This is an experimental method and it remains so while this warning is present.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: **MotionEvent** class Touch received. The touch is in parent coordinates.

See [relativelayout](#) for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(*touch*)

Receive a touch move event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_touch_up(*touch*)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

previous()

Return the name of the previous screen from the screen list.

remove_widget(*widget*, *args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: **Widget** Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

screen_names

List of the names of all the **Screen** widgets added. The list is read only.

screens_names is an [AliasProperty](#) and is read-only. It is updated if the screen list changes or the name of a screen changes.

screens

List of all the **Screen** widgets added. You should not change this list manually. Use the [add_widget](#) method instead.

screens is a [ListProperty](#) and defaults to [], read-only.

switch_to(*screen*, **options)

Add a new or existing screen to the ScreenManager and switch to it. The previous screen will be “switched away” from. *options* are the [transition](#) options that will be changed before the animation happens.

If no previous screens are available, the screen will be used as the main one:

```
sm = ScreenManager()
sm.switch_to(screen1)
# later
sm.switch_to(screen2, direction='left')
# later
sm.switch_to(screen3, direction='right', duration=1.)
```

If any animation is in progress, it will be stopped and replaced by this one: you should avoid this because the animation will just look weird. Use either `switch_to()` or `current` but not both.

The `screen` name will be changed if there is any conflict with the current screen.

transition

Transition object to use for animating the transition from the current screen to the next one being shown.

For example, if you want to use a `WipeTransition` between slides:

```
from kivy.uix.screenmanager import ScreenManager, Screen,
WipeTransition

sm = ScreenManager(transition=WipeTransition())
sm.add_widget(Screen(name='first'))
sm.add_widget(Screen(name='second'))

# by default, the first added screen will be shown. If you want to
# show another one, just set the 'current' property.
sm.current = 'second'
```

`transition` is an `ObjectProperty` and defaults to a `SlideTransition`.

Changed in version 1.8.0: Default transition has been changed from `SwapTransition` to `SlideTransition`.

exception kivy.uix.screenmanager.ScreenManagerException

Bases: `Exception`

Exception for the `ScreenManager`.

class kivy.uix.screenmanager.ShaderTransition

Bases: `kivy.uix.screenmanager.TransitionBase`

Transition class that uses a Shader for animating the transition between 2 screens. By default, this class doesn't assign any fragment/vertex shader. If you want to create your own fragment shader for the transition, you need to declare the header yourself and include the "t", "tex_in" and "tex_out" uniform:

```
# Create your own transition. This shader implements a "fading"
# transition.
fs = """$HEADER
uniform float t;
uniform sampler2D tex_in;
uniform sampler2D tex_out;

void main(void) {
    vec4 cin = texture2D(tex_in, tex_coord0);
```

(continues on next page)

```

    vec4 cout = texture2D(tex_out, tex_coord0);
    gl_FragColor = mix(cout, cin, t);
}

"""

# And create your transition
tr = ShaderTransition(fs=fs)
sm = ScreenManager(transition=tr)

```

add_screen(screen)

(internal) Used to add a screen to the [ScreenManager](#).

clearcolor

Sets the color of Fbo ClearColor.

New in version 1.9.0.

`clearcolor` is a [ColorProperty](#) and defaults to [0, 0, 0, 1].

Changed in version 2.0.0: Changed from [ListProperty](#) to [ColorProperty](#).

fs

Fragment shader to use.

`fs` is a [StringProperty](#) and defaults to None.

remove_screen(screen)

(internal) Used to remove a screen from the [ScreenManager](#).

stop()

(internal) Stops the transition. This is automatically called by the [ScreenManager](#).

vs

Vertex shader to use.

`vs` is a [StringProperty](#) and defaults to None.

class kivy.uix.screenmanager.SlideTransition

Bases: [kivy.uix.screenmanager.TransitionBase](#)

Slide Transition, can be used to show a new screen from any direction: left, right, up or down.

direction

Direction of the transition.

`direction` is an [OptionProperty](#) and defaults to 'left'. Can be one of 'left', 'right', 'up' or 'down'.

class kivy.uix.screenmanager.SwapTransition(kwargs)**

Bases: [kivy.uix.screenmanager.TransitionBase](#)

Swap transition that looks like iOS transition when a new window appears on the screen.

add_screen(screen)

(internal) Used to add a screen to the [ScreenManager](#).

start(manager)

(internal) Starts the transition. This is automatically called by the [ScreenManager](#).

class kivy.uix.screenmanager.TransitionBase

Bases: [kivy.event.EventDispatcher](#)

TransitionBase is used to animate 2 screens within the [ScreenManager](#). This class acts as a base for other implementations like the [SlideTransition](#) and [SwapTransition](#).

Events

on_progress: Transition object, progression float Fired during the animation of the transition.

on_complete: Transition object Fired when the transition is finished.

add_screen(*screen*)

(internal) Used to add a screen to the *ScreenManager*.

duration

Duration in seconds of the transition.

duration is a *NumericProperty* and defaults to .4 (= 400ms).

Changed in version 1.8.0: Default duration has been changed from 700ms to 400ms.

is_active

Indicate whether the transition is currently active or not.

is_active is a *BooleanProperty* and defaults to False, read-only.

manager

ScreenManager object, set when the screen is added to a manager.

manager is an *ObjectProperty* and defaults to None, read-only.

remove_screen(*screen*)

(internal) Used to remove a screen from the *ScreenManager*.

screen_in

Property that contains the screen to show. Automatically set by the *ScreenManager*.

screen_in is an *ObjectProperty* and defaults to None.

screen_out

Property that contains the screen to hide. Automatically set by the *ScreenManager*.

screen_out is an *ObjectProperty* and defaults to None.

start(*manager*)

(internal) Starts the transition. This is automatically called by the *ScreenManager*.

stop()

(internal) Stops the transition. This is automatically called by the *ScreenManager*.

class kivy.uix.screenmanager.WipeTransition

Bases: *kivy.uix.screenmanager.ShaderTransition*

Wipe transition, based on a fragment Shader.

45.36 ScrollView

New in version 1.0.4.

The *ScrollView* widget provides a scrollable/pannable viewport that is clipped at the scrollview's bounding box.

45.36.1 Scrolling Behavior

The ScrollView accepts only one child and applies a viewport/window to it according to the `scroll_x` and `scroll_y` properties. Touches are analyzed to determine if the user wants to scroll or control the child in some other manner: you cannot do both at the same time. To determine if interaction is a scrolling gesture, these properties are used:

- `scroll_distance`: the minimum distance to travel, defaults to 20 pixels.
- `scroll_timeout`: the maximum time period, defaults to 55 milliseconds.

If a touch travels `scroll_distance` pixels within the `scroll_timeout` period, it is recognized as a scrolling gesture and translation (scroll/pan) will begin. If the timeout occurs, the touch down event is dispatched to the child instead (no translation).

The default value for those settings can be changed in the configuration file:

```
[widgets]
scroll_timeout = 250
scroll_distance = 20
```

New in version 1.1.1: ScrollView now animates scrolling in Y when a mousewheel is used.

45.36.2 Limiting to the X or Y Axis

By default, the ScrollView allows scrolling along both the X and Y axes. You can explicitly disable scrolling on an axis by setting the `do_scroll_x` or `do_scroll_y` properties to False.

45.36.3 Managing the Content Size and Position

The ScrollView manages the position of its children similarly to a `RelativeLayout` but does not use the `size_hint`. You must carefully specify the `size` of your content to get the desired scroll/pan effect.

By default, the `size_hint` is (1, 1), so the content size will fit your ScrollView exactly (you will have nothing to scroll). You must deactivate at least one of the `size_hint` instructions (x or y) of the child to enable scrolling. Setting `size_hint_min` to not be None will also enable scrolling for that dimension when the `ScrollView` is smaller than the minimum size.

To scroll a `GridLayout` on its Y-axis/vertically, set the child's width to that of the ScrollView (`size_hint_x=1`), and set the `size_hint_y` property to None:

```
from kivy.uix.gridlayout import GridLayout
from kivy.uix.button import Button
from kivy.uix.scrollview import ScrollView
from kivy.core.window import Window
from kivy.app import runTouchApp

layout = GridLayout(cols=1, spacing=10, size_hint_y=None)
# Make sure the height is such that there is something to scroll.
layout.bind(minimum_height=layout.setter('height'))
for i in range(100):
    btn = Button(text=str(i), size_hint_y=None, height=40)
    layout.add_widget(btn)
root = ScrollView(size_hint=(1, None), size=(Window.width, Window.height))
root.add_widget(layout)
```

(continues on next page)

```
runTouchApp(root)
```

Kv Example:

```
ScrollView:
    do_scroll_x: False
    do_scroll_y: True

Label:
    size_hint_y: None
    height: self.texture_size[1]
    text_size: self.width, None
    padding: 10, 10
    text:
        'really some amazing text\n' * 100
```

45.36.4 Overscroll Effects

New in version 1.7.0.

When scrolling would exceed the bounds of the `ScrollView`, it uses a `ScrollEffect` to handle the overscroll. These effects can perform actions like bouncing back, changing opacity, or simply preventing scrolling beyond the normal boundaries. Note that complex effects may perform many computations, which can be slow on weaker hardware.

You can change what effect is being used by setting `effect_cls` to any effect class. Current options include:

- `ScrollEffect`: Does not allow scrolling beyond the `ScrollView` boundaries.
- `DampedScrollEffect`: The current default. Allows the user to scroll beyond the normal boundaries, but has the content spring back once the touch/click is released.
- `OpacityScrollEffect`: Similar to the `DampedScrollEffect`, but also reduces opacity during overscroll.

You can also create your own scroll effect by subclassing one of these, then pass it as the `effect_cls` in the same way.

Alternatively, you can set `effect_x` and/or `effect_y` to an *instance* of the effect you want to use. This will override the default effect set in `effect_cls`.

All the effects are located in the `kivy.effects`.

```
class kivy.uix.scrollview.ScrollView(**kwargs)
    Bases: kivy.uix.stencilview.StencilView
```

`ScrollView` class. See module documentation for more information.

Events

`on_scroll_start` Generic event fired when scrolling starts from touch.

`on_scroll_move` Generic event fired when scrolling move from touch.

`on_scroll_stop` Generic event fired when scrolling stops from touch.

Changed in version 1.9.0: `on_scroll_start`, `on_scroll_move` and `on_scroll_stop` events are now dispatched when scrolling to handle nested `ScrollViews`.

Changed in version 1.7.0: `auto_scroll`, `scroll_friction`, `scroll_moves`, `scroll_stoptime`' has been deprecated, use `:attr:`effect_cls`` instead.

`add_widget(widget, *args, **kwargs)`

Add a new widget as a child of this widget.

Parameters

`widget: Widget` Widget to add to our list of children.

`index: int, defaults to 0` Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

`canvas: str, defaults to None` Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

`always_overscroll`

Make sure user can overscroll even if there is not enough content to require scrolling.

This is useful if you want to trigger some action on overscroll, but there is not always enough content to trigger it.

`always_overscroll` is a [BooleanProperty](#) and defaults to `True`.

New in version 2.0.0.

The option was added and enabled by default, set to False to get the previous behavior of only allowing to overscroll when there is enough content to allow scrolling.

`bar_color`

Color of horizontal / vertical scroll bar, in RGBA format.

New in version 1.2.0.

`bar_color` is a [ColorProperty](#) and defaults to [.7, .7, .7, .9].

Changed in version 2.0.0: Changed from [ListProperty](#) to [ColorProperty](#).

`bar_inactive_color`

Color of horizontal / vertical scroll bar (in RGBA format), when no scroll is happening.

New in version 1.9.0.

`bar_inactive_color` is a [ColorProperty](#) and defaults to [.7, .7, .7, .2].

Changed in version 2.0.0: Changed from [ListProperty](#) to [ColorProperty](#).

`bar_margin`

Margin between the bottom / right side of the scrollview when drawing the horizontal / vertical scroll bar.

New in version 1.2.0.

bar_margin is a *NumericProperty*, default to 0

bar_pos

Which side of the scroll view to place each of the bars on.

bar_pos is a *ReferenceListProperty* of (*bar_pos_x*, *bar_pos_y*)

bar_pos_x

Which side of the ScrollView the horizontal scroll bar should go on. Possible values are ‘top’ and ‘bottom’.

New in version 1.8.0.

bar_pos_x is an *OptionProperty*, defaults to ‘bottom’.

bar_pos_y

Which side of the ScrollView the vertical scroll bar should go on. Possible values are ‘left’ and ‘right’.

New in version 1.8.0.

bar_pos_y is an *OptionProperty* and defaults to ‘right’.

bar_width

Width of the horizontal / vertical scroll bar. The width is interpreted as a height for the horizontal bar.

New in version 1.2.0.

bar_width is a *NumericProperty* and defaults to 2.

convert_distance_to_scroll(dx, dy)

Convert a distance in pixels to a scroll distance, depending on the content size and the scrollview size.

The result will be a tuple of scroll distance that can be added to *scroll_x* and *scroll_y*.

do_scroll

Allow scroll on X or Y axis.

do_scroll is a *AliasProperty* of (*do_scroll_x* + *do_scroll_y*)

do_scroll_x

Allow scroll on X axis.

do_scroll_x is a *BooleanProperty* and defaults to True.

do_scroll_y

Allow scroll on Y axis.

do_scroll_y is a *BooleanProperty* and defaults to True.

effect_cls

Class effect to instantiate for X and Y axis.

New in version 1.7.0.

effect_cls is an *ObjectProperty* and defaults to *DampedScrollEffect*.

Changed in version 1.8.0: If you set a string, the *Factory* will be used to resolve the class.

effect_x

Effect to apply for the X axis. If None is set, an instance of *effect_cls* will be created.

New in version 1.7.0.

effect_x is an *ObjectProperty* and defaults to None.

effect_y

Effect to apply for the Y axis. If None is set, an instance of **effect_cls** will be created.

New in version 1.7.0.

effect_y is an *ObjectProperty* and defaults to None, read-only.

hbar

Return a tuple of (position, size) of the horizontal scrolling bar.

New in version 1.2.0.

The position and size are normalized between 0-1, and represent a proportion of the current scrollview height. This property is used internally for drawing the little horizontal bar when you're scrolling.

hbar is a *AliasProperty*, readonly.

on_motion(etype, me)

Called when a motion event is received.

Parameters

etype: str Event type, one of "begin", "update" or "end"

me: **MotionEvent** Received motion event

Returns bool True to stop event dispatching

New in version 2.1.0.

Warning: This is an experimental method and it remains so while this warning is present.

on_touch_down(touch)

Receive a touch down event.

Parameters

touch: **MotionEvent** class Touch received. The touch is in parent coordinates.

See *relativelayout* for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See *on_touch_down()* for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See *on_touch_down()* for more information.

remove_widget(widget, *args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: **Widget** Widget to remove from our children list.

```
>>> from kivy.uix.button import Button  
>>> root = Widget()  
>>> button = Button()
```

(continues on next page)

```
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

scroll_distance

Distance to move before scrolling the *ScrollView*, in pixels. As soon as the distance has been traveled, the *ScrollView* will start to scroll, and no touch event will go to children. It is advisable that you base this value on the dpi of your target device's screen.

scroll_distance is a *NumericProperty* and defaults to 20 (pixels), according to the default value in user configuration.

scroll_timeout

Timeout allowed to trigger the *scroll_distance*, in milliseconds. If the user has not moved *scroll_distance* within the timeout, the scrolling will be disabled, and the touch event will go to the children.

scroll_timeout is a *NumericProperty* and defaults to 55 (milliseconds) according to the default value in user configuration.

Changed in version 1.5.0: Default value changed from 250 to 55.

scroll_to(widget, padding=10, animate=True)

Scrolls the viewport to ensure that the given widget is visible, optionally with padding and animation. If *animate* is True (the default), then the default animation parameters will be used. Otherwise, it should be a dict containing arguments to pass to *Animation* constructor.

New in version 1.9.1.

scroll_type

Sets the type of scrolling to use for the content of the scrollview. Available options are: ['content'], ['bars'], ['bars', 'content'].

['content']	Content is scrolled by dragging or swiping the content directly.
['bars']	Content is scrolled by dragging or swiping the scroll bars.
['bars', 'content']	Content is scrolled by either of the above methods.

New in version 1.8.0.

scroll_type is an *OptionProperty* and defaults to ['content'].

scroll_wheel_distance

Distance to move when scrolling with a mouse wheel. It is advisable that you base this value on the dpi of your target device's screen.

New in version 1.8.0.

scroll_wheel_distance is a *NumericProperty*, defaults to 20 pixels.

scroll_x

X scrolling value, between 0 and 1. If 0, the content's left side will touch the left side of the ScrollView. If 1, the content's right side will touch the right side.

This property is controlled by *ScrollView* only if *do_scroll_x* is True.

scroll_x is a *NumericProperty* and defaults to 0.

scroll_y

Y scrolling value, between 0 and 1. If 0, the content's bottom side will touch the bottom side of the ScrollView. If 1, the content's top side will touch the top side.

This property is controlled by *ScrollView* only if *do_scroll_y* is True.

scroll_y is a *NumericProperty* and defaults to 1.

smooth_scroll_end

Whether smooth scroll end should be used when scrolling with the mouse-wheel and the factor of transforming the scroll distance to velocity. This option also enables velocity addition meaning if you scroll more, you will scroll faster and further. The recommended value is 10. The velocity is calculated as `scroll_wheel_distance * smooth_scroll_end`.

New in version 1.11.0.

`smooth_scroll_end` is a [NumericProperty](#) and defaults to None.

to_local(x, y, **k)

Transform parent coordinates to local (current widget) coordinates.

See [relativelayout](#) for details on the coordinate systems.

Parameters

`relative: bool, defaults to False` Change to True if you want to translate coordinates to relative widget coordinates.

to_parent(x, y, **k)

Transform local (current widget) coordinates to parent coordinates.

See [relativelayout](#) for details on the coordinate systems.

Parameters

`relative: bool, defaults to False` Change to True if you want to translate relative positions from a widget to its parent coordinates.

update_from_scroll(*largs)

Force the reposition of the content, according to current value of `scroll_x` and `scroll_y`.

This method is automatically called when one of the `scroll_x`, `scroll_y`, `pos` or `size` properties change, or if the size of the content changes.

vbar

Return a tuple of (position, size) of the vertical scrolling bar.

New in version 1.2.0.

The position and size are normalized between 0-1, and represent a proportion of the current scrollview height. This property is used internally for drawing the little vertical bar when you're scrolling.

`vbar` is a [AliasProperty](#), readonly.


viewport_size

(internal) Size of the internal viewport. This is the size of your only child in the scrollview.

45.37 Settings

New in version 1.0.7.

This module provides a complete and extensible framework for adding a Settings interface to your application. By default, the interface uses a [SettingsWithSpinner](#), which consists of a [Spinner](#) (top) to switch between individual settings panels (bottom). See [Different panel layouts](#) for some alternatives.



A [SettingsPanel](#) represents a group of configurable options. The [SettingsPanel.title](#) property is used by [Settings](#) when a panel is added: it determines the name of the sidebar button. SettingsPanel controls a [ConfigParser](#) instance.

The panel can be automatically constructed from a JSON definition file: you describe the settings you want and corresponding sections/keys in the ConfigParser instance... and you're done!

Settings are also integrated into the [App](#) class. Use [Settings.add_kivy_panel\(\)](#) to configure the Kivy core settings in a panel.

45.37.1 Create a panel from JSON

To create a panel from a JSON-file, you need two things:

- a [ConfigParser](#) instance with default values
- a JSON file

Warning: The [kivy.config.ConfigParser](#) is required. You cannot use the default ConfigParser from Python libraries.

You must create and handle the [ConfigParser](#) object. SettingsPanel will read the values from the associated ConfigParser instance. Make sure you have set default values (using [setdefaults](#)) for all the sections/keys in your JSON file!

The JSON file contains structured information to describe the available settings. Here is an example:

```
[
  {
    "type": "title",
    "title": "Windows"
  },
  {
    "type": "bool",
    "title": "Fullscreen",
    "desc": "Set the window in windowed or fullscreen",
    "section": "graphics",
    "key": "fullscreen"
  }
]
```

Each element in the root list represents a setting that the user can configure. Only the “type” key is mandatory: an instance of the associated class will be created and used for the setting - other keys are assigned to corresponding properties of that class.

Type	Associated class
title	<i>SettingTitle</i>
bool	<i>SettingBoolean</i>
numeric	<i>SettingNumeric</i>
options	<i>SettingOptions</i>
string	<i>SettingString</i>
path	<i>SettingPath</i>
color	<i>SettingColor</i>

New in version 1.1.0: Added *SettingPath* type

New in version 2.1.0: Added *SettingColor* type

In the JSON example above, the first element is of type “title”. It will create a new instance of *SettingTitle* and apply the rest of the key-value pairs to the properties of that class, i.e. “title”: “Windows” sets the *title* property of the panel to “Windows”.

To load the JSON example to a *Settings* instance, use the *Settings.add_json_panel()* method. It will automatically instantiate a *SettingsPanel* and add it to *Settings*:

```
from kivy.config import ConfigParser

config = ConfigParser()
config.read('myconfig.ini')

s = Settings()
s.add_json_panel('My custom panel', config, 'settings_custom.json')
s.add_json_panel('Another panel', config, 'settings_test2.json')

# then use the s as a widget...
```

45.37.2 Different panel layouts

A kivy `App` can automatically create and display a `Settings` instance. See the `settings_cls` documentation for details on how to choose which settings class to display.

Several pre-built settings widgets are available. All except `SettingsWithNoMenu` include close buttons triggering the `on_close` event.

- `Settings`: Displays settings with a sidebar at the left to switch between json panels.
- `SettingsWithSidebar`: A trivial subclass of `Settings`.
- `SettingsWithSpinner`: Displays settings with a spinner at the top, which can be used to switch between json panels. Uses `InterfaceWithSpinner` as the `interface_cls`. This is the default behavior from Kivy 1.8.0.
- `SettingsWithTabbedPanel`: Displays json panels as individual tabs in a `TabbedPanel`. Uses `InterfaceWithTabbedPanel` as the `interface_cls`.
- `SettingsWithNoMenu`: Displays a single json panel, with no way to switch to other panels and no close button. This makes it impossible for the user to exit unless `close_settings()` is overridden with a different close trigger! Uses `InterfaceWithNoMenu` as the `interface_cls`.

You can construct your own settings panels with any layout you choose by setting `Settings.interface_cls`. This should be a widget that displays a json settings panel with some way to switch between panels. An instance will be automatically created by `Settings`.

Interface widgets may be anything you like, but *must* have a method `add_panel` that receives newly created json settings panels for the interface to display. See the documentation for `InterfaceWithSidebar` for more information. They may optionally dispatch an `on_close` event, for instance if a close button is clicked. This event is used by `Settings` to trigger its own `on_close` event.

For a complete, working example, please see `kivy/examples/settings/main.py`.

```
class kivy.uix.settings.ContentPanel(**kwargs)
    Bases: kivy.uix.scrollview.ScrollView
```

A class for displaying settings panels. It displays a single settings panel at a time, taking up the full size and shape of the ContentPanel. It is used by `InterfaceWithSidebar` and `InterfaceWithSpinner` to display settings.

add_panel(*panel, name, uid*)

This method is used by `Settings` to add new panels for possible display. Any replacement for `ContentPanel` *must* implement this method.

Parameters

panel: `SettingsPanel` It should be stored and displayed when requested.

name: The name of the panel as a string. It may be used to represent the panel.

uid: A unique int identifying the panel. It should be stored and used to identify panels when switching.

add_widget(*args, **kwargs)

Add a new widget as a child of this widget.

Parameters

widget: `Widget` Widget to add to our list of children.

index: `int, defaults to 0` Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full

discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

container

(internal) A reference to the GridLayout that contains the settings panel.

container is an [ObjectProperty](#) and defaults to None.

current_panel

(internal) A reference to the current settings panel.

current_panel is an [ObjectProperty](#) and defaults to None.

current_uid

(internal) A reference to the uid of the current settings panel.

current_uid is a [NumericProperty](#) and defaults to 0.

on_current_uid(*args)

The uid of the currently displayed panel. Changing this will automatically change the displayed panel.

Parameters

uid: A panel uid. It should be used to retrieve and display a settings panel that has previously been added with [add_panel\(\)](#).

panels

(internal) Stores a dictionary mapping settings panels to their uids.

panels is a [DictProperty](#) and defaults to {}.

remove_widget(*args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: Widget Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

class kivy.uix.settings.InterfaceWithSidebar(*args, **kwargs)

Bases: [kivy.uix.boxlayout.BoxLayout](#)

The default Settings interface class. It displays a sidebar menu with names of available settings panels, which may be used to switch which one is currently displayed.

See [add_panel\(\)](#) for information on the method you must implement if creating your own interface.

This class also dispatches an event ‘on_close’, which is triggered when the sidebar menu’s close button is released. If creating your own interface widget, it should also dispatch such an event which will automatically be caught by [Settings](#) and used to trigger its own ‘on_close’ event.

add_panel(panel, name, uid)

This method is used by Settings to add new panels for possible display. Any replacement for ContentPanel *must* implement this method.

Parameters

panel: [SettingsPanel](#) It should be stored and the interface should provide a way to switch between panels.

name: The name of the panel as a string. It may be used to represent the panel but isn’t necessarily unique.

uid: A unique int identifying the panel. It should be used to identify and switch between panels.

content

(internal) A reference to the panel display widget (a [ContentPanel](#)).

content is an [ObjectProperty](#) and defaults to None.

menu

(internal) A reference to the sidebar menu widget.

menu is an [ObjectProperty](#) and defaults to None.

class kivy.uix.settings.MenuSidebar(kwargs)**

Bases: [kivy.uix.floatlayout.FloatLayout](#)

The menu used by [InterfaceWithSidebar](#). It provides a sidebar with an entry for each settings panel, which the user may click to select.

add_item(name, uid)

This method is used to add new panels to the menu.

Parameters

name: The name (a string) of the panel. It should be used to represent the panel in the menu.

uid: The name (an int) of the panel. It should be used internally to represent the panel and used to set self.selected_uid when the panel is changed.

buttons_layout

(internal) Reference to the GridLayout that contains individual settings panel menu buttons.

buttons_layout is an [ObjectProperty](#) and defaults to None.

close_button

(internal) Reference to the widget’s Close button.

buttons_layout is an [ObjectProperty](#) and defaults to None.

on_selected_uid(*args)

(internal) unselects any currently selected menu buttons, unless they represent the current panel.

selected_uid

The uid of the currently selected panel. This may be used to switch between displayed panels, e.g. by binding it to the [current_uid](#) of a ContentPanel.

`selected_uid` is a *NumericProperty* and defaults to 0.

class kivy.uix.settings.**SettingBoolean**(**kwargs)
Bases: *kivy.uix.settings.SettingItem*

Implementation of a boolean setting on top of a *SettingItem*. It is visualized with a *Switch* widget. By default, 0 and 1 are used for values: you can change them by setting *values*.

values

Values used to represent the state of the setting. If you want to use “yes” and “no” in your ConfigParser instance:

```
SettingBoolean(..., values=['no', 'yes'])
```

Warning: You need a minimum of two values, the index 0 will be used as False, and index 1 as True

values is a *ListProperty* and defaults to [‘0’, ‘1’]

class kivy.uix.settings.**SettingItem**(**kwargs)
Bases: *kivy.uix.floatlayout.FloatLayout*

Base class for individual settings (within a panel). This class cannot be used directly; it is used for implementing the other setting classes. It builds a row with a title/description (left) and a setting control (right).

Look at *SettingBoolean*, *SettingNumeric* and *SettingOptions* for usage examples.

Events

on_release Fired when the item is touched and then released.

add_widget(*args, **kwargs)

Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the *Widgets Programming Guide*.

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget’s canvas to. Can be ‘before’, ‘after’ or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

content

(internal) Reference to the widget that contains the real setting. As soon as the content object is set, any further call to add_widget will call the content.add_widget. This is automatically

set.

`content` is an *ObjectProperty* and defaults to None.

desc

Description of the setting, rendered on the line below the title.

`desc` is a *StringProperty* and defaults to None.

disabled

Indicate if this setting is disabled. If True, all touches on the setting item will be discarded.

`disabled` is a *BooleanProperty* and defaults to False.

key

Key of the token inside the `section` in the *ConfigParser* instance.

`key` is a *StringProperty* and defaults to None.

on_touch_down(`touch`)

Receive a touch down event.

Parameters

`touch: MotionEvent class` Touch received. The touch is in parent coordinates.

See `relativelayout` for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_up(`touch`)

Receive a touch up event. The touch is in parent coordinates.

See `on_touch_down()` for more information.

panel

(internal) Reference to the SettingsPanel for this setting. You don't need to use it.

`panel` is an *ObjectProperty* and defaults to None.

section

Section of the token inside the *ConfigParser* instance.

`section` is a *StringProperty* and defaults to None.

selected_alpha

(internal) Float value from 0 to 1, used to animate the background when the user touches the item.

`selected_alpha` is a *NumericProperty* and defaults to 0.

title

Title of the setting, defaults to '<No title set>'.

`title` is a *StringProperty* and defaults to '<No title set>'.

value

Value of the token according to the *ConfigParser* instance. Any change to this value will trigger a `Settings.on_config_change()` event.

`value` is an *ObjectProperty* and defaults to None.

class `kivy.uix.settings.SettingNumeric(**kwargs)`
Bases: `kivy.uix.settings.SettingsString`

Implementation of a numeric setting on top of a `SettingString`. It is visualized with a `Label` widget that, when clicked, will open a `Popup` with a `TextInput` so the user can enter a custom value.

```
class kivy.uix.settings.SettingOptions(**kwargs)
Bases: kivy.uix.settings.SettingItem
```

Implementation of an option list on top of a *SettingItem*. It is visualized with a *Label* widget that, when clicked, will open a *Popup* with a list of options from which the user can select.

options

List of all availables options. This must be a list of “string” items. Otherwise, it will crash. :)

options is a *ObjectProperty* and defaults to [].

popup

(internal) Used to store the current popup when it is shown.

popup is an *ObjectProperty* and defaults to None.

```
class kivy.uix.settings.SettingPath(**kwargs)
```

Bases: *kivy.uix.settings.SettingItem*

Implementation of a Path setting on top of a *SettingItem*. It is visualized with a *Label* widget that, when clicked, will open a *Popup* with a *FileChooserListView* so the user can enter a custom value.

New in version 1.1.0.

dirselect

Whether to allow selection of directories.

dirselect is a *BooleanProperty* and defaults to True.

New in version 1.10.0.

popup

(internal) Used to store the current popup when it is shown.

popup is an *ObjectProperty* and defaults to None.

show_hidden

Whether to show ‘hidden’ filenames. What that means is operating-system-dependent.

show_hidden is an *BooleanProperty* and defaults to False.

New in version 1.10.0.

textinput

(internal) Used to store the current textinput from the popup and to listen for changes.

textinput is an *ObjectProperty* and defaults to None.

```
class kivy.uix.settings.SettingString(**kwargs)
```

Bases: *kivy.uix.settings.SettingItem*

Implementation of a string setting on top of a *SettingItem*. It is visualized with a *Label* widget that, when clicked, will open a *Popup* with a *TextInput* so the user can enter a custom value.

popup

(internal) Used to store the current popup when it’s shown.

popup is an *ObjectProperty* and defaults to None.

textinput

(internal) Used to store the current textinput from the popup and to listen for changes.

textinput is an *ObjectProperty* and defaults to None.

```
class kivy.uix.settings.SettingTitle(**kwargs)
```

Bases: *kivy.uix.label.Label*

A simple title label, used to organize the settings in sections.

```
class kivy.uix.settings.Settings(*args, **kwargs)
Bases: kivy.uix.boxlayout.BoxLayout
```

Settings UI. Check module documentation for more information on how to use this class.

Events

on_config_change: ConfigParser instance, section, key, value Fired when the section's key-value pair of a ConfigParser changes.

on_close Fired by the default panel when the Close button is pressed.

add_interface()

(Internal) creates an instance of *Settings.interface_cls*, and sets it to *interface*. When json panels are created, they will be added to this interface which will display them to the user.

add_json_panel(title, config, filename=None, data=None)

Create and add a new *SettingsPanel* using the configuration *config* with the JSON definition *filename*. If *filename* is not set, then the JSON definition is read from the *data* parameter instead.

Check the [Create a panel from JSON](#) section in the documentation for more information about JSON format and the usage of this function.

add_kivy_panel()

Add a panel for configuring Kivy. This panel acts directly on the kivy configuration. Feel free to include or exclude it in your configuration.

See [use_kivy_settings\(\)](#) for information on enabling/disabling the automatic kivy panel.

create_json_panel(title, config, filename=None, data=None)

Create new *SettingsPanel*.

New in version 1.5.0.

Check the documentation of [add_json_panel\(\)](#) for more information.

interface

(internal) Reference to the widget that will contain, organise and display the panel configuration panel widgets.

interface is an *ObjectProperty* and defaults to None.

interface_cls

The widget class that will be used to display the graphical interface for the settings panel. By default, it displays one Settings panel at a time with a sidebar to switch between them.

interface_cls is an *ObjectProperty* and defaults to *InterfaceWithSidebar*.

Changed in version 1.8.0: If you set a string, the *Factory* will be used to resolve the class.

on_touch_down(touch)

Receive a touch down event.

Parameters

touch: *MotionEvent* class Touch received. The touch is in parent coordinates.
See [relativelayout](#) for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

register_type(tp, cls)

Register a new type that can be used in the JSON definition.

```
class kivy.uix.settings.SettingsPanel(**kwargs)
Bases: kivy.uix.gridlayout.GridLayout
```

This class is used to construct panel settings, for use with a *Settings* instance or subclass.

config

A *kivy.config.ConfigParser* instance. See module documentation for more information.

get_value(section, key)

Return the value of the section/key from the *config* ConfigParser instance. This function is used by *SettingItem* to get the value for a given section/key.

If you don't want to use a ConfigParser instance, you might want to override this function.

settings

A *Settings* instance that will be used to fire the *on_config_change* event.

title

Title of the panel. The title will be reused by the *Settings* in the sidebar.

```
class kivy.uix.settings.SettingsWithNoMenu(*args, **kwargs)
```

Bases: *kivy.uix.settings.Settings*

A settings widget that displays a single settings panel with *no* Close button. It will not accept more than one Settings panel. It is intended for use in programs with few enough settings that a full panel switcher is not useful.

Warning: This Settings panel does *not* provide a Close button, and so it is impossible to leave the settings screen unless you also add other behaviour or override *display_settings()* and *close_settings()*.

```
class kivy.uix.settings.SettingsWithSidebar(*args, **kwargs)
```

Bases: *kivy.uix.settings.Settings*

A settings widget that displays settings panels with a sidebar to switch between them. This is the default behaviour of *Settings*, and this widget is a trivial wrapper subclass.

```
class kivy.uix.settings.SettingsWithSpinner(*args, **kwargs)
```

Bases: *kivy.uix.settings.Settings*


A settings widget that displays one settings panel at a time with a spinner at the top to switch between them.

```
class kivy.uix.settings.SettingsWithTabbedPanel(*args, **kwargs)
```

Bases: *kivy.uix.settings.Settings*

A settings widget that displays settings panels as pages in a *TabbedPanel*.

45.38 Slider



The **Slider** widget looks like a scrollbar. It supports horizontal and vertical orientations, min/max values and a default value.

To create a slider from -100 to 100 starting from 25:

```
from kivy.uix.slider import Slider
s = Slider(min=-100, max=100, value=25)
```

To create a vertical slider:

```
from kivy.uix.slider import Slider
s = Slider(orientation='vertical')
```

To create a slider with a red line tracking the value:

```
from kivy.uix.slider import Slider
s = Slider(value_track=True, value_track_color=[1, 0, 0, 1])
```

Kv Example:

```
BoxLayout:
    Slider:
        id: slider
        min: 0
        max: 100
        step: 1
        orientation: 'vertical'

    Label:
        text: str(slider.value)
```

class kivy.uix.slider.Slider(kwargs)**

Bases: *kivy.uix.widget.Widget*

Class for creating a Slider widget.

Check module documentation for more details.

background_disabled_horizontal

Background of the disabled slider used in the horizontal orientation.

New in version 1.10.0.

background_disabled_horizontal is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/sliderh_background_disabled*.

background_disabled_vertical

Background of the disabled slider used in the vertical orientation.

New in version 1.10.0.

background_disabled_vertical is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/sliderv_background_disabled*.

background_horizontal

Background of the slider used in the horizontal orientation.

New in version 1.10.0.

background_horizontal is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/sliderh_background*.

background_vertical

Background of the slider used in the vertical orientation.

New in version 1.10.0.

background_vertical is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/sliderv_background*.

background_width

Slider's background's width (thickness), used in both horizontal and vertical orientations.

background_width is a *NumericProperty* and defaults to 36sp.

border_horizontal

Border used to draw the slider background in horizontal orientation.

border_horizontal is a *ListProperty* and defaults to [0, 18, 0, 18].

border_vertical

Border used to draw the slider background in vertical orientation.

border_vertical is a *ListProperty* and defaults to [18, 0, 18, 0].

cursor_disabled_image

Path of the image used to draw the disabled slider cursor.

cursor_image is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/slider_cursor_disabled*.

cursor_height

Height of the cursor image.

cursor_height is a *NumericProperty* and defaults to 32sp.

cursor_image

Path of the image used to draw the slider cursor.

cursor_image is a *StringProperty* and defaults to *atlas://data/images/defaulttheme/slider_cursor*.

cursor_size

Size of the cursor image.

cursor_size is a *ReferenceListProperty* of (*cursor_width*, *cursor_height*) properties.

cursor_width

Width of the cursor image.

cursor_width is a *NumericProperty* and defaults to 32sp.

max

Maximum value allowed for *value*.

max is a *NumericProperty* and defaults to 100.

min

Minimum value allowed for *value*.

min is a *NumericProperty* and defaults to 0.

on_touch_down (*touch*)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.

See *relativelayout* for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

orientation

Orientation of the slider.

orientation is an [OptionProperty](#) and defaults to 'horizontal'. Can take a value of 'vertical' or 'horizontal'.

padding

Padding of the slider. The padding is used for graphical representation and interaction. It prevents the cursor from going out of the bounds of the slider bounding box.

By default, padding is 16sp. The range of the slider is reduced from padding *2 on the screen. It allows drawing the default cursor of 32sp width without having the cursor go out of the widget.

padding is a [NumericProperty](#) and defaults to 16sp.

range

Range of the slider in the format (minimum value, maximum value):

```
>>> slider = Slider(min=10, max=80)
>>> slider.range
[10, 80]
>>> slider.range = (20, 100)
>>> slider.min
20
>>> slider.max
100
```

range is a [ReferenceListProperty](#) of (*min*, *max*) properties.

sensitivity

Whether the touch collides with the whole body of the widget or with the slider handle part only.

New in version 1.10.1.

sensitivity is a [OptionProperty](#) and defaults to 'all'. Can take a value of 'all' or 'handle'.

step

Step size of the slider.

New in version 1.4.0.

Determines the size of each interval or step the slider takes between *min* and *max*. If the value range can't be evenly divisible by step the last step will be capped by slider.max. A zero value will result in the smallest possible intervals/steps, calculated from the (pixel) position of the slider.

step is a [NumericProperty](#) and defaults to 0.

value

Current value used for the slider.

`value` is a *NumericProperty* and defaults to 0.

value_normalized

Normalized value inside the `range` (min/max) to 0-1 range:

```
>>> slider = Slider(value=50, min=0, max=100)
>>> slider.value
50
>>> slider.value_normalized
0.5
>>> slider.value = 0
>>> slider.value_normalized
0
>>> slider.value = 100
>>> slider.value_normalized
1
```

You can also use it for setting the real value without knowing the minimum and maximum:

```
>>> slider = Slider(min=0, max=200)
>>> slider.value_normalized = .5
>>> slider.value
100
>>> slider.value_normalized = 1.
>>> slider.value
200
```

`value_normalized` is an *AliasProperty*.

value_pos

Position of the internal cursor, based on the normalized value.

`value_pos` is an *AliasProperty*.

value_track

Decides if slider should draw the line indicating the space between `min` and `value` properties values.

`value_track` is a *BooleanProperty* and defaults to False.

value_track_color

Color of the `value_line` in rgba format.

`value_track_color` is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

value_track_width

Width of the track line.

`value_track_width` is a *NumericProperty* and defaults to 3dp.

45.39 Spinner

New in version 1.4.0.



Spinner is a widget that provides a quick way to select one value from a set. In the default state, a spinner shows its currently selected value. Touching the spinner displays a dropdown menu with all the other available values from which the user can select a new one.

Example:

```
from kivy.base import runTouchApp
from kivy.uix.spinner import Spinner

spinner = Spinner(
    # default value shown
    text='Home',
    # available values
    values=('Home', 'Work', 'Other', 'Custom'),
    # just for positioning in our example
    size_hint=(None, None),
    size=(100, 44),
    pos_hint={'center_x': .5, 'center_y': .5})

def show_selected_value(spinner, text):
    print('The spinner', spinner, 'has text', text)

spinner.bind(text=show_selected_value)

runTouchApp(spinner)
```

Kv Example:

```
FloatLayout:
    Spinner:
        size_hint: None, None
        size: 100, 44
        pos_hint: {'center': (.5, .5)}
```

(continues on next page)

```

text: 'Home'
values: 'Home', 'Work', 'Other', 'Custom'
on_text:
    print("The spinner {} has text {}".format(self, self.text))

```

class kivy.uix.spinner.Spinner(kwargs)**Bases: *kivy.uix.button.Button*

Spinner class, see module documentation for more information.

dropdown_cls

Class used to display the dropdown list when the Spinner is pressed.

dropdown_cls is an *ObjectProperty* and defaults to *DropDown*.

Changed in version 1.8.0: If set to a string, the *Factory* will be used to resolve the class name.

is_open

By default, the spinner is not open. Set to True to open it.

is_open is a *BooleanProperty* and defaults to False.

New in version 1.4.0.

option_cls

Class used to display the options within the dropdown list displayed under the Spinner. The *text* property of the class will be used to represent the value.

The option class requires:

- a *text* property, used to display the value.
- an *on_release* event, used to trigger the option when pressed/touched.
- a *size_hint_y* of None.
- the *height* to be set.

option_cls is an *ObjectProperty* and defaults to *SpinnerOption*.

Changed in version 1.8.0: If you set a string, the *Factory* will be used to resolve the class.

sync_height

Each element in a dropdown list uses a default/user-supplied height. Set to True to propagate the Spinner's height value to each dropdown list element.

New in version 1.10.0.

sync_height is a *BooleanProperty* and defaults to False.

text_autoupdate

Indicates if the spinner's *text* should be automatically updated with the first value of the *values* property. Setting it to True will cause the spinner to update its *text* property every time attr:*values* are changed.

New in version 1.10.0.

text_autoupdate is a *BooleanProperty* and defaults to False.

values

Values that can be selected by the user. It must be a list of strings.

values is a *ListProperty* and defaults to [].


```
class kivy.uix.spinner.SpinnerOption(**kwargs)
```

Bases: *kivy.uix.button.Button*

Special button used in the *Spinner* dropdown list. By default, this is just a *Button* with a `size_hint_y` of `None` and a height of `48dp`.

45.40 Splitter

New in version 1.5.0.



The *Splitter* is a widget that helps you re-size its child widget/layout by letting you re-size it via dragging the boundary or double tapping the boundary. This widget is similar to the *ScrollView* in that it allows only one child widget.

Usage:

```
splitter = Splitter(sizable_from = 'right')
splitter.add_widget(layout_or_widget_instance)
splitter.min_size = 100
splitter.max_size = 250
```

To change the size of the strip/border used for resizing:

```
splitter.strip_size = '10pt'
```

To change its appearance:

```
splitter.strip_cls = your_custom_class
```

You can also change the appearance of the `strip_cls`, which defaults to `SplitterStrip`, by overriding the `kv` rule in your app:

```
<SplitterStrip>:
    horizontal: True if self.parent and self.parent.sizable_from[0] in ('t
    ↵', 'b') else False
    background_normal: 'path to normal horizontal image' if self.
    ↵horizontal else 'path to vertical normal image'
    background_down: 'path to pressed horizontal image' if self.horizontal_
    ↵else 'path to vertical pressed image'
```

```
class kivy.uix.splitter.Splitter(**kwargs)
Bases: kivy.uix.boxlayout.BoxLayout
```

See module documentation.

Events

on_press: Fired when the splitter is pressed.

on_release: Fired when the splitter is released.

Changed in version 1.6.0: Added *on_press* and *on_release* events.

```
add_widget(widget, index=0, *args, **kwargs)
```

Add a new widget as a child of this widget.

Parameters

widget: **Widget** Widget to add to our list of children.

index: **int, defaults to 0** Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

canvas: **str, defaults to None** Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

border

Border used for the [BorderImage](#) graphics instruction.

This must be a list of four values: (bottom, right, top, left). Read the BorderImage instructions for more information about how to use it.

border is a [ListProperty](#) and defaults to (4, 4, 4, 4).

```
clear_widgets(*args, **kwargs)
```

Remove all (or the specified) **children** of this widget. If the 'children' argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The *children* argument can be used to specify the children you want to remove.

Changed in version 2.1.0: Specifying an empty *children* list leaves the widgets unchanged. Previously it was treated like **None** and all children were removed.

keep_within_parent

If True, will limit the splitter to stay within its parent widget.

keep_within_parent is a [BooleanProperty](#) and defaults to False.

New in version 1.9.0.

max_size

Specifies the maximum size beyond which the widget is not resizable.

max_size is a *NumericProperty* and defaults to *500pt*.

min_size

Specifies the minimum size beyond which the widget is not resizable.

min_size is a *NumericProperty* and defaults to *100pt*.

remove_widget(widget, *args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: Widget Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

rescale_with_parent

If True, will automatically change size to take up the same proportion of the parent widget when it is resized, while staying within *min_size* and *max_size*. As long as these attributes can be satisfied, this stops the *Splitter* from exceeding the parent size during rescaling.

rescale_with_parent is a *BooleanProperty* and defaults to False.

New in version 1.9.0.

sizable_from

Specifies whether the widget is resizable. Options are: *left*, *right*, *top* or *bottom*

sizable_from is an *OptionProperty* and defaults to *left*.

strip_cls

Specifies the class of the resize Strip.

strip_cls is an *kivy.properties.ObjectProperty* and defaults to *SplitterStrip*, which is of type *Button*.

Changed in version 1.8.0: If you set a string, the *Factory* will be used to resolve the class.

strip_size

Specifies the size of resize strip

strip_size is a *NumericProperty* defaults to *10pt*

45.41 Stack Layout



New in version 1.0.5.

The **StackLayout** arranges children vertically or horizontally, as many as the layout can fit. The size of the individual children widgets do not have to be uniform.

For example, to display widgets that get progressively larger in width:

```
root = StackLayout()
for i in range(25):
    btn = Button(text=str(i), width=40 + i * 5, size_hint=(None, 0.15))
    root.add_widget(btn)
```



```
class kivy.uix.stacklayout.StackLayout(**kwargs)
Bases: kivy.uix.layout.Layout
```

Stack layout class. See module documentation for more information.

do_layout(*largs)

This function is called when a layout is called by a trigger. If you are writing a new Layout subclass, don't call this function directly but use `_trigger_layout()` instead.

The function is by default called *before* the next frame, therefore the layout isn't updated

immediately. Anything depending on the positions of e.g. children should be scheduled for the next frame.

New in version 1.0.8.

minimum_height

Minimum height needed to contain all children. It is automatically set by the layout.

New in version 1.0.8.

minimum_height is a [kivy.properties.NumericProperty](#) and defaults to 0.

minimum_size

Minimum size needed to contain all children. It is automatically set by the layout.

New in version 1.0.8.

minimum_size is a [ReferenceListProperty](#) of (*minimum_width*, *minimum_height*) properties.

minimum_width

Minimum width needed to contain all children. It is automatically set by the layout.

New in version 1.0.8.

minimum_width is a [kivy.properties.NumericProperty](#) and defaults to 0.

orientation

Orientation of the layout.

orientation is an [OptionProperty](#) and defaults to 'lr-tb'.

Valid orientations are 'lr-tb', 'tb-lr', 'rl-tb', 'tb-rl', 'lr-bt', 'bt-lr', 'rl-bt' and 'bt-rl'.

Changed in version 1.5.0: *orientation* now correctly handles all valid combinations of 'lr', 'rl', 'tb', 'bt'. Before this version only 'lr-tb' and 'tb-lr' were supported, and 'tb-rl' was misnamed and placed widgets from bottom to top and from right to left (reversed compared to what was expected).

Note: 'lr' means Left to Right. 'rl' means Right to Left. 'tb' means Top to Bottom. 'bt' means Bottom to Top.

padding

Padding between the layout box and its children: [padding_left, padding_top, padding_right, padding_bottom].

padding also accepts a two argument form [padding_horizontal, padding_vertical] and a single argument form [padding].

Changed in version 1.7.0: Replaced the NumericProperty with a VariableListProperty.

padding is a [VariableListProperty](#) and defaults to [0, 0, 0, 0].

spacing

Spacing between children: [spacing_horizontal, spacing_vertical].

spacing also accepts a single argument form [spacing].

spacing is a [VariableListProperty](#) and defaults to [0, 0].

45.42 Stencil View

New in version 1.0.4.

StencilView limits the drawing of child widgets to the StencilView's bounding box. Any drawing outside the bounding box will be clipped (trashed).

The StencilView uses the stencil graphics instructions under the hood. It provides an efficient way to clip the drawing area of children.

Note: As with the stencil graphics instructions, you cannot stack more than 128 stencil-aware widgets.


Note: StencilView is not a layout. Consequently, you have to manage the size and position of its children directly. You can combine (subclass both) a StencilView and a Layout in order to achieve a layout's behavior. For example:

```
class BoxStencil(BoxLayout, StencilView):  
    pass
```

```
class kivy.uix.stencilview.StencilView(**kwargs)  
    Bases: kivy.uix.widget.Widget  
    StencilView class. See module documentation for more information.
```

45.43 Switch

New in version 1.0.7.



The **Switch** widget is active or inactive, like a mechanical light switch. The user can swipe to the left/right to activate/deactivate it:

```
switch = Switch(active=True)
```

To attach a callback that listens to the activation state:

```
def callback(instance, value):  
    print('the switch', instance, 'is', value)
```

(continues on next page)

```
switch = Switch()
switch.bind(active=callback)
```

By default, the representation of the widget is static. The minimum size required is 83x32 pixels (defined by the background image). The image is centered within the widget.

The entire widget is active, not just the part with graphics. As long as you swipe over the widget's bounding box, it will work.

Note: If you want to control the state with a single touch instead of a swipe, use the `ToggleButton` instead.

Kv Example:

```
BoxLayout:
    Label:
        text: 'power up'
    Switch:
        id: switch
    Label:
        text: 'wooooooooooooh' if switch.active else ''
```

class kivy.uix.switch.Switch(kwargs)**
Bases: `kivy.uix.widget.Widget`

Switch class. See module documentation for more information.

active

Indicate whether the switch is active or inactive.

`active` is a `BooleanProperty` and defaults to False.

active_norm_pos

(internal) Contains the normalized position of the movable element inside the switch, in the 0-1 range.

`active_norm_pos` is a `NumericProperty` and defaults to 0.

on_touch_down(touch)

Receive a touch down event.

Parameters

`touch: MotionEvent class` Touch received. The touch is in parent coordinates.
See `relativelayout` for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See `on_touch_down()` for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See `on_touch_down()` for more information.

touch_control

(internal) Contains the touch that currently interacts with the switch.


touch_control is an *ObjectProperty* and defaults to None.

touch_distance

(internal) Contains the distance between the initial position of the touch and the current position to determine if the swipe is from the left or right.

touch_distance is a *NumericProperty* and defaults to 0.

45.44 TabbedPanel



New in version 1.3.0.

The *TabbedPanel* widget manages different widgets in tabs, with a header area for the actual tab buttons and a content area for showing the current tab content.

The *TabbedPanel* provides one default tab.

45.44.1 Simple example

```
...
TabbedPanel
=====

Test of the widget TabbedPanel.
...

from kivy.app import App
from kivy.uix.tabbedpanel import TabbedPanel
from kivy.lang import Builder

Builder.load_string("""
<Test>:
    size_hint: .5, .5
    pos_hint: {'center_x': .5, 'center_y': .5}
    do_default_tab: False
```

(continues on next page)

```

TabbedPaneItem:
    text: 'first tab'
    Label:
        text: 'First tab content area'
TabbedPaneItem:
    text: 'tab2'
    BoxLayout:
        Label:
            text: 'Second tab content area'
        Button:
            text: 'Button that does nothing'
TabbedPaneItem:
    text: 'tab3'
    RstDocument:
        text:
            '\n'.join(("Hello world", "-----",
                      "You are in the third tab."))
"""

)

class Test(TabbedPanel):
    pass

class TabbedPaneApp(App):
    def build(self):
        return Test()

if __name__ == '__main__':
    TabbedPaneApp().run()

```

Note: A new class `TabbedPaneItem` has been introduced in 1.5.0 for convenience. So now one can simply add a `TabbedPaneItem` to a `TabbedPane` and *content* to the `TabbedPaneItem` as in the example provided above.

45.44.2 Customize the Tabbed Panel

You can choose the position in which the tabs are displayed:

```
tab_pos = 'top_mid'
```

An individual tab is called a `TabbedPaneHeader`. It is a special button containing a *content* property. You add the `TabbedPaneHeader` first, and set its *content* property separately:

```
tp = TabbedPane()
th = TabbedPaneHeader(text='Tab2')
tp.add_widget(th)
```

An individual tab, represented by a `TabbedPaneHeader`, needs its content set. This content can be any widget. It could be a layout with a deep hierarchy of widgets, or it could be an individual widget, such

as a label or a button:

```
th.content = your_content_instance
```

There is one “shared” main content area active at any given time, for all the tabs. Your app is responsible for adding the content of individual tabs and for managing them, but it’s not responsible for content switching. The tabbed panel handles switching of the main content object as per user action.

There is a default tab added when the tabbed panel is instantiated. Tabs that you add individually as above, are added in addition to the default tab. Thus, depending on your needs and design, you will want to customize the default tab:

```
tp.default_tab_text = 'Something Specific To Your Use'
```

The default tab machinery requires special consideration and management. Accordingly, an `on_default_tab` event is provided for associating a callback:

```
tp.bind(default_tab = my_default_tab_callback)
```

It’s important to note that by default, `default_tab_cls` is of type `TabbedPanelHeader` and thus has the same properties as other tabs.

Since 1.5.0, it is now possible to disable the creation of the `default_tab` by setting `do_default_tab` to False.

Tabs and content can be removed in several ways:

```
tp.remove_widget(widget/tabbed_panel_header)
or
tp.clear_widgets() # to clear all the widgets in the content area
or
tp.clear_tabs() # to remove the TabbedPanelHeaders
```

To access the children of the tabbed panel, use `content.children`:

```
tp.content.children
```

To access the list of tabs:

```
tp.tab_list
```

To change the appearance of the main tabbed panel content:

```
background_color = (1, 0, 0, .5) #50% translucent red
border = [0, 0, 0, 0]
background_image = 'path/to/background/image'
```

To change the background of a individual tab, use these two properties:

```
tab_header_instance.background_normal = 'path/to/tab_head/img'
tab_header_instance.background_down = 'path/to/tab_head/img_pressed'
```

A `TabbedPanelStrip` contains the individual tab headers. To change the appearance of this tab strip, override the canvas of `TabbedPanelStrip`. For example, in the kv language:

```
<TabbedPanelStrip>
    canvas:
        Color:
```

(continues on next page)

```

    rgba: (0, 1, 0, 1) # green
Rectangle:
    size: self.size
    pos: self.pos

```

By default the tabbed panel strip takes its background image and color from the tabbed panel's background_image and background_color.

class kivy.uix.tabbedpanel.StripLayout(kwargs)**
Bases: *kivy.uix.gridlayout.GridLayout*

The main layout that is used to house the entire tabbedpanel strip including the blank areas in case the tabs don't cover the entire width/height.

New in version 1.8.0.

background_image

Background image to be used for the Strip layout of the TabbedPanel.

background_image is a *StringProperty* and defaults to a transparent image.

border

Border property for the *background_image*.

border is a *ListProperty* and defaults to [4, 4, 4]

class kivy.uix.tabbedpanel.TabbedPanel(kwargs)**
Bases: *kivy.uix.gridlayout.GridLayout*

The TabbedPanel class. See module documentation for more information.

add_widget(widget, *args, **kwargs)

Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the *Widgets Programming Guide*.

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```

>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)

```

background_color

Background color, in the format (r, g, b, a).

background_color is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

background_disabled_image

Background image of the main shared content object when disabled.

New in version 1.8.0.

background_disabled_image is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/tab’.

background_image

Background image of the main shared content object.

background_image is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/tab’.

border

Border used for *BorderImage* graphics instruction, used itself for *background_image*.

Can be changed for a custom background.

It must be a list of four values: (bottom, right, top, left). Read the *BorderImage* instructions for more information.

border is a *ListProperty* and defaults to (16, 16, 16, 16)

clear_widgets(*args, **kwargs)

Remove all (or the specified) *children* of this widget. If the ‘*children*’ argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The *children* argument can be used to specify the children you want to remove.

Changed in version 2.1.0: Specifying an empty *children* list leaves the widgets unchanged. Previously it was treated like *None* and all children were removed.

content

This is the object holding (current_tab’s content is added to this) the content of the current tab. To Listen to the changes in the content of the current tab, you should bind to *current_tabs content* property.

content is an *ObjectProperty* and defaults to ‘None’.

current_tab

Links to the currently selected or active tab.

New in version 1.4.0.

current_tab is an *AliasProperty*, read-only.

default_tab

Holds the default tab.

Note: For convenience, the automatically provided default tab is deleted when you change *default_tab* to something else. As of 1.5.0, this behaviour has been extended to every *default_tab* for consistency and not just the automatically provided one.

default_tab is an *AliasProperty*.

default_tab_cls

Specifies the class to use for the styling of the default tab.

New in version 1.4.0.

Warning: *default_tab_cls* should be subclassed from *TabbedPanelHeader*

`default_tab_cls` is an *ObjectProperty* and defaults to *TabbedPanelHeader*. If you set a string, the *Factory* will be used to resolve the class.

Changed in version 1.8.0: The *Factory* will resolve the class if a string is set.

default_tab_content

Holds the default tab content.

`default_tab_content` is an *AliasProperty*.

default_tab_text

Specifies the text displayed on the default tab header.

`default_tab_text` is a *StringProperty* and defaults to ‘default tab’.

do_default_tab

Specifies whether a default_tab head is provided.

New in version 1.5.0.

`do_default_tab` is a *BooleanProperty* and defaults to ‘True’.

remove_widget(widget, *args, **kwargs)

Remove a widget from the children of this widget.

Parameters

`widget: Widget` Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

strip_border

Border to be used on `strip_image`.

New in version 1.8.0.

`strip_border` is a *ListProperty* and defaults to [4, 4, 4, 4].

strip_image

Background image of the tabbed strip.

New in version 1.8.0.

`strip_image` is a *StringProperty* and defaults to a empty image.

switch_to(header, do_scroll=False)

Switch to a specific panel header.

Changed in version 1.10.0.

If used with `do_scroll=True`, it scrolls to the header’s tab too.

`switch_to()` cannot be called from within the *TabbedPanel* or its subclass’ `__init__` method. If that is required, use the *Clock* to schedule it. See [discussion](#) for full example.

tab_height

Specifies the height of the tab header.

`tab_height` is a *NumericProperty* and defaults to 40.

tab_list

List of all the tab headers.

`tab_list` is an *AliasProperty* and is read-only.

tab_pos

Specifies the position of the tabs relative to the content. Can be one of: *left_top*, *left_mid*, *left_bottom*, *top_left*, *top_mid*, *top_right*, *right_top*, *right_mid*, *right_bottom*, *bottom_left*, *bottom_mid*, *bottom_right*.

tab_pos is an *OptionProperty* and defaults to ‘*top_left*’.

tab_width

Specifies the width of the tab header.

tab_width is a *NumericProperty* and defaults to 100.

class kivy.uix.tabbedpanel.**TabbedPanelContent**(**kwargs)

Bases: *kivy.uix.floatlayout.FloatLayout*

The TabbedPanelContent class.

exception kivy.uix.tabbedpanel.**TabbedPanelException**

Bases: *Exception*

The TabbedPanelException class.

class kivy.uix.tabbedpanel.**TabbedPanelHeader**(**kwargs)

Bases: *kivy.uix.togglebutton.ToggleButton*

A Base for implementing a Tabbed Panel Head. A button intended to be used as a Heading/Tab for a TabbedPanel widget.

You can use this TabbedPanelHeader widget to add a new tab to a TabbedPanel.

content

Content to be loaded when this tab header is selected.

content is an *ObjectProperty* and defaults to None.

on_touch_down(touch)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.

See *relativelayout* for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

class kivy.uix.tabbedpanel.**TabbedPanelItem**(**kwargs)

Bases: *kivy.uix.tabbedpanel.TabbedPanelHeader*

This is a convenience class that provides a header of type TabbedPanelHeader and links it with the content automatically. Thus facilitating you to simply do the following in kv language:

```
<TabbedPanel>:  
    # ...other settings  
    TabbedPanelItem:  
        BoxLayout:  
            Label:  
                text: 'Second tab content area'  
            Button:  
                text: 'Button that does nothing'
```

New in version 1.5.0.

add_widget(widget, *args, **kwargs)

Add a new widget as a child of this widget.

Parameters

widget: Widget Widget to add to our list of children.

index: int, defaults to 0 Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the [Widgets Programming Guide](#).

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

remove_widget(*args, **kwargs)

Remove a widget from the children of this widget.

Parameters

widget: Widget Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

class kivy.uix.tabbedpanel.TabbedPanelStrip(kwargs)**

Bases: [kivy.uix.gridlayout.GridLayout](#)

A strip intended to be used as background for Heading/Tab. This does not cover the blank areas in case the tabs don't cover the entire width/height of the TabbedPanel(use [StripLayout](#) for that).

tabbed_panel


Link to the panel that the tab strip is a part of.

tabbed_panel is an [ObjectProperty](#) and defaults to None .

45.45 Text Input

New in version 1.0.4.





The `TextInput` widget provides a box for editable plain text.

Unicode, multiline, cursor navigation, selection and clipboard features are supported.

The `TextInput` uses two different coordinate systems:

- (x, y) - coordinates in pixels, mostly used for rendering on screen.
- (col, row) - cursor index in characters / lines, used for selection and cursor movement.

45.45.1 Usage example

To create a multiline `TextInput` (the ‘enter’ key adds a new line):

```
from kivy.uix.textinput import TextInput
textinput = TextInput(text='Hello world')
```

To create a singleline `TextInput`, set the `TextInput.multiline` property to False (the ‘enter’ key will defocus the TextInput and emit an `TextInput.on_text_validate()` event):

```
def on_enter(instance, value):
    print('User pressed enter in', instance)

textinput = TextInput(text='Hello world', multiline=False)
textinput.bind(on_text_validate=on_enter)
```

The textinput’s text is stored in its `TextInput.text` property. To run a callback when the text changes:

```
def on_text(instance, value):
    print('The widget', instance, 'have:', value)

textinput = TextInput()
textinput.bind(text=on_text)
```

You can set the `focus` to a Textinput, meaning that the input box will be highlighted and keyboard focus will be requested:

```
textinput = TextInput(focus=True)
```

The textinput is defocused if the ‘escape’ key is pressed, or if another widget requests the keyboard. You can bind a callback to the `focus` property to get notified of focus changes:

```
def on_focus(instance, value):
    if value:
        print('User focused', instance)
    else:
        print('User defocused', instance)
```

(continues on next page)

```
textinput = TextInput()
textinput.bind(focus=on_focus)
```

See *FocusBehavior*, from which the *TextInput* inherits, for more details.

45.45.2 Selection

The selection is automatically updated when the cursor position changes. You can get the currently selected text from the *TextInput.selection_text* property.

45.45.3 Filtering

You can control which text can be added to the *TextInput* by overwriting *TextInput.insert_text()*. Every string that is typed, pasted or inserted by any other means into the *TextInput* is passed through this function. By overwriting it you can reject or change unwanted characters.

For example, to write only in capitalized characters:

```
class CapitalInput(TextInput):

    def insert_text(self, substring, from_undo=False):
        s = substring.upper()
        return super().insert_text(s, from_undo=from_undo)
```

Or to only allow floats (0 - 9 and a single period):

```
class FloatInput(TextInput):

    pat = re.compile('[^0-9]')
    def insert_text(self, substring, from_undo=False):
        pat = self.pat
        if '.' in self.text:
            s = re.sub(pat, '', substring)
        else:
            s = '.'.join(
                re.sub(pat, '', s)
                for s in substring.split('.', 1))
        return super().insert_text(s, from_undo=from_undo)
```

45.45.4 Default shortcuts

Shortcuts	Description
Left	Move cursor to left
Right	Move cursor to right
Up	Move cursor to up
Down	Move cursor to down
Home	Move cursor at the beginning of the line
End	Move cursor at the end of the line
PageUp	Move cursor to 3 lines before
PageDown	Move cursor to 3 lines after
Backspace	Delete the selection or character before the cursor
Del	Delete the selection of character after the cursor
Shift + <dir>	Start a text selection. Dir can be Up, Down, Left or Right
Control + c	Copy selection
Control + x	Cut selection
Control + v	Paste clipboard content
Control + a	Select all the content
Control + z	undo
Control + r	redo

Note: To enable Emacs-style keyboard shortcuts, you can use [EmacsBehavior](#).

class `kivy.uix.textinput.TextInput(**kwargs)`
Bases: `kivy.uix.behaviors.focus.FocusBehavior, kivy.uix.widget.Widget`

TextInput class. See module documentation for more information.

Events

`on_text_validate` Fired only in multiline=False mode when the user hits ‘enter’. This will also unfocus the TextInput.

`on_double_tap` Fired when a double tap happens in the text input. The default behavior selects the text around the cursor position. More info at [on_double_tap\(\)](#).

`on_triple_tap` Fired when a triple tap happens in the text input. The default behavior selects the line around the cursor position. More info at [on_triple_tap\(\)](#).

`on_quad_touch` Fired when four fingers are touching the text input. The default behavior selects the whole text. More info at [on_quad_touch\(\)](#).

Warning: When changing a `TextInput` property that requires re-drawing, e.g. modifying the `text`, the updates occur on the next clock cycle and not instantly. This might cause any changes to the `TextInput` that occur between the modification and the next cycle to be ignored, or to use previous values. For example, after a update to the `text`, changing the cursor in the same clock frame will move it using the previous text and will likely end up in an incorrect position. The solution is to schedule any updates to occur on the next clock cycle using `schedule_once()`.

Note: Selection is cancelled when TextInput is focused. If you need to show selection when TextInput is focused, you should delay (use Clock.schedule) the call to the functions for selecting

text (select_all, select_text).

Changed in version 1.10.0: `background_disabled_active` has been removed.

Changed in version 1.9.0: `TextInput` now inherits from `FocusBehavior.keyboard_mode`, `show_keyboard()`, `hide_keyboard()`, `focus()`, and `input_type` have been removed since they are now inherited from `FocusBehavior`.

Changed in version 1.7.0: `on_double_tap`, `on_triple_tap` and `on_quad_touch` events added.

Changed in version 2.1.0: `keyboardSuggestions` is now inherited from `FocusBehavior`.

allow_copy

Decides whether to allow copying the text.

New in version 1.8.0.

`allow_copy` is a `BooleanProperty` and defaults to True.

auto_indent

Automatically indent multiline text.

New in version 1.7.0.

`auto_indent` is a `BooleanProperty` and defaults to False.

background_active

Background image of the TextInput when it's in focus.

New in version 1.4.1.

`background_active` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/textinput_active'.

background_color

Current color of the background, in (r, g, b, a) format.

New in version 1.2.0.

`background_color` is a `ColorProperty` and defaults to [1, 1, 1, 1] (white).

Changed in version 2.0.0: Changed from `ListProperty` to `ColorProperty`.

background_disabled_normal

Background image of the TextInput when disabled.

New in version 1.8.0.

`background_disabled_normal` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/textinput_disabled'.

background_normal

Background image of the TextInput when it's not in focus.

New in version 1.4.1.

`background_normal` is a `StringProperty` and defaults to 'atlas://data/images/defaulttheme/textinput'.

base_direction

Base direction of text, this impacts horizontal alignment when `halign` is `auto` (the default). Available options are: `None`, `"ltr"` (left to right), `"rtl"` (right to left) plus `"weak_ltr"` and `"weak rtl"`.

Note: This feature requires the Pango text provider.

Note: Weak modes are currently not implemented in Kivy text layout, and have the same effect as setting strong mode.

New in version 1.10.1.

`base_direction` is an *OptionProperty* and defaults to None (autodetect RTL if possible, otherwise LTR).

border

Border used for *BorderImage* graphics instruction. Used with `background_normal` and `background_active`. Can be used for a custom background.

New in version 1.4.1.

It must be a list of four values: (bottom, right, top, left). Read the *BorderImage* instruction for more information about how to use it.

`border` is a *ListProperty* and defaults to (4, 4, 4, 4).

cancel_selection()

Cancel current selection (if any).

copy(*data*=‘’)

Copy the value provided in argument *data* into current clipboard. If data is not of type string it will be converted to string. If no data is provided then current selection if present is copied.

New in version 1.8.0.

cursor

Tuple of (col, row) values indicating the current cursor position. You can set a new (col, row) if you want to move the cursor. The scrolling area will be automatically updated to ensure that the cursor is visible inside the viewport.

`cursor` is an *AliasProperty*.

cursor_blink

This property is used to set whether the graphic cursor should blink or not.

Changed in version 1.10.1: `cursor_blink` has been refactored to enable switching the blinking on/off and the previous behavior has been moved to a private `_cursor_blink` property. The previous default value `False` has been changed to `True`.

`cursor_blink` is a *BooleanProperty* and defaults to True.

cursor_col

Current column of the cursor.

`cursor_col` is an *AliasProperty* to `cursor[0]`, read-only.

cursor_color

Current color of the cursor, in (r, g, b, a) format.

New in version 1.9.0.

`cursor_color` is a *ColorProperty* and defaults to [1, 0, 0, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

cursor_index(*cursor*=None)

Return the cursor index in the text/value.

cursor_offset()

Get the cursor x offset on the current line.

cursor_pos

Current position of the cursor, in (x, y).

cursor_pos is an *AliasProperty*, read-only.

cursor_row

Current row of the cursor.

cursor_row is an *AliasProperty* to cursor[1], read-only.

cursor_width

Current width of the cursor.

New in version 1.10.0.

cursor_width is a *NumericProperty* and defaults to '1sp'.

cut()

Copy current selection to clipboard then delete it from TextInput.

New in version 1.8.0.

delete_selection(*from_undo=False*)

Delete the current text selection (if any).

disabled_foreground_color

Current color of the foreground when disabled, in (r, g, b, a) format.

New in version 1.8.0.

disabled_foreground_color is a *ColorProperty* and defaults to [0, 0, 0, 5] (50% transparent black).

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

do_backspace(*from_undo=False, mode='bkspc'*)

Do backspace operation from the current cursor position. This action might do several things:

- removing the current selection if available.
- removing the previous char and move the cursor back.
- do nothing, if we are at the start.

do_cursor_movement(*action, control=False, alt=False*)

Move the cursor relative to its current position. Action can be one of :

- cursor_left: move the cursor to the left
- cursor_right: move the cursor to the right
- cursor_up: move the cursor on the previous line
- cursor_down: move the cursor on the next line
- cursor_home: move the cursor at the start of the current line
- cursor_end: move the cursor at the end of current line
- cursor_pgup: move one "page" before
- cursor_pgdown: move one "page" after

In addition, the behavior of certain actions can be modified:

- control + cursor_left: move the cursor one word to the left
- control + cursor_right: move the cursor one word to the right
- control + cursor_up: scroll up one line
- control + cursor_down: scroll down one line

- control + cursor_home: go to beginning of text
- control + cursor_end: go to end of text
- alt + cursor_up: shift line(s) up
- alt + cursor_down: shift line(s) down

Changed in version 1.9.1.

do_redo()

Do redo operation.

New in version 1.3.0.

This action re-does any command that has been un-done by do_undo/ctrl+z. This function is automatically called when *ctrl+r* keys are pressed.

do_undo()

Do undo operation.

New in version 1.3.0.

This action un-does any edits that have been made since the last call to reset_undo(). This function is automatically called when *ctrl+z* keys are pressed.

do_wrap

If True, and the text is multiline, then lines larger than the width of the widget will wrap around to the next line, avoiding the need for horizontal scrolling. Disabling this option ensure one line is always displayed as one line.

do_wrap is a *BooleanProperty* and defaults to True.

versionadded:: 2.1.0

font_context

Font context. *None* means the font is used in isolation, so you are guaranteed to be drawing with the TTF file resolved by *font_name*. Specifying a value here will load the font file into a named context, enabling fallback between all fonts in the same context. If a font context is set, you are not guaranteed that rendering will actually use the specified TTF file for all glyphs (Pango will pick the one it thinks is best).

If Kivy is linked against a system-wide installation of FontConfig, you can load the system fonts by specifying a font context starting with the special string *system://*. This will load the system fontconfig configuration, and add your application-specific fonts on top of it (this imposes a significant risk of family name collision, Pango may not use your custom font file, but pick one from the system)

Note: This feature requires the Pango text provider.

New in version 1.10.1.

font_context is a *StringProperty* and defaults to None.

font_family

Font family, this is only applicable when using *font_context* option. The specified font family will be requested, but note that it may not be available, or there could be multiple fonts registered with the same family. The value can be a family name (string) available in the font context (for example a system font in a *system://* context, or a custom font file added using `kivy.core.text.FontContextManager`). If set to *None*, font selection is controlled by the *font_name* setting.

Note: If using `font_name` to reference a custom font file, you should leave this as `None`. The family name is managed automatically in this case.

Note: This feature requires the Pango text provider.

New in version 1.10.1.

`font_family` is a *StringProperty* and defaults to `None`.

font_name

Filename of the font to use. The path can be absolute or relative. Relative paths are resolved by the `resource_find()` function.

Warning: Depending on your text provider, the font file may be ignored. However, you can mostly use this without problems.

If the font used lacks the glyphs for the particular language/symbols you are using, you will see '[]' blank box characters instead of the actual glyphs. The solution is to use a font that has the glyphs you need to display. For example, to display , use a font like freesans.ttf that has the glyph.

`font_name` is a *StringProperty* and defaults to 'Roboto'. This value is taken from `Config`.

font_size

Font size of the text in pixels.

`font_size` is a *NumericProperty* and defaults to 15 `sp`.

foreground_color

Current color of the foreground, in (r, g, b, a) format.

New in version 1.2.0.

`foreground_color` is a *ColorProperty* and defaults to [0, 0, 0, 1] (black).

Changed in version 2.0.0: Changed from `ListProperty` to `ColorProperty`.

get_cursor_from_index(index)

Return the (col, row) of the cursor from text index.

get_cursor_from_xy(x, y)

Return the (col, row) of the cursor from an (x, y) position.

halign

Horizontal alignment of the text.

`halign` is an *OptionProperty* and defaults to 'auto'. Available options are : auto, left, center and right. Auto will attempt to autodetect horizontal alignment for RTL text (Pango only), otherwise it behaves like `left`.

New in version 1.10.1.

handle_image_left

Image used to display the Left handle on the TextInput for selection.

New in version 1.8.0.

`handle_image_left` is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/selector_left'.

handle_image_middle

Image used to display the middle handle on the TextInput for cursor positioning.

New in version 1.8.0.

handle_image_middle is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/selector_middle’.

handle_image_right

Image used to display the Right handle on the TextInput for selection.

New in version 1.8.0.

handle_image_right is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/selector_right’.

hint_text

Hint text of the widget, shown if text is “”.

New in version 1.6.0.

Changed in version 1.10.0: The property is now an AliasProperty and byte values are decoded to strings. The hint text will stay visible when the widget is focused.

hint_text a *AliasProperty* and defaults to “”.

hint_text_color

Current color of the hint_text text, in (r, g, b, a) format.

New in version 1.6.0.

hint_text_color is a *ColorProperty* and defaults to [0.5, 0.5, 0.5, 1.0] (grey).

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

input_filter

Filters the input according to the specified mode, if not None. If None, no filtering is applied.

New in version 1.9.0.

input_filter is an *ObjectProperty* and defaults to *None*. Can be one of *None*, ‘*int*’ (string), or ‘*float*’ (string), or a callable. If it is ‘*int*’, it will only accept numbers. If it is ‘*float*’ it will also accept a single period. Finally, if it is a callable it will be called with two parameters; the string to be added and a bool indicating whether the string is a result of undo (True). The callable should return a new substring that will be used instead.

insert_text(*substring, from_undo=False*)

Insert new text at the current cursor position. Override this function in order to pre-process text for input validation.

keyboard_on_key_down(*window, keycode, text, modifiers*)

The method bound to the keyboard when the instance has focus.

When the instance becomes focused, this method is bound to the keyboard and will be called for every input press. The parameters are the same as *kivy.core.window.WindowBase.on_key_down()*.

When overwriting the method in the derived widget, super should be called to enable tab cycling. If the derived widget wishes to use tab for its own purposes, it can call super after it has processed the character (if it does not wish to consume the tab).

Similar to other keyboard functions, it should return True if the key was consumed.

keyboard_on_key_up(*window, keycode*)

The method bound to the keyboard when the instance has focus.

When the instance becomes focused, this method is bound to the keyboard and will be called for every input release. The parameters are the same as `kivy.core.window.WindowBase.on_key_up()`.

When overwriting the method in the derived widget, super should be called to enable defocusing on escape. If the derived widget wishes to use escape for its own purposes, it can call super after it has processed the character (if it does not wish to consume the escape).

See `keyboard_on_key_down()`

line_height

Height of a line. This property is automatically computed from the `font_name`, `font_size`. Changing the line_height will have no impact.

Note: `line_height` is the height of a single line of text. Use `minimum_height`, which also includes padding, to get the height required to display the text properly.

`line_height` is a `NumericProperty`, read-only.

line_spacing

Space taken up between the lines.

New in version 1.8.0.

`line_spacing` is a `NumericProperty` and defaults to 0.

minimum_height

Minimum height of the content inside the TextInput.

New in version 1.8.0.

`minimum_height` is a readonly `AliasProperty`.

Warning: `minimum_width` is calculated based on `width` therefore code like this will lead to an infinite loop:

```
<FancyTextInput>:  
    height: self.minimum_height  
    width: self.height
```

multiline

If True, the widget will be able show multiple lines of text. If False, the “enter” keypress will defocus the textinput instead of adding a new line.

`multiline` is a `BooleanProperty` and defaults to True.

on_cursor(*instance, value*)

When the cursor is moved, reset cursor blinking to keep it showing, and update all the graphics.

on_cursor_blink(*instance, value*)

trigger blink event reset to switch blinking while focused

on_double_tap()

This event is dispatched when a double tap happens inside TextInput. The default behavior is to select the word around the current cursor position. Override this to provide different behavior. Alternatively, you can bind to this event to provide additional functionality.

on_quad_touch()

This event is dispatched when four fingers are touching inside TextInput. The default behavior is to select all text. Override this to provide different behavior. Alternatively, you can bind to this event to provide additional functionality.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: **MotionEvent class** Touch received. The touch is in parent coordinates.
See [relativelayout](#) for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(*touch*)

Receive a touch move event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_touch_up(*touch*)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_triple_tap()

This event is dispatched when a triple tap happens inside TextInput. The default behavior is to select the line around current cursor position. Override this to provide different behavior. Alternatively, you can bind to this event to provide additional functionality.

padding

Padding of the text: [padding_left, padding_top, padding_right, padding_bottom].

padding also accepts a two argument form [padding_horizontal, padding_vertical] and a one argument form [padding].

Changed in version 1.7.0: Replaced AliasProperty with VariableListProperty.

padding is a **VariableListProperty** and defaults to [6, 6, 6, 6].

padding_x

Horizontal padding of the text: [padding_left, padding_right].

padding_x also accepts a one argument form [padding_horizontal].

padding_x is a **VariableListProperty** and defaults to [0, 0]. This might be changed by the current theme.

Deprecated since version 1.7.0: Use *padding* instead.

padding_y

Vertical padding of the text: [padding_top, padding_bottom].

padding_y also accepts a one argument form [padding_vertical].

padding_y is a **VariableListProperty** and defaults to [0, 0]. This might be changed by the current theme.

Deprecated since version 1.7.0: Use *padding* instead.

password

If True, the widget will display its characters as the character set in [password_mask](#).

New in version 1.2.0.

password is a **BooleanProperty** and defaults to False.

password_mask

Sets the character used to mask the text when `password` is True.

New in version 1.10.0.

`password_mask` is a *StringProperty* and defaults to '*'.

paste()

Insert text from system Clipboard into the `TextInput` at current cursor position.

New in version 1.8.0.

property pgmove_speed

how much vertical distance hitting pg_up or pg_down will move

readonly

If True, the user will not be able to change the content of a textinput.

New in version 1.3.0.

`readonly` is a *BooleanProperty* and defaults to False.

replace_crlf

Automatically replace CRLF with LF.

New in version 1.9.1.

`replace_crlf` is a *BooleanProperty* and defaults to True.

reset_undo()

Reset undo and redo lists from memory.

New in version 1.3.0.

scroll_distance

Minimum distance to move before change from scroll to selection mode, in pixels. It is advisable that you base this value on the dpi of your target device's screen.

New in version 2.1.0.

`scroll_distance` is a NumericProperty and defaults to 20 pixels.

scroll_from_swipe

Allow to scroll the text using swipe gesture according to `scroll_timeout` and `scroll_distance`.

New in version 2.1.0.

`scroll_from_swipe` is a BooleanProperty and defaults to True on mobile OS's, False on desktop OS's.

scroll_timeout

Timeout allowed to trigger the `scroll_distance`, in milliseconds. If the user has not moved `scroll_distance` within the timeout, the scrolling will be disabled, and the selection mode will start.

New in version 2.1.0.

`scroll_timeout` is a NumericProperty and defaults to 250 milliseconds.

scroll_x

X scrolling value of the viewport. The scrolling is automatically updated when the cursor is moved or text changed. If there is no user input, the scroll_x and scroll_y properties may be changed.

`scroll_x` is a *NumericProperty* and defaults to 0.

scroll_y

Y scrolling value of the viewport. See [scroll_x](#) for more information.

scroll_y is a [NumericProperty](#) and defaults to 0.

select_all()

Select all of the text displayed in this TextInput.

New in version 1.4.0.

select_text(*start, end*)

Select a portion of text displayed in this TextInput.

New in version 1.4.0.

Parameters

start Index of textinput.text from where to start selection

end Index of textinput.text till which the selection should be displayed

selection_color

Current color of the selection, in (r, g, b, a) format.

Warning: The color should always have an “alpha” component less than 1 since the selection is drawn after the text.

selection_color is a [ColorProperty](#) and defaults to [0.1843, 0.6549, 0.8313, .5].

Changed in version 2.0.0: Changed from [ListProperty](#) to [ColorProperty](#).

selection_from

If a selection is in progress or complete, this property will represent the cursor index where the selection started.

Changed in version 1.4.0: *selection_from* is an [AliasProperty](#) and defaults to None, readonly.

selection_text

Current content selection.

selection_text is a [StringProperty](#) and defaults to "", readonly.

selection_to

If a selection is in progress or complete, this property will represent the cursor index where the selection started.

Changed in version 1.4.0: *selection_to* is an [AliasProperty](#) and defaults to None, readonly.

tab_width

By default, each tab will be replaced by four spaces on the text input widget. You can set a lower or higher value.

tab_width is a [NumericProperty](#) and defaults to 4.

text

Text of the widget.

Creation of a simple hello world:

```
widget = TextInput(text='Hello world')
```

If you want to create the widget with an unicode string, use:

```
widget = TextInput(text=u'My unicode string')
```

text is an *AliasProperty*.

text_language

Language of the text, if None Pango will determine it from locale. This is an RFC-3066 format language tag (as a string), for example “en_US”, “zh_CN”, “fr” or “ja”. This can impact font selection, metrics and rendering. For example, the same bytes of text can look different for *ur* and *ar* languages, though both use Arabic script.

Note: This feature requires the Pango text provider.

New in version 1.10.1.

text_language is a *StringProperty* and defaults to None.

text_validate_unfocus

If True, the `TextInput.on_text_validate()` event will unfocus the widget, therefore make it stop listening to the keyboard. When disabled, the `TextInput.on_text_validate()` event can be fired multiple times as the result of TextInput keeping the focus enabled.

New in version 1.10.1.

text_validate_unfocus is a *BooleanProperty* and defaults to True.

use_bubble

Indicates whether the cut/copy/paste bubble is used.

New in version 1.7.0.

use_bubble is a *BooleanProperty* and defaults to True on mobile OS’s, False on desktop OS’s.

use_handles

Indicates whether the selection handles are displayed.

New in version 1.8.0.

use_handles is a *BooleanProperty* and defaults to True on mobile OS’s, False on desktop OS’s.

write_tab

Whether the tab key should move focus to the next widget or if it should enter a tab in the `TextInput`. If *True* a tab will be written, otherwise, focus will move to the next widget.

New in version 1.9.0.

write_tab is a *BooleanProperty* and defaults to *True*.

45.46 Toggle button



The `ToggleButton` widget acts like a checkbox. When you touch or click it, the state toggles between ‘normal’ and ‘down’ (as opposed to a `Button` that is only ‘down’ as long as it is pressed).

Toggle buttons can also be grouped to make radio buttons - only one button in a group can be in a 'down' state. The group name can be a string or any other hashable Python object:

```
btn1 = ToggleButton(text='Male', group='sex')
btn2 = ToggleButton(text='Female', group='sex', state='down')
btn3 = ToggleButton(text='Mixed', group='sex')
```


Only one of the buttons can be 'down'/checked at the same time.

To configure the ToggleButton, you can use the same properties that you can use for a [Button](#) class.

```
class kivy.uix.togglebutton.ToggleButton(**kwargs)
    Bases: kivy.uix.behaviors.togglebutton.ToggleButtonBehavior, kivy.uix.button.Button
```

ToggleButton class, see module documentation for more information.

45.47 Tree View



New in version 1.0.4.

[TreeView](#) is a widget used to represent a tree structure. It is currently very basic, supporting a minimal feature set.

45.47.1 Introduction

A [TreeView](#) is populated with [TreeViewNode](#) instances, but you cannot use a [TreeViewNode](#) directly. You must combine it with another widget, such as [Label](#), [Button](#) or even your own widget. The TreeView always creates a default root node, based on [TreeViewLabel](#).

[TreeViewNode](#) is a class object containing needed properties for serving as a tree node. Extend [TreeViewNode](#) to create custom node types for use with a [TreeView](#).

For constructing your own subclass, follow the pattern of TreeViewLabel which combines a Label and a TreeViewNode, producing a [TreeViewLabel](#) for direct use in a TreeView instance.

To use the TreeViewLabel class, you could create two nodes directly attached to root:

```
tv = TreeView()
tv.add_node(TreeViewLabel(text='My first item'))
tv.add_node(TreeViewLabel(text='My second item'))
```

Or, create two nodes attached to a first:

```

tv = TreeView()
n1 = tv.add_node(TreeViewLabel(text='Item 1'))
tv.add_node(TreeViewLabel(text='SubItem 1'), n1)
tv.add_node(TreeViewLabel(text='SubItem 2'), n1)

```

If you have a large tree structure, perhaps you would need a utility function to populate the tree view:

```

def populate_tree_view(tree_view, parent, node):
    if parent is None:
        tree_node = tree_view.add_node(TreeViewLabel(text=node['node_id'],
                                                      is_open=True))
    else:
        tree_node = tree_view.add_node(TreeViewLabel(text=node['node_id'],
                                                      is_open=True), parent)

    for child_node in node['children']:
        populate_tree_view(tree_view, tree_node, child_node)

tree = {'node_id': '1',
        'children': [{'node_id': '1.1',
                      'children': [{'node_id': '1.1.1',
                                    'children': [{'node_id': '1.1.1.1',
                                                  'children': []},
                                                 {'node_id': '1.1.1.2',
                                                  'children': []},
                                                 {'node_id': '1.1.1.3',
                                                  'children': []}]},
                      {'node_id': '1.1.2',
                        'children': []},
                      {'node_id': '1.1.3',
                        'children': []}]},
                  {'node_id': '1.2',
                    'children': []}]

class TreeWidget(FloatLayout):
    def __init__(self, **kwargs):
        super(TreeWidget, self).__init__(**kwargs)

        tv = TreeView(root_options=dict(text='Tree One'),
                      hide_root=False,
                      indent_level=4)

        populate_tree_view(tv, None, tree)

        self.add_widget(tv)

```

The root widget in the tree view is opened by default and has text set as 'Root'. If you want to change that, you can use the `TreeView.root_options` property. This will pass options to the root widget:

```

tv = TreeView(root_options=dict(text='My root label'))

```

45.47.2 Creating Your Own Node Widget

For a button node type, combine a `Button` and a `TreeViewNode` as follows:

```
class TreeViewButton(Button, TreeViewNode):
    pass
```

You must know that, for a given node, only the `size_hint_x` will be honored. The allocated width for the node will depend of the current width of the TreeView and the level of the node. For example, if a node is at level 4, the width allocated will be:

```
treeview.width - treeview.indent_start - treeview.indent_level * node.level
```

You might have some trouble with that. It is the developer's responsibility to correctly handle adapting the graphical representation nodes, if needed.

`class kivy.uix.treeview.TreeView(**kwargs)`
Bases: `kivy.uix.widget.Widget`

TreeView class. See module documentation for more information.

Events

`on_node_expand: (node,)` Fired when a node is being expanded

`on_nodeCollapse: (node,)` Fired when a node is being collapsed

`add_node(node, parent=None)`

Add a new node to the tree.

Parameters

`node: instance of a TreeViewNode` Node to add into the tree

`parent: instance of a TreeViewNode, defaults to None` Parent node to attach the new node. If `None`, it is added to the `root` node.

`Returns` the node `node`.

`deselect_node(*args)`

Deselect any selected node.

New in version 1.10.0.

`get_node_at_pos(pos)`

Get the node at the position (x, y).

`hide_root`

Use this property to show/hide the initial root node. If True, the root node will appear as a closed node.

`hide_root` is a `BooleanProperty` and defaults to False.

`indent_level`

Width used for the indentation of each level except the first level.

Computation of indent for each level of the tree is:

```
indent = indent_start + level * indent_level
```

`indent_level` is a `NumericProperty` and defaults to 16.

`indent_start`

Indentation width of the level 0 / root node. This is mostly the initial size to accommodate a tree icon (collapsed / expanded). See `indent_level` for more information about the computation of level indentation.

indent_start is a *NumericProperty* and defaults to 24.

iterate_all_nodes(*node=None*)

Generator to iterate over all nodes from *node* and down whether expanded or not. If *node* is *None*, the generator start with *root*.

iterate_open_nodes(*node=None*)

Generator to iterate over all the expended nodes starting from *node* and down. If *node* is *None*, the generator start with *root*.

To get all the open nodes:

```
treeview = TreeView()  
# ... add nodes ...  
for node in treeview.iterate_open_nodes():  
    print(node)
```

load_func

Callback to use for asynchronous loading. If set, asynchronous loading will be automatically done. The callback must act as a Python generator function, using *yield* to send data back to the treeview.

The callback should be in the format:

```
def callback(treeview, node):  
    for name in ('Item 1', 'Item 2'):  
        yield TreeViewLabel(text=name)
```

load_func is a *ObjectProperty* and defaults to None.

minimum_height

Minimum height needed to contain all children.

New in version 1.0.9.

minimum_height is a *NumericProperty* and defaults to 0.

minimum_size

Minimum size needed to contain all children.

New in version 1.0.9.

minimum_size is a *ReferenceListProperty* of (*minimum_width*, *minimum_height*) properties.

minimum_width

Minimum width needed to contain all children.

New in version 1.0.9.

minimum_width is a *NumericProperty* and defaults to 0.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.

See *relativelayout* for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

remove_node(*node*)

Removes a node from the tree.

New in version 1.0.7.

Parameters

node: instance of a [TreeViewNode](#) Node to remove from the tree. If **node** is **root**, it is not removed.

root

Root node.

By default, the root node widget is a [TreeViewLabel](#) with text 'Root'. If you want to change the default options passed to the widget creation, use the **root_options** property:

```
treeview = TreeView(root_options={  
    'text': 'Root directory',  
    'font_size': 15})
```

root_options will change the properties of the [TreeViewLabel](#) instance. However, you cannot change the class used for root node yet.

root is an [AliasProperty](#) and defaults to None. It is read-only. However, the content of the widget can be changed.

root_options

Default root options to pass for root widget. See **root** property for more information about the usage of **root_options**.

root_options is an [ObjectProperty](#) and defaults to {}.

select_node(node)

Select a node in the tree.

selected_node

Node selected by [TreeView.select_node\(\)](#) or by touch.

selected_node is a [AliasProperty](#) and defaults to None. It is read-only.

toggle_node(node)

Toggle the state of the node (open/collapsed).

exception kivy.uix.treeview.TreeViewException

Bases: Exception

Exception for errors in the [TreeView](#).

class kivy.uix.treeview.TreeViewLabel(**kwargs)

Bases: [kivy.uix.label.Label](#), [kivy.uix.treeview.TreeViewNode](#)

Combines a [Label](#) and a [TreeViewNode](#) to create a [TreeViewLabel](#) that can be used as a text node in the tree.

See module documentation for more information.

class kivy.uix.treeview.TreeViewNode(**kwargs)

Bases: [builtins.object](#)

TreeViewNode class, used to build a node class for a TreeView object.

color_selected

Background color of the node when the node is selected.

color_selected is a [ColorProperty](#) and defaults to [.1, .1, .1, 1].

Changed in version 2.0.0: Changed from [ListProperty](#) to [ColorProperty](#).

even_color

Background color of even nodes when the node is not selected.

bg_color is a *ColorProperty* and defaults to [.5, .5, .5, .1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

is_leaf

Boolean to indicate whether this node is a leaf or not. Used to adjust the graphical representation.

is_leaf is a *BooleanProperty* and defaults to True. It is automatically set to False when child is added.

is_loaded

Boolean to indicate whether this node is already loaded or not. This property is used only if the *TreeView* uses asynchronous loading.

is_loaded is a *BooleanProperty* and defaults to False.

is_open

Boolean to indicate whether this node is opened or not, in case there are child nodes. This is used to adjust the graphical representation.

Warning: This property is automatically set by the *TreeView*. You can read but not write it.

is_open is a *BooleanProperty* and defaults to False.

is_selected

Boolean to indicate whether this node is selected or not. This is used to adjust the graphical representation.

Warning: This property is automatically set by the *TreeView*. You can read but not write it.

is_selected is a *BooleanProperty* and defaults to False.

level

Level of the node.

level is a *NumericProperty* and defaults to -1.

no_selection

Boolean used to indicate whether selection of the node is allowed or not.

no_selection is a *BooleanProperty* and defaults to False.

nodes

List of nodes. The nodes list is different than the children list. A node in the nodes list represents a node on the tree. An item in the children list represents the widget associated with the node.

Warning: This property is automatically set by the *TreeView*. You can read but not write it.

nodes is a *ListProperty* and defaults to [].

odd

This property is set by the TreeView widget automatically and is read-only.

odd is a *BooleanProperty* and defaults to False.

odd_color

Background color of odd nodes when the node is not selected.

odd_color is a *ColorProperty* and defaults to [1., 1., 1., 0.]

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

parent_node

Parent node. This attribute is needed because the *parent* can be None when the node is not displayed.

New in version 1.0.7.

parent_node is an *ObjectProperty* and defaults to None.

45.48 Video

The *Video* widget is used to display video files and streams. Depending on your Video core provider, platform, and plugins, you will be able to play different formats. For example, the pygame video provider only supports MPEG1 on Linux and OSX. GStreamer is more versatile, and can read many video containers and codecs such as MKV, OGV, AVI, MOV, FLV (if the correct gstreamer plugins are installed). Our *VideoBase* implementation is used under the hood.

Video loading is asynchronous - many properties are not available until the video is loaded (when the texture is created):

```
def on_position_change(instance, value):
    print('The position in the video is', value)

def on_duration_change(instance, value):
    print('The duration of the video is', value)

video = Video(source='PandaSneezes.avi')
video.bind(
    position=on_position_change,
    duration=on_duration_change
)
```

One can define a preview image which gets displayed until the video is started/loaded by passing *preview* to the constructor:

```
video = Video(
    source='PandaSneezes.avi',
    preview='PandaSneezes_preview.png'
)
```

One can display the placeholder image when the video stops by reacting on eos:

```
def on_eos_change(self, inst, val):
    if val and self.preview:
        self.set_texture_from_resource(self.preview)

video.bind(eos=on_eos_change)
```

```
class kivy.uix.video.Video(**kwargs)
```

Bases: *kivy.uix.image.Image*

Video class. See module documentation for more information.

duration

Duration of the video. The duration defaults to -1, and is set to a real duration when the video is loaded.

duration is a *NumericProperty* and defaults to -1.

eos

Boolean, indicates whether the video has finished playing or not (reached the end of the stream).

eos is a *BooleanProperty* and defaults to False.

loaded

Boolean, indicates whether the video is loaded and ready for playback or not.

New in version 1.6.0.

loaded is a *BooleanProperty* and defaults to False.

options

Options to pass at Video core object creation.

New in version 1.0.4.

options is an *kivy.properties.ObjectProperty* and defaults to {}.

play

Deprecated since version 1.4.0: Use *state* instead.

Boolean, indicates whether the video is playing or not. You can start/stop the video by setting this property:

```
# start playing the video at creation
video = Video(source='movie.mkv', play=True)

# create the video, and start later
video = Video(source='movie.mkv')
# and later
video.play = True
```

play is a *BooleanProperty* and defaults to False.

Deprecated since version 1.4.0: Use *state* instead.

position

Position of the video between 0 and *duration*. The position defaults to -1 and is set to a real position when the video is loaded.

position is a *NumericProperty* and defaults to -1.

preview

Filename / source of a preview image displayed before video starts.

preview is a *StringProperty* and defaults to None.

If set, it gets displayed until the video is loaded/started.

New in version 2.1.0.

seek(percent, precise=True)

Change the position to a percentage (strictly, a proportion) of duration.

Parameters

percent: float or int Position to seek as a proportion of the total duration, must be between 0-1.

precise: bool, defaults to True Precise seeking is slower, but seeks to exact requested percent.

Warning: Calling `seek()` before the video is loaded has no effect.

New in version 1.2.0.

Changed in version 1.10.1: The `precise` keyword argument has been added.

state

String, indicates whether to play, pause, or stop the video:

```
# start playing the video at creation
video = Video(source='movie.mkv', state='play')

# create the video, and start later
video = Video(source='movie.mkv')
# and later
video.state = 'play'
```

`state` is an *OptionProperty* and defaults to 'stop'.

unload()

Unload the video. The playback will be stopped.

New in version 1.8.0.

volume


Volume of the video, in the range 0-1. 1 means full volume, 0 means mute.

`volume` is a *NumericProperty* and defaults to 1.

45.49 Video player

New in version 1.2.0.

The video player widget can be used to play video and let the user control the play/pausing, volume and position. The widget cannot be customized much because of the complex assembly of numerous base widgets.




45.49.1 Annotations

If you want to display text at a specific time and for a certain duration, consider annotations. An annotation file has a ".jsa" extension. The player will automatically load the associated annotation file if it exists.

An annotation file is JSON-based, providing a list of label dictionary items. The key and value must match one of the [VideoPlayerAnnotation](#) items. For example, here is a short version of a jsa file that you can find in `examples/widgets/cityCC0.jsa`:

```
[{"start": 0, "duration": 2, "text": "This is an example of annotation"}, {"start": 2, "duration": 2, "bgcolor": [0.5, 0.2, 0.4, 0.5], "text": "You can change the background color"}]
```

For our cityCC0.mpg example, the result will be:



If you want to experiment with annotation files, test with:

```
python -m kivy.uix.videoplayer examples/widgets/cityCC0.mpg
```

45.49.2 Fullscreen

The video player can play the video in fullscreen, if `VideoPlayer.allowFullscreen` is activated by a double-tap on the video. By default, if the video is smaller than the Window, it will be not stretched.

You can allow stretching by passing custom options to a `VideoPlayer` instance:

```
player = VideoPlayer(source='myvideo.avi', state='play',
    options={'allow_stretch': True})
```

45.49.3 End-of-stream behavior

You can specify what happens when the video has finished playing by passing an `eos` (end of stream) directive to the underlying `VideoBase` class. `eos` can be one of 'stop', 'pause' or 'loop' and defaults to 'stop'. For example, in order to loop the video:

```
player = VideoPlayer(source='myvideo.avi', state='play',
    options={'eos': 'loop'})
```

Note: The `eos` property of the `VideoBase` class is a string specifying the end-of-stream behavior. This property differs from the `eos` properties of the `VideoPlayer` and `Video` classes, whose `eos` property is simply a boolean indicating that the end of the file has been reached.

class `kivy.uix.videoplayer.VideoPlayer(**kwargs)`
Bases: `kivy.uix.gridlayout.GridLayout`

VideoPlayer class. See module documentation for more information.

allow fullscreen

By default, you can double-tap on the video to make it fullscreen. Set this property to False to prevent this behavior.

allow fullscreen is a *BooleanProperty* defaults to True.

annotations

If set, it will be used for reading annotations box.

annotations is a *StringProperty* and defaults to “”.

duration

Duration of the video. The duration defaults to -1 and is set to the real duration when the video is loaded.

duration is a *NumericProperty* and defaults to -1.

fullscreen

Switch to fullscreen view. This should be used with care. When activated, the widget will remove itself from its parent, remove all children from the window and will add itself to it. When fullscreen is unset, all the previous children are restored and the widget is restored to its previous parent.

Warning: The re-add operation doesn't care about the index position of its children within the parent.

fullscreen is a *BooleanProperty* and defaults to False.

image_loading

Image filename used when the video is loading.

image_loading is a *StringProperty* and defaults to ‘data/images/image-loading.zip’.

image_overlay_play

Image filename used to show a “play” overlay when the video has not yet started.

image_overlay_play is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/player-play-overlay’.

image_pause

Image filename used for the “Pause” button.

image_pause is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/media-playback-pause’.

image_play

Image filename used for the “Play” button.

image_play is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/media-playback-start’.

image_stop

Image filename used for the “Stop” button.

image_stop is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/media-playback-stop’.

image_volumehigh

Image filename used for the volume icon when the volume is high.

image_volumehigh is a *StringProperty* and defaults to ‘atlas://data/images/defaulttheme/audio-volume-high’.

image_volumelow

Image filename used for the volume icon when the volume is low.

image_volumelow is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/audio-volume-low'.

image_volumemedium

Image filename used for the volume icon when the volume is medium.

image_volumemedium is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/audio-volume-medium'.

image_volumemuted

Image filename used for the volume icon when the volume is muted.

image_volumemuted is a *StringProperty* and defaults to 'atlas://data/images/defaulttheme/audio-volume-muted'.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.

See *relativelayout* for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

options

Optional parameters can be passed to a *Video* instance with this property.

options a *DictProperty* and defaults to {}.

play

Deprecated since version 1.4.0: Use *state* instead.

Boolean, indicates whether the video is playing or not. You can start/stop the video by setting this property:

```
# start playing the video at creation
video = VideoPlayer(source='movie.mkv', play=True)

# create the video, and start later
video = VideoPlayer(source='movie.mkv')
# and later
video.play = True
```

play is a *BooleanProperty* and defaults to False.

position

Position of the video between 0 and *duration*. The position defaults to -1 and is set to the real position when the video is loaded.

position is a *NumericProperty* and defaults to -1.

seek(*percent*, *precise=True*)

Change the position to a percentage (strictly, a proportion) of duration.

Parameters

percent: float or int Position to seek as a proportion of total duration, must be between 0-1.

precise: bool, defaults to True Precise seeking is slower, but seeks to exact requested percent.

Warning: Calling seek() before the video is loaded has no effect.

New in version 1.2.0.

Changed in version 1.10.1: The *precise* keyword argument has been added.

source

Source of the video to read.

source is a *StringProperty* and defaults to ''.

Changed in version 1.4.0.

state

String, indicates whether to play, pause, or stop the video:

```
# start playing the video at creation
video = VideoPlayer(source='movie.mkv', state='play')

# create the video, and start later
video = VideoPlayer(source='movie.mkv')
# and later
video.state = 'play'
```

state is an *OptionProperty* and defaults to 'stop'.

thumbnail

Thumbnail of the video to show. If None, VideoPlayer will try to find the thumbnail from the *source* + '.png'.

thumbnail a *StringProperty* and defaults to ''.

Changed in version 1.4.0.

volume

Volume of the video in the range 0-1. 1 means full volume and 0 means mute.

volume is a *NumericProperty* and defaults to 1.

class kivy.uix.videoplayer.VideoPlayerAnnotation(kwargs)**

Bases: *kivy.uix.label.Label*

Annotation class used for creating annotation labels.

Additional keys are available:

- bgcolor: [r, g, b, a] - background color of the text box
- bgsource: 'filename' - background image used for the background text box
- border: (n, e, s, w) - border used for the background image

duration

Duration of the annotation.

duration is a *NumericProperty* and defaults to 1.

start

Start time of the annotation.

start is a *NumericProperty* and defaults to 0.

45.50 VKeyboard



New in version 1.0.8.

VKeyboard is an onscreen keyboard for Kivy. Its operation is intended to be transparent to the user. Using the widget directly is NOT recommended. Read the section [Request keyboard](#) first.

45.50.1 Modes

This virtual keyboard has a docked and free mode:

- docked mode (`VKeyboard.docked` = True) Generally used when only one person is using the computer, like a tablet or personal computer etc.
- free mode: (`VKeyboard.docked` = False) Mostly for multitouch surfaces. This mode allows multiple virtual keyboards to be used on the screen.

If the docked mode changes, you need to manually call `VKeyboard.setup_mode()` otherwise the change will have no impact. During that call, the VKeyboard, implemented on top of a `Scatter`, will change the behavior of the scatter and position the keyboard near the target (if target and docked mode is set).

45.50.2 Layouts

The virtual keyboard is able to load a custom layout. If you create a new layout and put the JSON in `<kivy_data_dir>/keyboards/<layoutid>.json`, you can load it by setting `VKeyboard.layout` to your layoutid.

The JSON must be structured like this:

```
{  
    "title": "Title of your layout",  
    "description": "Description of your layout",  
    "cols": 15,  
    "rows": 5,  
  
    ...  
}
```

Then, you need to describe the keys in each row, for either a “normal”, “shift” or a “special” (added in version 1.9.0) mode. Keys for this row data must be named `normal_<row>`, `shift_<row>` and `special_<row>`. Replace `row` with the row number. Inside each row, you will describe the key. A key is a 4 element list in the format:

```
[ <text displayed on the keyboard>, <text to put when the key is pressed>,
  <text that represents the keycode>, <size of cols> ]
```

Here are example keys:

```
# f key
["f", "f", "f", 1]
# capslock
[ "", " ", "tab", 1.5]
```

Finally, complete the JSON:

```
{
    ...
    "normal_1": [
        ["`", "`", "`", 1],      ["1", "1", "1", 1],      ["2", "2", "2", 1],
        ["3", "3", "3", 1],      ["4", "4", "4", 1],      ["5", "5", "5", 1],
        ["6", "6", "6", 1],      ["7", "7", "7", 1],      ["8", "8", "8", 1],
        ["9", "9", "9", 1],      ["0", "0", "0", 1],      ["+", "+", "+", 1],
        [=, =, =, 1],           [null, "backspace", 2]
    ],
    "shift_1": [ ... ],
    "normal_2": [ ... ],
    "special_2": [ ... ],
    ...
}
```

45.50.3 Request Keyboard

The instantiation of the virtual keyboard is controlled by the configuration. Check `keyboard_mode` and `keyboard_layout` in the [Configuration object](#).

If you intend to create a widget that requires a keyboard, do not use the virtual keyboard directly, but prefer to use the best method available on the platform. Check the `request_keyboard()` method in the [Window](#).

If you want a specific layout when you request the keyboard, you should write something like this (from 1.8.0, numeric.json can be in the same directory as your main.py):

```
keyboard = Window.request_keyboard(
    self._keyboard_close, self)
if keyboard.widget:
    vkeyboard = self._keyboard.widget
    vkeyboard.layout = 'numeric.json'
```

```
class kivy.uix.vkeyboard.VKeyboard(**kwargs)
Bases: kivy.uix.scatter.Scatter
```

VKeyboard is an onscreen keyboard with multitouch support. Its layout is entirely customizable and you can switch between available layouts using a button in the bottom right of the widget.

Events

`on_key_down: keycode, internal, modifiers` Fired when the keyboard received a key down event (key press).

on_key_up: `keycode, internal, modifiers` Fired when the keyboard received a key up event (key release).

available_layouts

Dictionary of all available layouts. Keys are the layout ID, and the value is the JSON (translated into a Python object).

`available_layouts` is a *DictProperty* and defaults to {}.

background

Filename of the background image.

`background` is a *StringProperty* and defaults to `atlas://data/images/defaulttheme/vkeyboard_background`.

background_border

Background image border. Used for controlling the `border` property of the background.

`background_border` is a *ListProperty* and defaults to [16, 16, 16, 16]

background_color

Background color, in the format (r, g, b, a). If a background is set, the color will be combined with the background texture.

`background_color` is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

background_disabled

Filename of the background image when the vkeyboard is disabled.

New in version 1.8.0.

`background_disabled` is a *StringProperty* and defaults to `atlas://data/images/defaulttheme/vkeyboard_disabled_background`.

callback

Callback can be set to a function that will be called if the VKeyboard is closed by the user.

`target` is an *ObjectProperty* instance and defaults to None.

collide_margin(x, y)

Do a collision test, and return True if the (x, y) is inside the vkeyboard margin.

docked

Indicate whether the VKeyboard is docked on the screen or not. If you change it, you must manually call `setup_mode()` otherwise it will have no impact. If the VKeyboard is created by the Window, the docked mode will be automatically set by the configuration, using the `keyboard_mode` token in [kivy] section.

`docked` is a *BooleanProperty* and defaults to False.

font_size

`font_size`, specifies the size of the text on the virtual keyboard keys. It should be kept within limits to ensure the text does not extend beyond the bounds of the key or become too small to read.

New in version 1.10.0.

`font_size` is a *NumericProperty* and defaults to 20.

key_background_color

Key background color, in the format (r, g, b, a). If a key background is set, the color will be combined with the key background texture.

`key_background_color` is a *ColorProperty* and defaults to [1, 1, 1, 1].

Changed in version 2.0.0: Changed from *ListProperty* to *ColorProperty*.

key_background_down

Filename of the key background image for use when a touch is active on the widget.

key_background_down is a *StringProperty* and defaults to `atlas://data/images/defaulttheme/vkeyboard_key_down`.

key_background_normal

Filename of the key background image for use when no touches are active on the widget.

key_background_normal is a *StringProperty* and defaults to `atlas://data/images/defaulttheme/vkeyboard_key_normal`.

key_border

Key image border. Used for controlling the *border* property of the key.

key_border is a *ListProperty* and defaults to [16, 16, 16, 16]

key_disabled_background_normal

Filename of the key background image for use when no touches are active on the widget and vkeyboard is disabled.

New in version 1.8.0.

key_disabled_background_normal is a *StringProperty* and defaults to `atlas://data/images/defaulttheme/vkeyboard_disabled_key_normal`.

key_margin

Key margin, used to create space between keys. The margin is composed of four values, in pixels:

```
key_margin = [top, right, bottom, left]
```

key_margin is a *ListProperty* and defaults to [2, 2, 2, 2]

layout

Layout to use for the VKeyboard. By default, it will be the layout set in the configuration, according to the *keyboard_layout* in *[kivy]* section.

Changed in version 1.8.0: If layout is a .json filename, it will loaded and added to the available_layouts.

layout is a *StringProperty* and defaults to None.

layout_path

Path from which layouts are read.

layout is a *StringProperty* and defaults to <kivy_data_dir>/keyboards/

margin_hint

Margin hint, used as spacing between keyboard background and keys content. The margin is composed of four values, between 0 and 1:

```
margin_hint = [top, right, bottom, left]
```

The margin hints will be multiplied by width and height, according to their position.

margin_hint is a *ListProperty* and defaults to [.05, .06, .05, .06]

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.
See [relativelayout](#) for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

refresh(force=False)

(internal) Recreate the entire widget and graphics according to the selected layout.

setup_mode(*args)

Call this method when you want to readjust the keyboard according to options: **docked** or not, with attached **target** or not:

- If **docked** is True, it will call [setup_mode_dock\(\)](#)
- If **docked** is False, it will call [setup_mode_free\(\)](#)

Feel free to overload these methods to create new positioning behavior.

setup_mode_dock(*args)

Setup the keyboard in docked mode.

Dock mode will reset the rotation, disable translation, rotation and scale. Scale and position will be automatically adjusted to attach the keyboard to the bottom of the screen.

Note: Don't call this method directly, use [setup_mode\(\)](#) instead.

setup_mode_free()

Setup the keyboard in free mode.

Free mode is designed to let the user control the position and orientation of the keyboard. The only real usage is for a multiuser environment, but you might found other ways to use it. If a **target** is set, it will place the vkeyboard under the target.

Note: Don't call this method directly, use [setup_mode\(\)](#) instead.

target

Target widget associated with the VKeyboard. If set, it will be used to send keyboard events. If the VKeyboard mode is "free", it will also be used to set the initial position.

target is an [ObjectProperty](#) instance and defaults to None.

45.51 Widget class

The [Widget](#) class is the base class required for creating Widgets. This widget class was designed with a couple of principles in mind:

- *Event Driven*

Widget interaction is built on top of events that occur. If a property changes, the widget can respond to the change in the 'on_<propname>' callback. If nothing changes, nothing will be done. That's the main goal of the [Property](#) class.

- *Separation Of Concerns (the widget and its graphical representation)*

Widgets don't have a `draw()` method. This is done on purpose: The idea is to allow you to create your own graphical representation outside the widget class. Obviously you can still use all the available properties to do that, so that your representation properly reflects the widget's current state. Every widget has its own `Canvas` that you can use to draw. This separation allows Kivy to run your application in a very efficient manner.

- *Bounding Box / Collision*

Often you want to know if a certain point is within the bounds of your widget. An example would be a button widget where you only want to trigger an action when the button itself is actually touched. For this, you can use the `collide_point()` method, which will return True if the point you pass to it is inside the axis-aligned bounding box defined by the widget's position and size. If a simple AABB is not sufficient, you can override the method to perform the collision checks with more complex shapes, e.g. a polygon. You can also check if a widget collides with another widget with `collide_widget()`.

We also have some default values and behaviors that you should be aware of:

- A `Widget` is not a `Layout`: it will not change the position or the size of its children. If you want control over positioning or sizing, use a `Layout`.
- The default size of a widget is (100, 100). This is only changed if the parent is a `Layout`. For example, if you add a `Label` inside a `Button`, the label will not inherit the button's size or position because the button is not a `Layout`: it's just another `Widget`.
- The default size_hint is (1, 1). If the parent is a `Layout`, then the widget size will be the parent layout's size.
- `on_touch_down()`, `on_touch_move()`, `on_touch_up()` don't do any sort of collisions. If you want to know if the touch is inside your widget, use `collide_point()`.

45.51.1 Using Properties

When you read the documentation, all properties are described in the format:

`<name> is a <property class> and defaults to <default value>.`

e.g.

`text` is a `StringProperty` and defaults to ''.

If you want to be notified when the `pos` attribute changes, i.e. when the widget moves, you can bind your own callback function like this:

```
def callback_pos(instance, value):
    print('The widget', instance, 'moved to', value)

wid = Widget()
wid.bind(pos=callback_pos)
```

Read more about [Properties](#).

45.51.2 Basic drawing

Widgets support a range of drawing instructions that you can use to customize the look of your widgets and layouts. For example, to draw a background image for your widget, you can do the following:

```
def redraw(self, args):
    self.bg_rect.size = self.size
    self.bg_rect.pos = self.pos

widget = Widget()
with widget.canvas:
    widget.bg_rect = Rectangle(source="cover.jpg", pos=self.pos, size=self.
    →size)
widget.bind(pos=redraw, size=redraw)
```

To draw a background in kv:

```
Widget:
    canvas:
        Rectangle:
            source: "cover.jpg"
            size: self.size
            pos: self.pos
```

These examples only scratch the surface. Please see the [kivy.graphics](#) documentation for more information.

45.51.3 Widget touch event bubbling

When you catch touch events between multiple widgets, you often need to be aware of the order in which these events are propagated. In Kivy, events bubble up from the first child upwards through the other children. If a widget has children, the event is passed through its children before being passed on to the widget after it.

As the `on_touch_up()` method inserts widgets at index 0 by default, this means the event goes from the most recently added widget back to the first one added. Consider the following:

```
box = BoxLayout()
box.add_widget(Label(text="a"))
box.add_widget(Label(text="b"))
box.add_widget(Label(text="c"))
```

The label with text “c” gets the event first, “b” second and “a” last. You can reverse this order by manually specifying the index:

```
box = BoxLayout()
box.add_widget(Label(text="a"), index=0)
box.add_widget(Label(text="b"), index=1)
box.add_widget(Label(text="c"), index=2)
```

Now the order would be “a”, “b” then “c”. One thing to keep in mind when using kv is that declaring a widget uses the `add_widget()` method for insertion. Hence, using

```
BoxLayout:
    MyLabel:
```

(continues on next page)

```

        text: "a"
MyLabel:
    text: "b"
MyLabel:
    text: "c"

```

would result in the event order “c”, “b” then “a” as “c” was actually the last added widget. It thus has index 0, “b” index 1 and “a” index 2. Effectively, the child order is the reverse of its listed order.

This ordering is the same for the `on_touch_move()` and `on_touch_up()` events.

In order to stop this event bubbling, a method can return `True`. This tells Kivy the event has been handled and the event propagation stops. For example:

```

class MyWidget(Widget):
    def on_touch_down(self, touch):
        If <some_condition>:
            # Do stuff here and kill the event
            return True
        else:
            return super(MyWidget, self).on_touch_down(touch)

```

This approach gives you good control over exactly how events are dispatched and managed. Sometimes, however, you may wish to let the event be completely propagated before taking action. You can use the `Clock` to help you here:

```

class MyWidget(Label):
    def on_touch_down(self, touch, after=False):
        if after:
            print "Fired after the event has been dispatched!"
        else:
            Clock.schedule_once(lambda dt: self.on_touch_down(touch, True))
            return super(MyWidget, self).on_touch_down(touch)

```

45.51.4 Usage of `Widget.center`, `Widget.right`, and `Widget.top`

A common mistake when using one of the computed properties such as `Widget.right` is to use it to make a widget follow its parent with a KV rule such as `right: self.parent.right`. Consider, for example:

```

FloatLayout:
    id: layout
    width: 100
    Widget:
        id: wid
        right: layout.right

```

The (mistaken) expectation is that this rule ensures that `wid.right` will always be whatever layout’s `right` is - that is `wid.right` and `layout.right` will always be identical. In actual fact, this rule only says that “whenever layout’s `right` changes, `wid.right` will be set to that value”. The difference being that as long as `layout.right` doesn’t change, `wid.right` could be anything, even a value that will make them different.

Specifically, for the KV code above, consider the following example:

```
>>> print(layout.right, wid.right)
(100, 100)
>>> wid.x = 200
>>> print(layout.right, wid.right)
(100, 300)
```

As can be seen, initially they are in sync, however, when we change `wid.x` they go out of sync because `layout.right` is not changed and the rule is not triggered.

The proper way to make the widget follow its parent's right is to use `Widget.pos_hint`. If instead of `right: layout.right` we did `pos_hint: {'right': 1}`, then the widgets right will always be set to be at the parent's right at each layout update.

class `kivy.uix.widget.Widget(**kwargs)`
Bases: `kivy.uix.widget.WidgetBase`

Widget class. See module documentation for more information.

Events

`on_touch_down: (touch,)` Fired when a new touch event occurs. `touch` is the touch object.

`on_touch_move: (touch,)` Fired when an existing touch moves. `touch` is the touch object.

`on_touch_up: (touch,)` Fired when an existing touch disappears. `touch` is the touch object.

`on_kv_post: (base_widget,)` Fired after all the kv rules associated with the widget and all other widgets that are in any of those rules have had all their kv rules applied. `base_widget` is the base-most widget whose instantiation triggered the kv rules (i.e. the widget instantiated from Python, e.g. `MyWidget()`).

Changed in version 1.11.0.

Warning: Adding a `__del__` method to a class derived from Widget with Python prior to 3.4 will disable automatic garbage collection for instances of that class. This is because the Widget class creates reference cycles, thereby preventing garbage collection.

Changed in version 1.0.9: Everything related to event properties has been moved to the `EventDispatcher`. Event properties can now be used when constructing a simple class without subclassing `Widget`.

Changed in version 1.5.0: The constructor now accepts `on_*` arguments to automatically bind callbacks to properties or events, as in the Kv language.

add_widget(widget, index=0, canvas=None)

Add a new widget as a child of this widget.

Parameters

`widget: Widget` Widget to add to our list of children.

`index: int, defaults to 0` Index to insert the widget in the list. Notice that the default of 0 means the widget is inserted at the beginning of the list and will thus be drawn on top of other sibling widgets. For a full discussion of the index and widget hierarchy, please see the `Widgets Programming Guide`.

New in version 1.0.5.

canvas: str, defaults to None Canvas to add widget's canvas to. Can be 'before', 'after' or None for the default canvas.

New in version 1.9.0.

```
>>> from kivy.uix.button import Button
>>> from kivy.uix.slider import Slider
>>> root = Widget()
>>> root.add_widget(Button())
>>> slider = Slider()
>>> root.add_widget(slider)
```

apply_class_lang_rules(*root=None, ignored_consts={}, rule_children=None*)

Method that is called by kivy to apply the kv rules of this widget's class.

Parameters

root: Widget The root widget that instantiated this widget in kv, if the widget was instantiated in kv, otherwise **None**.

ignored_consts: set (internal) See [apply\(\)](#).

rule_children: list (internal) See [apply\(\)](#).

This is useful to be able to execute code before/after the class kv rules are applied to the widget. E.g. if the kv code requires some properties to be initialized before it is used in a binding rule. If overwriting remember to call `super`, otherwise the kv rules will not be applied.

In the following example,

```
class MyWidget(Widget):
    pass

class OtherWidget(MyWidget):
    pass
```

```
<MyWidget>: my_prop: some_value
<OtherWidget>: other_prop: some_value
```

When `OtherWidget` is instantiated with `OtherWidget()`, the widget's [apply_class_lang_rules\(\)](#) is called and it applies the kv rules of this class - `<MyWidget>` and `<OtherWidget>`.

Similarly, when the widget is instantiated from kv, e.g.

```
<MyBox@BoxLayout>:
    height: 55
    OtherWidget:
        width: 124
```

`OtherWidget`'s [apply_class_lang_rules\(\)](#) is called and it applies the kv rules of this class - `<MyWidget>` and `<OtherWidget>`.

Note: It applies only the class rules not the instance rules. I.e. in the above kv example in the `MyBox` rule when `OtherWidget` is instantiated, its [apply_class_lang_rules\(\)](#) applies the `<MyWidget>` and `<OtherWidget>` rules to it - it does not apply the `width: 124` rule.

The `width: 124` rule is part of the `MyBox` rule and is applied by the `MyBox`'s instance's `apply_class_lang_rules()`.

Changed in version 1.11.0.

canvas = None

Canvas of the widget.

The canvas is a graphics object that contains all the drawing instructions for the graphical representation of the widget.

There are no general properties for the Widget class, such as background color, to keep the design simple and lean. Some derived classes, such as Button, do add such convenience properties but generally the developer is responsible for implementing the graphics representation for a custom widget from the ground up. See the derived widget classes for patterns to follow and extend.

See [Canvas](#) for more information about the usage.

center

Center position of the widget.

`center` is a [ReferenceListProperty](#) of (`center_x`, `center_y`) properties.

center_x

X center position of the widget.

`center_x` is an [AliasProperty](#) of (`x + width / 2.`).

center_y

Y center position of the widget.

`center_y` is an [AliasProperty](#) of (`y + height / 2.`).

children

List of children of this widget.

`children` is a [ListProperty](#) and defaults to an empty list.

Use `add_widget()` and `remove_widget()` for manipulating the children list. Don't manipulate the children list directly unless you know what you are doing.

clear_widgets(children=None)

Remove all (or the specified) `children` of this widget. If the 'children' argument is specified, it should be a list (or filtered list) of children of the current widget.

Changed in version 1.8.0: The `children` argument can be used to specify the children you want to remove.

Changed in version 2.1.0: Specifying an empty `children` list leaves the widgets unchanged. Previously it was treated like `None` and all children were removed.

cls

Class of the widget, used for styling.

collide_point(x, y)

Check if a point (x, y) is inside the widget's axis aligned bounding box.

Parameters

`x: numeric` x position of the point (in parent coordinates)

`y: numeric` y position of the point (in parent coordinates)

Returns A bool. True if the point is inside the bounding box, False otherwise.

```
>>> Widget(pos=(10, 10), size=(50, 50)).collide_point(40, 40)
True
```

collide_widget(wid)

Check if another widget collides with this widget. This function performs an axis-aligned bounding box intersection test by default.

Parameters

wid: **Widget** class Widget to test collision with.

Returns bool. True if the other widget collides with this widget, False otherwise.

```
>>> wid = Widget(size=(50, 50))
>>> wid2 = Widget(size=(50, 50), pos=(25, 25))
>>> wid.collide_widget(wid2)
True
>>> wid2.pos = (55, 55)
>>> wid.collide_widget(wid2)
False
```

disabled

Indicates whether this widget can interact with input or not.

disabled is an **AliasProperty** and defaults to False.

Note:

1. Child Widgets, when added to a disabled widget, will be disabled automatically.
 2. Disabling/enabling a parent disables/enables all of its children.
-

New in version 1.8.0.

Changed in version 1.10.1: *disabled* was changed from a **BooleanProperty** to an **AliasProperty** to allow access to its previous state when a parent's disabled state is changed.

export_as_image(*args, **kwargs)

Return an core **Image** of the actual widget.

New in version 1.11.0.

export_to_png(filename, *args, **kwargs)

Saves an image of the widget and its children in png format at the specified filename. Works by removing the widget canvas from its parent, rendering to an **Fbo**, and calling **save()**.

Note: The image includes only this widget and its children. If you want to include widgets elsewhere in the tree, you must call **export_to_png()** from their common parent, or use **screenshot()** to capture the whole window.

Note: The image will be saved in png format, you should include the extension in your filename.

New in version 1.9.0.

Parameters

filename: str The filename with which to save the png.

scale: float The amount by which to scale the saved image, defaults to 1.

New in version 1.11.0.

get_parent_window()

Return the parent window.

Returns Instance of the parent window. Can be a *WindowBase* or *Widget*.

get_root_window()

Return the root window.

Returns Instance of the root window. Can be a *WindowBase* or *Widget*.

get_window_matrix(*x=0, y=0*)

Calculate the transformation matrix to convert between window and widget coordinates.

Parameters

x: float, defaults to 0 Translates the matrix on the x axis.

y: float, defaults to 0 Translates the matrix on the y axis.

height

Height of the widget.

height is a *NumericProperty* and defaults to 100.

Warning: Keep in mind that the *height* property is subject to layout logic and that this has not yet happened at the time of the widget's *__init__* method.

Warning: A negative height is not supported.

ids

This is a dictionary of ids defined in your kv language. This will only be populated if you use ids in your kv language code.

New in version 1.7.0.

ids is a *DictProperty* and defaults to an empty dict {}.

The *ids* are populated for each root level widget definition. For example:

```
# in kv
<MyWidget@Widget>:
    id: my_widget
    Label:
        id: label_widget
    Widget:
        id: inner_widget
        Label:
            id: inner_label
    TextInput:
        id: text_input
    OtherWidget:
        id: other_widget
```

(continues on next page)

```
<OtherWidget@Widget>
    id: other_widget
    Label:
        id: other_label
    TextInput:
        id: other_textinput
```

Then, in python:

```
>>> widget = MyWidget()
>>> print(widget.ids)
{'other_widget': <weakproxy at 041CFED0 to OtherWidget at 041BEC38>
 ↴,
 'inner_widget': <weakproxy at 04137EA0 to Widget at 04138228>,
 'inner_label': <weakproxy at 04143540 to Label at 04138260>,
 'label_widget': <weakproxy at 04137B70 to Label at 040F97A0>,
 'text_input': <weakproxy at 041BB5D0 to TextInput at 041BEC00>}
>>> print(widget.ids['other_widget'].ids)
{'other_textinput': <weakproxy at 041DBB40 to TextInput at
 ↴041BEF48>,
 'other_label': <weakproxy at 041DB570 to Label at 041BEEA0>}
>>> print(widget.ids['label_widget'].ids)
{}
```

motion_filter

Holds a dict of *type_id* to *list* of child widgets registered to receive motion events of *type_id*.

Don't change the property directly but use *register_for_motion_event()* and *unregister_for_motion_event()* to register and unregister for motion events. If *self* is registered it will always be the first element in the list.

New in version 2.1.0.

Warning: This is an experimental property and it remains so while this warning is present.

on_motion(*etype*, *me*)

Called when a motion event is received.

Parameters

etype: *str* Event type, one of "begin", "update" or "end"

me: *MotionEvent* Received motion event

Returns *bool* *True* to stop event dispatching

New in version 2.1.0.

Warning: This is an experimental method and it remains so while this warning is present.

on_touch_down(*touch*)

Receive a touch down event.

Parameters

touch: MotionEvent class Touch received. The touch is in parent coordinates.
See [relativeLayout](#) for a discussion on coordinate systems.

Returns bool If True, the dispatching of the touch event will stop. If False, the event will continue to be dispatched to the rest of the widget tree.

on_touch_move(touch)

Receive a touch move event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

on_touch_up(touch)

Receive a touch up event. The touch is in parent coordinates.

See [on_touch_down\(\)](#) for more information.

opacity

Opacity of the widget and all its children.

New in version 1.4.1.

The opacity attribute controls the opacity of the widget and its children. Be careful, it's a cumulative attribute: the value is multiplied by the current global opacity and the result is applied to the current context color.

For example, if the parent has an opacity of 0.5 and a child has an opacity of 0.2, the real opacity of the child will be $0.5 * 0.2 = 0.1$.

Then, the opacity is applied by the shader as:

```
frag_color = color * vec4(1.0, 1.0, 1.0, opacity);
```

opacity is a [NumericProperty](#) and defaults to 1.0.

parent

Parent of this widget. The parent of a widget is set when the widget is added to another widget and unset when the widget is removed from its parent.

parent is an [ObjectProperty](#) and defaults to None.

pos

Position of the widget.

pos is a [ReferenceListProperty](#) of (**x**, **y**) properties.

pos_hint

Position hint. This property allows you to set the position of the widget inside its parent layout (similar to size_hint).

For example, if you want to set the top of the widget to be at 90% height of its parent layout, you can write:

```
widget = Widget(pos_hint={'top': 0.9})
```

The keys 'x', 'right' and 'center_x' will use the parent width. The keys 'y', 'top' and 'center_y' will use the parent height.

See [Float Layout](#) for further reference.

Note: **pos_hint** is not used by all layouts. Check the documentation of the layout in question to see if it supports pos_hint.

pos_hint is an [ObjectProperty](#) containing a dict.

property proxy_ref

Return a proxy reference to the widget, i.e. without creating a reference to the widget. See [weakref.proxy](#) for more information.

New in version 1.7.2.

register_for_motion_event(type_id, widget=None)

Register to receive motion events of *type_id*.

Override [on_motion\(\)](#) or bind to *on_motion* event to handle the incoming motion events.

Parameters

type_id: str Motion event type id (eg. “touch”, “hover”, etc.)

widget: Widget Child widget or *self* if omitted

New in version 2.1.0.

Note: Method can be called multiple times with the same arguments.

Warning: This is an experimental method and it remains so while this warning is present.

remove_widget(widget)

Remove a widget from the children of this widget.

Parameters

widget: Widget Widget to remove from our children list.

```
>>> from kivy.uix.button import Button
>>> root = Widget()
>>> button = Button()
>>> root.add_widget(button)
>>> root.remove_widget(button)
```

right

Right position of the widget.

right is an *AliasProperty* of (*x + width*).

size

Size of the widget.

size is a *ReferenceListProperty* of (*width, height*) properties.

size_hint

Size hint.

size_hint is a *ReferenceListProperty* of (*size_hint_x, size_hint_y*) properties.

See *size_hint_x* for more information.

size_hint_max

Maximum size when using *size_hint*.

size_hint_max is a *ReferenceListProperty* of (*size_hint_max_x, size_hint_max_y*) properties.

New in version 1.10.0.

size_hint_max_x

When not None, the x-direction maximum size (in pixels, like `width`) when `size_hint_x` is also not None.

Similar to `size_hint_min_x`, except that it sets the maximum width.

`size_hint_max_x` is a *NumericProperty* and defaults to None.

New in version 1.10.0.

size_hint_max_y

When not None, the y-direction maximum size (in pixels, like `height`) when `size_hint_y` is also not None.

Similar to `size_hint_min_y`, except that it sets the maximum height.

`size_hint_max_y` is a *NumericProperty* and defaults to None.

New in version 1.10.0.

size_hint_min

Minimum size when using `size_hint`.

`size_hint_min` is a *ReferenceListProperty* of (`size_hint_min_x`, `size_hint_min_y`) properties.

New in version 1.10.0.

size_hint_min_x

When not None, the x-direction minimum size (in pixels, like `width`) when `size_hint_x` is also not None.

When `size_hint_x` is not None, it is the minimum width that the widget will be set due to the `size_hint_x`. I.e. when a smaller size would be set, `size_hint_min_x` is the value used instead for the widget width. When None, or when `size_hint_x` is None, `size_hint_min_x` doesn't do anything.

Only the *Layout* and *Window* classes make use of the hint.

`size_hint_min_x` is a *NumericProperty* and defaults to None.

New in version 1.10.0.

size_hint_min_y

When not None, the y-direction minimum size (in pixels, like `height`) when `size_hint_y` is also not None.

When `size_hint_y` is not None, it is the minimum height that the widget will be set due to the `size_hint_y`. I.e. when a smaller size would be set, `size_hint_min_y` is the value used instead for the widget height. When None, or when `size_hint_y` is None, `size_hint_min_y` doesn't do anything.

Only the *Layout* and *Window* classes make use of the hint.

`size_hint_min_y` is a *NumericProperty* and defaults to None.

New in version 1.10.0.

size_hint_x

x size hint. Represents how much space the widget should use in the direction of the x axis relative to its parent's width. Only the *Layout* and *Window* classes make use of the hint.

The `size_hint` is used by layouts for two purposes:

- When the layout considers widgets on their own rather than in relation to its other children, the `size_hint_x` is a direct proportion of the parent width, normally between 0.0 and 1.0. For instance, a widget with `size_hint_x=0.5` in a vertical `BoxLayout` will take up

half the BoxLayout's width, or a widget in a FloatLayout with `size_hint_x=0.2` will take up 20% of the FloatLayout width. If the `size_hint` is greater than 1, the widget will be wider than the parent.

- When multiple widgets can share a row of a layout, such as in a horizontal BoxLayout, their widths will be their `size_hint_x` as a fraction of the sum of widget `size_hints`. For instance, if the `size_hint_xs` are (0.5, 1.0, 0.5), the first widget will have a width of 25% of the parent width.

`size_hint_x` is a *NumericProperty* and defaults to 1.

`size_hint_y`

y size hint.

`size_hint_y` is a *NumericProperty* and defaults to 1.

See `size_hint_x` for more information, but with widths and heights swapped.

`to_local(x, y, relative=False)`

Transform parent coordinates to local (current widget) coordinates.

See `relativelayout` for details on the coordinate systems.

Parameters

`relative: bool, defaults to False` Change to True if you want to translate coordinates to relative widget coordinates.

`to_parent(x, y, relative=False)`

Transform local (current widget) coordinates to parent coordinates.

See `relativelayout` for details on the coordinate systems.

Parameters

`relative: bool, defaults to False` Change to True if you want to translate relative positions from a widget to its parent coordinates.

`to_widget(x, y, relative=False)`

Convert the coordinate from window to local (current widget) coordinates.

See `relativelayout` for details on the coordinate systems.

`to_window(x, y, initial=True, relative=False)`

If `initial` is True, the default, it transforms `parent` coordinates to window coordinates. Otherwise, it transforms `local` (current widget) coordinates to window coordinates.

See `relativelayout` for details on the coordinate systems.

`top`

Top position of the widget.

`top` is an *AliasProperty* of (`y + height`).

`unregister_for_motion_event(type_id, widget=None)`

Unregister to receive motion events of `type_id`.

Parameters

`type_id: str` Motion event type id (eg. "touch", "hover", etc.)

`widget: Widget` Child widget or `self` if omitted

New in version 2.1.0.

Note: Method can be called multiple times with the same arguments.

Warning: This is an experimental method and it remains so while this warning is present.

`walk`(*restrict=False*, *loopback=False*)

Iterator that walks the widget tree starting with this widget and goes forward returning widgets in the order in which layouts display them.

Parameters

restrict: bool, defaults to False If True, it will only iterate through the widget and its children (or children of its children etc.). Defaults to False.

loopback: bool, defaults to False If True, when the last widget in the tree is reached, it'll loop back to the uppermost root and start walking until we hit this widget again. Naturally, it can only loop back when *restrict* is False. Defaults to False.

Returns A generator that walks the tree, returning widgets in the forward layout order.

For example, given a tree with the following structure:

```
GridLayout:  
    Button  
BoxLayout:  
    id: box  
    Widget  
    Button  
Widget
```

walking this tree:

```
>>> # Call walk on box with loopback True, and restrict False  
>>> [type(widget) for widget in box.walk(loopback=True)]  
[<class 'BoxLayout'>, <class 'Widget'>, <class 'Button'>,  
 <class 'Widget'>, <class 'GridLayout'>, <class 'Button'>]  
>>> # Now with loopback False, and restrict False  
>>> [type(widget) for widget in box.walk()]  
[<class 'BoxLayout'>, <class 'Widget'>, <class 'Button'>,  
 <class 'Widget'>]  
>>> # Now with restrict True  
>>> [type(widget) for widget in box.walk(restrict=True)]  
[<class 'BoxLayout'>, <class 'Widget'>, <class 'Button'>]
```

New in version 1.9.0.

`walk_reverse`(*loopback=False*)

Iterator that walks the widget tree backwards starting with the widget before this, and going backwards returning widgets in the reverse order in which layouts display them.

This walks in the opposite direction of `walk()`, so a list of the tree generated with `walk()` will be in reverse order compared to the list generated with this, provided *loopback* is True.

Parameters

loopback: bool, defaults to False If True, when the uppermost root in the tree is reached, it'll loop back to the last widget and start walking back until after we hit widget again. Defaults to False.

Returns A generator that walks the tree, returning widgets in the reverse layout order.

For example, given a tree with the following structure:

```
GridLayout:  
    Button  
    BoxLayout:  
        id: box  
        Widget  
        Button  
    Widget
```

walking this tree:

```
>>> # Call walk on box with loopback True  
>>> [type(widget) for widget in box.walk_reverse(loopback=True)]  
[<class 'Button'>, <class 'GridLayout'>, <class 'Widget'>,  
 <class 'Button'>, <class 'Widget'>, <class 'BoxLayout'>]  
>>> # Now with loopback False  
>>> [type(widget) for widget in box.walk_reverse()]  
[<class 'Button'>, <class 'GridLayout'>]  
>>> forward = [w for w in box.walk(loopback=True)]  
>>> backward = [w for w in box.walk_reverse(loopback=True)]  
>>> forward == backward[::-1]  
True
```

New in version 1.9.0.

width

Width of the widget.

width is a *NumericProperty* and defaults to 100.

Warning: Keep in mind that the *width* property is subject to layout logic and that this has not yet happened at the time of the widget's *__init__* method.

Warning: A negative width is not supported.

x

X position of the widget.

x is a *NumericProperty* and defaults to 0.

y

Y position of the widget.

y is a *NumericProperty* and defaults to 0.

exception kivy.uix.widget.WidgetException

Bases: *Exception*

Fired when the widget gets an exception.

Part VI

APPENDIX

The appendix contains licensing information and an enumeration of all the different modules, classes, functions and variables available in Kivy.

LICENSE

Kivy is released and distributed under the terms of the MIT license starting version 1.7.2. Older versions are still under the LGPLv3.

You should have received a copy of the MIT license alongside your Kivy distribution. See the LICENSE file in the Kivy root folder. An online version of the license can be found at:

<https://github.com/kivy/kivy/blob/master/LICENSE>

In a nutshell, the license allows you to use Kivy in your own projects regardless of whether they are open source, closed source, commercial or free. Even if the license doesn't require it, we would really appreciate when you make changes to the Kivy sourcecode **itself**, share those changes with us!

For a list of authors, please see the file AUTHORS that accompanies the Kivy source code distribution (next to LICENSE).

Kivy – Copyright 2010-2022, The Kivy Authors.

PYTHON MODULE INDEX

k
kivy, 187
kivy._version, 188
kivy.animation, 188
kivy.app, 197
kivy.atlas, 213
kivy.base, 255
kivy.cache, 216
kivy.clock, 218
kivy.compat, 233
kivy.config, 233
kivy.context, 240
kivy.core, 297
kivy.core.audio, 297
kivy.core.camera, 299
kivy.core.clipboard, 300
kivy.core.gl, 300
kivy.core.image, 301
kivy.core.spelling, 305
kivy.core.text, 306
kivy.core.text.markup, 313
kivy.core.text.text_layout, 310
kivy.core.video, 315
kivy.core.window, 316
kivy.deps, 335
kivy.effects, 337
kivy.effects.dampedscroll, 337
kivy.effects.kinetic, 338
kivy.effects.opacityscroll, 340
kivy.effects.scroll, 340
kivy.event, 240
kivy.eventmanager, 343
kivy.factory, 249
kivy.garden, 347
kivy.geometry, 250
kivy.gesture, 251
kivy.graphics, 351
kivy.graphics.cgl, 378
kivy.graphics.compiler, 387
kivy.graphics.context, 382
kivy.graphics.context_instructions,
 378
kivy.graphics.fbo, 383
kivy.graphics.gl_instructions, 386
kivy.graphics.instructions, 373
kivy.graphics.opengl, 388
kivy.graphics.opengl_utils, 397
kivy.graphics.scissor_instructions,
 398
kivy.graphics.shader, 399
kivy.graphics.stencil_instructions,
 401
kivy.graphics.svg, 403
kivy.graphics.tesselator, 404
kivy.graphics.texture, 407
kivy.graphics.transformation, 414
kivy.graphics.vertex_instructions, 417
kivy.input, 429
kivy.input.factory, 452
kivy.input.motionevent, 447
kivy.input.postproc, 434
kivy.input.postproc.calibration, 434
kivy.input.postproc.dejitter, 435
kivy.input.postproc.doubletap, 435
kivy.input.postproc.ignorelist, 436
kivy.input.postproc.retaintouch, 436
kivy.input.postproc.tripletap, 436
kivy.input.provider, 453
kivy.input.providers, 437
kivy.input.providers.androidjoystick,
 437
kivy.input.providers.hidinput, 440
kivy.input.providers.leapfinger, 438
kivy.input.providers.linuxwacom, 442
kivy.input.providers.mactouch, 442
kivy.input.providers.mouse, 438
kivy.input.providers.mtdev, 441
kivy.input.providers.probesysfs, 437
kivy.input.providers.tuio, 443
kivy.input.providers.wm_common, 438
kivy.input.recorder, 444
kivy.input.shape, 453
kivy.interactive, 252
kivy.lang, 455
kivy.lang.builder, 472
kivy.lang.parser, 476
kivy.lib, 477

kivy.lib.ddsfile, 477
kivy.lib.gstplayer, 477
kivy.lib.mtdev, 478
kivy.loader, 211
kivy.logger, 258
kivy.metrics, 260
kivy.modules, 481
kivy.modules.console, 482
kivy.modules.inspector, 486
kivy.modules.joycursor, 488
kivy.modules.keybinding, 489
kivy.modules.monitor, 489
kivy.modules.recorder, 490
kivy.modules.screen, 490
kivy.modules.touchring, 491
kivy.modules.webdebugger, 491
kivy.multistroke, 263
kivy.network, 493
kivy.network.urlrequest, 493
kivy.parser, 272
kivy.properties, 273
kivy.resources, 288
kivy.storage, 497
kivy.storage.dictstore, 501
kivy.storage.jsonstore, 501
kivy.storage.redisstore, 501
kivy.support, 288
kivy.tools, 503
kivy.tools.packaging, 504
kivy.uix, 505
kivy.uix.accordion, 555
kivy.uix.actionbar, 560
kivy.uix.anchorlayout, 566
kivy.uix.behaviors, 505
kivy.uix.behaviors.button, 518
kivy.uix.behaviors.codenavigation, 519
kivy.uix.behaviors.compoundselection, 520
kivy.uix.behaviors.cover, 525
kivy.uix.behaviors.drag, 527
kivy.uix.behaviors.emacs, 528
kivy.uix.behaviors.focus, 529
kivy.uix.behaviors.knspase, 533
kivy.uix.behaviors.togglebutton, 539
kivy.uix.behaviors.touchripple, 540
kivy.uix.boxlayout, 567
kivy.uix.bubble, 570
kivy.uix.button, 574
kivy.uix.camera, 576
kivy.uix.carousel, 577
kivy.uix.checkbox, 581
kivy.uix.codeinput, 583
kivy.uix.colorpicker, 584
kivy.uix.dropdown, 586
kivy.uix.effectwidget, 590
kivy.uix.filechooser, 595
kivy.uix.floatlayout, 605
kivy.uix.gesturesurface, 607
kivy.uix.gridlayout, 610
kivy.uix.image, 614
kivy.uix.label, 618
kivy.uix.layout, 631
kivy.uix.modalview, 633
kivy.uix.pagelayout, 636
kivy.uix.popup, 638
kivy.uix.progressbar, 641
kivy.uix.recycleboxlayout, 642
kivy.uix.recyclegridlayout, 642
kivy.uix.recyclelayout, 643
kivy.uix.recycleview, 542
kivy.uix.recycleview.datamodel, 548
kivy.uix.recycleview.layout, 549
kivy.uix.recycleview.views, 552
kivy.uix.relativelayout, 645
kivy.uix.rst, 650
kivy.uix.sandbox, 653
kivy.uix.scatter, 655
kivy.uix.scatterlayout, 660
kivy.uix.screenmanager, 662
kivy.uix.scrollview, 671
kivy.uix.settings, 678
kivy.uix.slider, 688
kivy.uix.spinner, 693
kivy.uix.splitter, 695
kivy.uix.stacklayout, 698
kivy.uix.stencilview, 700
kivy.uix.switch, 700
kivy.uix.tabbedpanel, 702
kivy.uix.textinput, 709
kivy.uix.togglebutton, 723
kivy.uixtreeview, 724
kivy.uix.video, 730
kivy.uix.videoplayer, 733
kivy.uix.vkeyboard, 738
kivy.uix.widget, 742
kivy.utils, 289
kivy.vector, 291
kivy.weakmethod, 295
kivy.weakproxy, 295

INDEX

A

a (*kivy.graphics.ClearColor attribute*), 357
a (*kivy.graphics.Color attribute*), 358
a (*kivy.graphics.context_instructions.Color attribute*), 379
a (*kivy.graphics.gl_instructions.ClearColor attribute*), 386
a (*kivy.uix.colorpicker.ColorWheel attribute*), 585
AbstractStore (*class in kivy.storage*), 499
accept_stroke() (*kivy.uix.gesturesurface.GestureContainer method*), 608
Accordion (*class in kivy.uix.accordion*), 557
accordion (*kivy.uix.accordion.AccordionItem attribute*), 558
AccordionException, 557
AccordionItem (*class in kivy.uix.accordion*), 557
action_previous (*kivy.uix.actionbar.ActionView attribute*), 565
action_view (*kivy.uix.actionbar.ActionBar attribute*), 561
ActionBar (*class in kivy.uix.actionbar*), 561
ActionBarException, 561
ActionButton (*class in kivy.uix.actionbar*), 561
ActionCheck (*class in kivy.uix.actionbar*), 562
ActionDropDown (*class in kivy.uix.actionbar*), 562
ActionGroup (*class in kivy.uix.actionbar*), 562
ActionItem (*class in kivy.uix.actionbar*), 563
ActionOverflow (*class in kivy.uix.actionbar*), 563
ActionPrevious (*class in kivy.uix.actionbar*), 563
ActionSeparator (*class in kivy.uix.actionbar*), 564
ActionToggleButton (*class in kivy.uix.actionbar*), 565
ActionView (*class in kivy.uix.actionbar*), 565
activate() (*kivy.modules.console.ConsoleAddon method*), 486
activated (*kivy.modules.console.Console attribute*), 485
active (*kivy.uix.checkbox.CheckBox attribute*), 581
active (*kivy.uix.switch.Switch attribute*), 701
active_norm_pos (*kivy.uix.switch.Switch attribute*), 701
add() (*kivy.graphics.Canvas method*), 355

add() (*kivy.graphics.InstructionGroup method*), 361
add() (*kivy.graphics.instructions.Canvas method*), 374
add() (*kivy.graphics.instructions.InstructionGroup method*), 375
add_callback() (*kivy.config.ConfigParser method*), 238
add_contour() (*kivy.graphics.tesselator.Tesselator method*), 406
add_event_listener() (*kivy.base.EventLoopBase method*), 255
add_gesture() (*kivy.gesture.GestureDatabase method*), 251
add_gesture() (*kivy.multistroke.Recognizer method*), 268
add_handler() (*kivy.base.ExceptionManagerBase method*), 257
add_input_provider() (*kivy.base.EventLoopBase method*), 255
add_interface() (*kivy.uix.settings.Settings method*), 687
add_item() (*kivy.uix.settings.MenuSidebar method*), 683
add_json_panel() (*kivy.uix.settings.Settings method*), 687
add_kivy_panel() (*kivy.uix.settings.Settings method*), 687
add_mipmap() (*kivy.core.image.ImageData method*), 304
add_node() (*kivy.uixtreeview.TreeView method*), 726
add_panel() (*kivy.modules.console.Console method*), 485
add_panel() (*kivy.uix.settings.ContentPanel method*), 681
add_panel() (*kivy.uix.settings.InterfaceWithSidebar method*), 683
add_point() (*kivy.gesture.GestureStroke method*), 252
add_point() (*kivy.graphics.Point method*), 367
add_point() (*kivy.graphics.vertex_instructions.Point method*), 425
add_point() (*kivy.multistroke.UnistrokeTemplate method*), 271

add_postproc_module() (kivy.base.EventLoopBase method), 255
add_reload_observer() (kivy.graphics.context.Context method), 382
add_reload_observer() (kivy.graphics.Fbo method), 359
add_reload_observer() (kivy.graphics.fbo.Fbo method), 384
add_reload_observer() (kivy.graphics.texture.Texture method), 410
add_screen() (kivy.uix.screenmanager.ShaderTransition method), 670
add_screen() (kivy.uix.screenmanager.SwapTransition method), 670
add_screen() (kivy.uix.screenmanager.TransitionBase method), 671
add_stroke() (kivy.gesture.Gesture method), 251
add_stroke() (kivy.multistroke.Candidate method), 265
add_stroke() (kivy.multistroke.MultistrokeGesture method), 266
add_stroke() (kivy.uix.gesturesurface.GestureContainer method), 608
add_toolbar_widget() (kivy.modules.console.Console method), 485
add_widget() (kivy.core.window.WindowBase method), 319
add_widget() (kivy.uix.accordion.Accordion method), 557
add_widget() (kivy.uix.accordion.AccordionItem method), 558
add_widget() (kivy.uix.actionbar.ActionBar method), 561
add_widget() (kivy.uix.actionbar.ActionGroup method), 562
add_widget() (kivy.uix.actionbar.ActionOverflow method), 563
add_widget() (kivy.uix.actionbar.ActionView method), 565
add_widget() (kivy.uix.boxlayout.BoxLayout method), 568
add_widget() (kivy.uix.bubble.Bubble method), 572
add_widget() (kivy.uix.carousel.Carousel method), 578
add_widget() (kivy.uix.dropdown.DropDown method), 588
add_widget() (kivy.uix.effectwidget.EffectWidget method), 593
add_widget() (kivy.uix.filechooser.FileChooser method), 600
add_widget() (kivy.uix.floatlayout.FloatLayout method), 606
add_widget() (kivy.uix.layout.Layout method), 632
add_widget() (kivy.uix.popup.Popup method), 639
add_widget() (kivy.uix.recycleview.RecycleView method), 546
add_widget() (kivy.uix.sandbox.Sandbox method), 654
add_widget() (kivy.uix.scatterlayout.ScatterLayout method), 661
add_widget() (kivy.uix.screenmanager.ScreenManager method), 667
add_widget() (kivy.uix.scrollview.ScrollView method), 674
add_widget() (kivy.uix.settings.ContentPanel method), 681
add_widget() (kivy.uix.settings.SettingItem method), 684
add_widget() (kivy.uix.splitter.Splitter method), 696
add_widget() (kivy.uix.tabbedpanel.TabbedPanel method), 705
add_widget() (kivy.uix.tabbedpanel.TabbedPanelItem method), 708
add_widget() (kivy.uix.widget.Widget method), 746
adddefaultsection() (kivy.config.ConfigParser method), 239
addons (kivy.modules.console.Console attribute), 485
AdvancedEffectBase (class in kivy.uix.effectwidget), 592
after (kivy.graphics.Canvas attribute), 355
after (kivy.graphics.instructions.Canvas attribute), 374
AliasProperty (class in kivy.properties), 277
allow_copy (kivy.uix.textinput.TextInput attribute), 713
allow_fullscreen (kivy.uix.videoplayer.VideoPlayer attribute), 734
allow_no_selection (kivy.uix.behaviors.togglebutton.ToggleButtonBehavior attribute), 539
allow_no_selection (kivy.uix.behaviors.ToggleButtonBehavior attribute), 516
allow_screensaver (kivy.core.window.WindowBase attribute), 319
allow_stretch (kivy.uix.image.Image attribute), 615
always_overscroll (kivy.uix.scrollview.ScrollView attribute), 674
always_release (kivy.uix.behaviors.button.ButtonBehavior

attribute), 519
always_release (*kivy.uix.behaviors.ButtonBehavior attribute*), 507
always_release (*kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute*), 542
always_release (*kivy.uix.behaviors.TouchRippleButtonBehavior attribute*), 518
anchor_x (*kivy.graphics.svg.Svg attribute*), 403
anchor_x (*kivy.uix.anchorlayout.AnchorLayout attribute*), 566
anchor_y (*kivy.graphics.svg.Svg attribute*), 403
anchor_y (*kivy.uix.anchorlayout.AnchorLayout attribute*), 566
AnchorLayout (*class in kivy.uix.anchorlayout*), 566
anchors (*kivy.core.text.markup.MarkupLabel property*), 314
anchors (*kivy.uix.label.Label attribute*), 622
AndroidMotionEventProvider (*class in kivy.input.providers.androidjoystick*), 437
angle (*kivy.graphics.context_instructions.Rotate attribute*), 381
angle (*kivy.graphics.Rotate attribute*), 369
angle() (*kivy.vector.Vector method*), 293
angle_end (*kivy.graphics.Ellipse attribute*), 359
angle_end (*kivy.graphics.vertex_instructions.Ellipse attribute*), 419
angle_start (*kivy.graphics.Ellipse attribute*), 359
angle_start (*kivy.graphics.vertex_instructions.Ellipse attribute*), 419
anim_available (*kivy.core.image.Image property*), 302
anim_cancel_duration (*kivy.uix.carousel.Carousel attribute*), 578
anim_delay (*kivy.core.image.Image property*), 302
anim_delay (*kivy.uix.image.Image attribute*), 616
anim_duration (*kivy.uix.accordion.Accordion attribute*), 557
anim_func (*kivy.uix.accordion.Accordion attribute*), 557
anim_index (*kivy.core.image.Image property*), 302
anim_kwarg (*kivy.uix.pagelayout.PageLayout attribute*), 637
anim_loop (*kivy.uix.image.Image attribute*), 616
anim_move_duration (*kivy.uix.carousel.Carousel attribute*), 578
anim_reset() (*kivy.core.image.Image method*), 302
anim_type (*kivy.uix.carousel.Carousel attribute*), 578
animated_properties (*kivy.animation.Animation property*), 190
Animation (*class in kivy.animation*), 190
AnimationTransition (*class in kivy.animation*), 191
annotations (*kivy.uix.videoplayer.VideoPlayer attribute*), 735
App (*class in kivy.app*), 204
app_previous_button (*kivy.uix.actionbar.ActionPrevious attribute*), 564
app_bar_height (*kivy.uix.actionbar.ActionPrevious attribute*), 564
app_icon_width (*kivy.uix.actionbar.ActionPrevious attribute*), 564
append() (*kivy.cache.Cache static method*), 216
apply() (*kivy.lang.builder.BuilderBase method*), 472
apply() (*kivy.lang.BuilderBase method*), 468
apply_class_lang_rules() (*kivy.uix.widget.Widget method*), 747
apply_property() (*kivy.event.EventDispatcher method*), 241
apply_rules() (*kivy.lang.builder.BuilderBase method*), 473
apply_rules() (*kivy.lang.BuilderBase method*), 468
apply_selection() (*kivy.uix.recycleview.layout.LayoutSelectionBehavior method*), 549
apply_transform() (*kivy.uix.scatter.Scatter method*), 657
apply_transform_2d() (*kivy.input.MotionEvent method*), 429
apply_transform_2d() (*kivy.input.motionevent.MotionEvent method*), 448
ApplyContextMatrix (*class in kivy.graphics*), 352
arrow_image (*kivy.uix.bubble.Bubble attribute*), 572
arrow_pos (*kivy.uix.bubble.Bubble attribute*), 572
ask_update() (*kivy.graphics.Callback method*), 355
ask_update() (*kivy.graphics.Canvas method*), 355
ask_update() (*kivy.graphics.instructions.Callback method*), 373
ask_update() (*kivy.graphics.instructions.Canvas method*), 374
ask_update() (*kivy.graphics.texture.Texture method*), 410
ask_update() (*kivy.graphics.texture.TextureRegion method*), 413
async_clear() (*kivy.storage.AbstractStore method*), 499
async_count() (*kivy.storage.AbstractStore method*), 499
async_delete() (*kivy.storage.AbstractStore method*), 499
async_exists() (*kivy.storage.AbstractStore method*), 499
async_find() (*kivy.storage.AbstractStore method*), 499

async_get() (*kivy.storage.AbstractStore method*), [B](#)
 499
async_idle() (*kivy.base.EventLoopBase method*), [B](#)
 255
async_idle() (*kivy.clock.ClockBaseBehavior method*), [B](#)
 225
async_idle() (*kivy.clock.ClockBaseFreeInterruptOnly method*), [B](#)
 226
async_idle() (*kivy.clock.ClockBaseInterruptBehavior method*), [B](#)
 226
async_keys() (*kivy.storage.AbstractStore method*), [B](#)
 500
async_put() (*kivy.storage.AbstractStore method*), [B](#)
 500
async_run() (*kivy.app.App method*), [B](#)
 204
async_runTouchApp() (*in module kivy.app*), [B](#)
 210
async_runTouchApp() (*in module kivy.base*), [B](#)
 257
async_tick() (*kivy.clock.ClockBaseBehavior method*), [B](#)
 225
AsyncImage (*class in kivy.uix.image*), [B](#)
 615
Atlas (*class in kivy.atlas*), [B](#)
attach.recycleview() (*kivy.uix.recycleview.datamodel.RecycleDataAdapter method*), [B](#)
 548
attach.recycleview() (*kivy.uix.recycleview.datamodel.RecycleDataAdapter method*), [B](#)
 549
attach.recycleview() (*kivy.uix.recycleview.views.RecycleDataAdapter method*), [B](#)
 553
attach_to (*kivy.uix.dropdown.DropDown attribute*), [B](#)
 588
attach_to (*kivy.uix.modalview.ModalView attribute*), [B](#)
 634
auto_bring_to_front (*kivy.uix.scatter.Scatter attribute*), [B](#)
 657
auto_dismiss (*kivy.uix.dropdown.DropDown attribute*), [B](#)
 588
auto_dismiss (*kivy.uix.modalview.ModalView attribute*), [B](#)
 635
auto_indent (*kivy.uix.textinput.TextInput attribute*), [B](#)
 713
auto_scale (*kivy.graphics.BorderImage attribute*), [B](#)
 354
auto_scale (*kivy.graphics.vertex_instructions.BorderImage attribute*), [B](#)
 419
auto_width (*kivy.uix.dropdown.DropDown attribute*), [B](#)
 588
available_layouts (*kivy.uix.vkeyboard.VKeyboard attribute*), [B](#)
 740
axis (*kivy.graphics.context_instructions.Rotate attribute*), [B](#)
 381
axis (*kivy.graphics.Rotate attribute*), [B](#)
 369
b (*kivy.graphics.ClearColor attribute*), [B](#)
 357
b (*kivy.graphics.Color attribute*), [B](#)
 358
b (*kivy.graphics.context_instructions.Color attribute*), [B](#)
 380
b (*kivy.graphics.gl_instructions.ClearColor attribute*), [B](#)
 386
b (*kivy.uix.colorpicker.ColorWheel attribute*), [B](#)
 585
background (*kivy.uix.modalview.ModalView attribute*), [B](#)
 635
background (*kivy.uix.vkeyboard.VKeyboard attribute*), [B](#)
 740
background_active (*kivy.uix.textinput.TextInput attribute*), [B](#)
 713
background_border (*kivy.uix.vkeyboard.VKeyboard attribute*), [B](#)
 740
background_checkbox_disabled_down (*kivy.uix.checkbox.CheckBox attribute*), [B](#)
 581
background_checkbox_disabled_normal (*kivy.uix.checkbox.CheckBox attribute*), [B](#)
 581
background_checkbox_down (*kivy.uix.checkbox.CheckBox attribute*), [B](#)
 582
background_checkbox_normal (*kivy.uix.checkbox.CheckBox attribute*), [B](#)
 582
background_color (*kivy.uix.actionbar.ActionBar attribute*), [B](#)
 561
background_color (*kivy.uix.actionbar.ActionView attribute*), [B](#)
 565
background_color (*kivy.uix.bubble.Bubble attribute*), [B](#)
 572
background_color (*kivy.uix.button.Button attribute*), [B](#)
 575
background_color (*kivy.uix.effectwidget.EffectWidget attribute*), [B](#)
 593
background_color (*kivy.uix.modalview.ModalView attribute*), [B](#)
 635
background_color (*kivy.uix.rst.RstDocument attribute*), [B](#)
 651
background_color (*kivy.uix.tabbedpanel.TabbedPanel attribute*), [B](#)
 705
background_color (*kivy.uix.textinput.TextInput attribute*), [B](#)
 713
background_color (*kivy.uix.vkeyboard.VKeyboard attribute*), [B](#)
 740
background_disabled (*kivy.uix.vkeyboard.VKeyboard attribute*), [B](#)

740
background_disabled_down (*kivy.uix.button.Button attribute*), [575](#)
background_disabled_horizontal (*kivy.uix.slider.Slider attribute*), [689](#)
background_disabled_image (*kivy.uix.tabbedpanel.TabbedPanel attribute*), [706](#) at-
background_disabled_normal (*kivy.uix.accordion.AccordionItem attribute*), [558](#) at-
background_disabled_normal (*kivy.uix.button.Button attribute*), [575](#)
background_disabled_normal (*kivy.uix.textinput.TextInput attribute*), [713](#) at-
background_disabled_selected (*kivy.uix.accordion.AccordionItem attribute*), [558](#) at-
background_disabled_vertical (*kivy.uix.slider.Slider attribute*), [689](#)
background_down (*kivy.uix.actionbar.ActionItem attribute*), [563](#)
background_down (*kivy.uix.button.Button attribute*), [575](#)
background_horizontal (*kivy.uix.slider.Slider attribute*), [689](#)
background_image (*kivy.uix.actionbar.ActionBar attribute*), [561](#)
background_image (*kivy.uix.actionbar.ActionSeparator attribute*), [564](#) at-
background_image (*kivy.uix.actionbar.ActionView attribute*), [565](#)
background_image (*kivy.uix.bubble.Bubble attribute*), [572](#)
background_image (*kivy.uix.tabbedpanel.StripLayout attribute*), [705](#)
background_image (*kivy.uix.tabbedpanel.TabbedPanel attribute*), [706](#) at-
background_normal (*kivy.uix.accordion.AccordionItem attribute*), [558](#) at-
background_normal (*kivy.uix.actionbar.ActionItem attribute*), [563](#)
background_normal (*kivy.uix.button.Button attribute*), [575](#)
background_normal (*kivy.uix.textinput.TextInput attribute*), [713](#)
background_radio_disabled_down (*kivy.uix.checkbox.CheckBox attribute*), [582](#)
background_radio_disabled_normal (*kivy.uix.checkbox.CheckBox attribute*), [582](#)
background_radio_down (*kivy.uix.checkbox.CheckBox attribute*), [582](#)
background_radio_normal (*kivy.uix.checkbox.CheckBox attribute*), [582](#)
background_selected (*kivy.uix.accordion.AccordionItem attribute*), [558](#) at-
background_vertical (*kivy.uix.slider.Slider attribute*), [689](#)
background_width (*kivy.uix.slider.Slider attribute*), [690](#)
bar_color (*kivy.uix.scrollviewScrollView attribute*), [674](#)
bar_inactive_color (*kivy.uix.scrollviewScrollView attribute*), [674](#)
bar_margin (*kivy.uix.scrollviewScrollView attribute*), [674](#)
bar_pos (*kivy.uix.scrollviewScrollView attribute*), [675](#)
bar_pos_x (*kivy.uix.scrollviewScrollView attribute*), [675](#)
bar_pos_y (*kivy.uix.scrollviewScrollView attribute*), [675](#)
bar_width (*kivy.uix.scrollviewScrollView attribute*), [675](#)
base_direction (*kivy.uix.label.Label attribute*), [623](#)
base_direction (*kivy.uix.textinput.TextInput attribute*), [713](#)
base_font_size (*kivy.uix.rst.RstDocument attribute*), [651](#)
bbox (*kivy.uix.scatter.Scatter attribute*), [657](#)
before (*kivy.graphics.Canvas attribute*), [355](#)
before (*kivy.graphics.instructions.Canvas attribute*), [374](#)
best (*kivy.multistroke.ProgressTracker property*), [268](#)
Bezier (*class in kivy.graphics*), [352](#)
Bezier (*class in kivy.graphics.vertex_instructions*), [417](#)
bezier (*kivy.graphics.Line attribute*), [363](#)
bezier (*kivy.graphics.vertex_instructions.Line attribute*), [421](#)
bezier_precision (*kivy.graphics.Line attribute*), [363](#)
bezier_precision (*kivy.graphics.vertex_instructions.Line attribute*), [421](#)
bind() (*kivy.event.EventDispatcher method*), [241](#)

bind() (*kivy.event.Observable* method), 249
bind() (*kivy.graphics.Fbo* method), 359
bind() (*kivy.graphics.fbo.Fbo* method), 384
bind() (*kivy.graphics.texture.Texture* method), 410
bind() (*kivy.graphics.texture.TextureRegion* method), 413
bind() (*kivy.lang.builder.Observable* method), 475
bind() (*kivy.lang.Observable* method), 471
bind() (*kivy.properties.Property* method), 286
BindTexture (*class* in *kivy.graphics*), 353
BindTexture (*class* in *kivy.graphics.context_instructions*), 378
blit_buffer() (*kivy.graphics.texture.Texture* method), 410
blit_data() (*kivy.graphics.texture.Texture* method), 411
bold (*kivy.uix.label.Label* attribute), 623
BooleanProperty (*class* in *kivy.properties*), 278
border (*kivy.graphics.BorderImage* attribute), 354
border (*kivy.graphics.vertex_instructions.BorderImage* attribute), 419
border (*kivy.uix.actionbar.ActionBar* attribute), 561
border (*kivy.uix.bubble.Bubble* attribute), 572
border (*kivy.uix.button.Button* attribute), 575
border (*kivy.uix.modalview.ModalView* attribute), 635
border (*kivy.uix.pagelayout.PageLayout* attribute), 637
border (*kivy.uix.splitter.Splitter* attribute), 696
border (*kivy.uix.tabbedpanel.StripLayout* attribute), 705
border (*kivy.uix.tabbedpanel.TabbedPanel* attribute), 706
border (*kivy.uix.textinput.TextInput* attribute), 714
border_auto_scale (*kivy.uix.bubble.Bubble* attribute), 573
border_horizontal (*kivy.uix.slider.Slider* attribute), 690
border_vertical (*kivy.uix.slider.Slider* attribute), 690
BorderImage (*class* in *kivy.graphics*), 353
BorderImage (*class* in *kivy.graphics.vertex_instructions*), 418
borderless (*kivy.core.window.WindowBase* attribute), 319
boundary() (*in module kivy.utils*), 289
BoundedNumericProperty (*class* in *kivy.properties*), 278
bounds (*kivy.properties.BoundedNumericProperty* attribute), 279
BoxLayout (*class* in *kivy.uix.boxlayout*), 568
Bubble (*class* in *kivy.uix.bubble*), 572
BubbleButton (*class* in *kivy.uix.bubble*), 573
BubbleContent (*class* in *kivy.uix.bubble*), 574
bufferfmt (*kivy.graphics.texture.Texture* attribute), 411
build() (*kivy.app.App* method), 205
build_config() (*kivy.app.App* method), 205
build_settings() (*kivy.app.App* method), 205
Builder (*in module kivy.lang.builder*), 472
BuilderBase (*class* in *kivy.lang*), 468
BuilderBase (*class* in *kivy.lang.builder*), 472
BuilderException, 471, 475
Button (*class* in *kivy.uix.button*), 574
button (*kivy.input MotionEvent* attribute), 429
button (*kivy.input.motionevent MotionEvent* attribute), 448
ButtonBehavior (*class* in *kivy.uix.behaviors*), 506
ButtonBehavior (*class* in *kivy.uix.behaviors.button*), 518
buttons_layout (*kivy.uix.settings.MenuSidebar* attribute), 683

C

Cache (*class* in *kivy.cache*), 216
Callback (*class* in *kivy.graphics*), 354
Callback (*class* in *kivy.graphics.instructions*), 373
callback (*kivy.clock.ClockEvent* attribute), 227
callback (*kivy.core.window.Keyboard* attribute), 317
callback (*kivy.graphics.Callback* attribute), 355
callback (*kivy.graphics.instructions.Callback* attribute), 374
callback (*kivy.uix.vkeyboard.VKeyboard* attribute), 740
Camera (*class* in *kivy.uix.camera*), 576
CameraBase (*class* in *kivy.core.camera*), 299
cancel() (*kivy.animation.Animation* method), 190
cancel() (*kivy.clock.ClockEvent* method), 227
cancel() (*kivy.effects.kinetic.KineticEffect* method), 338
cancel() (*kivy.network.urlrequest.UrlRequest* method), 495
cancel() (*kivy.uix.filechooser.FileChooserController* method), 601
cancel() (*kivy.uix.filechooser.FileChooserProgressBase* method), 604
cancel_all() (*kivy.animation.Animation* static method), 190
cancel_property() (*kivy.animation.Animation* method), 191
cancel_selection() (*kivy.uix.textinput.TextInput* method), 714
Candidate (*class* in *kivy.multistroke*), 264
Canvas (*class* in *kivy.graphics*), 355
Canvas (*class* in *kivy.graphics.instructions*), 374
canvas (*kivy.uix.widget.Widget* attribute), 748
CanvasBase (*class* in *kivy.graphics*), 356
CanvasBase (*class* in *kivy.graphics.instructions*), 375

`cap` (*kivy.graphics.Line* attribute), 363
`cap` (*kivy.graphics.vertex_instructions.Line* attribute), 421
`cap_precision` (*kivy.graphics.Line* attribute), 363
`cap_precision` (*kivy.graphics.vertex_instructions.Line* attribute), 421
`CardTransition` (class in *kivy.uix.screenmanager*), 665
`Carousel` (class in *kivy.uix.carousel*), 577
`center` (*kivy.core.window.WindowBase* attribute), 319
`center` (*kivy.uix.widget.Widget* attribute), 748
`center_stroke()` (*kivy.gesture.GestureStroke* method), 252
`center_x` (*kivy.uix.widget.Widget* attribute), 748
`center_y` (*kivy.uix.widget.Widget* attribute), 748
`cgl_get_backend_name()` (in module *kivy.graphics.cgl*), 378
`cgl_get_initialized_backend_name()` (in module *kivy.graphics.cgl*), 378
`cgl_init()` (in module *kivy.graphics.cgl*), 378
`ChangeState` (class in *kivy.graphics*), 356
`ChannelMixEffect` (class in *kivy.uix.effectwidget*), 592
`check()` (*kivy.core.spelling.SpellingBase* method), 305
`CheckBox` (class in *kivy.uix.checkbox*), 581
`children` (*kivy.core.window.WindowBase* attribute), 319
`children` (*kivy.graphics.InstructionGroup* attribute), 361
`children` (*kivy.graphics.instructions.InstructionGroup* attribute), 375
`children` (*kivy.uix.widget.Widget* attribute), 748
`chunk_size` (*kivy.network.urlrequest.UrlRequest* property), 495
`cid` (*kivy.clock.ClockEvent* attribute), 227
`circle` (*kivy.graphics.Line* attribute), 363
`circle` (*kivy.graphics.vertex_instructions.Line* attribute), 421
`circumcircle()` (in module *kivy.geometry*), 250
`clear()` (*kivy.core.window.WindowBase* method), 320
`clear()` (*kivy.graphics.Canvas* method), 355
`clear()` (*kivy.graphics.InstructionGroup* method), 361
`clear()` (*kivy.graphics.instructions.Canvas* method), 374
`clear()` (*kivy.graphics.instructions.InstructionGroup* method), 375
`clear()` (*kivy.storage.AbstractStore* method), 500
`clear()` (*kivy.utils.SafeList* method), 289
`clear_buffer()` (*kivy.graphics.Fbo* method), 360
`clear_buffer()` (*kivy.graphics.fbo.Fbo* method), 385
`clear_color` (*kivy.graphics.ClearBuffers* attribute), 356
`clear_color` (*kivy.graphics.Fbo* attribute), 360
`clear_color` (*kivy.graphics.fbo.Fbo* attribute), 385
`clear_color` (*kivy.graphics.gl_instructions.ClearBuffers* attribute), 386
`clear_depth` (*kivy.graphics.ClearBuffers* attribute), 356
`clear_depth` (*kivy.graphics.gl_instructions.ClearBuffers* attribute), 386
`clear_selection()` (*kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior* method), 522
`clear_selection()` (*kivy.uix.behaviors.CompoundSelectionBehavior* method), 507
`clear_stencil` (*kivy.graphics.ClearBuffers* attribute), 356
`clear_stencil` (*kivy.graphics.gl_instructions.ClearBuffers* attribute), 386
`clear_widgets()` (*kivy.uix.actionbar.ActionGroup* method), 562
`clear_widgets()` (*kivy.uix.bubble.Bubble* method), 573
`clear_widgets()` (*kivy.uix.carousel.Carousel* method), 578
`clear_widgets()` (*kivy.uix.dropdown.DropDown* method), 588
`clear_widgets()` (*kivy.uix.effectwidget.EffectWidget* method), 593
`clear_widgets()` (*kivy.uix.sandbox.Sandbox* method), 654
`clear_widgets()` (*kivy.uix.scatterlayout.ScatterLayout* method), 661
`clear_widgets()` (*kivy.uix.screenmanager.ScreenManager* method), 667
`clear_widgets()` (*kivy.uix.splitter.Splitter* method), 696
`clear_widgets()` (*kivy.uix.tabbedpanel.TabbedPanel* method), 706
`clear_widgets()` (*kivy.uix.widget.Widget* method), 748
`ClearBuffers` (class in *kivy.graphics*), 356
`ClearBuffers` (class in *kivy.graphics.gl_instructions*), 386
`ClearColor` (class in *kivy.graphics*), 356
`ClearColor` (class in *kivy.graphics.gl_instructions*), 386
`clearcolor` (*kivy.core.window.WindowBase* attribute), 320
`clearcolor` (*kivy.uix.screenmanager.ShaderTransition* attribute), 670
`Clock` (in module *kivy.clock*), 224
`clock` (*kivy.clock.ClockEvent* attribute), 227
`clock()` (in module *kivy.compat*), 233

clock_ended_callback (*kivy.clock.ClockEvent attribute*), 227
clock_resolution (*kivy.clock.CyClockBase attribute*), 228
ClockBase (*class in kivy.clock*), 224
ClockBaseBehavior (*class in kivy.clock*), 224
ClockBaseFreeInterruptAll (*class in kivy.clock*), 226
ClockBaseFreeInterruptOnly (*class in kivy.clock*), 226
ClockBaseInterrupt (*class in kivy.clock*), 226
ClockBaseInterruptBehavior (*class in kivy.clock*), 226
ClockBaseInterruptFreeBehavior (*class in kivy.clock*), 226
ClockEvent (*class in kivy.clock*), 227
ClockNotRunningError, 228
close (*kivy.graphics.Line attribute*), 364
close (*kivy.graphics.vertex_instructions.Line attribute*), 422
close() (*kivy.base.EventLoopBase method*), 255
close() (*kivy.core.window.WindowBase method*), 320
close_button (*kivy.uix.settings.MenuSidebar attribute*), 683
close_settings() (*kivy.app.App method*), 205
cls (*kivy.uix.widget.Widget attribute*), 748
cm (*kivy.metrics.MetricsBase attribute*), 261
cm() (*in module kivy.metrics*), 262
CodeInput (*class in kivy.uix.codeinput*), 583
CodeNavigationBehavior (*class in kivy.uix.behaviors*), 507
CodeNavigationBehavior (*class in kivy.uix.behaviors.codenavigation*), 519
col_default_width (*kivy.uix.gridlayout.GridLayout attribute*), 612
col_force_default (*kivy.uix.gridlayout.GridLayout attribute*), 612
collapse (*kivy.uix.accordion.AccordionItem attribute*), 559
collapse_alpha (*kivy.uix.accordion.AccordionItem attribute*), 559
collide_margin() (*kivy.uix.vkeyboard.VKeyboard method*), 740
collide_point() (*kivy.uix.scatter.Scatter method*), 657
collide_point() (*kivy.uix.scatter.ScatterPlane method*), 660
collide_point() (*kivy.uix.scatterlayout.ScatterPlane method*), 662
collide_point() (*kivy.uix.widget.Widget method*), 748
collide_widget() (*kivy.uix.widget.Widget method*), 749
Color (*class in kivy.graphics*), 357
Color (*class in kivy.graphics.context_instructions*), 379
color (*kivy.graphics.svg.Svg attribute*), 404
color (*kivy.uix.actionbar.ActionPrevious attribute*), 564
color (*kivy.uix.checkbox.CheckBox attribute*), 582
color (*kivy.uix.colorpicker.ColorPicker attribute*), 585
color (*kivy.uix.colorpicker.ColorWheel attribute*), 585
color (*kivy.uix.image.Image attribute*), 616
color (*kivy.uix.label.Label attribute*), 623
color_selected (*kivy.uixtreeview.TreeNode attribute*), 728
colorfmt (*kivy.graphics.texture.Texture attribute*), 411
ColorPicker (*class in kivy.uix.colorpicker*), 585
ColorProperty (*class in kivy.properties*), 279
colors (*kivy.uix.rst.RstDocument attribute*), 652
ColorWheel (*class in kivy.uix.colorpicker*), 585
cols (*kivy.uix.gridlayout.GridLayout attribute*), 612
cols_minimum (*kivy.uix.gridlayout.GridLayout attribute*), 612
complete_stroke() (*kivy.uix.gesturesurface.GestureContainer method*), 608
CompoundSelectionBehavior (*class in kivy.uix.behaviors*), 507
CompoundSelectionBehavior (*class in kivy.uix.behaviors.compoundselection*), 522
compute_visible_views() (*kivy.uix.recycleboxlayout.RecycleBoxLayout method*), 642
compute_visible_views() (*kivy.uix.recyclegridlayout.RecycleGridLayout method*), 643
compute_visible_views() (*kivy.uix.recycleview.layout.RecycleLayoutManagerBehavior method*), 552
Config (*in module kivy.config*), 238
config (*kivy.app.App attribute*), 205
config (*kivy.uix.settings.SettingsPanel attribute*), 688
ConfigParser (*class in kivy.config*), 238
ConfigParserProperty (*class in kivy.properties*), 280
Console (*class in kivy.modules.console*), 484
Console (*kivy.modules.console.ConsoleAddon attribute*), 486
ConsoleAddon (*class in kivy.modules.console*), 486
ConsoleButton (*class in kivy.modules.console*),

486
ConsoleLabel (*class in kivy.modules.console*), 486
ConsoleToggleButton (*class in kivy.modules.console*), 486
container (*kivy.uix.accordion.AccordionItem attribute*), 559
container (*kivy.uix.dropdown.DropDown attribute*), 589
container (*kivy.uix.settings.ContentPanel attribute*), 682
container_title (*kivy.uix.accordion.AccordionItem attribute*), 559
content (*kivy.uix.bubble.Bubble attribute*), 573
content (*kivy.uix.popup.Popup attribute*), 640
content (*kivy.uix.settings.InterfaceWithSidebar attribute*), 683
content (*kivy.uix.settings.SettingItem attribute*), 684
content (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 706
content (*kivy.uix.tabbedpanel.TabbedPanelHeader attribute*), 708
content_height (*kivy.core.text.LabelBase property*), 308
content_size (*kivy.core.text.LabelBase property*), 308
content_size (*kivy.uix.accordion.AccordionItem attribute*), 559
content_width (*kivy.core.text.LabelBase property*), 308
ContentPanel (*class in kivy.uix.settings*), 681
Context (*class in kivy.context*), 240
Context (*class in kivy.graphics.context*), 382
ContextInstruction (*class in kivy.graphics*), 358
ContextInstruction (*class in kivy.graphics.instructions*), 375
ContextualActionView (*class in kivy.uix.actionbar*), 565
convert_distance_to_scroll() (*kivy.uix.scrollview.ScrollView method*), 675
copy() (*kivy.uix.textinput.TextInput method*), 714
copy_to() (*kivy.input MotionEvent method*), 429
copy_to() (*kivy.input.motionevent MotionEvent method*), 449
CoreCriticalException, 297
count() (*kivy.storage.AbstractStore method*), 500
counter (*kivy.input.recorder.Recorder attribute*), 446
cover_pos (*kivy.uix.behaviors.cover.CoverBehavior attribute*), 526
cover_pos (*kivy.uix.behaviors.CoverBehavior attribute*), 511
cover_size (*kivy.uix.behaviors.cover.CoverBehavior attribute*), 526
cover_size (*kivy.uix.behaviors.CoverBehavior attribute*), 511
CoverBehavior (*class in kivy.uix.behaviors*), 511
CoverBehavior (*class in kivy.uix.behaviors.cover*), 526
create() (*kivy.atlas.Atlas static method*), 215
create() (*kivy.graphics.texture.Texture static method*), 411
create() (*kivy.input.providers.tuio.TuioMotionEventProvider static method*), 444
create_from() (*kivy.lang.builder.BuilderBase class method*), 473
create_from() (*kivy.lang.BuilderBase class method*), 469
create_from_data() (*kivy.graphics.texture.Texture static method*), 412
create_inspector() (*in module kivy.modules.inspector*), 487
create_joycursor() (*in module kivy.modules.joycursor*), 488
create_json_panel() (*kivy.uix.settings.Settings method*), 687
create_lifecycle_aware_trigger() (*kivy.clock.CyClockBase method*), 228
create_lifecycle_aware_trigger() (*kivy.clock.CyClockBaseFree method*), 231
create_lifecycle_aware_trigger_free() (*kivy.clock.CyClockBaseFree method*), 232
create_property() (*kivy.event.EventDispatcher method*), 243
create_settings() (*kivy.app.App method*), 205
create_trigger() (*kivy.clock.CyClockBase method*), 229
create_trigger() (*kivy.clock.CyClockBaseFree method*), 232
create_trigger_free() (*kivy.clock.CyClockBaseFree method*), 232
create_view() (*kivy.uix.recycleview.views.RecycleDataAdapter method*), 553
create_window() (*kivy.core.window.WindowBase method*), 320
current (*kivy.uix.screenmanager.ScreenManager attribute*), 667
current_color (*kivy.graphics.svg.Svg attribute*), 404
current_panel (*kivy.uix.settings.ContentPanel attribute*), 682
current_screen (*kivy.uix.screenmanager.ScreenManager attribute*), 667
current_slide (*kivy.uix.carousel.Carousel attribute*), 578
current_tab (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 706

current_uid (*kivy.uix.settings.ContentPanel attribute*), 682
cursor (*kivy.uix.textinput.TextInput attribute*), 714
cursor_blink (*kivy.uix.textinput.TextInput attribute*), 714
cursor_col (*kivy.uix.textinput.TextInput attribute*), 714
cursor_color (*kivy.uix.textinput.TextInput attribute*), 714
cursor_disabled_image (*kivy.uix.slider.Slider attribute*), 690
cursor_height (*kivy.uix.slider.Slider attribute*), 690
cursor_image (*kivy.uix.slider.Slider attribute*), 690
cursor_index() (*kivy.uix.textinput.TextInput method*), 714
cursor_offset() (*kivy.uix.textinput.TextInput method*), 714
cursor_pos (*kivy.uix.textinput.TextInput attribute*), 714
cursor_row (*kivy.uix.textinput.TextInput attribute*), 715
cursor_size (*kivy.uix.slider.Slider attribute*), 690
cursor_width (*kivy.uix.slider.Slider attribute*), 690
cursor_width (*kivy.uix.textinput.TextInput attribute*), 715
custom_titlebar (*kivy.core.window.WindowBase attribute*), 320
cut() (*kivy.uix.textinput.TextInput method*), 715
CyClockBase (*class in kivy.clock*), 228
CyClockBaseFree (*class in kivy.clock*), 231

D

DampedScrollEffect (*class in kivy.effects.dampedscroll*), 337
dash_length (*kivy.graphics.Bezier attribute*), 353
dash_length (*kivy.graphics.Line attribute*), 364
dash_length (*kivy.graphics.vertex_instructions.Bezier attribute*), 418
dash_length (*kivy.graphics.vertex_instructions.Line attribute*), 422
dash_offset (*kivy.graphics.Bezier attribute*), 353
dash_offset (*kivy.graphics.Line attribute*), 364
dash_offset (*kivy.graphics.vertex_instructions.Bezier attribute*), 418
dash_offset (*kivy.graphics.vertex_instructions.Line attribute*), 422
dashes (*kivy.graphics.Line attribute*), 364
dashes (*kivy.graphics.vertex_instructions.Line attribute*), 422
data (*kivy.core.image.ImageData property*), 304
data (*kivy.uix.recycleview.datamodel.RecycleDataModel attribute*), 548
data (*kivy.uix.recycleview.RecycleView attribute*), 547
data_model (*kivy.uix.recycleview.RecycleViewBehavior attribute*), 547
DDSEException, 478
deactivate() (*kivy.modules.console.ConsoleAddon method*), 486
decode_result() (*kivy.network.urlrequest.UrlRequest method*), 495
default_height (*kivy.uix.recyclelayout.RecycleLayout attribute*), 643
default_pos_hint
 (*kivy.uix.recyclelayout.RecycleLayout attribute*), 643
default_size (*kivy.uix.recyclelayout.RecycleLayout attribute*), 643
default_size_hint
 (*kivy.uix.recyclelayout.RecycleLayout attribute*), 643
default_size_hint_max
 (*kivy.uix.recyclelayout.RecycleLayout attribute*), 643
default_size_hint_min
 (*kivy.uix.recyclelayout.RecycleLayout attribute*), 643
default_size_hint_x
 (*kivy.uix.recyclelayout.RecycleLayout attribute*), 643
default_size_hint_x_max
 (*kivy.uix.recyclelayout.RecycleLayout attribute*), 644
default_size_hint_x_min
 (*kivy.uix.recyclelayout.RecycleLayout attribute*), 644
default_size_hint_y
 (*kivy.uix.recyclelayout.RecycleLayout attribute*), 644
default_size_hint_y_max
 (*kivy.uix.recyclelayout.RecycleLayout attribute*), 644
default_size_hint_y_min
 (*kivy.uix.recyclelayout.RecycleLayout attribute*), 644
default_tab (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 706
default_tab_cls (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 706
default_tab_content
 (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 707
default_tab_text
 (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 707
default_width (*kivy.uix.recyclelayout.RecycleLayout attribute*), 644
defaultvalue (*kivy.properties.Property attribute*), 286

delete() (*kivy.storage.AbstractStore* method), 500
delete_selection()
 (*kivy.uix.textinput.TextInput* method), 715
delete_word_left()
 (*kivy.uix.behaviors.emacs.EmacsBehavior* method), 529
delete_word_left()
 (*kivy.uix.behaviors.EmacsBehavior* method), 512
delete_word_right()
 (*kivy.uix.behaviors.emacs.EmacsBehavior* method), 529
delete_word_right()
 (*kivy.uix.behaviors.EmacsBehavior* method), 512
density (*kivy.metrics.MetricsBase* attribute), 261
depack() (*kivy.input MotionEvent* method), 429
depack() (*kivy.input.motionevent MotionEvent* method), 449
depack() (*kivy.input.providers.hidinput.HIDMotionEvent* method), 440
depack() (*kivy.input.providers.leapfinger.LeapFingerEdit* method), 438
depack() (*kivy.input.providers.linuxwacom.LinuxWacom* method), 442
depack() (*kivy.input.providers.mtdev.MTDMotionEvent* method), 441
depack() (*kivy.input.providers.tuio.Tuio2dCurMotionEvent* method), 443
depack() (*kivy.input.providers.tuio.Tuio2dObjMotionEvent* method), 443
deprecated() (in module *kivy.utils*), 289
desc (*kivy.uix.settings.SelectedItem* attribute), 685
deselect_node() (*kivy.uix.behaviors.compoundselection.CompoundSelection* method), 522
deselect_node() (*kivy.uix.behaviors.CompoundSelection* method), 508
deselect_node() (*kivy.uix.recycleview.layout.LayoutSelectionBehavior* method), 550
deselect_node() (*kivy.uix.treeview.TreeView* method), 726
destroy_settings() (*kivy.app.App* method), 205
detach_recycleview()
 (*kivy.uix.recycleview.datamodel.RecycleDataModel* method), 549
detach_recycleview()
 (*kivy.uix.recycleview.datamodel.RecycleDataModelBehavior* method), 549
detach_recycleview()
 (*kivy.uix.recycleview.views.RecycleDataAdapter* method), 553
device (*kivy.input MotionEvent* attribute), 429
device (*kivy.input.motionevent MotionEvent* attribute), 449
DictProperty (class in *kivy.properties*), 282
DictStore (class in *kivy.storage.dictstore*), 501
difference() (in module *kivy.utils*), 289
direction (*kivy.uix.carousel.Carousel* attribute), 578
direction (*kivy.uix.screenmanager.SlideTransition* attribute), 670
directory (*kivy.app.App* property), 206
dirselect (*kivy.uix.filechooser.FileChooserController* attribute), 601
dirselect (*kivy.uix.settings.SettingPath* attribute), 686
disable_hover (*kivy.input.providers.mouse.MouseMotionEventProvider* property), 439
disabled (*kivy.uix.settings.SelectedItem* attribute), 685
disabled (*kivy.uix.widget.Widget* attribute), 749
disabled_color (*kivy.uix.label.Label* attribute), 623
disabled_foreground_color
 (*kivy.uix.textinput.TextInput* attribute), 715
disabled_outline_color (*kivy.uix.label.Label* attribute), 623
dismiss (*kivy.uix.dropdown.DropDown* method), 589
dismiss() (*kivy.uix.modalview.ModalView* method), 635
dismiss_on_select
 (*kivy.uix.dropdown.DropDown* attribute), 589
dispatch() (*kivy.event.EventDispatcher* method), 244
dispatch() (*kivy.eventmanager.EventManagerBase* method), 244
dispatch() (*kivy.properties.Property* method), 286
dispatch_children()
 (*kivy.event.EventDispatcher* method), 244
dispatch_done()
 (*kivy.input MotionEvent* method), 429
dispatch_done() (*kivy.input.motionevent MotionEvent* method), 449
dispatch_generic()
 (*kivy.event.EventDispatcher* method), 244
dispatch_input() (*kivy.base.EventLoopBase* method), 255
dispatch_mode (*kivy.input MotionEvent* attribute), 430
dispatch_mode (*kivy.input.motionevent MotionEvent* attribute), 449
displacement (*kivy.effects.scroll.ScrollEffect* attribute), 340
display_border (*kivy.graphics.BorderImage* at-

tribute), 354
display_border (*kivy.graphics.vertex_instructions.Border* attribute), 419
display_settings() (*kivy.app.App* method), 206
distance() (*kivy.input MotionEvent* method), 430
distance() (*kivy.input.motionevent MotionEvent* method), 449
distance() (*kivy.vector.Vector* method), 293
distance2() (*kivy.vector.Vector* method), 293
do_backspace() (*kivy.uix.textinput.TextInput* method), 715
do_collide_after_children
 (*kivy.uix.scatter.Scatter* attribute), 658
do_cursor_movement()
 (*kivy.uix.textinput.TextInput* method), 715
do_default_tab (*kivy.uix.tabbedpanel.TabbedPanel* attribute), 707
do_layout() (*kivy.uix.anchorlayout.AnchorLayout* method), 566
do_layout() (*kivy.uix.boxlayout.BoxLayout* method), 568
do_layout() (*kivy.uix.floatlayout.FloatLayout* method), 606
do_layout() (*kivy.uix.gridlayout.GridLayout* method), 613
do_layout() (*kivy.uix.layout.Layout* method), 632
do_layout() (*kivy.uix.pagelayout.PageLayout* method), 637
do_layout() (*kivy.uix.recyclelayout.RecycleLayout* method), 644
do_layout() (*kivy.uix.relativelayout.RelativeLayout* method), 649
do_layout() (*kivy.uix.stacklayout.StackLayout* method), 698
do_redo() (*kivy.uix.textinput.TextInput* method), 716
do_rotation (*kivy.uix.scatter.Scatter* attribute), 658
do_scale (*kivy.uix.scatter.Scatter* attribute), 658
do_scroll (*kivy.uix.scrollview.ScrollView* attribute), 675
do_scroll_x (*kivy.uix.scrollview.ScrollView* attribute), 675
do_scroll_y (*kivy.uix.scrollview.ScrollView* attribute), 675
do_translation (*kivy.uix.scatter.Scatter* attribute), 658
do_translation_x (*kivy.uix.scatter.Scatter* attribute), 658
do_translation_y (*kivy.uix.scatter.Scatter* attribute), 658
do_undo() (*kivy.uix.textinput.TextInput* method), 716
do_wrap (*kivy.uix.textinput.TextInput* attribute), 716
docked (*kivy.uix.vkeyboard.VKeyboard* attribute), 740
document_root (*kivy.uix.rst.RstDocument* attribute), 652
dot() (*kivy.vector.Vector* method), 293
dot_product() (*kivy.gesture.Gesture* method), 251
double_tap_time (*kivy.input MotionEvent* attribute), 430
double_tap_time (*kivy.input.motionevent MotionEvent* attribute), 449
dp (*kivy.metrics.MetricsBase* attribute), 261
dp() (in module *kivy.metrics*), 262
dpi (*kivy.core.window.WindowBase* attribute), 320
dpi (*kivy.metrics.MetricsBase* attribute), 261
dpi2px() (in module *kivy.metrics*), 262
dpi_rounded (*kivy.metrics.MetricsBase* attribute), 262
dpos (*kivy.input MotionEvent* property), 430
dpos (*kivy.input.motionevent MotionEvent* property), 449
drag_distance (*kivy.uix.behaviors.drag.DragBehavior* attribute), 527
drag_distance (*kivy.uix.behaviors.DragBehavior* attribute), 511
drag_rect_height
 (*kivy.uix.behaviors.drag.DragBehavior* attribute), 527
drag_rect_height
 (*kivy.uix.behaviors.DragBehavior* attribute), 511
drag_rect_width (*kivy.uix.behaviors.drag.DragBehavior* attribute), 528
drag_rect_width (*kivy.uix.behaviors.DragBehavior* attribute), 512
drag_rect_x (*kivy.uix.behaviors.drag.DragBehavior* attribute), 528
drag_rect_x (*kivy.uix.behaviors.DragBehavior* attribute), 512
drag_rect_y (*kivy.uix.behaviors.drag.DragBehavior* attribute), 528
drag_rect_y (*kivy.uix.behaviors.DragBehavior* attribute), 512
drag_rectangle (*kivy.uix.behaviors.drag.DragBehavior* attribute), 528
drag_rectangle (*kivy.uix.behaviors.DragBehavior* attribute), 512
drag_threshold (*kivy.effects.scroll.ScrollEffect* attribute), 340
drag_timeout (*kivy.uix.behaviors.drag.DragBehavior* attribute), 528
drag_timeout (*kivy.uix.behaviors.DragBehavior* attribute), 512
DragBehavior (class in *kivy.uix.behaviors*), 511
DragBehavior (class in *kivy.uix.behaviors.drag*),

527
draw() (*kivy.graphics.Canvas method*), **356**
draw() (*kivy.graphics.instructions.Canvas method*),
374
DropDown (*class in kivy.uix.dropdown*), **587**
dropdown_cls (*kivy.uix.spinner.Spinner attribute*),
694
dropdown_width (*kivy.uix.actionbar.ActionGroup attribute*), **562**
dsx (*kivy.input MotionEvent attribute*), **430**
dsx (*kivy.input.motionevent MotionEvent attribute*),
449
dsy (*kivy.input MotionEvent attribute*), **430**
dsy (*kivy.input.motionevent MotionEvent attribute*),
449
dsz (*kivy.input MotionEvent attribute*), **430**
dsz (*kivy.input.motionevent MotionEvent attribute*),
449
duration (*kivy.animation.Animation property*), **191**
duration (*kivy.core.video.VideoBase property*), **315**
duration (*kivy.uix.screenmanager.FallOutTransition attribute*), **666**
duration (*kivy.uix.screenmanager.RiseInTransition attribute*), **666**
duration (*kivy.uix.screenmanager.TransitionBase attribute*), **671**
duration (*kivy.uix.video.Video attribute*), **731**
duration (*kivy.uix.videoplayer.VideoPlayer attribute*), **735**
duration (*kivy.uix.videoplayer.VideoPlayerAnnotation event attribute*), **737**
dx (*kivy.input MotionEvent attribute*), **430**
dx (*kivy.input.motionevent MotionEvent attribute*),
449
dy (*kivy.input MotionEvent attribute*), **430**
dy (*kivy.input.motionevent MotionEvent attribute*),
449
dz (*kivy.input MotionEvent attribute*), **430**
dz (*kivy.input.motionevent MotionEvent attribute*),
449
E
edge_damping (*kivy.effects.dampedscroll.DampedScrollView attribute*), **337**
effect_cls (*kivy.uix.scrollview.ScrollView attribute*), **675**
effect_x (*kivy.uix.scrollview.ScrollView attribute*),
675
effect_y (*kivy.uix.scrollview.ScrollView attribute*),
675
EffectBase (*class in kivy.uix.effectwidget*), **592**
effects (*kivy.uix.effectwidget.EffectWidget attribute*), **593**
EffectWidget (*class in kivy.uix.effectwidget*), **593**
element_count (*kivy.graphics.tesselator.Tesselator attribute*), **406**
Ellipse (*class in kivy.graphics*), **358**
Ellipse (*class in kivy.graphics.vertex_instructions*),
419
ellipse (*kivy.graphics.Line attribute*), **364**
ellipse (*kivy.graphics.vertex_instructions.Line attribute*), **422**
ellipsis_options (*kivy.uix.label.Label attribute*), **624**
EmacsBehavior (*class in kivy.uix.behaviors*), **512**
EmacsBehavior (*class in kivy.uix.behaviors.emacs*),
529
emit() (*kivy.logger.LoggerHistory method*), **259**
ensure_window() (*kivy.base.EventLoopBase method*), **256**
entry_released()
(kivy.uix.filechooser.FileChooserController method), **601**
entry_touched() (*kivy.uix.filechooser.FileChooserController method*), **601**
eos (*kivy.uix.video.Video attribute*), **731**
error (*kivy.network.urlrequest.UrlRequest property*), **495**
error_image (*kivy.loader.LoaderBase property*),
211
escape_markup() (*in module kivy.utils*), **290**
even_color (*kivy.uix.treeview.TreeViewNode attribute*), **728**
event_managers (*kivy.core.window.WindowBase attribute*), **321**
event_managers_dict
(kivy.core.window.WindowBase attribute), **321**
EventDispatcher (*class in kivy.event*), **240**
EventLoop (*in module kivy.base*), **255**
EventLoopBase (*class in kivy.base*), **255**
EventManagerBase (*class in kivy.eventmanager*),
344
events() (*kivy.event.EventDispatcher method*), **244**
ExceptionHandler (*class in kivy.base*), **257**
ExceptionManager (*in module kivy.base*), **257**
ExceptionManagerBase (*class in kivy.base*), **257**
exists() (*kivy.storage.AbstractStore method*), **500**
exit() (*kivy.base.EventLoopBase method*), **256**
export_as_image() (*kivy.uix.widget.Widget method*), **749**
export_gesture() (*kivy.multistroke.Recognizer method*), **268**
export_to_png() (*kivy.uix.widget.Widget method*), **749**
F
Factory (*in module kivy.factory*), **250**
FactoryException, **250**
FadeTransition (*class in kivy.uix.screenmanager*), **665**

FallOutTransition (class in *kivy.uix.screenmanager*), 665
fbind() (*kivy.event.EventDispatcher* method), 244
fbind() (*kivy.event.Observable* method), 249
fbind() (*kivy.lang.builder.Observable* method), 475
fbind() (*kivy.lang.Observable* method), 471
Fbo (class in *kivy.graphics*), 359
Fbo (class in *kivy.graphics.fbo*), 384
fbo (*kivy.uix.effectwidget.EffectBase* attribute), 592
fbo_list (*kivy.uix.effectwidget.EffectWidget* attribute), 594
file_encodings (*kivy.uix.filechooser.FileChooserConfig* attribute), 601
file_system (*kivy.uix.filechooser.FileChooserController* attribute), 601
FileChooser (class in *kivy.uix.filechooser*), 599
FileChooserController (class in *kivy.uix.filechooser*), 600
FileChooserIconLayout (class in *kivy.uix.filechooser*), 603
FileChooserIconView (class in *kivy.uix.filechooser*), 603
FileChooserListLayout (class in *kivy.uix.filechooser*), 604
FileChooserListView (class in *kivy.uix.filechooser*), 604
FileChooserProgressBase (class in *kivy.uix.filechooser*), 604
filename (*kivy.atlas.Atlas* attribute), 216
filename (*kivy.core.audio.Sound* attribute), 298
filename (*kivy.core.image.Image* property), 302
filename (*kivy.core.video.VideoBase* property), 315
filename (*kivy.input.recorder.Recorder* attribute), 446
files (*kivy.uix.filechooser.FileChooserController* attribute), 601
FileSystemAbstract (class in *kivy.uix.filechooser*), 604
FileSystemLocal (class in *kivy.uix.filechooser*), 605
filter() (*kivy.multistroke.Recognizer* method), 268
filter_dirs (*kivy.uix.filechooser.FileChooserController* attribute), 601
filters (*kivy.uix.filechooser.FileChooserController* attribute), 601
find() (*kivy.gesture.GestureDatabase* method), 251
find() (*kivy.storage.AbstractStore* method), 500
find_base_direction() (*kivy.core.text.LabelBase* static method), 308
find_colliding_gesture() (*kivy.uix.gesturesurface.GestureSurface* method), 609
find_double_tap() (*kivy.input.postproc.doubletap.InputPostproc* method), 436
find_triple_tap() (*kivy.input.postproc.tripletap.InputPostproc* method), 437
flag_data_update() (*kivy.graphics.Instruction* method), 360
flag_data_update() (*kivy.graphics.instructions.Instruction* method), 375
flag_update() (*kivy.graphics.Instruction* method), 360
flag_update() (*kivy.graphics.instructions.Instruction* method), 375
flag_update_canvas() (*kivy.graphics.context.Context* method), 382
flip() (*kivy.core.window.WindowBase* method), 321
flip_horizontal() (*kivy.graphics.texture.Texture* method), 412
flip_vertical (*kivy.core.image.ImageData* attribute), 304
flip_vertical() (*kivy.graphics.texture.Texture* method), 412
FloatLayout (class in *kivy.uix.floatlayout*), 606
flush() (*kivy.graphics.context.Context* method), 382
flush() (*kivy.logger.LoggerHistory* method), 259
fmt (*kivy.core.image.ImageData* attribute), 304
focus (*kivy.core.window.WindowBase* attribute), 321
focus (*kivy.uix.behaviors.focus.FocusBehavior* attribute), 530
focus (*kivy.uix.behaviors.FocusBehavior* attribute), 513
focus_next (*kivy.uix.behaviors.focus.FocusBehavior* attribute), 530
focus_next (*kivy.uix.behaviors.FocusBehavior* attribute), 513
focus_previous (*kivy.uix.behaviors.focus.FocusBehavior* attribute), 531
focus_previous (*kivy.uix.behaviors.FocusBehavior* attribute), 513
FocusBehavior (class in *kivy.uix.behaviors*), 512
FocusBehavior (class in *kivy.uix.behaviors.focus*), 530
focused (*kivy.uix.behaviors.focus.FocusBehavior* attribute), 531
focused (*kivy.uix.behaviors.FocusBehavior* attribute), 513
font_blended (*kivy.uix.label.Label* attribute), 624
font_context (*kivy.uix.label.Label* attribute), 624
font_context (*kivy.uix.textinput.TextInput* attribute), 716
font_family (*kivy.uix.label.Label* attribute), 624
font_family (*kivy.uix.textinput.TextInput* attribute), 624

tribute), 716
font_features (*kivy.uix.label.Label attribute*), 625
font_hinting (*kivy.uix.label.Label attribute*), 625
font_kerning (*kivy.uix.label.Label attribute*), 625
font_name (*kivy.uix.colorpicker.ColorPicker attribute*), 585
font_name (*kivy.uix.filechooser.FileChooserController attribute*), 602
font_name (*kivy.uix.label.Label attribute*), 625
font_name (*kivy.uix.textinput.TextInput attribute*), 717
font_size (*kivy.uix.label.Label attribute*), 625
font_size (*kivy.uix.textinput.TextInput attribute*), 717
font_size (*kivy.uix.vkeyboard.VKeyboard attribute*), 740
fontid (*kivy.core.text.LabelBase property*), 309
fontscale (*kivy.metrics.MetricsBase attribute*), 262
foreground_color (*kivy.uix.textinput.TextInput attribute*), 717
fork() (*kivy.uix.behaviors.knspaced.KNSpace method*), 537
frames (*kivy.clock.ClockBaseBehavior property*), 225
frames_displayed (*kivy.clock.ClockBaseBehavior property*), 225
frametime (*kivy.clock.ClockBaseBehavior property*), 225
free (*kivy.clock.FreeClockEvent attribute*), 232
FreeClockEvent (*class in kivy.clock*), 232
friction (*kivy.effects.kinetic.KineticEffect attribute*), 338
fs (*kivy.graphics.shader.Shader attribute*), 401
fs (*kivy.uix.screenmanager.ShaderTransition attribute*), 670
fullscreen (*kivy.core.window.WindowBase attribute*), 321
fullscreen (*kivy.uix.videoplayer.VideoPlayer attribute*), 735
funbind() (*kivy.event.EventDispatcher method*), 246
funbind() (*kivy.event.Observable method*), 249
funbind() (*kivy.lang.builder.Observable method*), 476
funbind() (*kivy.lang.Observable method*), 471
func_op (*kivy.graphics.stencil_instructions.StencilUse attribute*), 403
func_op (*kivy.graphics.StencilUse attribute*), 371
FXAAEffect (*class in kivy.uix.effectwidget*), 594

G

g (*kivy.graphics.ClearColor attribute*), 357
g (*kivy.graphics.Color attribute*), 358
g (*kivy.graphics.context_instructions.Color attribute*), 380
g (*kivy.graphics.gl_instructions.ClearColor attribute*), 386
g (*kivy.uix.colorpicker.ColorWheel attribute*), 585
garden_system_dir (*in module kivy.garden*), 349
Gesture (*class in kivy.gesture*), 251
gesture_to_str() (*kivy.gesture.GestureDatabase method*), 252
GestureContainer (*class in kivy.uix.gesturesurface*), 607
GestureDatabase (*class in kivy.gesture*), 251
GestureStroke (*class in kivy.gesture*), 252
GestureSurface (*class in kivy.uix.gesturesurface*), 608
get() (*kivy.cache.Cache static method*), 217
get() (*kivy.config.ConfigParser method*), 239
get() (*kivy.graphics.transformation.Matrix method*), 414
get() (*kivy.input.factory MotionEventFactory static method*), 452
get() (*kivy.input.MotionEventFactory static method*), 433
get() (*kivy.properties.AliasProperty method*), 278
get() (*kivy.properties.Property method*), 286
get() (*kivy.properties.ReferenceListProperty method*), 287
get() (*kivy.storage.AbstractStore method*), 500
get_angle_similarity()
(kivy.multistroke.Candidate method), 265
get_application_config() (*kivy.app.App method*), 206
get_application_icon() (*kivy.app.App method*), 206
get_application_name() (*kivy.app.App method*), 206
get_before_frame_events()
(kivy.clock.CyClockBase method), 229
get_boottime() (*kivy.clock.ClockBaseBehavior method*), 225
get_cached_extents() (*kivy.core.text.LabelBase method*), 309
get_callback() (*kivy.clock.ClockEvent method*), 227
get_clock_ended_callback()
(kivy.clock.ClockEvent method), 227
get_color_from_hex() (*in module kivy.utils*), 290
get_configparser() (*kivy.config.ConfigParser static method*), 239
get_connection_for_scheme()
(kivy.network.urlrequest.UrlRequest method), 495
get_current_context() (*in module kivy.context*), 240
get_cursor_from_index()
(kivy.uix.textinput.TextInput method),

get_cursor_from_xy() (kivy.uix.textinput.TextInput method), [717](#)
get_distance() (kivy.multistroke.MultistrokeGesture method), [266](#)
get_events() (kivy.clock.CyClockBase method), [229](#)
get_extents() (kivy.core.text.LabelBase method), [309](#)
get_focus_next() (kivy.uix.behaviors.focus.FocusBehavior method), [531](#)
get_focus_next() (kivy.uix.behaviors.FocusBehavior method), [513](#)
get_focus_previous() (kivy.uix.behaviors.focus.FocusBehavior method), [531](#)
get_focus_previous() (kivy.uix.behaviors.FocusBehavior method), [513](#)
get_format() (kivy.properties.NumericProperty method), [283](#)
get_fps() (kivy.clock.ClockBaseBehavior method), [225](#)
get_gesture() (kivy.uix.gesturesurface.GestureSurface method), [609](#)
get_gl_backend_name() (kivy.core.window.WindowBase method), [321](#)
get_group() (kivy.graphics.InstructionGroup method), [361](#)
get_group() (kivy.graphics.instructions.InstructionGroup method), [375](#)
get_hex_from_color() (in module kivy.utils), [290](#)
get_index_of_node() (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior method), [522](#)
get_index_of_node() (kivy.uix.behaviors.CompoundSelectionBehavior method), [508](#)
get_index_of_node() (kivy.uix.recycleview.layout.LayoutSelectionBehavior method), [550](#)
get_lastaccess() (kivy.cache.Cache static method), [217](#)
get_max() (kivy.properties.BoundedNumericProperty method), [279](#)
get_min() (kivy.properties.BoundedNumericProperty method), [279](#)
get_min_free_timeout() (kivy.clock.CyClockBaseFree method), [232](#)
get_min_timeout() (kivy.clock.CyClockBase method), [229](#)
get_mipmap() (kivy.core.image.ImageData method), [304](#)
get_nice_size() (kivy.uix.filechooser.FileChooserController method), [602](#)
get_node_at_pos() (kivy.uixtreeview.TreeView method), [726](#)
get_parent_window() (kivy.uix.widget.Widget method), [750](#)
get_pixel_color() (kivy.graphics.Fbo method), [360](#)
get_pixel_color() (kivy.graphics.fbo.Fbo method), [385](#)
get_pos() (kivy.core.audio.Sound method), [298](#)
get_property_observers() (kivy.event.EventDispatcher method), [246](#)
get_protractor_vector() (kivy.multistroke.Candidate method), [265](#)
get_random_color() (in module kivy.utils), [290](#)
get_region() (kivy.graphics.texture.Texture method), [412](#)
get_resolution() (kivy.clock.CyClockBase method), [229](#)
get_rfps() (kivy.clock.ClockBaseBehavior method), [225](#)
get_rigid_rotation() (kivy.gesture.Gesture method), [251](#)
get_root_window() (kivy.uix.widget.Widget method), [750](#)
get_running_app() (kivy.app.App static method), [206](#)
get_score() (kivy.gesture.Gesture method), [251](#)
get_screen() (kivy.uix.screenmanager.ScreenManager method), [667](#)
get_selectable_nodes() (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior method), [522](#)
get_selectable_nodes() (kivy.uix.behaviors.CompoundSelectionBehavior method), [508](#)
get_selectable_nodes() (kivy.uix.recycleview.layout.LayoutSelectionBehavior method), [550](#)
get_start_unit_vector() (kivy.multistroke.Candidate method), [265](#)
get_system_fonts_dir() (kivy.core.text.LabelBase static method), [309](#)
get_time() (kivy.clock.ClockBaseBehavior method), [225](#)
get_timestamp() (kivy.cache.Cache static method), [217](#)
get_value() (kivy.uix.settings.SettingsPanel

method), 688
`get_vectors()` (*kivy.uix.gesturesurface.GestureController* method), 608
`get_view()` (*kivy.uix.recycleview.views.RecycleDataAdapter* method), 553
`get_view_index_at()` (*kivy.uix.recycleboxlayout.RecycleBoxLayout* method), 642
`get_view_index_at()` (*kivy.uix.recyclegridlayout.RecycleGridLayout* method), 643
`get_view_index_at()` (*kivy.uix.recycleview.layout.RecycleLayoutManagerBehavior* method), 552
`get_visible_view()` (*kivy.uix.recycleview.views.RecycleDataAdapter* method), 553
`get_widgets()` (*kivy.uix.behaviors.togglebutton.ToggleButtonBehavior*, static method), 539
`get_widgets()` (*kivy.uix.behaviors.ToggleButtonBehavior*, static method), 516
`get_window_matrix()` (*kivy.uix.widget.Widget* method), 750
`getdefault()` (*kivy.config.ConfigParser* method), 239
`getdefaultint()` (*kivy.config.ConfigParser* method), 239
`getsize()` (*kivy.uix.filechooser.FileSystemAbstract* method), 604
`getsize()` (*kivy.uix.filechooser.FileSystemLocal* method), 605
`getter()` (*kivy.event.EventDispatcher* method), 246
`gl_backends_allowed` (*kivy.core.window.WindowBase* attribute), 321
`gl_backends_ignored` (*kivy.core.window.WindowBase* attribute), 321
`gl_dealloc()` (*kivy.graphics.context.Context* method), 382
`gl_get_extensions()` (in module *kivy.graphics.opengl_utils*), 397
`gl_get_texture_formats()` (in module *kivy.graphics.opengl_utils*), 397
`gl_get_version()` (in module *kivy.graphics.opengl_utils*), 397
`gl_get_version_major()` (in module *kivy.graphics.opengl_utils*), 397
`gl_get_version_minor()` (in module *kivy.graphics.opengl_utils*), 397
`gl_has_capability()` (in module *kivy.graphics.opengl_utils*), 397
`gl_has_extension()` (in module *kivy.graphics.opengl_utils*), 398
`gl_has_texture_conversion()` (in module *kivy.graphics.opengl_utils*), 398
`gl_has_texture_format()` (in module *kivy.graphics.opengl_utils*), 398
`gl_has_texture_native_format()` (in module *kivy.graphics.opengl_utils*), 398
`gl_init_resources()` (in module *kivy.graphics*), 373
`gl_init_resources()` (in module *kivy.graphics.context_instructions*), 382
`gl_init_symbols()` (in module *kivy.graphics.opengl*), 397
`gl_register_get_size()` (in module *kivy.graphics.opengl_utils*), 398
`glActiveTexture()` (in module *kivy.graphics.opengl*), 388
`glAttachShader()` (in module *kivy.graphics.opengl*), 388
`glBindAttribLocation()` (in module *kivy.graphics.opengl*), 388
`glBindBuffer()` (in module *kivy.graphics.opengl*), 388
`glBindFramebuffer()` (in module *kivy.graphics.opengl*), 388
`glBindRenderbuffer()` (in module *kivy.graphics.opengl*), 388
`glBindTexture()` (in module *kivy.graphics.opengl*), 388
`glBlendColor()` (in module *kivy.graphics.opengl*), 388
`glBlendEquation()` (in module *kivy.graphics.opengl*), 388
`glBlendEquationSeparate()` (in module *kivy.graphics.opengl*), 388
`glBlendFunc()` (in module *kivy.graphics.opengl*), 388
`glBlendFuncSeparate()` (in module *kivy.graphics.opengl*), 388
`glBufferData()` (in module *kivy.graphics.opengl*), 388
`glBufferSubData()` (in module *kivy.graphics.opengl*), 388
`glCheckFramebufferStatus()` (in module *kivy.graphics.opengl*), 388
`glClear()` (in module *kivy.graphics.opengl*), 388
`glClearColor()` (in module *kivy.graphics.opengl*), 388
`glClearStencil()` (in module *kivy.graphics.opengl*), 389
`glColorMask()` (in module *kivy.graphics.opengl*), 389
`glCompileShader()` (in module *kivy.graphics.opengl*), 389
`glCompressedTexImage2D()` (in module *kivy.graphics.opengl*), 389
`glCompressedTexSubImage2D()` (in module *kivy.graphics.opengl*), 389

glCopyTexImage2D() (in module <i>kivy.graphics.opengl</i>), 389	module	glGenTextures() (in module <i>kivy.graphics.opengl</i>), 390	module
glCopyTexSubImage2D() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetActiveAttrib() (in module <i>kivy.graphics.opengl</i>), 390	module
glCreateProgram() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetActiveUniform() (in module <i>kivy.graphics.opengl</i>), 391	module
glCreateShader() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetAttachedShaders() (in module <i>kivy.graphics.opengl</i>), 391	module
glCullFace() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetAttribLocation() (in module <i>kivy.graphics.opengl</i>), 391	module
glDeleteBuffers() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetBooleanv() (in module <i>kivy.graphics.opengl</i>), 391	module
glDeleteFramebuffers() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetBufferParameteriv() (in module <i>kivy.graphics.opengl</i>), 391	module
glDeleteProgram() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetError() (in module <i>kivy.graphics.opengl</i>), 391	module
glDeleteRenderbuffers() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetFloatv() (in module <i>kivy.graphics.opengl</i>), 391	module
glDeleteShader() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetFramebufferAttachmentParameteriv() (in module <i>kivy.graphics.opengl</i>), 391	module
glDeleteTextures() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetIntegerv() (in module <i>kivy.graphics.opengl</i>), 391	module
glDepthFunc() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetProgramInfoLog() (in module <i>kivy.graphics.opengl</i>), 391	module
glDepthMask() (in module <i>kivy.graphics.opengl</i>), 389	module	glGetProgramiv() (in module <i>kivy.graphics.opengl</i>), 391	module
glDetachShader() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetRenderbufferParameteriv() (in module <i>kivy.graphics.opengl</i>), 391	module
glDisable() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetShaderInfoLog() (in module <i>kivy.graphics.opengl</i>), 391	module
glDisableVertexAttribArray() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetShaderiv() (in module <i>kivy.graphics.opengl</i>), 392	module
glDrawArrays() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetShaderPrecisionFormat() (in module <i>kivy.graphics.opengl</i>), 392	module
glDrawElements() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetShaderSource() (in module <i>kivy.graphics.opengl</i>), 392	module
glEnable() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetString() (in module <i>kivy.graphics.opengl</i>), 392	module
glEnableVertexAttribArray() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetTexParameterfv() (in module <i>kivy.graphics.opengl</i>), 392	module
glFinish() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetTexParameteriv() (in module <i>kivy.graphics.opengl</i>), 392	module
glFlush() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetUniformfv() (in module <i>kivy.graphics.opengl</i>), 392	module
glFramebufferRenderbuffer() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetUniformiv() (in module <i>kivy.graphics.opengl</i>), 392	module
glFramebufferTexture2D() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetUniformLocation() (in module <i>kivy.graphics.opengl</i>), 392	module
glFrontFace() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetVertexAttribfv() (in module <i>kivy.graphics.opengl</i>), 392	module
glGenBuffers() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetVertexAttribiv() (in module <i>kivy.graphics.opengl</i>), 392	module
glGenerateMipmap() (in module <i>kivy.graphics.opengl</i>), 390	module	glGetVertexAttribPointerv() (in module <i>kivy.graphics.opengl</i>), 392	module
glGenFramebuffers() (in module <i>kivy.graphics.opengl</i>), 390	module	glHint() (in module <i>kivy.graphics.opengl</i>), 392	module
glGenRenderbuffers() (in module <i>kivy.graphics.opengl</i>), 390	module		

`glIsBuffer()` (in module `kivy.graphics.opengl`), 392
`glIsEnabled()` (in module `kivy.graphics.opengl`), 392
`glIsFramebuffer()` (in module `kivy.graphics.opengl`), 392
`glIsProgram()` (in module `kivy.graphics.opengl`), 393
`glIsRenderbuffer()` (in module `kivy.graphics.opengl`), 393
`glIsShader()` (in module `kivy.graphics.opengl`), 393
`glIsTexture()` (in module `kivy.graphics.opengl`), 393
`glLineWidth()` (in module `kivy.graphics.opengl`), 393
`glLinkProgram()` (in module `kivy.graphics.opengl`), 393
`glPixelStorei()` (in module `kivy.graphics.opengl`), 393
`glPolygonOffset()` (in module `kivy.graphics.opengl`), 393
`glReadPixels()` (in module `kivy.graphics.opengl`), 393
`glReleaseShaderCompiler()` (in module `kivy.graphics.opengl`), 393
`glRenderbufferStorage()` (in module `kivy.graphics.opengl`), 393
`glSampleCoverage()` (in module `kivy.graphics.opengl`), 393
`glScissor()` (in module `kivy.graphics.opengl`), 393
`glShaderBinary()` (in module `kivy.graphics.opengl`), 393
`glShaderSource()` (in module `kivy.graphics.opengl`), 393
`glsl` (`kivy.uix.effectwidget.EffectBase` attribute), 592
`glStencilFunc()` (in module `kivy.graphics.opengl`), 393
`glStencilFuncSeparate()` (in module `kivy.graphics.opengl`), 393
`glStencilMask()` (in module `kivy.graphics.opengl`), 394
`glStencilMaskSeparate()` (in module `kivy.graphics.opengl`), 394
`glStencilOp()` (in module `kivy.graphics.opengl`), 394
`glStencilOpSeparate()` (in module `kivy.graphics.opengl`), 394
`glTexImage2D()` (in module `kivy.graphics.opengl`), 394
`glTexParameterf()` (in module `kivy.graphics.opengl`), 394
`glTexParameterfv()` (in module `kivy.graphics.opengl`), 394
`glTexParameteri()` (in module `kivy.graphics.opengl`), 394
`glTexParameteriv()` (in module `kivy.graphics.opengl`), 394
`glTexSubImage2D()` (in module `kivy.graphics.opengl`), 394
`glUniform1f()` (in module `kivy.graphics.opengl`), 394
`glUniform1fv()` (in module `kivy.graphics.opengl`), 394
`glUniform1i()` (in module `kivy.graphics.opengl`), 394
`glUniform1iv()` (in module `kivy.graphics.opengl`), 394
`glUniform2f()` (in module `kivy.graphics.opengl`), 395
`glUniform2fv()` (in module `kivy.graphics.opengl`), 395
`glUniform2i()` (in module `kivy.graphics.opengl`), 395
`glUniform2iv()` (in module `kivy.graphics.opengl`), 395
`glUniform3f()` (in module `kivy.graphics.opengl`), 395
`glUniform3fv()` (in module `kivy.graphics.opengl`), 395
`glUniform3i()` (in module `kivy.graphics.opengl`), 395
`glUniform3iv()` (in module `kivy.graphics.opengl`), 395
`glUniform4f()` (in module `kivy.graphics.opengl`), 395
`glUniform4fv()` (in module `kivy.graphics.opengl`), 395
`glUniform4i()` (in module `kivy.graphics.opengl`), 395
`glUniform4iv()` (in module `kivy.graphics.opengl`), 395
`glUniformMatrix2fv()` (in module `kivy.graphics.opengl`), 396
`glUniformMatrix3fv()` (in module `kivy.graphics.opengl`), 396
`glUniformMatrix4fv()` (in module `kivy.graphics.opengl`), 396
`glUseProgram()` (in module `kivy.graphics.opengl`), 396
`glValidateProgram()` (in module `kivy.graphics.opengl`), 396
`glVertexAttrib1f()` (in module `kivy.graphics.opengl`), 396
`glVertexAttrib1fv()` (in module `kivy.graphics.opengl`), 396
`glVertexAttrib2f()` (in module `kivy.graphics.opengl`), 396
`glVertexAttrib2fv()` (in module `kivy.graphics.opengl`), 396

glVertexAttrib3f() (in *kivy.graphics.opengl*), 396
glVertexAttrib3fv() (in *kivy.graphics.opengl*), 396
glVertexAttrib4f() (in *kivy.graphics.opengl*), 396
glVertexAttrib4fv() (in *kivy.graphics.opengl*), 397
glVertexAttribPointer() (in *kivy.graphics.opengl*), 397
glViewport() (in module *kivy.graphics.opengl*), 397
goto() (*kivy.uix.rst.RstDocument* method), 652
goto_node() (*kivy.uix.behaviors.compoundselection.CompoundSelection*.*CompoundSelectionBehavior* attribute), 522
has_after (*kivy.graphics.instructions.Canvas* attribute), 356
has_before (*kivy.graphics.instructions.Canvas* attribute), 374
has_before (*kivy.graphics.Canvas* attribute), 356
has_binder (*kivy.clock.CyClockBase* attribute), 230
has_screen() (*kivy.uix.screenmanager.ScreenManager* method), 667
has_started (*kivy.clock.CyClockBase* attribute), 230
have_properties_to_animate() (*kivy.animation.Animation* method), 191
hbar (*kivy.uix.scrollview.ScrollView* attribute), 676
height (*kivy.core.image.Image* property), 302
height (*kivy.core.image.ImageData* property), 304
height (*kivy.core.window.WindowBase* attribute), 322
height (*kivy.graphics.svg.Svg* attribute), 404
GraphicException, 360, 419
GridLayout (class in *kivy.uix.gridlayout*), 612
GridLayoutException, 614
group (*kivy.graphics.Instruction* attribute), 360
group (*kivy.graphics.instructions.Instruction* attribute), 375
group (*kivy.uix.behaviors.togglebutton.ToggleButtonBehavior* attribute), 540
group (*kivy.uix.behaviors.ToggleButtonBehavior* attribute), 516

H

h (*kivy.core.text.text_layout.LayoutLine* attribute), 310
h (*kivy.graphics.Color* attribute), 358
h (*kivy.graphics.context_instructions.Color* attribute), 380
halign (*kivy.uix.label.Label* attribute), 626
halign (*kivy.uix.textinput.TextInput* attribute), 717
handle_exception() (*kivy.base.ExceptionHandler* method), 257
handle_exception() (*kivy.base.ExceptionManagerBase* method), 257
module handle_exception() (*kivy.clock.CyClockBase* method), 229
module handle_image_left (*kivy.uix.textinput.TextInput* attribute), 717
module handle_image_middle (*kivy.uix.textinput.TextInput* attribute), 717
module handle_image_right (*kivy.uix.textinput.TextInput* attribute), 718
handles() (*kivy.uix.gesturesurface.GestureContainer* method), 608
has_after (*kivy.uix.behaviors.Canvas* attribute), 356
has_binder (*kivy.uix.behaviors.Canvas* attribute), 374
has_binder (*kivy.graphics.instructions.Canvas* attribute), 356
has_binder (*kivy.graphics.instructions.Canvas* attribute), 374
has_binder (*kivy.clock.CyClockBase* attribute), 230
has_screen() (*kivy.uix.screenmanager.ScreenManager* method), 667
has_started (*kivy.clock.CyClockBase* attribute), 230
hide() (*kivy.core.window.WindowBase* method), 322
hide_keyboard() (*kivy.uix.behaviors.focus.FocusBehavior* method), 531
hide_keyboard() (*kivy.uix.behaviors.FocusBehavior* method), 513
hide_root (*kivy.uixtreeview.TreeView* attribute), 726
HIDMotionEvent (class in *kivy.input.providers.hidinput*), 440
highlight_at() (*kivy.modules.console.Console* method), 485
hint_text (*kivy.uix.textinput.TextInput* attribute), 718
hint_text_color (*kivy.uix.textinput.TextInput* attribute), 718
HorizontalBlurEffect (class in *kivy.uix.effectwidget*), 594
hsv (*kivy.graphics.Color* attribute), 358

hsv (*kivy.graphics.context_instructions.Color attribute*), 380
hsv (*kivy.uix.colorpicker.ColorPicker attribute*), 585
|
icon (*kivy.app.App attribute*), 207
icon (*kivy.core.window.WindowBase attribute*), 322
icon (*kivy.uix.actionbar.ActionButton attribute*), 562
icon (*kivy.uix.actionbar.ActionToggleButton attribute*), 565
id (*kivy.graphics.texture.Texture attribute*), 412
id (*kivy.input MotionEvent attribute*), 431
id (*kivy.input.motionevent MotionEvent attribute*), 450
identity() (*kivy.graphics.transformation.Matrix method*), 414
idle() (*kivy.base.EventLoopBase method*), 256
idle() (*kivy.clock.ClockBaseBehavior method*), 225
idle() (*kivy.clock.ClockBaseFreeInterruptOnly method*), 226
idle() (*kivy.clock.ClockBaseInterruptBehavior method*), 226
ids (*kivy.uix.widget.Widget attribute*), 750
ignore_perpendicular_swipes (*kivy.uix.carousel.Carousel attribute*), 579
ignored_touch (*kivy.uix.behaviors.focus.FocusBehavior attribute*), 531
ignored_touch (*kivy.uix.behaviors.FocusBehavior attribute*), 513
Image (*class in kivy.core.image*), 301
Image (*class in kivy.uix.image*), 615
image (*kivy.core.image.Image property*), 302
image() (*kivy.loader.LoaderBase method*), 211
image_loading (*kivy.uix.videoplayer.VideoPlayer attribute*), 735
image_overlay_play (*kivy.uix.videoplayer.VideoPlayer attribute*), 735
image_pause (*kivy.uix.videoplayer.VideoPlayer attribute*), 735
image_play (*kivy.uix.videoplayer.VideoPlayer attribute*), 735
image_ratio (*kivy.uix.image.Image attribute*), 616
image_stop (*kivy.uix.videoplayer.VideoPlayer attribute*), 735
image_volumehigh (*kivy.uix.videoplayer.VideoPlayer attribute*), 735
image_volumelow (*kivy.uix.videoplayer.VideoPlayer attribute*), 735
image_volumemedium (*kivy.uix.videoplayer.VideoPlayer attribute*), 736
image_volumemuted (*kivy.uix.videoplayer.VideoPlayer attribute*), 736
(*kivy.uix.videoplayer.VideoPlayer attribute*), 736
ImageData (*class in kivy.core.image*), 304
import_gesture() (*kivy.multistroke.Recognizer method*), 270
important (*kivy.uix.actionbar.ActionItem attribute*), 563
in_back() (*kivy.animation.AnimationTransition static method*), 191
in_bbox() (*kivy.vector.Vector static method*), 293
in_bounce() (*kivy.animation.AnimationTransition static method*), 192
in_circ() (*kivy.animation.AnimationTransition static method*), 192
in_cubic() (*kivy.animation.AnimationTransition static method*), 192
in_elastic() (*kivy.animation.AnimationTransition static method*), 192
in_expo() (*kivy.animation.AnimationTransition static method*), 192
in_out_back() (*kivy.animation.AnimationTransition static method*), 192
in_out_bounce() (*kivy.animation.AnimationTransition static method*), 193
in_out_circ() (*kivy.animation.AnimationTransition static method*), 193
in_out_cubic() (*kivy.animation.AnimationTransition static method*), 193
in_out_elastic() (*kivy.animation.AnimationTransition static method*), 193
in_out_expo() (*kivy.animation.AnimationTransition static method*), 193
in_out_quad() (*kivy.animation.AnimationTransition static method*), 193
in_out_quart() (*kivy.animation.AnimationTransition static method*), 194
in_out_quint() (*kivy.animation.AnimationTransition static method*), 194
in_out_sine() (*kivy.animation.AnimationTransition static method*), 194
in_quad() (*kivy.animation.AnimationTransition static method*), 194
in_quart() (*kivy.animation.AnimationTransition static method*), 194
in_quint() (*kivy.animation.AnimationTransition static method*), 194
in_sine() (*kivy.animation.AnimationTransition static method*), 195
inch (*kivy.metrics.MetricsBase attribute*), 262
inch() (*in module kivy.metrics*), 262
indent_level (*kivy.uix.treeview.TreeView attribute*), 726
indent_start (*kivy.uix.treeview.TreeView attribute*), 726

index (*kivy.core.camera.CameraBase property*), 300
index (*kivy.uix.camera.Camera attribute*), 576
index (*kivy.uix.carousel.Carousel attribute*), 579
index (*kivy.uix.filechooser.FileChooserProgressBase attribute*), 604
indexof() (*kivy.graphics.InstructionGroup method*), 361
indexof() (*kivy.graphics.instructions.InstructionGroup method*), 375
indices (*kivy.graphics.Mesh attribute*), 367
indices (*kivy.graphics.vertex_instructions.Mesh attribute*), 425
init() (*kivy.modules.console.ConsoleAddon method*), 486
init_async_lib() (*kivy.clock.ClockBaseBehavior method*), 225
init_async_lib()
 (*kivy.clock.ClockBaseInterruptBehavior method*), 226
init_camera() (*kivy.core.camera.CameraBase method*), 300
init_gesture() (*kivy.uix.gesturesurface.GestureSurface method*), 609
initial_height (*kivy.uix.recyclelayout.RecycleLayout attribute*), 644
initial_size (*kivy.uix.recyclelayout.RecycleLayout attribute*), 644
initial_width (*kivy.uix.recyclelayout.RecycleLayout attribute*), 644
input_absinfo (*class in kivy.lib.mtdev*), 478
input_event (*class in kivy.lib.mtdev*), 478
input_filter (*kivy.uix.textinput.TextInput attribute*), 718
input_type (*kivy.uix.behaviors.focus.FocusBehavior attribute*), 531
input_type (*kivy.uix.behaviors.FocusBehavior attribute*), 514
InputPostprocCalibration (*class in kivy.input.postproc.calibration*), 434
InputPostprocDejitter (*class in kivy.input.postproc.dejitter*), 435
InputPostprocDoubleTap (*class in kivy.input.postproc.doubletap*), 435
InputPostprocIgnoreList (*class in kivy.input.postproc.ignorelist*), 436
InputPostprocRetainTouch (*class in kivy.input.postproc.retaintouch*), 436
InputPostprocTripleTap (*class in kivy.input.postproc.tripletap*), 436
insert() (*kivy.graphics.InstructionGroup method*), 361
insert() (*kivy.graphics.instructions.InstructionGroup method*), 376
insert_text() (*kivy.uix.textinput.TextInput method*), 718
inside_group (*kivy.uix.actionbar.ActionItem attribute*), 563
inspect_enabled (*kivy.modules.console.Console attribute*), 485
install_android() (*in module kivy.support*), 288
install_gobject_iteration() (*in module kivy.support*), 288
install_twisted_reactor() (*in module kivy.support*), 288
Instruction (*class in kivy.graphics*), 360
Instruction (*class in kivy.graphics.instructions*), 375
InstructionGroup (*class in kivy.graphics*), 361
InstructionGroup (*class in kivy.graphics.instructions*), 375
InteractiveLauncher (*class in kivy.interactive*), 255
interface (*kivy.uix.settings.Settings attribute*), 687
interface_cls (*kivy.uix.settings.Settings attribute*), 687
InterfaceWithSidebar (*class in kivy.uix.settings*), 682
interpolate() (*in module kivy.utils*), 290
intersect() (*kivy.graphics.scissor_instructions.Rect method*), 399
intersection() (*in module kivy.utils*), 290
invalidate() (*kivy.uix.recycleview.views.RecycleDataAdapter method*), 553
inverse() (*kivy.graphics.transformation.Matrix method*), 414
InvertEffect (*class in kivy.uix.effectwidget*), 594
is_active (*kivy.uix.screenmanager.TransitionBase attribute*), 671
is_color_transparent() (*in module kivy.utils*), 290
is_dead() (*kivy.weakmethod.WeakMethod method*), 295
is_dir() (*kivy.uix.filechooser.FileSystemAbstract method*), 604
is_dir() (*kivy.uix.filechooser.FileSystemLocal method*), 605
is_double_tap (*kivy.input.MotionEvent attribute*), 431
is_double_tap (*kivy.input.motionevent.MotionEvent attribute*), 450
is_event_type() (*kivy.event.EventDispatcher method*), 246
is_finished (*kivy.network.urlrequest.UrlRequest property*), 495
is_focusable (*kivy.uix.behaviors.FocusBehavior attribute*), 532
is_focusable (*kivy.uix.behaviors.FocusBehavior attribute*), 514

is_hidden() (*kivy.uix.filechooser.FileSystemAbstract* method), 605
is_hidden() (*kivy.uix.filechooser.FileSystemLocal* method), 605
is_last_line (*kivy.core.text.text_layout.LayoutLine* attribute), 310
is_leaf (*kivy.uix.treeview.TreeNode* attribute), 729
is_loaded (*kivy.uix.treeview.TreeNode* attribute), 729
is_manual (*kivy.effects.kinetic.KineticEffect* attribute), 338
is_mouse_scrolling (*kivy.input MotionEvent* property), 431
is_mouse_scrolling (*kivy.input.motionevent MotionEvent* property), 450
is_open (*kivy.uix.actionbar.ActionGroup* attribute), 562
is_open (*kivy.uix.spinner.Spinner* attribute), 694
is_open (*kivy.uix.treeview.TreeNode* attribute), 729
is_selected (*kivy.uix.treeview.TreeNode* attribute), 729
is_shortened (*kivy.uix.label.Label* attribute), 626
is_touch (*kivy.input MotionEvent* attribute), 431
is_touch (*kivy.input.motionevent MotionEvent* attribute), 450
is_triggered (*kivy.clock.ClockEvent* attribute), 227
is_triple_tap (*kivy.input MotionEvent* attribute), 431
is_triple_tap (*kivy.input.motionevent MotionEvent* attribute), 450
isclose() (in module *kivy.compat*), 233
italic (*kivy.uix.label.Label* attribute), 626
iterate_all_nodes()
 (*kivy.uix.treeview.TreeView* method), 727
iterate_mipmaps() (*kivy.core.image.ImageData* method), 304
iterate_open_nodes()
 (*kivy.uix.treeview.TreeView* method), 727

J

joint (*kivy.graphics.Line* attribute), 365
joint (*kivy.graphics.vertex_instructions.Line* attribute), 423
joint_precision (*kivy.graphics.Line* attribute), 365
joint_precision (*kivy.graphics.vertex_instructions.Line* attribute), 423
JsonStore (class in *kivy.storage.jsonstore*), 501

K

keep_data (*kivy.uix.image.Image* attribute), 616
keep_ratio (*kivy.uix.image.Image* attribute), 616
keep_ref (*kivy.uix.behaviors.knspase.KNSpace* attribute), 538
keep_within_parent (*kivy.uix.splitter.Splitter* attribute), 696
key (*kivy.uix.settings.SettingItem* attribute), 685
key_background_color
 (*kivy.uix.vkeyboard.VKeyboard* attribute), 740
key_background_down
 (*kivy.uix.vkeyboard.VKeyboard* attribute), 741
key_background_normal
 (*kivy.uix.vkeyboard.VKeyboard* attribute), 741
key_bindings (*kivy.uix.behaviors.emacs.EmacsBehavior* attribute), 529
key_bindings (*kivy.uix.behaviors.EmacsBehavior* attribute), 512
key_border (*kivy.uix.vkeyboard.VKeyboard* attribute), 741
key_disabled_background_normal
 (*kivy.uix.vkeyboard.VKeyboard* attribute), 741
key_margin (*kivy.uix.vkeyboard.VKeyboard* attribute), 741
key_pos_hint (*kivy.uix.recyclelayout.RecycleLayout* attribute), 644
key_selection (*kivy.uix.recycleview.layout.LayoutSelectionBehavior* attribute), 551
key_size (*kivy.uix.recyclelayout.RecycleLayout* attribute), 644
key_size_hint (*kivy.uix.recyclelayout.RecycleLayout* attribute), 644
key_size_hint_max
 (*kivy.uix.recyclelayout.RecycleLayout* attribute), 645
key_size_hint_min
 (*kivy.uix.recyclelayout.RecycleLayout* attribute), 645
key_viewclass (*kivy.uix.recycleview.layout.RecycleLayoutManager* attribute), 552
key_viewclass (*kivy.uix.recycleview.RecycleView* attribute), 547
Keyboard (class in *kivy.core.window*), 316
keyboard (*kivy.uix.behaviors.focus.FocusBehavior* attribute), 532
keyboard (*kivy.uix.behaviors.FocusBehavior* attribute), 514
keyboard_anim_args
 (*kivy.core.window.WindowBase* attribute), 322
keyboard_height (*kivy.core.window.WindowBase* attribute), 322
keyboard_mode (*kivy.uix.behaviors.focus.FocusBehavior*

attribute), 532
keyboard_mode (*kivy.uix.behaviors.FocusBehavior attribute*), 515
keyboard_on_key_down()
 (*kivy.uix.behaviors.focus.FocusBehavior method*), 532
keyboard_on_key_down()
 (*kivy.uix.behaviors.FocusBehavior method*), 515
keyboard_on_key_down()
 (*kivy.uix.textinput.TextInput method*), 718
keyboard_on_key_up()
 (*kivy.uix.behaviors.focus.FocusBehavior method*), 533
keyboard_on_key_up()
 (*kivy.uix.behaviors.FocusBehavior method*), 515
keyboard_on_key_up()
 (*kivy.uix.textinput.TextInput method*), 718
keyboard_padding
 (*kivy.core.window.WindowBase attribute*), 322
keyboard_select (*kivy.uix.behaviors.compoundselection.CompoundSelection attribute*), 523
keyboard_select (*kivy.uix.behaviors.CompoundSelection attribute*), 509
keyboard_suggestions
 (*kivy.uix.behaviors.focus.FocusBehavior attribute*), 533
keyboard_suggestions
 (*kivy.uix.behaviors.FocusBehavior attribute*), 515
keycode_to_string()
 (*kivy.core.window.Keyboard method*), 317
keys() (*kivy.storage.AbstractStore method*), 500
KineticEffect (*class in kivy.effects.kinetic*), 338
kivy
 module, 187
kivy._version
 module, 188
kivy.animation
 module, 188
kivy.app
 module, 197
kivy.atlas
 module, 213
kivy.base
 module, 255
kivy.cache
 module, 216
kivy.clock
 module, 218
kivy.compat
 module, 233
kivy.config
 module, 233
kivy.context
 module, 240
kivy.core
 module, 297
kivy.core.audio
 module, 297
kivy.core.camera
 module, 299
kivy.core.clipboard
 module, 300
kivy.core.gl
 module, 300
kivy.core.image
 module, 301
kivy.core.spelling
 module, 305
kivy.core.text
 module, 306
kivy.core.text.markup
 module, 313
kivy.ComponentSelectableBehavior
 module, 310
kivy.Behavior.video
 module, 315
kivy.core.window
 module, 316
kivy.deps
 module, 335
kivy.effects
 module, 337
kivy.effects.dampedscroll
 module, 337
kivy.effects.kinetic
 module, 338
kivy.effects.opacityscroll
 module, 340
kivy.effects.scroll
 module, 340
kivy.event
 module, 240
kivy.eventmanager
 module, 343
kivy.factory
 module, 249
kivy.garden
 module, 347
kivy.geometry
 module, 250
kivy.gesture
 module, 251
kivy.graphics

```
    module, 351
kivy.graphics.cgl
    module, 378
kivy.graphics.compiler
    module, 387
kivy.graphics.context
    module, 382
kivy.graphics.context_instructions
    module, 378
kivy.graphics.fbo
    module, 383
kivy.graphics.gl_instructions
    module, 386
kivy.graphics.instructions
    module, 373
kivy.graphics.opengl
    module, 388
kivy.graphics.opengl_utils
    module, 397
kivy.graphics.scissor_instructions
    module, 398
kivy.graphics.shader
    module, 399
kivy.graphics.stencil_instructions
    module, 401
kivy.graphics.svg
    module, 403
kivy.graphics.tesselator
    module, 404
kivy.graphics.texture
    module, 407
kivy.graphics.transformation
    module, 414
kivy.graphics.vertex_instructions
    module, 417
kivy.input
    module, 429
kivy.input.factory
    module, 452
kivy.input.motionevent
    module, 447
kivy.input.postproc
    module, 434
kivy.input.postproc.calibration
    module, 434
kivy.input.postproc.dejitter
    module, 435
kivy.input.postproc.doubletap
    module, 435
kivy.input.postproc.ignorelist
    module, 436
kivy.input.postproc.retaintouch
    module, 436
kivy.input.postproc.tripletap
    module, 436
kivy.input.provider
    module, 453
kivy.input.providers
    module, 437
kivy.input.providers.androidjoystick
    module, 437
kivy.input.providers.hidinput
    module, 440
kivy.input.providers.leapfinger
    module, 438
kivy.input.providers.linuxwacom
    module, 442
kivy.input.providers.mactouch
    module, 442
kivy.input.providers.mouse
    module, 438
kivy.input.providers.mtdev
    module, 441
kivy.input.providers.probesysfs
    module, 437
kivy.input.providers.tuio
    module, 443
kivy.input.providers.wm_common
    module, 438
kivy.input.recorder
    module, 444
kivy.input.shape
    module, 453
kivy.interactive
    module, 252
kivy.lang
    module, 455
kivy.lang.builder
    module, 472
kivy.lang.parser
    module, 476
kivy.lib
    module, 477
kivy.lib.ddsfile
    module, 477
kivy.lib.gstplayer
    module, 477
kivy.lib.mtdev
    module, 478
kivy.loader
    module, 211
kivy.logger
    module, 258
kivy.metrics
    module, 260
kivy.modules
    module, 481
kivy.modules.console
    module, 482
kivy.modules.inspector
```

module, 486
kivy.modules.joycursor
 module, 488
kivy.modules.keybinding
 module, 489
kivy.modules.monitor
 module, 489

kivy.uix.module, 638
 kivy.uix.progressbar module, 641
 kivy.uix.recycleboxlayout module, 642
 kivy.uix.recyclegridlayout module, 642
 kivy.uix.recyclelayout module, 643
 kivy.uix.recycleview module, 542
 kivy.uix.recycleview.datamodel module, 548
 kivy.uix.recycleview.layout module, 549
 kivy.uix.recycleview.views module, 552
 kivy.uix.relativelayout module, 645
 kivy.uix.rst module, 650
 kivy.uix.sandbox module, 653
 kivy.uix.scatter module, 655
 kivy.uix.scatterlayout module, 660
 kivy.uix.screenmanager module, 662
 kivy.uix.scrollview module, 671
 kivy.uix.settings module, 678
 kivy.uix.slider module, 688
 kivy.uix.spinner module, 693
 kivy.uix.splitter module, 695
 kivy.uix.stacklayout module, 698
 kivy.uix.stencilview module, 700
 kivy.uix.switch module, 700
 kivy.uix.tabbedpanel module, 702
 kivy.uix.textinput module, 709
 kivy.uix.togglebutton module, 723
 kivy.uixtreeview module, 724
 kivy.uix.video module, 730
 kivy.uix.videoplayer module, 733
 kivy.uix.vkeyboard module, 738
 kivy.uix.widget module, 742
 kivy.utils module, 289
 kivy.vector module, 291
 kivy.weakmethod module, 295
 kivy.weakproxy module, 295
 kivy_base_dir (*in module kivy*), 187
 kivy_config_fn (*in module kivy*), 187
 kivy_configure() (*in module kivy*), 187
 kivy_data_dir (*in module kivy*), 187
 Kivy_examples_dir (*in module kivy*), 187
 kivy_home_dir (*in module kivy*), 187
 kivy_icons_dir (*in module kivy*), 187
 kivy_options (*in module kivy*), 187
 kivy_register_post_configuration() (*in module kivy*), 187
 kivy_shader_dir (*in module kivy*), 188
 kivy_usermodules_dir (*in module kivy*), 188
 knsname (*kivy.uix.behaviors.knspace.KNSpaceBehavior attribute*), 538
 KNSpace (*class in kivy.uix.behaviors.knspace*), 537
 knspace (*in module kivy.uix.behaviors.knspace*), 539
 knspace (*kivy.uix.behaviors.knspace.KNSpaceBehavior attribute*), 538
 knspace_key (*kivy.uix.behaviors.knspace.KNSpaceBehavior attribute*), 538
 KNSpaceBehavior (*class in kivy.uix.behaviors.knspace*), 538
 kv_directory (*kivy.app.App attribute*), 207
 kv_file (*kivy.app.App attribute*), 207

L

Label (*class in kivy.uix.label*), 622
 label (*kivy.core.text.LabelBase property*), 309
 LabelBase (*class in kivy.core.text*), 307
 last_touch (*kivy.uix.behaviors.button.ButtonBehavior attribute*), 519
 last_touch (*kivy.uix.behaviors.ButtonBehavior attribute*), 507
 last_touch (*kivy.uix.behaviors.touchripple.TouchRippleButtonBehavior attribute*), 542
 last_touch (*kivy.uix.behaviors.TouchRippleButtonBehavior attribute*), 518
 Layout (*class in kivy.uix.layout*), 631
 layout (*kivy.uix.filechooser.FileChooserController attribute*), 602

`layout` (*kivy.uix.vkeyboard.VKeyboard attribute*), 741
`layout_hint_with_bounds()` (*kivy.uix.layout.Layout method*), 632
`layout_manager` (*kivy.uix.recycleview.RecycleViewBehavior attribute*), 548
`layout_path` (*kivy.uix.vkeyboard.VKeyboard attribute*), 741
`layout_text()` (*in module kivy.core.text.text_layout*), 311
`LayoutChangeEvent`, 549
`LayoutLine` (*class in kivy.core.text.text_layout*), 310
`LayoutSelectionBehavior` (*class in kivy.uix.recycleview.layout*), 549
`LayoutWord` (*class in kivy.core.text.text_layout*), 311
`LeapFingerEvent` (*class in kivy.input.providers.leapfinger*), 438
`LeapFingerEventProvider` (*class in kivy.input.providers.leapfinger*), 438
`left` (*kivy.core.window.WindowBase attribute*), 322
`length` (*kivy.core.audio.Sound property*), 298
`length` (*kivy.properties.VariableListProperty attribute*), 287
`length()` (*kivy.graphics.InstructionGroup method*), 361
`length()` (*kivy.graphics.instructions.InstructionGroup method*), 376
`length()` (*kivy.vector.Vector method*), 293
`length2()` (*kivy.vector.Vector method*), 293
`level` (*kivy.uixtreeview.TreeNode attribute*), 729
`lexer` (*kivy.uix.codeinput.CodeInput attribute*), 583
`lh` (*kivy.core.text.text_layout.LayoutWord attribute*), 311
`limit_to` (*kivy.uix.bubble.Bubble attribute*), 573
`Line` (*class in kivy.graphics*), 361
`Line` (*class in kivy.graphics.vertex_instructions*), 419
`line_height` (*kivy.uix.label.Label attribute*), 626
`line_height` (*kivy.uix.textinput.TextInput attribute*), 719
`line_intersection()` (*kivy.vector.Vector static method*), 294
`line_spacing` (*kivy.uix.textinput.TextInput attribute*), 719
`line_wrap` (*kivy.core.text.text_layout.LayoutLine attribute*), 310
`linear()` (*kivy.animation.AnimationTransition static method*), 195
`link()` (*kivy.properties.DictProperty method*), 282
`link()` (*kivy.properties.ListProperty method*), 283
`link()` (*kivy.properties.Property method*), 286
`link()` (*kivy.properties.ReferenceListProperty method*), 287
`link()` (*kivy.properties.VariableListProperty method*), 288
`link_deps()` (*kivy.properties.AliasProperty method*), 278
`link_deps()` (*kivy.properties.ConfigParserProperty method*), 281
`link_deps()` (*kivy.properties.Property method*), 286
`link_deps()` (*kivy.properties.ReferenceListProperty method*), 287
`link_eagerly()` (*kivy.properties.AliasProperty method*), 278
`link_eagerly()` (*kivy.properties.Property method*), 286
`LinuxWacomMotionEvent` (*class in kivy.input.providers.linuxwacom*), 442
`list()` (*kivy.input.factory MotionEventFactory static method*), 453
`list()` (*kivy.input.MotionEventFactory static method*), 433
`list_languages()` (*kivy.core.spelling.SpellingBase method*), 305
`listdir()` (*kivy.uix.filechooser.FileSystemAbstract method*), 605
`listdir()` (*kivy.uix.filechooser.FileSystemLocal method*), 605
`list_property` (*class in kivy.properties*), 282
`load()` (*kivy.core.audio.Sound method*), 298
`load()` (*kivy.core.audio.SoundLoader static method*), 299
`load()` (*kivy.core.image.Image static method*), 302
`load()` (*kivy.core.video.VideoBase method*), 315
`load_config()` (*kivy.app.App method*), 207
`load_file()` (*kivy.lang.builder.BuilderBase method*), 473
`load_file()` (*kivy.lang.BuilderBase method*), 469
`load_func` (*kivy.uixtreeview.TreeView attribute*), 727
`load_kv()` (*kivy.app.App method*), 207
`load_memory()` (*kivy.core.image.Image method*), 303
`load_next()` (*kivy.uix.carousel.Carousel method*), 579
`load_previous()` (*kivy.uix.carousel.Carousel method*), 579
`load_slide()` (*kivy.uix.carousel.Carousel method*), 579
`load_string()` (*kivy.lang.builder.BuilderBase method*), 473
`load_string()` (*kivy.lang.BuilderBase method*), 469
`loaded` (*kivy.uix.video.Video attribute*), 731
`LoaderBase` (*class in kivy.loader*), 211
`LoadIdentity` (*class in kivy.graphics*), 366

loading_image (*kivy.loader.LoaderBase* property), 212
Logger (in module *kivy.logger*), 259
LoggerHistory (class in *kivy.logger*), 259
look_at() (*kivy.graphics.transformation.Matrix* method), 414
loop (*kivy.clock.ClockEvent* attribute), 227
loop (*kivy.core.audio.Sound* attribute), 298
loop (*kivy.uix.carousel.Carousel* attribute), 579
lw (*kivy.core.text.text_layout.LayoutWord* attribute), 311

M

MacMotionEventProvider (class in *kivy.input.providers.mactouch*), 442
mag_filter (*kivy.graphics.texture.Texture* attribute), 412
mainloop() (*kivy.core.window.WindowBase* method), 323
mainthread() (in module *kivy.clock*), 232
make_view_dirty() (*kivy.uix.recycleview.views.RecycleDataAdapter* method), 553
make_views_dirty() (*kivy.uix.recycleview.views.RecycleDataAdapter* method), 553
managed_textinput (*kivy.core.window.WindowBase* attribute), 323
manager (*kivy.uix.filechooser.FileChooser* attribute), 600
manager (*kivy.uix.screenmanager.Screen* attribute), 666
manager (*kivy.uix.screenmanager.TransitionBase* attribute), 671
margin_hint (*kivy.uix.vkeyboard.VKeyboard* attribute), 741
markup (*kivy.core.text.markup.MarkupLabel* property), 314
markup (*kivy.uix.actionbar.ActionPrevious* attribute), 564
markup (*kivy.uix.label.Label* attribute), 626
MarkupLabel (class in *kivy.core.text.markup*), 314
match() (*kivy.lang.builder.BuilderBase* method), 474
match() (*kivy.lang.BuilderBase* method), 469
match_candidate() (*kivy.multistroke.MultistrokeGesture* method), 266
match_rule_name() (*kivy.lang.builder.BuilderBase* method), 474
match_rule_name() (*kivy.lang.BuilderBase* method), 469
Matrix (class in *kivy.graphics.transformation*), 414
matrix (*kivy.graphics.context_instructions.MatrixInstruction* attribute), 380

matrix (*kivy.graphics.MatrixInstruction* attribute), 366
MatrixInstruction (class in *kivy.graphics*), 366
MatrixInstruction (class in *kivy.graphics.context_instructions*), 380
max (*kivy.effects.scroll.ScrollEffect* attribute), 340
max (*kivy.uix.progressbar.ProgressBar* attribute), 641
max (*kivy.uix.slider.Slider* attribute), 690
max_height (*kivy.uix.dropdown.DropDown* attribute), 589
max_history (*kivy.effects.kinetic.KineticEffect* attribute), 338
max_iteration (*kivy.clock.CyClockBase* attribute), 230
max_lines (*kivy.uix.label.Label* attribute), 626
max_size (*kivy.uix.splitter.Splitter* attribute), 696
max_upload_per_frame (*kivy.loader.LoaderBase* property), 212
maximize() (*kivy.core.window.WindowBase* method), 323
menu (*kivy.uix.settings.InterfaceWithSidebar* attribute), 683
MenuSidebar (class in *kivy.uix.settings*), 683
merge_gestures() (*kivy.uix.gesturesurface.GestureSurface* method), 609
Mesh (class in *kivy.graphics*), 366
Mesh (class in *kivy.graphics.vertex_instructions*), 424
meshes (*kivy.graphics.tesselator.Tesselator* attribute), 406
Metrics (in module *kivy.metrics*), 261
MetricsBase (class in *kivy.metrics*), 261
min (*kivy.effects.scroll.ScrollEffect* attribute), 340
min (*kivy.uix.slider.Slider* attribute), 690
min_distance (*kivy.effects.kinetic.KineticEffect* attribute), 339
min_filter (*kivy.graphics.texture.Texture* attribute), 412
min_move (*kivy.uix.carousel.Carousel* attribute), 579
min_overscroll (*kivy.effects.dampedscroll.DampedScrollEffect* attribute), 337
min_size (*kivy.uix.splitter.Splitter* attribute), 697
MIN_SLEEP (*kivy.clock.ClockBaseBehavior* attribute), 225
min_space (*kivy.uix.accordion.Accordion* attribute), 557
min_space (*kivy.uix.accordion.AccordionItem* attribute), 559
min_state_time (*kivy.uix.behaviors.button.ButtonBehavior* attribute), 519
min_state_time (*kivy.uix.behaviors.ButtonBehavior* attribute), 507
min_state_time (*kivy.uix.dropdown.DropDown* attribute), 589
min_velocity (*kivy.effects.kinetic.KineticEffect* attribute), 338

tribute), 339
minimize() (kivy.core.window.WindowBase
 method), 323
minimum_bounding_circle() (in module
 kivy.geometry), 250
minimum_height (kivy.core.window.WindowBase
 attribute), 323
minimum_height (kivy.uix.boxlayout.BoxLayout
 attribute), 569
minimum_height (kivy.uix.gridlayout.GridLayout
 attribute), 613
minimum_height (kivy.uix.stacklayout.StackLayout
 attribute), 699
minimum_height (kivy.uix.textinput.TextInput at-
 tribute), 719
minimum_height (kivy.uixtreeview.TreeView at-
 tribute), 727
minimum_size (kivy.uix.boxlayout.BoxLayout at-
 tribute), 569
minimum_size (kivy.uix.gridlayout.GridLayout at-
 tribute), 613
minimum_size (kivy.uix.stacklayout.StackLayout
 attribute), 699
minimum_size (kivy.uixtreeview.TreeView at-
 tribute), 727
minimum_width (kivy.core.window.WindowBase at-
 tribute), 323
minimum_width (kivy.uix.actionbar.ActionItem at-
 tribute), 563
minimum_width (kivy.uix.boxlayout.BoxLayout at-
 tribute), 569
minimum_width (kivy.uix.gridlayout.GridLayout
 attribute), 613
minimum_width (kivy.uix.stacklayout.StackLayout
 attribute), 699
minimum_width (kivy.uixtreeview.TreeView at-
 tribute), 727
mipmap (kivy.graphics.texture.Texture attribute), 412
mipmap (kivy.uix.actionbar.ActionItem attribute),
 563
mipmap (kivy.uix.image.Image attribute), 616
mipmap (kivy.uix.label.Label attribute), 626
mipmaps (kivy.core.image.ImageData attribute), 304
mm (kivy.metrics.MetricsBase attribute), 262
mm () (in module kivy.metrics), 263
ModalView (class in kivy.uix.modalview), 634
mode (kivy.graphics.Mesh attribute), 367
mode (kivy.graphics.vertex_instructions.Mesh at-
 tribute), 425
mode (kivy.modules.console.Console attribute), 485
mode (kivy.uix.actionbar.ActionGroup attribute), 562
mode (kivy.uix.screenmanager.CardTransition at-
 tribute), 665
MODE_DEFAULT_DISPATCH (in module
 kivy.eventmanager), 345
MODE_DONT_DISPATCH (in module
 kivy.eventmanager), 345
MODE_FILTERED_DISPATCH (in module
 kivy.eventmanager), 345
modifiers (kivy.core.window.WindowBase at-
 tribute), 323
module
 kivy, 187
 kivy._version, 188
 kivy.animation, 188
 kivy.app, 197
 kivy.atlas, 213
 kivy.base, 255
 kivy.cache, 216
 kivy.clock, 218
 kivy.compat, 233
 kivy.config, 233
 kivy.context, 240
 kivy.core, 297
 kivy.core.audio, 297
 kivy.core.camera, 299
 kivy.core.clipboard, 300
 kivy.core.gl, 300
 kivy.core.image, 301
 kivy.core.spelling, 305
 kivy.core.text, 306
 kivy.core.text.markup, 313
 kivy.core.text.text_layout, 310
 kivy.core.video, 315
 kivy.core.window, 316
 kivy.deps, 335
 kivy.effects, 337
 kivy.effects.dampedscroll, 337
 kivy.effects.kinetic, 338
 kivy.effects.opacityscroll, 340
 kivy.effects.scroll, 340
 kivy.event, 240
 kivy.eventmanager, 343
 kivy.factory, 249
 kivy.garden, 347
 kivy.geometry, 250
 kivy.gesture, 251
 kivy.graphics, 351
 kivy.graphics.cgl, 378
 kivy.graphics.compiler, 387
 kivy.graphics.context, 382
 kivy.graphics.context_instructions,
 378
 kivy.graphics.fbo, 383
 kivy.graphics.gl_instructions, 386
 kivy.graphics.instructions, 373
 kivy.graphics.opengl, 388
 kivy.graphics.opengl_utils, 397
 kivy.graphics.scissor_instructions,
 398

kivy.graphics.shader, 399
kivy.graphics.stencil_instructions,
 401
kivy.graphics.svg, 403
kivy.graphics.tesselator, 404
kivy.graphics.texture, 407
kivy.graphics.transformation, 414
kivy.graphics.vertex_instructions,
 417
kivy.input, 429
kivy.input.factory, 452
kivy.input.motionevent, 447
kivy.input.postproc, 434
kivy.input.postproc.calibration,
 434
kivy.input.postproc.dejitter, 435
kivy.input.postproc.doubletap, 435
kivy.input.postproc.ignorelist, 436
kivy.input.postproc.retaintouch,
 436
kivy.input.postproc.tripletap, 436
kivy.input.provider, 453
kivy.input.providers, 437
kivy.input.providers.androidjoystick,
 437
kivy.input.providers.hidinput, 440
kivy.input.providers.leapfinger,
 438
kivy.input.providers.linuxwacom,
 442
kivy.input.providers.mactouch, 442
kivy.input.providers.mouse, 438
kivy.input.providers.mtdev, 441
kivy.input.providers.probesysfs,
 437
kivy.input.providers.tuio, 443
kivy.input.providers.wm_common, 438
kivy.input.recorder, 444
kivy.input.shape, 453
kivy.interactive, 252
kivy.lang, 455
kivy.lang.builder, 472
kivy.lang.parser, 476
kivy.lib, 477
kivy.lib.ddsfile, 477
kivy.lib.gstplayer, 477
kivy.lib.mtdev, 478
kivy.loader, 211
kivy.logger, 258
kivy.metrics, 260
kivy.modules, 481
kivy.modules.console, 482
kivy.modules.inspector, 486
kivy.modules.joycursor, 488
kivy.modules.keybinding, 489
kivy.modules.monitor, 489
kivy.modules.recorder, 490
kivy.modules.screen, 490
kivy.modules.touchring, 491
kivy.modules.webdebugger, 491
kivy.multistroke, 263
kivy.network, 493
kivy.network.urlrequest, 493
kivy.parser, 272
kivy.properties, 273
kivy.resources, 288
kivy.storage, 497
kivy.storage.dictstore, 501
kivy.storage.jsonstore, 501
kivy.storage.redisstore, 501
kivy.support, 288
kivy.tools, 503
kivy.tools.packaging, 504
kivy.uix, 505
kivy.uix.accordion, 555
kivy.uix.actionbar, 560
kivy.uix.anchorlayout, 566
kivy.uix.behaviors, 505
kivy.uix.behaviors.button, 518
kivy.uix.behaviors.codenavigation,
 519
kivy.uix.behaviors.compoundselection,
 520
kivy.uix.behaviors.cover, 525
kivy.uix.behaviors.drag, 527
kivy.uix.behaviors.emacs, 528
kivy.uix.behaviors.focus, 529
kivy.uix.behaviors.knspase, 533
kivy.uix.behaviors.togglebutton,
 539
kivy.uix.behaviors.touchripple, 540
kivy.uix.boxlayout, 567
kivy.uix.bubble, 570
kivy.uix.button, 574
kivy.uix.camera, 576
kivy.uix.carousel, 577
kivy.uix.checkbox, 581
kivy.uix.codeinput, 583
kivy.uix.colorpicker, 584
kivy.uix.dropdown, 586
kivy.uix.effectwidget, 590
kivy.uix.filechooser, 595
kivy.uix.floatlayout, 605
kivy.uix.gesturesurface, 607
kivy.uix.gridlayout, 610
kivy.uix.image, 614
kivy.uix.label, 618
kivy.uix.layout, 631
kivy.uix.modalview, 633
kivy.uix.pagelayout, 636

kivy.uix.popup, 638
kivy.uix.progressbar, 641
kivy.uix.recycleboxlayout, 642
kivy.uix.recyclegridlayout, 642
kivy.uix.recyclelayout, 643
kivy.uix.recycleview, 542
kivy.uix.recycleview.datamodel, 548
kivy.uix.recycleview.layout, 549
kivy.uix.recycleview.views, 552
kivy.uix.relativelayout, 645
kivy.uix.rst, 650
kivy.uix.sandbox, 653
kivy.uix.scatter, 655
kivy.uix.scatterlayout, 660
kivy.uix.screenmanager, 662
kivy.uix.scrollview, 671
kivy.uix.settings, 678
kivy.uix.slider, 688
kivy.uix.spinner, 693
kivy.uix.splitter, 695
kivy.uix.stacklayout, 698
kivy.uix.stencilview, 700
kivy.uix.switch, 700
kivy.uix.tabbedpanel, 702
kivy.uix.textinput, 709
kivy.uix.togglebutton, 723
kivy.uixtreeview, 724
kivy.uix.video, 730
kivy.uix.videoplayer, 733
kivy.uix.vkeyboard, 738
kivy.uix.widget, 742
kivy.utils, 289
kivy.vector, 291
kivy.weakmethod, 295
kivy.weakproxy, 295
MonochromeEffect (class in *kivy.uix.effectwidget*), 594
motion_filter (*kivy.uix.widget.Widget* attribute), 751
MotionEvent (class in *kivy.input*), 429
MotionEvent (class in *kivy.input.motionevent*), 448
MotionEventFactory (class in *kivy.input*), 433
MotionEventFactory (class in *kivy.input.factory*), 452
MotionEventProvider (class in *kivy.input*), 433
MotionEventProvider (class in *kivy.input.provider*), 453
mouse_pos (*kivy.core.window.WindowBase* attribute), 323
MouseMotionEventProvider (class in *kivy.input.providers.mouse*), 439
move() (*kivy.input MotionEvent* method), 431
move() (*kivy.input.motionevent MotionEvent* method), 450
mtdev (class in *kivy.lib.mtdev*), 479
mtdev_caps (class in *kivy.lib.mtdev*), 479
MTDMotionEvent (class in *kivy.input.providers.mtdev*), 441
multiline (*kivy.uix.textinput.TextInput* attribute), 719
multiply() (*kivy.graphics.transformation.Matrix* method), 414
multiselect (*kivy.uix.behaviors.compoundselection.CompoundSelection* attribute), 523
multiselect (*kivy.uix.behaviors.CompoundSelectionBehavior* attribute), 509
multiselect (*kivy.uix.filechooser.FileChooserController* attribute), 602
MultistrokeGesture (class in *kivy.multistroke*), 265

N

name (*kivy.app.App* property), 208
name (*kivy.config.ConfigParser* property), 239
name (*kivy.uix.screenmanager.Screen* attribute), 666
next (*kivy.clock.ClockEvent* attribute), 227
next() (*kivy.uix.screenmanager.ScreenManager* method), 667
next_slide (*kivy.uix.carousel.Carousel* attribute), 579
no_selection (*kivy.uixtreeview.TreeViewNode* attribute), 729
nocache (*kivy.core.image.Image* property), 303
nocache (*kivy.uix.image.Image* attribute), 616
nodes (*kivy.uixtreeview.TreeViewNode* attribute), 729
nodes_order_reversed
 (*kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior* attribute), 523
nodes_order_reversed
 (*kivy.uix.behaviors.CompoundSelectionBehavior* attribute), 509
NoLanguageSelectedError, 305
norm_image_size (*kivy.uix.image.Image* attribute), 617
normal_matrix() (*kivy.graphics.transformation.Matrix* method), 415
normalize() (*kivy.gesture.Gesture* method), 251
normalize() (*kivy.vector.Vector* method), 294
normalize_stroke()
 (*kivy.gesture.GestureStroke* method), 252
NoSuchLangError, 305
NoTransition (class in *kivy.uix.screenmanager*), 666
num_workers (*kivy.loader.LoaderBase* property), 212
NumericProperty (class in *kivy.properties*), 283

O

ObjectProperty (class in *kivy.properties*), 284

`ObjectWithUid` (*class in kivy.event*), 248
`Observable` (*class in kivy.event*), 248
`Observable` (*class in kivy.lang*), 471
`Observable` (*class in kivy.lang.builder*), 475
`observable_dict` (*kivy.uix.recycleview.datamodel.RecycleData* property), 549
`odd` (*kivy.uix.treeview.TreeNode attribute*), 729
`odd_color` (*kivy.uix.treeview.TreeNode attribute*), 730
`on_anim_alpha()` (*kivy.uix.modalview.ModalView method*), 635
`on_bring_to_front()` (*kivy.uix.scatter.Scatter method*), 658
`on_close()` (*kivy.core.window.WindowBase method*), 323
`on_config_change()` (*kivy.app.App method*), 208
`on_context_created()` (*kivy.uix.sandbox.Sandbox method*), 654
`on_current_uid()` (*kivy.uix.settings.ContentPanel method*), 682
`on_cursor()` (*kivy.uix.textinput.TextInput method*), 719
`on_cursor_blink()` (*kivy.uix.textinput.TextInput method*), 719
`on_cursor_enter()` (*kivy.core.window.WindowBase method*), 324
`on_cursor_leave()` (*kivy.core.window.WindowBase method*), 324
`on_dismiss()` (*kivy.uix.modalview.ModalView method*), 635
`on_double_tap()` (*kivy.uix.textinput.TextInput method*), 719
`on_drop_begin()` (*kivy.core.window.WindowBase method*), 324
`on_drop_end()` (*kivy.core.window.WindowBase method*), 324
`on_drop_file()` (*kivy.core.window.WindowBase method*), 324
`on_drop_text()` (*kivy.core.window.WindowBase method*), 325
`on_exception()` (*kivy.uix.sandbox.Sandbox method*), 654
`on_flip()` (*kivy.core.window.WindowBase method*), 325
`on_hide()` (*kivy.core.window.WindowBase method*), 325
`on_joy_axis()` (*kivy.core.window.WindowBase method*), 326
`on_joy_ball()` (*kivy.core.window.WindowBase method*), 326
`on_joy_button_down()` (*kivy.core.window.WindowBase method*), 326
`on_joy_button_up()` (*kivy.core.window.WindowBase method*), 326
`on_joy_hat()` (*kivy.core.window.WindowBase method*), 326
`on_key_down()` (*kivy.core.window.WindowBase method*), 326
`on_key_up()` (*kivy.core.window.WindowBase method*), 326
`on_keyboard()` (*kivy.core.window.WindowBase method*), 326
`on_maximize()` (*kivy.core.window.WindowBase method*), 326
`on_memorywarning()` (*kivy.core.window.WindowBase method*), 326
`on_minimize()` (*kivy.core.window.WindowBase method*), 326
`on_motion()` (*kivy.core.window.WindowBase method*), 326
`on_motion()` (*kivy.uix.dropdown.DropDown method*), 589
`on_motion()` (*kivy.uix.modalview.ModalView method*), 635
`on_motion()` (*kivy.uix.relativelayout.RelativeLayout method*), 649
`on_motion()` (*kivy.uix.sandbox.Sandbox method*), 654
`on_motion()` (*kivy.uix.scatter.Scatter method*), 658
`on_motion()` (*kivy.uix.screenmanager.ScreenManager method*), 667
`on_motion()` (*kivy.uix.scrollview.ScrollView method*), 676
`on_motion()` (*kivy.uix.widget.Widget method*), 751
`on_mouse_down()` (*kivy.core.window.WindowBase method*), 327
`on_mouse_move()` (*kivy.core.window.WindowBase method*), 327
`on_mouse_up()` (*kivy.core.window.WindowBase method*), 327
`on_open()` (*kivy.uix.modalview.ModalView method*), 636
`on_pause()` (*kivy.app.App method*), 208
`on_pause()` (*kivy.base.EventLoopBase method*), 256
`on_pre_dismiss()` (*kivy.uix.modalview.ModalView method*), 636
`on_pre_open()` (*kivy.uix.modalview.ModalView method*), 636
`on_quad_touch()` (*kivy.uix.textinput.TextInput method*), 719
`on_request_close()`

(*kivy.core.window.WindowBase* method), 327
on_resize() (*kivy.core.window.WindowBase* method), 327
on_restore() (*kivy.core.window.WindowBase* method), 327
on_resume() (*kivy.app.App* method), 208
on_rotate() (*kivy.core.window.WindowBase* method), 327
on_schedule() (*kivy.clock.CyClockBase* method), 230
on_selected_uid()
 (*kivy.uix.settings.MenuSidebar* method), 683
on_show() (*kivy.core.window.WindowBase* method), 327
on_start() (*kivy.app.App* method), 208
on_start() (*kivy.base.EventLoopBase* method), 256
on_stop() (*kivy.app.App* method), 208
on_stop() (*kivy.base.EventLoopBase* method), 256
on_textedit() (*kivy.core.window.WindowBase* method), 327
on_textinput() (*kivy.core.window.WindowBase* method), 327
on_texture() (*kivy.core.image.Image* method), 303
on_touch_down() (*kivy.core.window.WindowBase* method), 328
on_touch_down() (*kivy.modules.console.Console* method), 485
on_touch_down() (*kivy.uix.accordion.AccordionItem* method), 559
on_touch_down() (*kivy.uix.carousel.Carousel* method), 579
on_touch_down() (*kivy.uix.colorpicker.ColorWheel* method), 585
on_touch_down() (*kivy.uix.dropdown.DropDown* method), 589
on_touch_down() (*kivy.uix.filechooser.FileChooserController* method), 602
on_touch_down() (*kivy.uix.filechooser.FileChooserProgressBase* method), 604
on_touch_down() (*kivy.uix.gesturesurface.GestureSurface* method), 610
on_touch_down() (*kivy.uix.label.Label* method), 627
on_touch_down() (*kivy.uix.modalview.ModalView* method), 636
on_touch_down() (*kivy.uix.pagelayout.PageLayout* method), 637
on_touch_down() (*kivy.uix.popup.Popup* method), 640
on_touch_down() (*kivy.uix.relativelayout.RelativeLayout* method), 650
on_touch_down() (*kivy.uix.sandbox.Sandbox* method), 655
on_touch_down() (*kivy.uix.scatter.Scatter* method), 659
on_touch_down() (*kivy.uix.screenmanager.ScreenManager* method), 668
on_touch_down() (*kivy.uix.scrollview.ScrollView* method), 676
on_touch_down() (*kivy.uix.settings.Settings* method), 687
on_touch_down() (*kivy.uix.slider.Slider* method), 690
on_touch_down() (*kivy.uix.switch.Switch* method), 701
on_touch_down() (*kivy.uix.tabbedpanel.TabbedPanelHeader* method), 708
on_touch_down() (*kivy.uix.textinput.TextInput* method), 720
on_touch_down() (*kivy.uixtreeview.TreeView* method), 727
on_touch_down() (*kivy.uix.videoplayer.VideoPlayer* method), 736
on_touch_down() (*kivy.uix.vkeyboard.VKeyboard* method), 741
on_touch_down() (*kivy.uix.widget.Widget* method), 751
on_touch_move() (*kivy.core.window.WindowBase* method), 328
on_touch_move() (*kivy.modules.console.Console* method), 485
on_touch_move() (*kivy.uix.carousel.Carousel* method), 580
on_touch_move() (*kivy.uix.colorpicker.ColorWheel* method), 586
on_touch_move() (*kivy.uix.dropdown.DropDown* method), 589
on_touch_move() (*kivy.uix.filechooser.FileChooserProgressBase* method), 604
on_touch_move() (*kivy.uix.gesturesurface.GestureSurface* method), 610
on_touch_move() (*kivy.uix.modalview.ModalView* method), 636
on_touch_move() (*kivy.uix.pagelayout.PageLayout* method), 637
on_touch_move() (*kivy.uix.relativelayout.RelativeLayout* method), 650
on_touch_move() (*kivy.uix.sandbox.Sandbox* method), 655
on_touch_move() (*kivy.uix.scatter.Scatter* method), 659
on_touch_move() (*kivy.uix.screenmanager.ScreenManager* method), 668
on_touch_move() (*kivy.uix.scrollview.ScrollView* method), 676
on_touch_move() (*kivy.uix.slider.Slider* method),

on_touch_move() 691
on_touch_move() (kivy.uix.switch.Switch method), 701
on_touch_move() (kivy.uix.textinput.TextInput method), 720
on_touch_move() (kivy.uix.widget.Widget method), 752
on_touch_up() (kivy.core.window.WindowBase method), 328
on_touch_up() (kivy.modules.console.Console method), 485
on_touch_up() (kivy.uix.carousel.Carousel method), 580
on_touch_up() (kivy.uix.colorpicker.ColorWheel method), 586
on_touch_up() (kivy.uix.dropdown.DropDown method), 589
on_touch_up() (kivy.uix.filechooser.FileChooserController method), 602
on_touch_up() (kivy.uix.filechooser.FileChooserProgressBase method), 604
on_touch_up() (kivy.uix.gesturesurface.GestureSurface method), 610
on_touch_up() (kivy.uix.modalview.ModalView method), 636
on_touch_up() (kivy.uix.pagelayout.PageLayout method), 637
on_touch_up() (kivy.uix.relativelayout.RelativeLayout method), 650
on_touch_up() (kivy.uix.sandbox.Sandbox method), 655
on_touch_up() (kivy.uix.scatter.Scatter method), 659
on_touch_up() (kivy.uix.screenmanager.ScreenManager method), 668
on_touch_up() (kivy.uix.scrollview.ScrollView method), 676
on_touch_up() (kivy.uix.settings.SettingItem method), 685
on_touch_up() (kivy.uix.slider.Slider method), 691
on_touch_up() (kivy.uix.switch.Switch method), 701
on_touch_up() (kivy.uix.textinput.TextInput method), 720
on_touch_up() (kivy.uix.vkeyboard.VKeyboard method), 742
on_touch_up() (kivy.uix.widget.Widget method), 752
on_transform_with_touch() (kivy.uix.scatter.Scatter method), 659
on_triple_tap() (kivy.uix.textinput.TextInput method), 720
opacity (kivy.graphics.Canvas attribute), 356
opacity (kivy.graphics.instructions.Canvas attribute), 374
opacity (kivy.uix.widget.Widget attribute), 752
OpacityScrollEffect (class in kivy.effects.opacityscroll), 340
open() (kivy.uix.dropdown.DropDown method), 590
open() (kivy.uix.modalview.ModalView method), 636
open_settings() (kivy.app.App method), 209
opos (kivy.input MotionEvent property), 431
opos (kivy.input.motionevent.MotionEvent property), 450
option_cls (kivy.uix.spinner.Spinner attribute), 694
OptionProperty (class in kivy.properties), 284
options (kivy.app.App attribute), 209
options (kivy.core.text.text_layout.LayoutWord attribute), 311
options (kivy.properties.OptionProperty attribute), 285
options (kivy.uix.settings.SettingsOptions attribute), 686
options (kivy.uix.video.Video attribute), 731
options (kivy.uix.videoplayer.VideoPlayer attribute), 736
order (kivy.uix.effectwidget.ChannelMixEffect attribute), 592
orientation (kivy.uix.accordion.Accordion attribute), 557
orientation (kivy.uix.accordion.AccordionItem attribute), 559
orientation (kivy.uix.boxlayout.BoxLayout attribute), 569
orientation (kivy.uix.bubble.Bubble attribute), 573
orientation (kivy.uix.gridlayout.GridLayout attribute), 613
orientation (kivy.uix.slider.Slider attribute), 691
orientation (kivy.uix.stacklayout.StackLayout attribute), 699
origin (kivy.graphics.context_instructions.Rotate attribute), 381
origin (kivy.graphics.context_instructions.Scale attribute), 381
origin (kivy.graphics.Rotate attribute), 369
origin (kivy.graphics.Scale attribute), 370
original_textures (kivy.atlas.Atlas attribute), 216
osx (kivy.input MotionEvent attribute), 431
osx (kivy.input.motionevent.MotionEvent attribute), 450
osy (kivy.input MotionEvent attribute), 431
osy (kivy.input.motionevent.MotionEvent attribute), 450
osz (kivy.input MotionEvent attribute), 431
osz (kivy.input.motionevent.MotionEvent attribute), 450

out_back() (*kivy.animation.AnimationTransition* static method), 195
out_bounce() (*kivy.animation.AnimationTransition* static method), 195
out_circ() (*kivy.animation.AnimationTransition* static method), 195
out_cubic() (*kivy.animation.AnimationTransition* static method), 195
out_elastic() (*kivy.animation.AnimationTransition* static method), 196
out_expo() (*kivy.animation.AnimationTransition* static method), 196
out_quad() (*kivy.animation.AnimationTransition* static method), 196
out_quart() (*kivy.animation.AnimationTransition* static method), 196
out_quint() (*kivy.animation.AnimationTransition* static method), 196
out_sine() (*kivy.animation.AnimationTransition* static method), 196
outline_color (*kivy.uix.label.Label* attribute), 627
outline_width (*kivy.uix.label.Label* attribute), 627
overdraw_width (*kivy.graphics.SmoothLine* attribute), 371
overdraw_width (*kivy.graphics.vertex_instructions*.*attribute*), 426
overflow_group (*kivy.uix.actionbar.ActionView* attribute), 565
overflow_image (*kivy.uix.actionbar.ActionOverflow* attribute), 563
overlay_color (*kivy.uix.modalview.ModalView* attribute), 636
overscroll (*kivy.effects.scroll.ScrollEffect* attribute), 340
ox (*kivy.input.MotionEvent* attribute), 431
ox (*kivy.input.motionevent.MotionEvent* attribute), 450
oy (*kivy.input.MotionEvent* attribute), 431
oy (*kivy.input.motionevent.MotionEvent* attribute), 450
oz (*kivy.input.MotionEvent* attribute), 431
oz (*kivy.input.motionevent.MotionEvent* attribute), 450

P

pack_width (*kivy.uix.actionbar.ActionItem* attribute), 563
padding (*kivy.uix.anchorlayout.AnchorLayout* attribute), 566
padding (*kivy.uix.boxlayout.BoxLayout* attribute), 569
padding (*kivy.uix.gridlayout.GridLayout* attribute), 613
padding (*kivy.uix.label.Label* attribute), 627
padding (*kivy.uix.slider.Slider* attribute), 691

padding (*kivy.uix.stacklayout.StackLayout* attribute), 699
padding (*kivy.uix.textinput.TextInput* attribute), 720
padding_x (*kivy.uix.label.Label* attribute), 627
padding_x (*kivy.uix.textinput.TextInput* attribute), 720
padding_y (*kivy.uix.label.Label* attribute), 627
padding_y (*kivy.uix.textinput.TextInput* attribute), 720
page (*kivy.uix.pagelayout.PageLayout* attribute), 637
page_count (*kivy.uix.behaviors.compoundselection.CompoundSelection* attribute), 523
page_count (*kivy.uix.behaviors.CompoundSelectionBehavior* attribute), 509
PageLayout (class in *kivy.uix.pagelayout*), 637
panel (*kivy.uix.settings.SettingItem* attribute), 685
panels (*kivy.uix.settings.ContentPanel* attribute), 682
parent (*kivy.core.window.WindowBase* attribute), 328
parent (*kivy.uix.behaviors.knspase.KNSpace* attribute), 538
parent (*kivy.uix.widget.Widget* attribute), 752
parentnode (*kivy.uixtreeview.TreeviewNode* attribute), 730
parse() (*kivy.lang.Parser* method), 472
parse() (*kivy.lang.parser.Parser* method), 476
parse_bool() (in module *kivy.parser*), 272
parse_color() (in module *kivy.parser*), 272
parse_filename() (in module *kivy.parser*), 272
parse_float (in module *kivy.parser*), 272
parse_float4() (in module *kivy.parser*), 272
parse_gesture() (*kivy.multistroke.Recognizer* method), 270
parse_int (in module *kivy.parser*), 272
parse_int2() (in module *kivy.parser*), 272
parse_kivy_version() (in module *kivy*), 188
parse_level() (*kivy.lang.Parser* method), 472
parse_level() (*kivy.lang.parser.Parser* method), 476
parse_string() (in module *kivy.parser*), 272
Parser (class in *kivy.lang*), 472
Parser (class in *kivy.lang.parser*), 476
ParserException, 472, 476
PASS (*kivy.base.ExceptionManagerBase* attribute), 257
password (*kivy.uix.textinput.TextInput* attribute), 720
password_mask (*kivy.uix.textinput.TextInput* attribute), 720
paste() (*kivy.uix.textinput.TextInput* method), 721
path (*kivy.uix.filechooser.FileChooserController* attribute), 602
path (*kivy.uix.filechooser.FileChooserProgressBase* at-

tribute), 604
pause() (*kivy.core.video.VideoBase* method), 315
pause() (*kivy.loader.LoaderBase* method), 212
permute() (*kivy.multistroke.MultistrokeGesture* method), 266
perspective() (*kivy.graphics.transformation.Matrix* method), 415
pgmove_speed (*kivy.uix.textinput.TextInput* property), 721
pick() (*kivy.modules.console.Console* method), 485
pitch (*kivy.core.audio.Sound* attribute), 298
pixel_size (*kivy.uix.effectwidget.PixelateEffect* attribute), 594
PixelateEffect (*class in kivy.uix.effectwidget*), 594
pixels (*kivy.graphics.Fbo* attribute), 360
pixels (*kivy.graphics.fbo.Fbo* attribute), 385
pixels (*kivy.graphics.texture.Texture* attribute), 412
pixels (*kivy.graphics.texture.TextureRegion* attribute), 413
platform (*in module kivy.utils*), 290
play (*kivy.input.recorder.Recorder* attribute), 446
play (*kivy.uix.camera.Camera* attribute), 576
play (*kivy.uix.video.Video* attribute), 731
play (*kivy.uix.videoplayer.VideoPlayer* attribute), 736
play() (*kivy.core.audio.Sound* method), 298
play() (*kivy.core.video.VideoBase* method), 315
Point (*class in kivy.graphics*), 367
Point (*class in kivy.graphics.vertex_instructions*), 425
points (*kivy.graphics.Bezier* attribute), 353
points (*kivy.graphics.Line* attribute), 365
points (*kivy.graphics.Point* attribute), 368
points (*kivy.graphics.Quad* attribute), 368
points (*kivy.graphics.Triangle* attribute), 372
points (*kivy.graphics.vertex_instructions.Bezier* attribute), 418
points (*kivy.graphics.vertex_instructions.Line* attribute), 423
points (*kivy.graphics.vertex_instructions.Point* attribute), 425
points (*kivy.graphics.vertex_instructions.Quad* attribute), 426
points (*kivy.graphics.vertex_instructions.Triangle* attribute), 427
points_distance() (*kivy.gesture.GestureStroke* method), 252
pointsize (*kivy.graphics.Point* attribute), 368
pointsize (*kivy.graphics.vertex_instructions.Point* attribute), 425
pop() (*kivy.context.Context* method), 240
pop() (*kivy.graphics.scissor_instructions.ScissorStack* method), 399
pop() (*kivy.input MotionEvent* method), 431
pop() (*kivy.input.motionevent MotionEvent* method), 431
method), 451
PopMatrix (*class in kivy.graphics*), 368
PopMatrix (*class in kivy.graphics.context_instructions*), 380
PopState (*class in kivy.graphics*), 368
Popup (*class in kivy.uix.popup*), 639
popup (*kivy.uix.settings.SettingsOptions* attribute), 686
popup (*kivy.uix.settings.SettingsPath* attribute), 686
popup (*kivy.uix.settings.SettingsString* attribute), 686
PopupException, 641
pos (*kivy.graphics.Rectangle* attribute), 368
pos (*kivy.graphics.vertex_instructions.Rectangle* attribute), 426
pos (*kivy.input MotionEvent* attribute), 431
pos (*kivy.input.motionevent MotionEvent* attribute), 451
pos (*kivy.uix.widget.Widget* attribute), 752
pos_hint (*kivy.uix.widget.Widget* attribute), 752
position (*kivy.core.video.VideoBase* property), 315
position (*kivy.uix.video.Video* attribute), 731
position (*kivy.uix.videoplayer.VideoPlayer* attribute), 736
post_dispatch_input() (*kivy.base.EventLoopBase* method), 256
post_idle() (*kivy.clock.ClockBaseBehavior* method), 225
ppos (*kivy.input MotionEvent* property), 431
ppos (*kivy.input.motionevent MotionEvent* property), 451
pre_idle() (*kivy.clock.ClockBaseBehavior* method), 226
preload() (*kivy.uix.rst.RstDocument* method), 652
premultiplied_texture() (*kivy.graphics.SmoothLine* method), 371
premultiplied_texture() (*kivy.graphics.vertex_instructions.SmoothLine* method), 426
prepare() (*kivy.multistroke.Candidate* method), 265
prepare() (*kivy.multistroke.UnistrokeTemplate* method), 271
prepare_templates() (*kivy.multistroke.Recognizer* method), 270
prev (*kivy.clock.ClockEvent* attribute), 227
preview (*kivy.uix.video.Video* attribute), 731
previous() (*kivy.uix.screenmanager.ScreenManager* method), 668
previous_image (*kivy.uix.actionbar.ActionPrevious* attribute), 564
previous_image_height (*kivy.uix.actionbar.ActionPrevious* attribute), 564
previous_image_width

*(kivy.uix.actionbar.ActionPrevious
attribute),* 564
previous_slide (*kivy.uix.carousel.Carousel
attribute*), 580
print_usage() (*kivy.cache.Cache static method*),
217
profile (*kivy.input MotionEvent attribute*), 431
profile (*kivy.input.motionevent MotionEvent
attribute*), 451
progress (*kivy.multistroke.ProgressTracker prop-
erty*), 268
progress_cls (*kivy.uix.filechooser.FileChooserController
attribute*), 603
ProgressBar (*class in kivy.uix.progressbar*), 641
ProgressTracker (*class in kivy.multistroke*), 267
project() (*kivy.graphics.transformation.Matrix
method*), 415
properties() (*kivy.event.EventDispatcher
method*), 246
Property (*class in kivy.properties*), 285
property() (*kivy.event.EventDispatcher method*),
247
property() (*kivy.uix.behaviors.knspase.KNSpace
method*), 538
proxy_ref (*kivy.event.EventDispatcher attribute*),
247
proxy_ref (*kivy.graphics.Instruction attribute*), 360
proxy_ref (*kivy.graphics.instructions.Instruction
attribute*), 375
proxy_ref (*kivy.uix.widget.Widget property*), 752
ProxyImage (*class in kivy.loader*), 213
psx (*kivy.input MotionEvent attribute*), 432
psx (*kivy.input.motionevent MotionEvent attribute*),
451
psy (*kivy.input MotionEvent attribute*), 432
psy (*kivy.input.motionevent MotionEvent attribute*),
451
psz (*kivy.input MotionEvent attribute*), 432
psz (*kivy.input.motionevent MotionEvent attribute*),
451
pt (*kivy.metrics.MetricsBase attribute*), 262
pt() (*in module kivy.metrics*), 263
push() (*kivy.graphics.scissor_instructions.ScissorStack
method*), 399
push() (*kivy.input MotionEvent method*), 432
push() (*kivy.input.motionevent MotionEvent
method*), 451
push_attrs_stack (*kivy.input MotionEvent
attribute*), 432
push_attrs_stack
*(kivy.input.motionevent MotionEvent
attribute)*, 451
PushMatrix (*class in kivy.graphics*), 368
PushMatrix (*class
in kivy.graphics.context_instructions*), 380
at- **PushState** (*class in kivy.graphics*), 368
put() (*kivy.storage.AbstractStore method*), 500
px (*kivy.input MotionEvent attribute*), 432
px (*kivy.input.motionevent MotionEvent attribute*),
451
py (*kivy.input MotionEvent attribute*), 432
py (*kivy.input.motionevent MotionEvent attribute*),
451
PY2 (*in module kivy.compat*), 233
pz (*kivy.input MotionEvent attribute*), 432
pz (*kivy.input.motionevent MotionEvent attribute*),
451

Q

Quad (*class in kivy.graphics*), 368
Quad (*class in kivy.graphics.vertex_instructions*), 425
QueryDict (*class in kivy.lib.ddsfile*), 478
QueryDict (*class in kivy.utils*), 289

R

r (*kivy.graphics.ClearColor attribute*), 357
r (*kivy.graphics.Color attribute*), 358
r (*kivy.graphics.context_instructions.Color attribute*),
380
r (*kivy.graphics.gl_instructions.ClearColor attribute*),
386
r (*kivy.uix.colorpicker.ColorWheel attribute*), 586
radius (*kivy.graphics.vertex_instructions.RoundedRectangle
attribute*), 426
RAISE (*kivy.base.ExceptionManagerBase attribute*),
257
raise_window() (*kivy.core.window.WindowBase
method*), 328
range (*kivy.uix.slider.Slider attribute*), 691
read() (*kivy.config.ConfigParser method*), 239
read_pixel() (*kivy.core.image.Image method*), 303
readonly (*kivy.uix.textinput.TextInput attribute*),
721
rebind (*kivy.properties.AliasProperty attribute*), 278
rebind (*kivy.properties.DictProperty attribute*), 282
rebind (*kivy.properties.ObjectProperty attribute*),
284
recognize() (*kivy.multistroke.Recognizer method*),
270
Recognizer (*class in kivy.multistroke*), 268
record (*kivy.input.recorder.Recorder attribute*), 446
record_attrs (*kivy.input.recorder.Recorder
attribute*), 446
record_profile_mask
*(kivy.input.recorder.Recorder
attribute)*, 446
Recorder (*class in kivy.input.recorder*), 446
Rect (*class in kivy.graphics.scissor_instructions*), 399
Rectangle (*class in kivy.graphics*), 368
Rectangle (*class
in kivy.graphics.vertex_instructions*), 426

rectangle (*kivy.graphics.Line attribute*), 365
rectangle (*kivy.graphics.vertex_instructions.Line attribute*), 423
RecycleBoxLayout (class in *kivy.uix.recycleboxlayout*), 642
RecycleDataAdapter (class in *kivy.uix.recycleview.views*), 552
RecycleDataModel (class in *kivy.uix.recycleview.datamodel*), 548
RecycleDataModelBehavior (class in *kivy.uix.recycleview.datamodel*), 549
RecycleDataViewBehavior (class in *kivy.uix.recycleview.views*), 554
RecycleGridLayout (class in *kivy.uix.recyclegridlayout*), 642
RecycleKVIDsDataViewBehavior (class in *kivy.uix.recycleview.views*), 554
RecycleLayout (class in *kivy.uix.recyclelayout*), 643
RecycleLayoutManagerBehavior (class in *kivy.uix.recycleview.layout*), 551
RecycleView (class in *kivy.uix.recycleview*), 546
recycleview (*kivy.uix.recycleview.datamodel.RecycleDataModel* attribute), 549
recycleview (*kivy.uix.recycleview.views.RecycleDataViewBehavior* attribute), 553
RecycleViewBehavior (class in *kivy.uix.recycleview*), 547
RedisStore (class in *kivy.storage.redisstore*), 501
reference_size (*kivy.uix.behaviors.cover.CoverBehavior* attribute), 526
reference_size (*kivy.uix.behaviors.CoverBehavior* attribute), 511
ReferenceListProperty (class in *kivy.properties*), 286
refresh() (*kivy.core.text.LabelBase* method), 309
refresh() (*kivy.uix.vkeyboard.VKeyboard* method), 742
refresh_fbo_setup() (*kivy.effectwidget.EffectWidget* method), 594
refresh_from_data() (*kivy.uix.recycleview.RecycleViewBehavior* method), 548
refresh_from_layout() (*kivy.uix.recycleview.RecycleViewBehavior* method), 548
refresh_from_viewport() (*kivy.uix.recycleview.RecycleViewBehavior* method), 548
refresh_view_attrs() (*kivy.uix.recycleview.views.RecycleDataAdapter* method), 553
refresh_view_attrs() (*kivy.uix.recycleview.views.RecycleDataViewBehavior* method), 554
refresh_view_attrs() (*kivy.uix.recycleview.views.RecycleDataViewBehavior* method), 555
refresh_view_attrs() (in *kivy.uix.recycleview.views.RecycleKVIDsDataViewBehavior* method), 555
refresh_view_layout() (in *kivy.uix.recyclelayout.RecycleLayout* method), 645
refresh_view_layout() (in *kivy.uix.recycleview.layout.RecycleLayoutManagerBehavior* method), 552
refresh_view_layout() (in *kivy.uix.recycleview.views.RecycleDataAdapter* method), 554
refresh_view_layout() (in *kivy.uix.recycleview.views.RecycleDataViewBehavior* method), 554
refs (*kivy.core.text.markup.MarkupLabel* property), 314
refs (*kivy.uix.label.Label* attribute), 627
register() (*kivy.cache.Cache* static method), 217
register() (*kivy.core.audio.SoundLoader* static method), 299
DeglitchBehavior (*kivy.core.text.LabelBase* static method), 309
register() (*kivy.input.factory.MotionEventFactory* static method), 453
register() (*kivy.input.MotionEventFactory* static method), 433
register() (*kivy.input.providers.tuio.TuioMotionEventProvider* static method), 444
register_context() (in module *kivy.context*), 240
register_event_manager() (*kivy.core.window.WindowBase* method), 328
register_event_type() (*kivy.event.EventDispatcher* method), 247
register_for_motion_event() (*kivy.uix.widget.Widget* method), 753
register_type() (*kivy.uix.settings.Settings* method), 687
reify (class in *kivy.utils*), 291
RelativeLayout (class in *kivy.uix.relativelayout*), 649
release() (*kivy.clock.ClockEvent* method), 227
release() (*kivy.core.window.Keyboard* method), 317
release() (*kivy.graphics.Fbo* method), 360
release() (*kivy.graphics.fbo.Fbo* method), 385
release_all_keyboards() (*kivy.core.window.WindowBase* method), 328
release_keyboard() (*kivy.core.window.WindowBase* method), 328

<code>release_ref</code> (<code>kivy.clock.ClockEvent</code> attribute), 227	328
<code>reload()</code> (<code>kivy.graphics.context.Context</code> method), 382	
<code>reload()</code> (<code>kivy.uix.image.Image</code> method), 617	
<code>remove()</code> (<code>kivy.cache.Cache</code> static method), 217	
<code>remove()</code> (<code>kivy.graphics.Canvas</code> method), 356	
<code>remove()</code> (<code>kivy.graphics.InstructionGroup</code> method), 361	
<code>remove()</code> (<code>kivy.graphics.instructions.Canvas</code> method), 375	
<code>remove()</code> (<code>kivy.graphics.instructions.InstructionGroup</code> method), 376	
<code>remove_android_splash()</code> (<code>kivy.base.EventLoopBase</code> method), 256	
<code>remove_callback()</code> (<code>kivy.config.ConfigParser</code> method), 239	
<code>remove_event_listener()</code> (<code>kivy.base.EventLoopBase</code> method), 256	
<code>remove_from_cache()</code> (<code>kivy.core.image.Image</code> method), 303	
<code>remove_from_cache()</code> (<code>kivy.uix.image.AsyncImage</code> method), 615	
<code>remove_from_cache()</code> (<code>kivy.uix.image.Image</code> method), 617	
<code>remove_group()</code> (<code>kivy.graphics.InstructionGroup</code> method), 361	
<code>remove_group()</code> (<code>kivy.graphics.instructions.InstructionGroup</code> method), 376	
<code>remove_handler()</code> (<code>kivy.base.ExceptionManagerBase</code> method), 257	
<code>remove_input_provider()</code> (<code>kivy.base.EventLoopBase</code> method), 256	
<code>remove_node()</code> (<code>kivy.uixtreeview.TreeView</code> method), 727	
<code>remove_postproc_module()</code> (<code>kivy.base.EventLoopBase</code> method), 256	
<code>remove_reload_observer()</code> (<code>kivy.graphics.context.Context</code> method), 382	
<code>remove_reload_observer()</code> (<code>kivy.graphics.Fbo</code> method), 360	
<code>remove_reload_observer()</code> (<code>kivy.graphics.fbo.Fbo</code> method), 385	
<code>remove_reload_observer()</code> (<code>kivy.graphics.texture.Texture</code> method), 412	
<code>remove_screen()</code> (<code>kivy.uix.screenmanager.ShaderTransition</code> attribute), 670	
<code>remove_screen()</code> (<code>kivy.uix.screenmanager.TransitionBase</code> method), 671	
<code>remove_toolbar_widget()</code> (<code>kivy.modules.console.Console</code> method), 485	
<code>remove_widget()</code> (<code>kivy.core.window.WindowBase</code> method), 328	
<code>remove_widget()</code> (<code>kivy.uix.accordion.AccordionItem</code> method), 559	
<code>remove_widget()</code> (<code>kivy.uix.actionbar.ActionView</code> method), 565	
<code>remove_widget()</code> (<code>kivy.uix.boxlayout.BoxLayout</code> method), 569	
<code>remove_widget()</code> (<code>kivy.uix.bubble.Bubble</code> method), 573	
<code>remove_widget()</code> (<code>kivy.uix.carousel.Carousel</code> method), 580	
<code>remove_widget()</code> (<code>kivy.uix.dropdown.DropDown</code> method), 590	
<code>remove_widget()</code> (<code>kivy.uix.effectwidget.EffectWidget</code> method), 594	
<code>remove_widget()</code> (<code>kivy.uix.floatlayout.FloatLayout</code> method), 607	
<code>remove_widget()</code> (<code>kivy.uix.layout.Layout</code> method), 633	
<code>remove_widget()</code> (<code>kivy.uix.recycleview.RecycleView</code> method), 547	
<code>remove_widget()</code> (<code>kivy.uix.sandbox.Sandbox</code> method), 655	
<code>remove_widget()</code> (<code>kivy.uix.scatterlayout.ScatterLayout</code> method), 661	
<code>remove_widget()</code> (<code>kivy.uix.screenmanager.ScreenManager</code> method), 668	
<code>remove_widget()</code> (<code>kivy.uix.scrollview.ScrollView</code> method), 676	
<code>remove_widget()</code> (<code>kivy.uix.settings.ContentPanel</code> method), 682	
<code>remove_widget()</code> (<code>kivy.uix.splitter.Splitter</code> method), 697	
<code>remove_widget()</code> (<code>kivy.uix.tabbedpanel.TabbedPanel</code> method), 707	
<code>remove_widget()</code> (<code>kivy.uix.tabbedpanel.TabbedPanelItem</code> method), 709	
<code>remove_widget()</code> (<code>kivy.uix.widget.Widget</code> method), 753	
<code>render()</code> (<code>kivy.core.text.LabelBase</code> method), 309	
<code>render()</code> (<code>kivy.core.text.markup.MarkupLabel</code> method), 314	
<code>render()</code> (<code>kivy.uix.rst.RstDocument</code> method), 652	
<code>RenderContext</code> (class in <code>kivy.graphics</code>), 368	
<code>RenderContext</code> (class in <code>kivy.graphics.instructions</code>), 376	
<code>replace_crlf</code> (<code>kivy.uix.textinput.TextInput</code> attribute), 721	
<code>req_body</code> (<code>kivy.network.urlrequest.UrlRequest</code> attribute), 495	
<code>req_headers</code> (<code>kivy.network.urlrequest.UrlRequest</code> attribute), 495	
<code>request_keyboard()</code>	

(kivy.core.window.WindowBase method), 329
require() (in module kivy), 188
rescale_with_parent (kivy.uix.splitter.Splitter attribute), 697
reset() (kivy.effects.scroll.ScrollEffect method), 340
reset_context (kivy.graphics.Callback attribute), 355
reset_context (kivy.graphics.instructions.Callback attribute), 374
reset_dpi() (kivy.metrics.MetricsBase method), 262
reset_metrics() (kivy.metrics.MetricsBase method), 262
reset_undo() (kivy.uix.textinput.TextInput method), 721
resolution (kivy.core.camera.CameraBase property), 300
resolution (kivy.uix.camera.Camera attribute), 576
resolve_path() (kivy.uix.rst.RstDocument method), 652
resource_add_path() (in module kivy.resources), 288
resource_find() (in module kivy.resources), 288
resource_remove_path() (in module kivy.resources), 288
resp_headers (kivy.network.urlrequest.UrlRequest property), 495
resp_status (kivy.network.urlrequest.UrlRequest property), 496
restore() (kivy.core.window.WindowBase method), 329
result (kivy.network.urlrequest.UrlRequest property), 496
resume() (kivy.loader.LoaderBase method), 212
rgb (kivy.graphics.ClearColor attribute), 357
rgb (kivy.graphics.Color attribute), 358
rgb (kivy.graphics.context_instructions.Color attribute), 380
rgb (kivy.graphics.gl_instructions.ClearColor attribute), 386
rgba (kivy.graphics.ClearColor attribute), 357
rgba (kivy.graphics.Color attribute), 358
rgba (kivy.graphics.context_instructions.Color attribute), 380
rgba (kivy.graphics.gl_instructions.ClearColor attribute), 386
rgba() (in module kivy.utils), 291
right (kivy.uix.widget.Widget attribute), 753
right_count (kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior attribute), 523
right_count (kivy.uix.behaviors.CompoundSelectionBehavior attribute), 509
ripple_duration_in (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 541
ripple_duration_in (kivy.uix.behaviors.TouchRippleBehavior attribute), 517
ripple_duration_out (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 541
ripple_duration_out (kivy.uix.behaviors.TouchRippleBehavior attribute), 517
ripple_fade() (kivy.uix.behaviors.touchripple.TouchRippleBehavior method), 541
ripple_fade() (kivy.uix.behaviors.TouchRippleBehavior method), 517
ripple_fade_from_alpha (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 541
ripple_fade_from_alpha (kivy.uix.behaviors.TouchRippleBehavior attribute), 517
ripple_fade_to_alpha (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 541
ripple_fade_to_alpha (kivy.uix.behaviors.TouchRippleBehavior attribute), 517
ripple_func_in (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 541
ripple_func_in (kivy.uix.behaviors.TouchRippleBehavior attribute), 517
ripple_func_out (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 541
ripple_func_out (kivy.uix.behaviors.TouchRippleBehavior attribute), 517
ripple_rad_default (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 541
ripple_rad_default (kivy.uix.behaviors.TouchRippleBehavior attribute), 517
ripple_scale (kivy.uix.behaviors.touchripple.TouchRippleBehavior attribute), 541
ripple_scale (kivy.uix.behaviors.TouchRippleBehavior attribute), 517
ripple_show() (kivy.uix.behaviors.touchripple.TouchRippleBehavior method), 541
ripple_show() (kivy.uix.behaviors.TouchRippleBehavior method), 517
RiseInTransition (class) in
CompoundSelectionBehavior, 666
root (kivy.app.App attribute), 209
root (kivy.uix.treeview.TreeView attribute), 728
root_options (kivy.uix.treeview.TreeView attribute), 728

`root_window` (*kivy.app.App* property), 209
`rootpath` (*kivy.uix.filechooser.FileChooserController* attribute), 603
`Rotate` (*class* in *kivy.graphics*), 369
`Rotate` (*class* in *kivy.graphics.context_instructions*), 380
`rotate()` (*kivy.graphics.transformation.Matrix* method), 415
`rotate()` (*kivy.vector.Vector* method), 294
`rotation` (*kivy.core.window.WindowBase* attribute), 329
`rotation` (*kivy.uix.scatter.Scatter* attribute), 659
`round_value` (*kivy.effects.dampedscroll.DampedScrollView* attribute), 337
`rounded_rectangle` (*kivy.graphics.Line* attribute), 365
`rounded_rectangle` (*kivy.graphics.vertex_instructions.Line* attribute), 423
`RoundedRectangle` (*class* in *kivy.graphics.vertex_instructions*), 426
`row_default_height` (*kivy.uix.GridLayout* attribute), 613
`row_force_default` (*kivy.uix.GridLayout* attribute), 614
`rowlength` (*kivy.core.image.ImageData* property), 304
`rows` (*kivy.uix.GridLayout* attribute), 614
`rows_minimum` (*kivy.uix.GridLayout* attribute), 614
`RstDocument` (*class* in *kivy.uix.rst*), 651
`run()` (*kivy.app.App* method), 209
`run()` (*kivy.base.EventLoopBase* method), 256
`run()` (*kivy.loader.LoaderBase* method), 212
`run()` (*kivy.network.urlrequest.UrlRequest* method), 496
`runTouchApp()` (*in module kivy.app*), 210
`runTouchApp()` (*in module kivy.base*), 257

S

`s` (*kivy.graphics.Color* attribute), 358
`s` (*kivy.graphics.context_instructions.Color* attribute), 380
`safeIn()` (*kivy.interactive.SafeMembrane* method), 255
`SafeList` (*class* in *kivy.utils*), 289
`SafeMembrane` (*class* in *kivy.interactive*), 255
`safeOut()` (*kivy.interactive.SafeMembrane* method), 255
`Sandbox` (*class* in *kivy.uix.sandbox*), 653
`save()` (*kivy.core.image.Image* method), 303
`save()` (*kivy.graphics.texture.Texture* method), 413
`Scale` (*class* in *kivy.graphics*), 370
`Scale` (*class* in *kivy.graphics.context_instructions*), 381
`scale` (*kivy.graphics.context_instructions.Scale* attribute), 381
`scale` (*kivy.graphics.Scale* attribute), 370
`scale` (*kivy.uix.Scatter* attribute), 659
`scale()` (*kivy.graphics.transformation.Matrix* method), 415
`scale_for_screen()` (*kivy.input MotionEvent* method), 432
`scale_for_screen()` (*kivy.input.motionevent MotionEvent* method), 451
`scale_max` (*kivy.uix.Scatter* attribute), 659
`scale_min` (*kivy.uix.Scatter* attribute), 659
`scale_stroke()` (*kivy.gesture.GestureStroke* method), 252
`ScanlinesEffect` (*class* in *kivy.uix.effectwidget*), 594
`Scatter` (*class* in *kivy.uix.scatter*), 657
`ScatterLayout` (*class* in *kivy.uix.scatterlayout*), 661
`ScatterPlane` (*class* in *kivy.uix.scatter*), 660
`ScatterPlaneLayout` (*class* in *kivy.uix.scatterlayout*), 662
`schedule_del_safe()` (*kivy.clock.CyClockBase* method), 230
`schedule_interval()` (*kivy.clock.CyClockBase* method), 230
`schedule_interval()` (*kivy.clock.CyClockBaseFree* method), 232
`schedule_interval_free()` (*kivy.clock.CyClockBaseFree* method), 232
`schedule_lifecycle_aware_del_safe()` (*kivy.clock.CyClockBase* method), 230
`schedule_once()` (*kivy.clock.CyClockBase* method), 231
`schedule_once()` (*kivy.clock.CyClockBaseFree* method), 232
`schedule_once_free()` (*kivy.clock.CyClockBaseFree* method), 232
`ScissorPop` (*class* in *kivy.graphics.scissor_instructions*), 399
`ScissorPush` (*class* in *kivy.graphics.scissor_instructions*), 399
`ScissorStack` (*class* in *kivy.graphics.scissor_instructions*), 399
`Screen` (*class* in *kivy.uix.screenmanager*), 666
`screen_in` (*kivy.uix.screenmanager.TransitionBase* attribute), 671
`screen_names` (*kivy.uix.screenmanager.ScreenManager* attribute), 668

`screen_out` (*kivy.uix.screenmanager.TransitionBase attribute*), 671
`ScreenManager` (*class in kivy.uix.screenmanager*), 667
`ScreenManagerException`, 669
`screens` (*kivy.uix.screenmanager.ScreenManager attribute*), 668
`screenshot()` (*kivy.core.window.WindowBase method*), 329
`scroll` (*kivy.effects.scroll.ScrollEffect attribute*), 340
`scroll_count` (*kivy.uix.behaviors.compoundselection attribute*), 523
`scroll_count` (*kivy.uix.behaviors.CompoundSelection attribute*), 509
`scroll_distance` (*kivy.uix.carousel.Carousel attribute*), 580
`scroll_distance` (*kivy.uix.scrollview.ScrollView attribute*), 677
`scroll_distance` (*kivy.uix.textinput.TextInput attribute*), 721
`scroll_from_swipe`
 (*kivy.uix.textinput.TextInput attribute*), 721
`scroll_timeout` (*kivy.uix.carousel.Carousel attribute*), 580
`scroll_timeout` (*kivy.uix.scrollview.ScrollView attribute*), 677
`scroll_timeout` (*kivy.uix.textinput.TextInput attribute*), 721
`scroll_to()` (*kivy.uix.scrollview.ScrollView method*), 677
`scroll_type` (*kivy.uix.scrollview.ScrollView attribute*), 677
`scroll_wheel_distance`
 (*kivy.uix.scrollview.ScrollView attribute*), 677
`scroll_x` (*kivy.uix.scrollview.ScrollView attribute*), 677
`scroll_x` (*kivy.uix.textinput.TextInput attribute*), 721
`scroll_y` (*kivy.uix.scrollview.ScrollView attribute*), 677
`scroll_y` (*kivy.uix.textinput.TextInput attribute*), 721
`ScrollEffect` (*class in kivy.effects.scroll*), 340
`ScrollView` (*class in kivy.uix.scrollview*), 673
`section` (*kivy.uix.settings.SettingItem attribute*), 685
`seek()` (*kivy.core.audio.Sound method*), 298
`seek()` (*kivy.core.video.VideoBase method*), 315
`seek()` (*kivy.uix.video.Video method*), 731
`seek()` (*kivy.uix.videoplayer.VideoPlayer method*), 736
`segment_intersection()` (*kivy.vector.Vector static method*), 294
`segments` (*kivy.graphics.Bezier attribute*), 353
`segments` (*kivy.graphics.Ellipse attribute*), 359
`segments` (*kivy.graphics.vertex_instructions.Bezier attribute*), 418
`segments` (*kivy.graphics.vertex_instructions.Ellipse attribute*), 419
`segments` (*kivy.graphics.vertex_instructions.RoundedRectangle attribute*), 426
`select()` (*kivy.uix.dropdown.DropDown method*), 590
`SelectableSelectionBehavior` (*kivy.uix.textinput.TextInput method*), 722
`SelectLanguage`
 (*kivy.core.spelling.SpellingBase method*), 305
`select_node()` (*kivy.uix.behaviors.compoundselection.CompoundSelection method*), 523
`select_node()` (*kivy.uix.behaviors.CompoundSelectionBehavior method*), 509
`select_node()` (*kivy.uix.recycleview.layout.LayoutSelectionBehavior method*), 551
`select_node()` (*kivy.uixtreeview.TreeView method*), 728
`select_text()` (*kivy.uix.textinput.TextInput method*), 722
`select_with_key_down()`
 (*kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior method*), 524
`select_with_key_down()`
 (*kivy.uix.behaviors.CompoundSelectionBehavior method*), 510
`select_with_key_up()`
 (*kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior method*), 524
`select_with_key_up()`
 (*kivy.uix.behaviors.CompoundSelectionBehavior method*), 510
`select_with_touch()`
 (*kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior method*), 524
`select_with_touch()`
 (*kivy.uix.behaviors.CompoundSelectionBehavior method*), 510
`selected_alpha` (*kivy.uix.settings.SettingItem attribute*), 685
`selected_node` (*kivy.uixtreeview.TreeView attribute*), 728
`selected_nodes` (*kivy.uix.behaviors.compoundselection.CompoundSelection attribute*), 524
`selected_nodes` (*kivy.uix.behaviors.CompoundSelectionBehavior attribute*), 510
`selected_uid` (*kivy.uix.settings.MenuSidebar attribute*), 683
`selection` (*kivy.uixfilechooser.FileChooserController attribute*), 603

`selection_color` (`kivy.uix.textinput.TextInput attribute`), 722
`selection_from` (`kivy.uix.textinput.TextInput attribute`), 722
`selection_text` (`kivy.uix.textinput.TextInput attribute`), 722
`selection_to` (`kivy.uix.textinput.TextInput attribute`), 722
`sensitivity` (`kivy.uix.slider.Slider attribute`), 691
`separator_color` (`kivy.uix.popup.Popup attribute`), 640
`separator_height` (`kivy.uix.popup.Popup attribute`), 640
`separator_image` (`kivy.uix.actionbar.ActionGroup attribute`), 562
`separator_width` (`kivy.uix.actionbar.ActionGroup attribute`), 562
`set()` (`kivy.config.ConfigParser method`), 239
`set()` (`kivy.graphics.context_instructions.Rotate method`), 381
`set()` (`kivy.graphics.Rotate method`), 370
`set()` (`kivy.graphics.transformation.Matrix method`), 416
`set()` (`kivy.properties.AliasProperty method`), 278
`set()` (`kivy.properties.ConfigParserProperty method`), 282
`set()` (`kivy.properties.DictProperty method`), 282
`set()` (`kivy.properties.ListProperty method`), 283
`set()` (`kivy.properties.Property method`), 286
`set()` (`kivy.properties.ReferenceListProperty method`), 287
`set_config()` (`kivy.properties.ConfigParserProperty method`), 282
`set_content()` (`kivy.modules.console.Console method`), 486
`set_custom_titlebar()` (`kivy.core.window.WindowBase method`), 330
`set_fbo_shader()` (`kivy.uix.effectwidget.AdvancedEffectBase method`), 592
`set_fbo_shader()` (`kivy.uix.effectwidget.EffectBase method`), 593
`set_icon()` (`kivy.core.window.WindowBase method`), 330
`set_max()` (`kivy.properties.BoundedNumericProperty method`), 279
`set_min()` (`kivy.properties.BoundedNumericProperty method`), 279
`set_name()` (`kivy.properties.Property method`), 286
`set_system_cursor()` (`kivy.core.window.WindowBase method`), 330
`set_title()` (`kivy.core.window.WindowBase method`), 331
`set_tree()` (`kivy.graphics.svg.Svg method`), 404
`set_visible_views()` (`kivy.uix.recyclelayout.RecycleLayout method`), 645
`set_visible_views()` (`kivy.uix.recycleview.layout.RecycleLayoutManagerBehavior method`), 552
`set_visible_views()` (`kivy.uix.recycleview.views.RecycleDataAdapter method`), 554
`set_vkeyboard_class()` (`kivy.core.window.WindowBase method`), 331
`set_window()` (`kivy.base.EventLoopBase method`), 256
`setall()` (`kivy.config.ConfigParser method`), 240
`setdefault()` (`kivy.config.ConfigParser method`), 240
`setdefaults()` (`kivy.config.ConfigParser method`), 240
`setitem()` (`kivy.properties.ReferenceListProperty method`), 287
`setter()` (`kivy.event.EventDispatcher method`), 247
`SettingBoolean` (`class in kivy.uix.settings`), 684
`SettingItem` (`class in kivy.uix.settings`), 684
`SettingNumeric` (`class in kivy.uix.settings`), 685
`SettingOptions` (`class in kivy.uix.settings`), 685
`SettingPath` (`class in kivy.uix.settings`), 686
`Settings` (`class in kivy.uix.settings`), 686
`settings` (`kivy.uix.settings.SettingsPanel attribute`), 688
`settings_cls` (`kivy.app.App attribute`), 209
`SettingsPanel` (`class in kivy.uix.settings`), 687
`SettingString` (`class in kivy.uix.settings`), 686
`SettingsWithNoMenu` (`class in kivy.uix.settings`), 688
`SettingsWithSidebar` (`class in kivy.uix.settings`), 688
`SettingsWithSpinner` (`class in kivy.uix.settings`), 688
`SettingsWithTabbedPanel` (`class in kivy.uix.settings`), 688
`SettingTitle` (`class in kivy.uix.settings`), 686
`setup_mode()` (`kivy.uix.vkeyboard.VKeyboard method`), 742
`setup_mode_dock()` (`kivy.uix.vkeyboard.VKeyboard method`), 742
`setup_mode_free()` (`kivy.uix.vkeyboard.VKeyboard method`), 742
`Shader` (`class in kivy.graphics.shader`), 401
`shader` (`kivy.graphics.instructions.RenderContext attribute`), 376

shader (*kivy.graphics.RenderContext attribute*), 369
ShaderTransition (class in *kivy.uix.screenmanager*), 669
Shape (class in *kivy.input.shape*), 453
shape (*kivy.input MotionEvent attribute*), 432
shape (*kivy.input.motionevent MotionEvent attribute*), 451
shape_color_key (*kivy.core.window.WindowBase attribute*), 331
shape_cutoff (*kivy.core.window.WindowBase attribute*), 331
shape_image (*kivy.core.window.WindowBase attribute*), 331
shape_mode (*kivy.core.window.WindowBase attribute*), 331
shaped (*kivy.core.window.WindowBase attribute*), 332
ShapeRect (class in *kivy.input.shape*), 453
shorten (*kivy.uix.label.Label attribute*), 628
shorten() (*kivy.core.text.LabelBase method*), 309
shorten_from (*kivy.uix.label.Label attribute*), 628
shorten_post() (*kivy.core.text.markup.MarkupLabel method*), 314
show() (*kivy.core.window.WindowBase method*), 332
show_arrow (*kivy.uix.bubble.Bubble attribute*), 573
show_cursor (*kivy.core.window.WindowBase attribute*), 332
show_errors (*kivy.uix.rst.RstDocument attribute*), 652
show_hidden (*kivy.uix.filechooser.FileChooserController attribute*), 603
show_hidden (*kivy.uix.settings.SettingPath attribute*), 686
show_keyboard() (*kivy.uix.behaviors.focus.FocusBehavior method*), 533
show_keyboard() (*kivy.uix.behaviors.FocusBehavior method*), 515
single_points_test() (*kivy.uix.gesturesurface.GestureContainer method*), 608
sizable_from (*kivy.uix.splitter.Splitter attribute*), 697
size (*kivy.core.image.Image property*), 304
size (*kivy.core.image.ImageData property*), 305
size (*kivy.core.window.WindowBase attribute*), 332
size (*kivy.graphics.Fbo attribute*), 360
size (*kivy.graphics.fbo.Fbo attribute*), 385
size (*kivy.graphics.Rectangle attribute*), 368
size (*kivy.graphics.texture.Texture attribute*), 413
size (*kivy.graphics.vertex_instructions.Rectangle attribute*), 426
size (*kivy.uix.effectwidget.HorizontalBlurEffect attribute*), 594
size (*kivy.uix.effectwidget.VerticalBlurEffect attribute*), 595
size (*kivy.uix.widget.Widget attribute*), 753
size_hint (*kivy.uix.widget.Widget attribute*), 753
size_hint_max (*kivy.uix.widget.Widget attribute*), 753
size_hint_max_x (*kivy.uix.widget.Widget attribute*), 753
size_hint_max_y (*kivy.uix.widget.Widget attribute*), 754
size_hint_min (*kivy.uix.widget.Widget attribute*), 754
size_hint_min_x (*kivy.uix.widget.Widget attribute*), 754
size_hint_min_y (*kivy.uix.widget.Widget attribute*), 754
size_hint_x (*kivy.uix.widget.Widget attribute*), 754
size_hint_y (*kivy.uix.widget.Widget attribute*), 755
Slider (class in *kivy.uix.slider*), 689
slides (*kivy.uix.carousel.Carousel attribute*), 580
SlideTransition (class in *kivy.uix.screenmanager*), 670
smooth_scroll_end (*kivy.uix.scrollview.ScrollView attribute*), 678
SmoothLine (class in *kivy.graphics*), 370
SmoothLine (class in *kivy.graphics.vertex_instructions*), 426
softinput_mode (*kivy.core.window.WindowBase attribute*), 332
sort_func (*kivy.uix.filechooser.FileChooserController attribute*), 603
Sound (class in *kivy.core.audio*), 298
SoundLoader (class in *kivy.core.audio*), 299
source (*kivy.core.audio.Sound attribute*), 299
source (*kivy.core.image.ImageData attribute*), 305
source (*kivy.graphics.BindTexture attribute*), 353
source (*kivy.graphics.context_instructions.BindTexture attribute*), 378
source (*kivy.graphics.instructions.VertexInstruction attribute*), 376
source (*kivy.graphics.shader.Shader attribute*), 401
source (*kivy.graphics.svg.Svg attribute*), 404
source (*kivy.graphics.VertexInstruction attribute*), 372
source (*kivy.uix.effectwidget.EffectBase attribute*), 593
source (*kivy.uix.image.Image attribute*), 617
source (*kivy.uix.rst.RstDocument attribute*), 652
source (*kivy.uix.videoplayer.VideoPlayer attribute*), 737
source_encoding (*kivy.uix.rst.RstDocument attribute*), 653
source_error (*kivy.uix.rst.RstDocument attribute*), 653

`source_stack` (*kivy.graphics.ApplyContextMatrix attribute*), 352
`sp` (*kivy.metrics.MetricsBase attribute*), 262
`sp()` (*in module kivy.metrics*), 263
`spacing` (*kivy.uix.boxlayout.BoxLayout attribute*), 569
`spacing` (*kivy.uix.gridlayout.GridLayout attribute*), 614
`spacing` (*kivy.uix.stacklayout.StackLayout attribute*), 699
`SpellingBase` (*class in kivy.core.spelling*), 305
`Spinner` (*class in kivy.uix.spinner*), 694
`SpinnerOption` (*class in kivy.uix.spinner*), 694
`split_str` (*kivy.uix.label.Label attribute*), 628
`Splitter` (*class in kivy.uix.splitter*), 695
`spos` (*kivy.input MotionEvent property*), 432
`spos` (*kivy.input.motionevent MotionEvent property*), 451
`spring_constant` (*kivy.effects.dampedscroll.Damped attribute*), 337
`stack` (*kivy.graphics.context_instructions.MatrixInstruction attribute*), 380
`stack` (*kivy.graphics.context_instructions.PopMatrix attribute*), 380
`stack` (*kivy.graphics.context_instructions.PushMatrix attribute*), 380
`stack` (*kivy.graphics.LoadIdentity attribute*), 366
`stack` (*kivy.graphics.MatrixInstruction attribute*), 366
`stack` (*kivy.graphics.PopMatrix attribute*), 368
`stack` (*kivy.graphics.PushMatrix attribute*), 368
`StackLayout` (*class in kivy.uix.stacklayout*), 698
`start` (*kivy.uix.videoplayer.VideoPlayerAnnotation attribute*), 737
`start()` (*in module kivy.modules.console*), 486
`start()` (*kivy.animation.Animation method*), 191
`start()` (*kivy.base.EventLoopBase method*), 256
`start()` (*kivy.core.camera.CameraBase method*), 300
`start()` (*kivy.effects.kinetic.KineticEffect method*), 339
`start()` (*kivy.effects.scroll.ScrollEffect method*), 340
`start()` (*kivy.eventmanager.EntityManagerBase method*), 345
`start()` (*kivy.input.MotionEventProvider method*), 433
`start()` (*kivy.input.provider.MotionEventProvider method*), 453
`start()` (*kivy.input.providers.androidjoystick.AndroidMotionEventProvider method*), 437
`start()` (*kivy.input.providers.leapfinger.LeapFingerEventProvider method*), 438
`start()` (*kivy.input.providers.mactouch.MacMotionEventProvider method*), 442
`start()` (*kivy.input.providers.mouse.MouseMotionEventProvider method*), 439
`start()` (*kivy.input.providers.tuio.TuioMotionEventProvider method*), 444
`start()` (*kivy.loader.LoaderBase method*), 212
`start()` (*kivy.uix.screenmanager.CardTransition method*), 665
`start()` (*kivy.uix.screenmanager.SwapTransition method*), 670
`start()` (*kivy.uix.screenmanager.TransitionBase method*), 671
`start_clock()` (*kivy.clock.CyClockBase method*), 231
`state` (*kivy.core.audio.Sound attribute*), 299
`state` (*kivy.core.video.VideoBase property*), 315
`state` (*kivy.uix.behaviors.button.ButtonBehavior attribute*), 519
`state` (*kivy.uix.behaviors.ButtonBehavior attribute*), 507
`state` (*kivy.uix.video.Video attribute*), 732
`state` (*kivy.uix.videoplayer.VideoPlayer attribute*), 737
`status` (*kivy.core.audio.Sound attribute*), 299
`std_dt` (*kivy.effects.kinetic.KineticEffect attribute*), 339
`StencilPop` (*class in kivy.graphics*), 371
`StencilPop` (*class in kivy.graphics.stencil_instructions*), 403
`StencilPush` (*class in kivy.graphics*), 371
`StencilPush` (*class in kivy.graphics.stencil_instructions*), 403
`StencilUnUse` (*class in kivy.graphics*), 371
`StencilUnUse` (*class in kivy.graphics.stencil_instructions*), 403
`StencilUse` (*class in kivy.graphics*), 371
`StencilUse` (*class in kivy.graphics.stencil_instructions*), 403
`StencilView` (*class in kivy.uix.stencilview*), 700
`step` (*kivy.uix.slider.Slider attribute*), 691
`stop()` (*in module kivy.modules.console*), 486
`stop()` (*in module kivy.modules.inspector*), 487
`stop()` (*in module kivy.modules.joycursor*), 489
`stop()` (*kivy.animation.Animation method*), 191
`stop()` (*kivy.app.App method*), 209
`stop()` (*kivy.base.EventLoopBase method*), 256
`stop()` (*kivy.core.audio.Sound method*), 299
`stop()` (*kivy.core.camera.CameraBase method*), 300
`stop()` (*kivy.core.video.VideoBase method*), 315
`stop()` (*kivy.effects.kinetic.KineticEffect method*), 339
`stop()` (*kivy.effects.scroll.ScrollEffect method*), 341
`stop_provider` (*kivy.eventmanager.EntityManagerBase method*), 345
`stop_provider` (*kivy.input.MotionEventProvider method*), 433
`stop_provider` (*kivy.input.provider.MotionEventProvider method*), 453

stop() (*kivy.input.providers.androidjoystick.AndroidMotionEventProvider method*), 437
stop() (*kivy.input.providers.mactouch.MacMotionEventProvider method*), 442
stop() (*kivy.input.providers.mouse.MouseMotionEventProvider method*), 440
stop() (*kivy.input.providers.tuio.TuioMotionEventProvider method*), 444
stop() (*kivy.loader.LoaderBase method*), 213
stop() (*kivy.multistroke.ProgressTracker method*), 268
stop() (*kivy.uix.screenmanager.ShaderTransition method*), 670
stop() (*kivy.uix.screenmanager.TransitionBase method*), 671
stop_all() (*kivy.animation.Animation static method*), 191
stop_clock() (*kivy.clock.CyClockBase method*), 231
stop_property() (*kivy.animation.Animation method*), 191
stopTouchApp() (*in module kivy.app*), 210
stopTouchApp() (*in module kivy.base*), 258
str_to_gesture() (*kivy.gesture.GestureDatabase method*), 252
strikethrough (*kivy.uix.label.Label attribute*), 628
string_to_keycode()
 (*kivy.core.window.Keyboard method*), 317
string_types (*in module kivy.compat*), 233
StringProperty (*class in kivy.properties*), 287
strip (*kivy.uix.label.Label attribute*), 629
strip_border (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 707
strip_cls (*kivy.uix.splitter.Splitter attribute*), 697
strip_comments() (*kivy.lang.Parser method*), 472
strip_comments()
 (*kivy.lang.parser.Parser method*), 476
strip_image (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 707
strip_size (*kivy.uix.splitter.Splitter attribute*), 697
StripLayout (*class in kivy.uix.tabbedpanel*), 705
stroke_length()
 (*kivy.gesture.GestureStroke method*), 252
strtotuple() (*in module kivy.utils*), 291
style (*kivy.uix.codeinput.CodeInput attribute*), 584
style_name (*kivy.uix.codeinput.CodeInput attribute*), 584
success (*kivy.graphics.shader.Shader attribute*), 401
suggest() (*kivy.core.spelling.SpellingBase method*), 306
Svg (*class in kivy.graphics.svg*), 403
SwapTransition (*class in kivy.uix.screenmanager*), 670
SwipeThreshold (*kivy.uix.pagelayout.PageLayout attribute*), 637
Switch (*class in kivy.uix.switch*), 701
switch_to() (*kivy.uix.screenmanager.ScreenManager method*), 668
switch_to() (*kivy.uix.tabbedpanel.TabbedPanel method*), 707
sx (*kivy.input MotionEvent attribute*), 432
sx (*kivy.input.motionevent MotionEvent attribute*), 451
sy (*kivy.input MotionEvent attribute*), 432
sy (*kivy.input.motionevent MotionEvent attribute*), 451
sync() (*kivy.lang.builder.BuilderBase method*), 474
sync() (*kivy.lang.BuilderBase method*), 469
sync_height (*kivy.uix.spinner.Spinner attribute*), 694
sync_with_dispatch (*kivy.input MotionEvent attribute*), 432
sync_with_dispatch
 (*kivy.input.motionevent MotionEvent attribute*), 451
system_size (*kivy.core.window.WindowBase attribute*), 333
sz (*kivy.input MotionEvent attribute*), 432
sz (*kivy.input.motionevent MotionEvent attribute*), 452

T

tab_height (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 707
tab_list (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 707
tab_pos (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 707
tab_width (*kivy.uix.tabbedpanel.TabbedPanel attribute*), 708
tab_width (*kivy.uix.textinput.TextInput attribute*), 722
tabbed_panel (*kivy.uix.tabbedpanel.TabbedPanelStrip attribute*), 709
TabbedPanel (*class in kivy.uix.tabbedpanel*), 705
TabbedPanelContent (*class in kivy.uix.tabbedpanel*), 708
TabbedPanelException, 708
TabbedPanelHeader (*class in kivy.uix.tabbedpanel*), 708
TabbedPanelItem (*class in kivy.uix.tabbedpanel*), 708
TabbedPanelStrip (*class in kivy.uix.tabbedpanel*), 709
target (*kivy.core.window.Keyboard attribute*), 317
target (*kivy.graphics.texture.Texture attribute*), 413
target (*kivy.uix.vkeyboard.VKeyboard attribute*), 742

`target_stack` (*kivy.graphics.ApplyContextMatrix attribute*), 352
`target_widget` (*kivy.effects.scroll.ScrollEffect attribute*), 341
`template()` (*kivy.lang.builder.BuilderBase method*), 474
`template()` (*kivy.lang.BuilderBase method*), 470
`tesselate()` (*kivy.graphics.tesselator.Tesselator method*), 406
`Tesselator` (*class in kivy.graphics.tesselator*), 405
`tex_coords` (*kivy.graphics.instructions.VertexInstruction attribute*), 377
`tex_coords` (*kivy.graphics.texture.Texture attribute*), 413
`tex_coords` (*kivy.graphics.VertexInstruction attribute*), 372
`text` (*kivy.core.text.LabelBase property*), 310
`text` (*kivy.core.text.text_layout.LayoutWord attribute*), 311
`text` (*kivy.uix.label.Label attribute*), 629
`text` (*kivy.uix.rst.RstDocument attribute*), 653
`text` (*kivy.uix.textinput.TextInput attribute*), 722
`text_autoupdate` (*kivy.uix.spinner.Spinner attribute*), 694
`text_entry_timeout`
 (*kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior attribute*), 524
`text_entry_timeout`
 (*kivy.uix.behaviors.CompoundSelectionBehavior attribute*), 510
`text_language` (*kivy.uix.label.Label attribute*), 629
`text_language` (*kivy.uix.textinput.TextInput attribute*), 723
`text_size` (*kivy.core.text.LabelBase property*), 310
`text_size` (*kivy.uix.label.Label attribute*), 629
`text_validate_unfocus`
 (*kivy.uix.textinput.TextInput attribute*), 723
`TextInput` (*class in kivy.uix.textinput*), 712
`textinput` (*kivy.uix.settings.SettingsPath attribute*), 686
`textinput` (*kivy.uix.settings.SettingsString attribute*), 686
`Texture` (*class in kivy.graphics.texture*), 410
`texture` (*kivy.core.camera.CameraBase property*), 300
`texture` (*kivy.core.image.Image property*), 304
`texture` (*kivy.core.video.VideoBase property*), 316
`texture` (*kivy.graphics.Fbo attribute*), 360
`texture` (*kivy.graphics.fbo.Fbo attribute*), 385
`texture` (*kivy.graphics.instructions.VertexInstruction attribute*), 377
`texture` (*kivy.graphics.VertexInstruction attribute*), 372
`texture` (*kivy.uix.effectwidget.EffectWidget attribute*), 594
`texture` (*kivy.uix.image.Image attribute*), 617
`texture` (*kivy.uix.label.Label attribute*), 629
`texture_size` (*kivy.uix.image.Image attribute*), 617
`texture_size` (*kivy.uix.label.Label attribute*), 630
`texture_update()` (*kivy.uix.label.Label method*), 630
`TextureRegion` (*class in kivy.graphics.texture*), 413
`textures` (*kivy.atlas.Atlas attribute*), 216
`thumbnail` (*kivy.uix.videoplayer.VideoPlayer attribute*), 737
`tick()` (*kivy.clock.ClockBaseBehavior method*), 226
`tick()` (*kivy.clock.ClockEvent method*), 228
`tick_draw()` (*kivy.clock.ClockBaseBehavior method*), 226
`time()` (*kivy.clock.ClockBaseBehavior static method*), 226
`time_end` (*kivy.input MotionEvent attribute*), 432
`time_end` (*kivy.input.motionevent MotionEvent attribute*), 452
`time_start` (*kivy.input MotionEvent attribute*), 432
`time_start` (*kivy.input.motionevent MotionEvent attribute*), 452
`time_update` (*kivy.input MotionEvent attribute*), 432
`time_update` (*kivy.input.motionevent MotionEvent attribute*), 452
`timeout` (*kivy.clock.ClockEvent attribute*), 228
`timeval` (*class in kivy.lib.mtdev*), 479
`title` (*kivy.app.App attribute*), 209
`title` (*kivy.uix.accordion.AccordionItem attribute*), 559
`title` (*kivy.uix.actionbar.ActionPrevious attribute*), 564
`title` (*kivy.uix.popup.Popup attribute*), 640
`title` (*kivy.uix.rst.RstDocument attribute*), 653
`title` (*kivy.uix.settings.SettingsItem attribute*), 685
`title` (*kivy.uix.settings.SettingsPanel attribute*), 688
`title_align` (*kivy.uix.popup.Popup attribute*), 640
`title_args` (*kivy.uix.accordion.AccordionItem attribute*), 559
`title_color` (*kivy.uix.popup.Popup attribute*), 640
`title_font` (*kivy.uix.popup.Popup attribute*), 641
`title_size` (*kivy.uix.popup.Popup attribute*), 641
`title_template` (*kivy.uix.accordion.AccordionItem attribute*), 560
`to_absolute_pos()` (*kivy.input MotionEvent method*), 432
`to_absolute_pos()`
 (*kivy.input.motionevent MotionEvent method*), 452
`to_local()` (*kivy.uix.relativelayout.RelativeLayout*

method), 650
to_local() (*kivy.uix.scatter.Scatter method*), 659
to_local() (*kivy.uix.scrollview.ScrollView method*), 678
to_local() (*kivy.uix.widget.Widget method*), 755
to_normalized_pos()
(kivy.core.window.WindowBase method),
 333
to_parent() (*kivy.uix.relativelayout.RelativeLayout method*), 650
to_parent() (*kivy.uix.scatter.Scatter method*), 659
to_parent() (*kivy.uix.scrollview.ScrollView method*), 678
to_parent() (*kivy.uix.widget.Widget method*), 755
to_widget() (*kivy.uix.widget.Widget method*), 755
to_window() (*kivy.uix.widget.Widget method*), 755
toctrees (*kivy.uix.rst.RstDocument attribute*), 653
toggle_fullscreen()
(kivy.core.window.WindowBase method),
 333
toggle_node() (*kivy.uix.treeview.TreeView method*), 728
ToggleButton (*class in kivy.uix.togglebutton*), 724
ToggleButtonBehavior (*class in kivy.uix.behaviors*), 515
ToggleButtonBehavior (*class in kivy.uix.behaviors.togglebutton*), 539
tolist() (*kivy.graphics.transformation.Matrix method*), 416
top (*kivy.core.window.WindowBase attribute*), 333
top (*kivy.uix.widget.Widget attribute*), 755
total (*kivy.uix.filechooser.FileChooserProgressBase attribute*), 604
touch_control (*kivy.uix.switch.Switch attribute*),
 701
touch_deselect_last
(kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior attribute), 524
touch_deselect_last
(kivy.uix.behaviors.CompoundSelectionBehavior attribute), 510
touch_distance (*kivy.uix.switch.Switch attribute*),
 702
touch_multiselect
(kivy.uix.behaviors.compoundselection.CompoundSelectionBehavior attribute), 525
touch_multiselect
(kivy.uix.behaviors.CompoundSelectionBehavior attribute), 510
touches (*kivy.base.EventLoopBase property*), 256
TouchRippleBehavior (*class in kivy.uix.behaviors*), 516
TouchRippleBehavior (*class in kivy.uix.behaviors.touchripple*), 540
TouchRippleButtonBehavior (*class in kivy.uix.behaviors*), 517
TouchRippleButtonBehavior (*class in kivy.uix.behaviors.touchripple*), 542
transfer_gesture()
(kivy.multistroke.Recognizer method),
 271
transform (*kivy.uix.scatter.Scatter attribute*), 659
transform_inv (*kivy.uix.scatter.Scatter attribute*),
 660
transform_motion_event_2d()
(kivy.core.window.WindowBase method),
 333
transform_point()
(kivy.graphics.transformation.Matrix method), 416
transition (*kivy.animation.Animation property*),
 191
transition (*kivy.uix.screenmanager.ScreenManager attribute*), 669
transition_progress
(kivy.uix.screenmanager.Screen attribute),
 666
transition_state
(kivy.uix.screenmanager.Screen attribute),
 667
TransitionBase (*class in kivy.uix.screenmanager*), 670
Translate (*class in kivy.graphics*), 371
Translate (*class in kivy.graphics.context_instructions*), 382
translate() (*kivy.graphics.transformation.Matrix method*), 416
translation_touches (*kivy.uix.scatter.Scatter attribute*), 660
transpose() (*kivy.graphics.transformation.Matrix method*), 416
TreeViewBehavior (*kivy.uix.treeview*), 726
TreeViewException, 728
TreeViewLabel (*class in kivy.uix.treeview*), 728
TreeNode (*class in kivy.uix.treeview*), 728
Triangle (*class in kivy.graphics*), 371
Triangle (*class in kivy.graphics.vertex_instructions*), 426
trigger_action()
(kivy.uix.behaviors.button.ButtonBehavior method), 519
trigger_action()
(kivy.uix.behaviors.ButtonBehavior method),
 507
trigger_change() (*kivy.properties.AliasProperty method*), 278
trigger_change()
(kivy.properties.ReferenceListProperty method), 287
trigger_gl_dealloc()

`(kivy.graphics.context.Context method), 383`
`triggered() (in module kivy.clock), 232`
`triple_tap_time (kivy.input MotionEvent attribute), 433`
`triple_tap_time (kivy.input.motionevent MotionEvent attribute), 452`
`Tuio2dCurMotionEvent (class in kivy.input.providers.tuio), 443`
`Tuio2dObjMotionEvent (class in kivy.input.providers.tuio), 443`
`TuioMotionEventProvider (class in kivy.input.providers.tuio), 443`
`type_id (kivy.input MotionEvent attribute), 433`
`type_id (kivy.input.motionevent MotionEvent attribute), 452`
`type_ids (kivy.eventmanager.EventManagerBase attribute), 345`

U

`ud (kivy.input MotionEvent attribute), 433`
`ud (kivy.input.motionevent MotionEvent attribute), 452`
`uid (kivy.input MotionEvent attribute), 433`
`uid (kivy.input.motionevent MotionEvent attribute), 452`
`unbind() (kivy.event.EventDispatcher method), 248`
`unbind() (kivy.event.Observable method), 249`
`unbind() (kivy.lang.builder.Observable method), 476`
`unbind() (kivy.lang.Observable method), 471`
`unbind() (kivy.properties.Property method), 286`
`unbind_property() (kivy.lang.builder.BuilderBase method), 474`
`unbind_property() (kivy.lang.BuilderBase method), 470`
`unbind_uid() (kivy.event.EventDispatcher method), 248`
`unbind_uid() (kivy.event.Observable method), 249`
`unbind_uid() (kivy.lang.builder.Observable method), 476`
`unbind_uid() (kivy.lang.Observable method), 471`
`unbind_uid() (kivy.properties.Property method), 286`
`unbind_widget() (kivy.lang.builder.BuilderBase method), 474`
`unbind_widget() (kivy.lang.BuilderBase method), 470`
`underline (kivy.uix.label.Label attribute), 630`
`underline_color (kivy.uix.rst.RstDocument attribute), 653`
`unfocus_on_touch (kivy.uix.behaviors.focus.FocusBehavior attribute), 533`
`unfocus_on_touch (kivy.uix.behaviors.FocusBehavior attribute), 515`
`ungrab() (kivy.input MotionEvent method), 433`
`ungrab() (kivy.input.motionevent MotionEvent method), 452`
`ungrab_mouse() (kivy.core.window.WindowBase method), 333`
`unicode_errors (kivy.uix.label.Label attribute), 630`
`uniforms (kivy.uix.effectwidget.AdvancedEffectBase attribute), 592`
`uninstall_twisted_reactor() (in module kivy.support), 289`
`UnistrokeTemplate (class in kivy.multistroke), 271`
`unload() (kivy.core.audio.Sound method), 299`
`unload() (kivy.core.video.VideoBase method), 316`
`unload() (kivy.uix.video.Video method), 732`
`unload_file() (kivy.lang.builder.BuilderBase method), 475`
`unload_file() (kivy.lang.BuilderBase method), 471`
 `unregister() (kivy.input.providers.tuio.TuioMotionEventProvider static method), 444`
`unregister_event_manager() (kivy.core.window.WindowBase method), 334`
`unregister_event_type() (kivy.event.EventDispatcher method), 248`
`unregister_event_types() (kivy.event.EventDispatcher method), 248`
`unregister_for_motion_event() (kivy.uix.widget.Widget method), 755`
`unschedule() (kivy.clock.CyClockBase method), 231`
`up_count (kivy.uix.behaviors.compoundselection.CompoundSelectionB attribute), 525`
`up_count (kivy.uix.behaviors.CompoundSelectionBehavior attribute), 511`
`update() (kivy.effects.kinetic.KineticEffect method), 339`
`update() (kivy.effects.scroll.ScrollEffect method), 341`
`update() (kivy.input.MotionEventProvider method), 433`
`update() (kivy.input.provider.MotionEventProvider method), 453`
`update() (kivy.input.providers.androidjoystick.AndroidMotionEventP method), 437`
`update() (kivy.input.providers.leapfinger.LeapFingerEventProvider method), 438`
`update() (kivy.input.providers.mactouch.MacMotionEventProvider`

method), 442
update() (*kivy.input.providers.mouse.MouseMotionEventProvider* method), 440
update() (*kivy.input.providers.tuio.TuioMotionEventProvider* method), 444
update_bbox() (*kivy.uix.gesturesurface.GestureContainer* method), 608
update_config() (*kivy.config.ConfigParser* method), 240
update_from_scroll() (*kivy.uix.scrollviewScrollView* method), 678
update_velocity() (*kivy.effects.dampedscroll.DampedScrollEffect* method), 338
update_velocity() (*kivy.effects.kinetic.KineticEffect* method), 339
UpdateNormalMatrix (*class in kivy.graphics*), 372
url (*kivy.network.urlrequest.UrlRequest* attribute), 496
UrlRequest (*class in kivy.network.urlrequest*), 494
use_bubble (*kivy.uix.textinput.TextInput* attribute), 723
use_handles (*kivy.uix.textinput.TextInput* attribute), 723
use_kivy_settings (*kivy.app.App* attribute), 210
use_parent_frag_modelview
(kivy.graphics.instructions.RenderContext attribute), 376
use_parent_frag_modelview
(kivy.graphics.RenderContext attribute), 369
use_parent_modelview
(kivy.graphics.instructions.RenderContext attribute), 376
use_parent_modelview
(kivy.graphics.RenderContext attribute), 369
use_parent_projection
(kivy.graphics.instructions.RenderContext attribute), 376
use_parent_projection
(kivy.graphics.RenderContext attribute), 369
use_separator (*kivy.uix.actionbar.ActionGroup* attribute), 562
use_separator (*kivy.uix.actionbar.ActionView* attribute), 565
user_data_dir (*kivy.app.App* property), 210
usersize (*kivy.core.text.LabelBase* property), 310
usleep() (*kivy.clock.ClockBase* method), 224
usleep() (*kivy.clock.ClockBaseBehavior* method), 226
usleep() (*kivy.clock.ClockBaseInterruptBehavior*
method), 226
uvpos (*kivy.graphics.texture.Texture* attribute), 413
uvsize (*kivy.graphics.texture.Texture* attribute), 413
V
v (*kivy.graphics.Color* attribute), 358
v (*kivy.graphics.context_instructions.Color* attribute), 380
valign (*kivy.uix.label.Label* attribute), 630
value (*kivy.effects.kinetic.KineticEffect* attribute), 339
value (*kivy.uix.progressbar.ProgressBar* attribute), 641
value (*kivy.uix.settings.SettingItem* attribute), 685
value (*kivy.uix.slider.Slider* attribute), 691
value_normalized
(kivy.uix.progressbar.ProgressBar attribute), 642
value_normalized (*kivy.uix.slider.Slider* attribute), 692
value_pos (*kivy.uix.slider.Slider* attribute), 692
value_track (*kivy.uix.slider.Slider* attribute), 692
value_track_color (*kivy.uix.slider.Slider* attribute), 692
value_track_width (*kivy.uix.slider.Slider* attribute), 692
values (*kivy.uix.settings.SettingBoolean* attribute), 684
values (*kivy.uix.spinner.Spinner* attribute), 694
VariableListProperty (*class in kivy.properties*), 287
vbar (*kivy.uix.scrollviewScrollView* attribute), 678
Vector (*class in kivy.vector*), 292
velocity (*kivy.effects.kinetic.KineticEffect* attribute), 339
vertex_count (*kivy.graphics.tesselator.Tesselator* attribute), 406
VertexInstruction (*class in kivy.graphics*), 372
VertexInstruction (*class in kivy.graphics.instructions*), 376
VerticalBlurEffect (*class in kivy.uix.effectwidget*), 594
vertices (*kivy.graphics.Mesh* attribute), 367
vertices (*kivy.graphics.tesselator.Tesselator* attribute), 406
vertices (*kivy.graphics.vertex_instructions.Mesh* attribute), 425
Video (*class in kivy.uix.video*), 730
VideoBase (*class in kivy.core.video*), 315
VideoPlayer (*class in kivy.uix.videoplayer*), 734
VideoPlayerAnnotation (*class in kivy.uix.videoplayer*), 737
view_adapter (*kivy.uix.recycleview.RecycleViewBehavior* attribute), 548

v
view_clip() (*kivy.graphics.transformation.Matrix method*), 416
view_list (*kivy.uix.filechooser.FileChooser attribute*), 600
view_mode (*kivy.uix.filechooser.FileChooser attribute*), 600
viewclass (*kivy.uix.recycleview.layout.RecycleLayout attribute*), 552
viewclass (*kivy.uix.recycleview.RecycleView attribute*), 547
viewport_size (*kivy.uix.scrollview.ScrollView attribute*), 678
VKeyboard (*class in kivy.uix.vkeyboard*), 739
volume (*kivy.core.audio.Sound attribute*), 299
volume (*kivy.core.video.VideoBase property*), 316
volume (*kivy.uix.video.Video attribute*), 732
volume (*kivy.uix.videoplayer.VideoPlayer attribute*), 737
vs (*kivy.graphics.shader.Shader attribute*), 401
vs (*kivy.uix.screenmanager.ShaderTransition attribute*), 670

W

w (*kivy.core.text.text_layout.LayoutLine attribute*), 310
wait() (*kivy.network.urlrequest.UrlRequest method*), 496
walk() (*kivy.uix.widget.Widget method*), 756
walk_reverse() (*kivy.uix.widget.Widget method*), 756
weak_callback (*kivy.clock.ClockEvent attribute*), 228
weak_clock_ended_callback (*kivy.clock.ClockEvent attribute*), 228
WeakMethod (*class in kivy.weakmethod*), 295
WeakProxy (*class in kivy.weakproxy*), 295
wheel (*kivy.uix.colorpicker.ColorPicker attribute*), 585
Widget (*class in kivy.uix.widget*), 746
widget (*kivy.core.window.Keyboard attribute*), 317
widget (*kivy.modules.console.Console attribute*), 486
WidgetException, 757
width (*kivy.core.image.Image property*), 304
width (*kivy.core.image.ImageData property*), 305
width (*kivy.core.window.WindowBase attribute*), 334
width (*kivy.graphics.Line attribute*), 366
width (*kivy.graphics.svg.Svg attribute*), 404
width (*kivy.graphics.texture.Texture attribute*), 413
width (*kivy.graphics.vertex_instructions.Line attribute*), 424
width (*kivy.input.shape.ShapeRect attribute*), 453
width (*kivy.uix.widget.Widget attribute*), 757
window (*kivy.core.window.Keyboard attribute*), 317
window (*kivy.eventmanager.EventManagerBase attribute*), 345
window (*kivy.input.recorder.Recorder attribute*), 446
WindowBase (*class in kivy.core.window*), 317
WipeTransition (*class in kivy.uix.screenmanager*), 671
with_previous (*kivy.uix.actionbar.ActionPrevious attribute*), 564
Manda (*kivy.core.text.text_layout.LayoutLine attribute*), 310
wrap (*kivy.graphics.texture.Texture attribute*), 413
write() (*kivy.config.ConfigParser method*), 240
write_tab (*kivy.uix.textinput.TextInput attribute*), 723

X

x (*kivy.core.text.text_layout.LayoutLine attribute*), 311
x (*kivy.graphics.context_instructions.Scale attribute*), 381
x (*kivy.graphics.context_instructions.Translate attribute*), 382
x (*kivy.graphics.Scale attribute*), 370
x (*kivy.graphics.Translate attribute*), 371
x (*kivy.input MotionEvent attribute*), 433
x (*kivy.input.motionevent MotionEvent attribute*), 452
x (*kivy.uix.widget.Widget attribute*), 757
x (*kivy.vector.Vector property*), 294
xy (*kivy.graphics.context_instructions.Translate attribute*), 382
xy (*kivy.graphics.Translate attribute*), 371
xyz (*kivy.graphics.context_instructions.Scale attribute*), 381
xyz (*kivy.graphics.context_instructions.Translate attribute*), 382
xyz (*kivy.graphics.Scale attribute*), 370
xyz (*kivy.graphics.Translate attribute*), 371

Y

y (*kivy.core.text.text_layout.LayoutLine attribute*), 311
y (*kivy.graphics.context_instructions.Scale attribute*), 381
y (*kivy.graphics.context_instructions.Translate attribute*), 382
y (*kivy.graphics.Scale attribute*), 370
y (*kivy.graphics.Translate attribute*), 371
y (*kivy.input MotionEvent attribute*), 433
y (*kivy.input.motionevent MotionEvent attribute*), 452
y (*kivy.uix.widget.Widget attribute*), 757
y (*kivy.vector.Vector property*), 295

Z

z (*kivy.graphics.context_instructions.Scale attribute*), 381

- z (*kivy.graphics.context_instructions.Translate attribute*), 382
- z (*kivy.graphics.Scale attribute*), 370
- z (*kivy.graphics.Translate attribute*), 371
- z (*kivy.input MotionEvent attribute*), 433
- z (*kivy.input.motionevent MotionEvent attribute*), 452